

ADDENDUM No. 2

Date: 13.02.2024

Ref: Addendum 2

Enquiries: Thabile Sibiya

Email: sibiyaTh@eskom.co.za

To whom it may concern

RE: KZN113

The Manufacture, Test and Supply of various Medium and Low Voltage Cable Accessories on an “as and when” required basis for various Regional Distribution Centres located in the Central East Cluster (KwaZulu Natal and Free State Operating Units) over a period of thirty-six (36) months. Rotek will be responsible for transportation of the goods.

The following changes have been made to the tender enquiry KZN113:

Description	Current Description	Revised Description
The Technical Evaluation Criteria addendum for Central East Cluster MV and LV cable accessories that was issued has an error in point i)	Screened separable connector (SSC) kits shall be supplied without the 3x 70mmsq main earth braids and constant force springs (CFS).	<p>Only screened separable connector kits to be used on three core cable shall be supplied without the 3x 70mmsq main earth braids and constant force springs (CFS).</p> <p>The following shall apply: From Eskom standard 240-56030619 3.1.2.2: The main earthing conductor for indoor single-core cable type 4 and type 5 terminations shall be a 1000 mm and shall be supplied with the screened separable connector kits.</p> <p>For KZN113 please note: This requirement shall only be applicable to 630mmsq single core cable, type 4 terminations screened separable connector kits as per SAP no's 0687354, 0687359, 0687364, 0687369, 0687451, 0687456, 0687457.</p>

Yours faithfully,

 13 February 2024

Name: Thandi Xaba

Designation: Acting Procurement Manager – KZN OU (CEC KZN5438)