

CLARIFICATION No. 6

Date: 04.03.2024

Ref: Clarification 6



Enquiries: Thabile Sibiya

Tel: 031 710 5396

Email: sibiyaTh@eskom.co.za

RE: KZN113

The Manufacture, Test and Supply of various Medium and Low Voltage Cable Accessories on an “as and when” required basis for various Regional Distribution Centres located in the Central East Cluster (KwaZulu Natal and Free State Operating Units) over a period of thirty-six (36) months. Rotek will be responsible for transportation of the goods.

ITEM	Supplier Query	ESKOM response to clarification query
	<p>The main earthing conductor & tail length for outdoor 3 core termination shall be 1200mm.</p> <p>(Page 8 of Page 25)</p> <p>On the Eskom D-DT 8006 it remains 1600mm?</p> <ul style="list-style-type: none"> See attached highlighted in the documents... <div style="display: flex; justify-content: space-around; align-items: center;"> <div style="text-align: center;">  240-56030619 - D-DT 8006.pdf </div> <div style="text-align: center;">  240-56030619 - D-DT 8006.pdf </div> </div>	<p>Please use the Eskom DDT 8006 for outdoor terminations and other terminations for the long text description requirements but for 3 core outdoor terminations substitute the requirement of the termination tail length and main earth braid length as being 1600m with the requirement that the 3-core outdoor termination tail length and main earth braid length shall be 1200m.</p> <p>See also technical clarification no1 dated 12/02/2024 the Eskom tender portal under “Clarification queries and responses “folder”</p>