

REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Project Name: Refurbishment of Park Homes

Project Address: NCOU

Scope of the project: Refurbishment of Park homes (refer to scope of works page 26-28)

Compiled by	Accepted by	Accepted by
Name : Deon Bezuidenhoudt	Name : Magda Wyngaardt	Name : Tom Hlatshwayo
Signature : DB ezuidenhoudt	Signature :	Signature :
Date: 12/06/2023	Date : 15/06/2023	Date : 14/06/2023
Contractor Safety Officer Northern Cape/ Gemma Cluster	Contractor Safety Manager Northern Cape/ Gemma Cluster	Project Manager Northern Cape/ Gemma Cluster

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Content

		Page
1	. Introduction	7
2	Supporting Clauses	7
	2.1 Scope	7
	2.1.1 Purpose	8
	2.1.2 Applicability	8
	2.2 Normative/Informative References	8
	2.2.1 Normative	8
	2.2.2 Informative	9
	2.3 Definitions	10
	2.4 Abbreviations	14
	2.5 Roles and Responsibilities	16
	2.5.1 Commitment	16
	2.6 Related/Supporting Documents	26
3	Specification	26
	3.1 Scope of work	26
	3.2 Legal Compliance	28
	3.2.1 Section 37(2) (Legal) Agreement	28
	3.2.2 Hazardous work by children (Child Labour)	28
	3.3 Eskom Requirements	30
	3.4 Construction Professional Registration	30
	3.5 Notification of Construction Work	30
	3.6 SHE Policy	30
	3.7 COID	31
	3.8 Costing for SHE within the Project	31

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

3.9 Statutory Appointments	31
3.10 Eskom Life-saving Rules	31
3.11 Substance Abuse	34
3.12 Contractor organisational Structure	35
3.12.1 Principal Contractor Organogram	35
3.12.2 Appointed Contractor/s Organogram	35
3.13 Risk assessment (refer to 32-520)	36
3.14 Safe work procedures / method statements	37
3.15 Roof work (refer to 32- 418)	38
3.16 Construction Sites	38
3.17 Fire Equipment and maintenance	38
3.18 Flammable and Combustible Liquids	39
3.18.1 Refuelling at the construction site	39
3.19 First Aid and Equipment	37
3.19.1 Boxes and equipment	38
3.20 SHE Communication Systems	39
3.20.1 Statutory Health and Safety Committees	39
3.20.2 Non-statutory health and safety committees	40
3.20.3 Agenda	40
3.20.4 Minutes and action items for all health and safety committee meetings	42
3.20.5 Tool box talks / Daily team talks / pre job meetings	42
3.21 SHE Training	43
3.21.1 Induction training	43
3.21.2 Site specific induction training	43
3.21.3 Visitors to site induction	44

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

3.22 Contractor Site Establishment	44
3.22.1 Site roads	45
3.22.2 Construction vehicle safety	45
3.23 Housekeeping and Order	46
3.23.1 Stacking	46
3.24 Workplace Signage and Colour Coding	47
3.25 Tools and Equipment	47
3.25.1 Hand tools	48
3.26 Ladders	49
3.27 Scaffolding	49
3.28 Auditing	50
3.28.1 Approval and compliance of principal contractor SHE plan	50
3.28.2 Eskom SHE audits	50
3.28.3 Contractor audits	50
3.29 Smoking	51
3.30 Cellular Phones	51
3.31 Occupational Health, Hygiene and Rehabilitation	51
3.31.1 Medicals	51
3.32 Working at Heights	52
3.32.1 General Requirements	52
3.33 Risk Assessments	53
3.34 Safe Work Procedures and Practices / Safe Operating	53
3.35 Personal Protective Equipment Requirements	54
3.36 Incident Investigation	54
3.37 Emergency Management	59
3.38 Non-Conformance and Compliance	56

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

3.39 SHE File	57
3.40 Work Stoppage	58
3.41 Hours of Work	58
3.41.1 Normal work	58
3.41.2 Night work	59
3.41.3 Overtime	59
3.42 Omissions from Safety and Health Requirements Specification	59
3.43 Contract Sign-Off	59
3.44 Project Statistics	60
3.45 Weather Extremes	60
3.46 Dismantling, Assembly and Erecting of Structures	60
3.47 Excavation Work	62
3.48 COVID-19 Requirements	65
3.49 Working near or crossing National, Provincial or local roads	68
3.50 Existing Infrastructure and Services	68
3.51 Working in close proximity to large bodies of water	68
3.52 Asbestos Work (or Working in a naturally occurring Asbestos area)	68
3.53 Vegetation Management	68
3.53 Live Work	68
3.53 Security Management	68
3.53 Access to Farms and Rural areas, Private property, Public and Governmental la	and 68
3.53 Hazardous substances	68
3.53 Working in close proximity to Live apparatus	68
3.53 Routine On Job/ Task Observations	68

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

4.	Acceptance	74
5.	Revisions	74
3.	Annexures	75
	6.1 Annexure 1 – Flash Report Template	75
	6.2 Annexure 2 – Technical Instruction for Transportation of Personnel	78
	6.3 Annexure 3 – Training Needs Analysis/ Matrix	79
	6.5 Annexure 4 – Site Specific Evaluation Template	81
	6.6 Annexure 5 – 37(2) Agreement Template	99
	6.7 Annexure 6 – CR5(1)(K) Appointment Template	102
	6.8 Annexure 7 – Acknowledgement Form for OHS, Legal and other requirements	104
	6.9 Annexure 8 – Behavioural Observation Form	106
	6.10 Annexure 9 – Annexure D OHS KPI SHE Post-contract Reviews	107
	6.11 Annexure 10 – Task Observation Form	113
	6.12 Annexure 11 – Contractor SHE File Hand Back Record	117
	6.13 Annexure 12 – OHS Tender Evaluation Template	120
	6.14 Annexure 13 – On job observation template	120
	6.15 Annexure 14 – Working at heights on job observation template	120
	6.16 Annexure 15 – Costing for OHS	120
	6 16 Annexure 15 – Live Work On Joh Observation Form	120

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

1. Introduction

Eskom's responsibility and commitment is to ensure a safe working environment is in line with its Safety, Health, Environmental and Quality Policy, along with legislative obligations.

This SHE specification is Eskom the minimum requirements which are required to be met for the specific contract and for the duration of the contract period by contractors and where required, the delivery organisation.

The contractor is expected to develop a SHE plan which meets these requirements as well as all the relevant applicable legislation they conform to.

Eskom in no way assumes the contractor's legal responsibilities. The contractor is and remains accountable for the quality and the execution of his/her health and safety programme for his/her employees and appointed contractor employees.

This SHE specification reflects minimum requirements and should not be construed as all encompassing.

Note 1: All the requirements listed hereunder are in relation to the contract and do not supersede or replace any organizational SHE requirements.

Where requirements listed are already in place, then the organisational requirements must be taken cognisance of and listed in the respective SHE plans. If there are any additional Eskom and or legislative requirements listed in the SHE specification, then these must be addressed.

2. Supporting Clauses

2.1 Scope

This SHE specification lists the legislative and Eskom requirements and where applicable, any requirements pertaining to Local Authorities / Municipal by-laws / Environmental legislation that must be met by the contractor.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023	•	
Review Date	April 2024		

2.1.1 Purpose

This document will provide a standardised approach to the compilation of SHE specifications throughout Eskom for contracts, standards and NEC 3 contracts.

2.1.2 Applicability

This SHE specification is applicable to any contracting organisation who intends tendering for the contract.

2.2 Normative/Informative References

Parties using this document shall apply the most recent edition of the documents listed in the following paragraphs.

2.2.1 Normative (Add all relevant references applicable to Project for example legislative and other requirements)

- [1] Basic Conditions of Employment Act No 75 of 1997.
- [2] Occupational Health and Safety Act and Regulations No 85 of 1993.
- [3] National Environmental Management Act 107 of 1998.
- [4] National Road Traffic Act 93 of 1996.
- [5] 32-37 Eskom Substance Abuse Procedure.
- [6] 32-136 Contractor Health and Safety Requirements
- [7] 240-62196227 Life- saving Rules
- [8] 32-95 Environmental, Occupational Health and Safety Incident Management Procedure
- [9] 32-727 SHEQ Policy
- [10] 32-418 Working at Heights Procedure
- [11] 240-62946386 Vehicle and Driver Safety Management Procedure
- [12] 32-520 Risk Assessment procedure
- [13] Plant Safety Regulations.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Templa Identifi		240-73416879	Rev	2
Documen Identifier	t	High/Constr 1	Rev	1
Effective	Date	April 2023		
Review Da	ate	April 2024		

- [14] Code of Practice: Managing exposure to SARS-COV-2 in the workplace, 2022 Published in GG46596, on 24 June 2022, GNR 2191.
- [15] Any other related Legal and other requirements

2.2.2 Informative

- [1] Tobacco Products Control Act 83 of 1993 (Updated 2011.05.19)
- [2] SANS 1186 Symbolic Safety Signs
- [3] Constitution of the Republic of South Africa No 108 of 1996
- [4] DMN 34-110 Operating A Vehicle Mounted Crane
- [5] DMN 34-1981 Excavations.
- [6] Any other related Legal and other requirements

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

2.3 Definitions

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Definition	Explanation
Appointed contractor	Means a contractor appointed by the principal contractor
Baseline risk assessment	(32-520) baseline operational risks refer to the health and safety risks associated with all standard processes and routine activities in the business
Business unit (BU)	(32-296) means any defined unit within the Eskom environment, operating as a business under a particular cost-centre number. In the context of this document and in terms of health and safety, any reference to a BU includes a defined unit within any Eskom division and its subsidiaries
Client	(OHS Act) Eskom representative (Internal – Asset Owner), also referred to as the contract administrator/custodian or agent or project manager (as defined in the contract). He/she is the person responsible for ensuring that the works or services are executed in terms of the contract, as well as adherence to legislation pertaining to the contract.
Competent person	(OHS Act) means any person having the knowledge, training, experience, and qualifications, specific to the work or task being performed, provided that, where appropriate, qualifications and training are registered in terms of the South African Qualifications Authority Act, 1995 (Act No. 58 of 1995)
Contractor	(OHS Act) means an employer as defined in section 1 of the Act who performs contracted work and includes principal contractors
Construction work	Any work in connection with
	a. the construction, erection, alteration, renovation, repair, demolition or dismantling of or addition to a building or any similar structure.
	b. the construction, erection, maintenance, demolition or dismantling of any bridge, dam, canal, road, railway, runway, sewer or water reticulation system or the moving of earth, clearing of land, the making of excavation, piling or any similar civil engineering structure or type of work.
Consultant	means a person providing professional advice
Controlled disclosure	controlled disclosure to external parties (either enforced by law or discretionary)
Duty of care to the environment	(32-136) anybody who causes or has caused or may cause significant pollution or degradation of the environment must take reasonable measures to prevent such pollution or degradation from occurring, continuing, or recurring. If such harm to the environment is authorised by law or cannot reasonably be avoided or stopped, such person must minimise and rectify such pollution or degradation of the environment

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Definition	Explanation
Employee	(OHS Act) means, subject to the provisions of subsection (2), any person who is employed by or works for an employer and who receives or is entitled to receive any remuneration or who works under the direction or supervision of an employer or any other person
Employer	(OHS Act) means, subject to the provisions of subsection (2), any person who employs or provides work for any person and remunerates that person or expressly or tacitly undertakes to remunerate him/her, but excludes a TES (ex labour broker) as defined in section 1(1) of the Labour Relations Act 1956 (Act No. 28 of 1956)
Environment	 (32-94) means: a. the land, water, and atmosphere of the earth; b. micro-organisms and plant and animal life; and c. any part or combination of (a) and (b) and the interrelationships among and between them, and the physical, chemical, aesthetic, and cultural properties and conditions of the foregoing that influence human health and well-being
Environmental Management plan	A detailed plan of action prepared to ensure that recommendations for enhancing or ensuring positive impacts and limiting or preventing negative environmental impacts are implemented during the life-cycle of a project. This Environmental Management Plan should preferable form part of Eskom's Environmental Management System
Eskom requirements	Eskom requirements flowing from directives, policies, standards, procedures, specifications, work instructions, guidelines, or manuals
Fall protection plan	(OHS Act) means a documented plan of all risks relating to working from an elevated position, considering the nature of work undertaken, and setting out the procedures and methods to be applied in order to eliminate the risk
Hazard	(OHS Act) means a source of, or exposure to, danger
Hazard identification	(OHS Act) means the identification and documenting of existing or expected hazards to the health and safety of persons, which are normally associated with the type of construction work being executed or to be executed
Health and safety file	(OHS Act) means a file or other record in permanent form, containing the information required in relation to the contract.
Health and safety plan	(OHS Act) means a document plan that addresses hazards identified and includes safe work procedures to mitigate, reduce, or control hazards identified

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Definition	Explanation
Health and safety specification	(OHS Act) means a document specification of all health and safety requirements pertaining to associated to a contract, so as to ensure the health and safety of persons.
Health and safety requirements	means comprehensive health and safety requirements for a contract, project, site, and scope of work. This specification is intended to ensure the health and safety of persons, both workers and the public, and the duty of care to the environment. The health and safety requirements must be specific to each contract, project, site, and scope of work
Lifesaving Rules	(240-62196227) a rule that, if not adhered to, has the potential to cause serious harm to people
Medical Certificate of fitness	(OHS Act) means a certificate valid for one year, issued by an occupational health practitioner, issued in terms of the regulations, whom shall be registered with the Health Professions Council of South Africa
Medical surveillance	(OHS Act) means a planned programme or periodic examination (which may include clinical examinations, biological monitoring, or medical tests) of employees by an occupational health practitioner or, in prescribed cases, by an occupational medicine practitioner
Method statement	(OHS Act) means a written document detailing the key activities to be performed in order to reduce, as reasonably as practicable, the hazards identified in any risk assessment
Organisation	may be defined as a group of individuals (large of small) that is cooperating under the direction of executive leadership in accomplishment of certain common objects
Pre-job meetings	(34-227) means a meeting that is held prior to the commencement of the day's work and that is attended by all the relevant employees associated with the work task
Principal contractor	(In the text of this document) Means an employer, as defined in section 1 of the OHS Act, who intends to tender for or has signed a contract with Eskom for services rendered.
Provincial director	(OHS Act) means the provincial director as defined in Regulation 1 of the General Administrative Regulations under the Act
Responsible Manager	Is a Manager of a department, section or operating/business unit who has been appointed as part of the Eskom delegation of authority process with the aim to assist the applicable 16(2) assigned person in executing his/her duties in terms of the Occupational Health and Safety Act

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Definition	Explanation
Risk assessment	(OHS Act) means a programme to determine any risk associated with any hazard at a construction site in order to identify the steps needed to be taken to remove, reduce, or control such hazard.
Site	(34-228) means an Eskom department, unit, complex, building, specific project, work site, or the site where agents, clients, principal contractors, contractors, suppliers, vendors, and service providers provide a service to Eskom, directly or indirectly
Service provider	any private person or legal entity that provides any service(s) to Eskom for compensation
Subsidiary	(32-94) an enterprise controlled by another (called the parent) through the ownership of greater than 50% of its voting stock
Supplier	(32-1034)means a natural or legal person who renders a service and may include the following current or potential supplier vendor, contractor, consultant
Task	(34-227) a segment of work that requires a set of specific and distinct actions for its completion
Toolbox talks	(34-227) where the team leader, after conducting pre-task planning, shares all the tasks at hand and discusses task allocation, the identified risks, and the control measures with all his/her team members on site before commencing a specific task and documenting the agreed strategy. (This shall be done to ensure common understanding of the tasks, risks, and control measures required.)
The Act	(OHS Act) means the Occupational Health and Safety Act No. 85 of 1993, as amended, and the Regulations thereto
Visitor	any person visiting a workplace with the knowledge of, or under the supervision of, an employer.

2.4 Abbreviations

Abbreviation	Description
AIA	Approved Inspection Authority
BU	Business Unit
CE	Chief Executive
CNC	(Eskom) Customer Network Centre

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Abbreviation	Description
AIA	Approved Inspection Authority
BU	Business Unit
CE	Chief Executive
CR	Construction Regulations of the OHS Act
COID Act	Compensation for Occupational Injuries and Diseases Act
DMR	Driven Machinery Regulations
DoEL	Department of Labour (Inspection and Enforcement services – Provincial office)
EAP	Employee Assistance Program
EP	Emergency Preparedness
ERfW	Environmental Regulations for Workplaces
GAR	General Administrative Regulations
GSR	General Safety Regulations
HCS	Hazardous Chemical Substances
LDV	Light Delivery Vehicle
LoG	(COID) Letter of Good Standing
SDS	Safety Data Sheets
NEMA	National Environmental Management Act
OHS Act	Occupational Health and Safety Act and Regulations, 85 of 1993
SACPCMP	South African Council for the Project & Construction Management Professions
SABS	South African Bureau Standard
SANS	South African National Standard

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

2.5 Roles and Responsibilities

2.5.1 Commitment

Visible commitment is essential to providing a safe work environment. Managers, supervisors and employees at all levels must demonstrate their commitment by being proactively involved in the day to day operations, in particular the Occupational Health and Safety aspects of any project / contract. Legislation requires that each employee must take reasonable care of themselves and their fellow workers, from management level down to the lowest employee level.

2.5.2 Principal contractors and appointed contractors

Note 1: Most of the roles and responsibilities listed apply to both principal contractors and any appointed contractors. Where some of the listed do not apply to both, then the specific responsibilities will be listed and titled. The contractors shall:

- 1. Carry out all duties as listed in section 8, 9 and 10, the various other regulations that form part of the OHS Act and Regulation 7 of the Construction Regulations.
- The principal contractor must notify the provincial director of the Department of Labour in writing of all construction work if it falls within the scope of Regulation 4of the Construction Regulations (if this has not been arranged and or done by the client/agent);
- 3. Carry accountability and responsibility for the safety and health of their employees and their appointed contractors within their working area, as contemplated by section 37(2) of the OHS Act;
- 4. Shall keep a record of all employees including the appointed contractor employees, including date of induction, relevant skills and licenses and be able to produce this list at the request of the Eskom Project Manager.
- 5. Ensure that all their appointees are made aware of their accountabilities and responsibilities in terms of their appointment and that they advise and assist these appointees in the execution of their duties.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 6. Ensure that the minimum legislative, regulatory and Eskom SHE requirements are complied with on all work sites.
- 7. Give the Eskom project managers and line managers / responsible managers their full participation and cooperation.
- 8. Compile a SHE (health and safety) file where all relevant health and safety records must be kept for each work site.
- 9. The principal contractor must hand over a consolidated (to include any appointed contractors files) health and safety file to the Eskom project manager on completion of the project. This is to include all drawings, designs, lists of materials used and other applicable information about the completed project, as well as the list of appointed contractors, the agreement, and the type of work completed.
- 10. Contractors must hand over a consolidated (to include any appointed contractors files) health and safety file to the principal contractor on completion of the project. This is to include all drawings, designs, lists of materials used and other applicable information about the completed project, as well as the list of appointed contractors, the agreement, and the type of work completed.
- 11. The principal contractor must provide the project manager with a certified copy of his/her Compensation Commissioner's valid letter of good standing before the commencement of work and any future renewal letters obtained during the project for record-keeping purposes. The letter of good standing shall reflect the name of the contractor's company. Similarly, the principal contractor must provide the Eskom project manager with all the valid letters of good standing from their appointed contractors.
- 12. Contractors must provide the principal contractor with a certified copy of his/her Compensation Commissioner's valid letter of good standing before the commencement of work and any future renewal letters obtained during the project for record-keeping purposes. The letter of good standing shall reflect the name of the contractor's company.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 13. Appoint competent staff to perform the project work and ensure that all employees are trained in the health and safety aspects relating to such work and that the employees understand the hazards associated with all other work being carried out on the project.
- 14. Ensure that all employees are conversant with all relevant work procedures and that they adhere to such procedures. Similarly (without removing the appointed contractors' responsibilities), ensure that their appointed contractors and their employees are conversant with all relevant work procedures and that they adhere to such procedures.
- 15. Co-ordinate the activities of all the appointed contractors in the interests of safety and health;
- 16. Ensure that potential contractors (whom they intend appointing) submitting tenders have made detailed provision for the cost of safety and health measures throughout the project.
- 17. Stop his /her employees and any appointed contractors if project work is not in accordance with the health and safety plan or if such work poses a threat to the health and safety of persons or a risk of degradation to the environment.
- 18. Take reasonable steps to ensure cooperation between all their appointed contractors.
- 19. Only appoint contractors to do work, if satisfied that the contractor has the necessary competencies and resources to perform the work safely.
- 20. Appoint full-time competent employees in writing to supervise the performance of all specified work throughout the contract period.
- **Note 2:** No work may commence and or continue without the presence of the appointed project manager or project supervisor during performance of the contracted work.
 - 21. Ensure that the supervisor or manager do not supervise work on any site other than the site for which such supervisor has been appointed for.
- **Note 3**: In determining the number of appointed competent supervisors, the nature and scope of work being performed, shall be taken into consideration.
- **Note 4**: If a sufficient number of competent employee(s) have been appointed to assist the construction supervisor, the construction supervisor may supervise more than one site.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 22. Appoint a full time safety officer or construction safety officer (registered with SACPCMP) in writing.
- 23. Not victimise or dismiss employees, by virtue of the employees divulging health and safety information or suspecting such information has been divulged, in the interests of health and safety requirements;
- 24. Follow a process of disciplinary action if any of their employees or their appointed contractor employees have transgressed any of the requirements of the health and safety specification, safety and health plans, site rules or any other requirements.
- 25. Ensure that all appropriate precautions are taken to protect persons (visitors, members of the public, and other contractors) present at work or in the vicinity of a construction site against all risks that may arise from such site.
- 26. Before the commencement of any work, conduct risk assessments which shall include public safety. This should be done by a competent person appointed in writing with a view to identify hazardous and potentially hazardous work operations.
- 27. Ensure that pre-task risk assessments are conducted and documented daily and prior to the starting of any new task, irrespective of whether it is a repetitive task or not.
- 28. Take prime responsibility for all aspects of environmental management associated with the project activity for which they are responsible.
- 29. Provide any appointed contractor who is making a bid or is appointed to perform work on Eskom's behalf, with the relevant sections of the documented Eskom's SHE Specification.
- 30. Principal contractors are required to approve appointed contractor's health and safety plans if they meet all the requirements.
- 31. Must ensure that an organisation medical surveillance programme for the duration of the contract is in place and maintained.
- 32. Prior to having pre-employment and periodic medicals fitness examinations conducted, person/man job specifications must be compiled and handed to the occupational health practitioner.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 33. Ensure that pre-employment, periodic and exit medicals are carried out on their employees. Medical assessments must be conducted by a registered Occupational Health Practitioner. During the pre-employment medical, where employees will be required to work at heights, they will also be required to undergo the required employee physical and psychological fitness examinations.
- 34. Ensure, prior to the commencement of construction work, that all persons involved in the project work, as well as the appointed contractors, have received a health and safety induction training session. Similarly, ensure that all visitors to site undergo the site's induction training.
- 35. Ensure, prior to the commencement of construction work or contracted work, that all their employees involved in the project work, as well as the appointed contractors, have received task-specific training.
- 36. Issue risk-based personal protective equipment (PPE) as a measure of last resort to their employees, inspect such equipment regularly and ensure recipients of PPE are trained in the proper use, care and where necessary, the maintenance of PPE;

Note 5: should the principal contractor or his/her appointed contractors entertain visitors on site, they will be held responsible for the provision and wearing PPE.

- 37. Erect their own site huts, temporary buildings, storage areas, toilets, fencing, and any other structure as may be required. Any such structures shall be positioned and erected in compliance with any instructions from the Eskom project manager and the relevant site safety and fire prevention requirements;
- 38. On completion of the work remove all structures erected by them, and where required by law rehabilitate the environment.
- 39. Where performing work with the environment, ensure that minimal damage is done and that where an Environment Management Plan is in place, then adhere to the plan.
- 40. Respect the rights of land owners/lessors and the preservation of their registered activities;
- 41. Must have a substance abuse program which must be in line with the requirements of the OHS Act.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

42. Ensure that no alcohol or other intoxicating substances are brought on to, or remains on the work sites.

Note 6: Eskom will not tolerate the presence of anyone who is or who appears to be under the influence of alcohol or any other intoxicating substance whilst performing work for them or on any work site.

- 43. Ensure that all equipment and tools used comply with OHS Act requirements with respect to condition, use, care, storage, maintenance, and the management of these;
- 44. Ensure that all incidents are reported and investigated timeously by competent incident investigators.
- 45. Be involved in all of their appointed contractor's investigations.
- 46. Establish health and safety committees, hold such committee meetings on all sites, and ensure that appointed contractors participate in their health and safety meetings.
- 47. Chair their own health and safety committee meetings and record such meetings.
- 48. Appoint sufficient number of health and safety representatives in terms of legislative requirements and ensure that the appointed contractors appoint health and safety representatives for their work sites.
- 49. When appointing contractors, advise the project manager in writing timeously and obtain his/her approval prior to them commencing work.
- 50. Shall keep a record of all employees including the appointed contractor's employees, including date of induction, relevant skills and licenses and be able to produce this list at the request of the Eskom Project Manager.

2.5.3 Construction/ Site/ Project Managers/ Contract Managers

Note 1: No work may commence and or continue without the appointed supervisor or manager during the performance of the contracted work.

1. Not supervise construction work on any construction site other than the site they have been appointed to supervise;

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 2. Assist the contractor and/or the appointed safety officer in conducting site induction training for new staff and site visitors;
- 3. Instruct and train all employees under their control on any hazardous and related work procedures, before any work commences and thereafter, at such times as may be determined by a risk assessment;
- 4. Ensure that the minimum legislative and Eskom SHE requirements are complied with on all work sites:
- 5. Stop any construction work that is not in accordance with the safety and health plan or if such work poses a threat to the safety and health of persons or a risk of degradation to the environment;
- 6. Ensure that risk-based personal protective equipment (PPE) has been issued and employees wear/use the PPE as instructed.
- 7. Inspect such PPE on a regular basis and record the inspections;
- 8. Ensure that all incidents are reported to the client and are investigated.
- 9. Be involved in all investigations that occur within their area of responsibility.
- 10. Carry out audits and or inspections on their contractors at least monthly and any appointed contractors on instructions of their contractor.
- 11. Ensure that employees under their control are conversant with all relevant work procedures and that they adhere to such procedures;
- 12. Before the commencement of any work, where possible, assist in the conducting of risk assessments and ensure that appropriate mitigating measures have been considered and implemented.;
- 13. Ensure that daily or pre-task risk assessments are conducted and documented daily and prior to the starting of any new task, irrespective of whether it is a repetitive task. Ensure that the team are involved in the abovementioned risk assessments;
- 14. Hold tool box talks at the start of each day/ task to discuss health and safety issues as well as confirming the requirements of the daily risk assessments;
- 15. Ensure that all appropriate precautions are taken to protect persons (visitors, members of the public, and other contractors) present at work or in the vicinity of a construction site against all risks that may arise from such site.
- 16. Ensure that no alcohol or other intoxicating substances are brought on to, or remains on, the premises / work sites and that no employee remains on site if he/she is under the influence. Furthermore, report such instances to contract management;
- 17. Ensure that all equipment and tools used on site comply with OHS Act requirements with respect to condition, use, care, storage, maintenance, and the management of these.
- 18. Ensure that they and their contractor managers give clear and unambiguous instructions for the project work, to the employees for whom they are responsible for.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 19. Not victimise their employees by virtue of their employees divulging health and safety information or suspecting such information has been divulged, in the interests of health and safety requirements (reference section 26 of the OHS Act).
- 20. Where any work is performed which involves the environment, ensure that minimal damage is done to the environment and that where an Environment Management Plan is in place, then the plan adhere to the plan.
- 21. Stop any employee or contractor from performing construction work which is not in accordance with the principal contractor's and or appointed contractors health and safety plan which poses a threat to the health and safety of persons.

2.5.4 Contractor site supervisor or Contract Supervisor

Must:

- 1. Be competent to perform the required supervisory tasks;
- 2. Ensure their employees and all appointed contractors comply with the required statutory and Eskom project requirements;
- 3. Inspect all work done by the Contractors to ensure adherence to Eskom's standards and specifications
- 4. Conduct follow-up inspections to ensure findings are closed out and preventative action is in place.
- 5. Monitor contractors for adhere to statutory requirements and safety standards.
- 6. Monitor contractors overall SHE performance on site in order to achieve excellent
- 7. Ensuring a Safe working environment is established and maintained by the contractor for the elimination of unsafe acts by all people whilst on the project site.
- 8. Discuss all SHE related problems with the relevant contractor management timeously in the first instance and thereafter the Eskom project manager in the second instance relating to procedure requirements, non-conformance's identified, corrective actions, audits and inspection schedules.
- 9. Ensuring that quality records are maintained in accordance with legislative and Eskom requirements;
- 10. Continual liaison between the principal contractor, appointed contractors and employees.
- 11. Ensures that employees and appointed contractors are aware of latest standards, procedures, work instructions and safety regulations issued by Eskom:

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 12. Conduct site Inspections for compliance to SHE requirements and compiles the relevant inspection reports.
- 13. Submit the observation reports to the relevant management.
- 14. Have meaningful participation in the project statutory health and safety committee meetings.
- 15. Participate in all appointed contractor incident investigations.
- 16. Participate in the principal contractors emergency preparedness planning.
- 17. Ensure that their own employees and those of any appointed contractor are competent to perform the tasks assigned.
- 18. Issue site instructions on behalf of the principal contractor where and when the appointed contractors deviate from safety requirements.
- 19. Assist the principal contractor with the handing over process, in particular the SHE file and relevant documentation.

2.5.5 Employees

Must:

- 1. Be responsible for their own safety and health and that of their co-workers;
- 2. Co-operate with their employer to meet all of the employer's as well as legislative and Eskom requirements;
- 3. Familiarise themselves with their responsibilities during induction and awareness training sessions, some of which are:
 - a. familiarising themselves with their workplaces and safety and health procedures;
 - b. working in a manner that does not endanger them or cause harm to others;
 - c. ensuring that the work area is kept tidy;
 - d. reporting all incidents and near misses;
 - e. protecting fellow workers against injury by performing job observations;
 - f. reporting unsafe acts and unsafe conditions;
 - g. reporting any situation that may become dangerous; and
 - h. carrying out lawful orders and obeying safety and health rules;
- 4. Who become aware of any person disregarding a safety notice, instruction, or regulation, immediately report this to the person concerned. If the person persists, stop that person from working, and report the matter to contractor management and/or Eskom's project manager or supervisor immediately.
- 5. Not damage, alter, remove, render ineffective, or interfere with anything that has been provided for the protection of the site or for the health and safety of persons this includes any guarding of machinery or equipment.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879 Rev	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 6. Obey any safety signs and adhere to any site demarcation at all times.
- 7. When entering or leaving the site, do so via the official designated access/departure routes. Where reflective jackets/bibs are required to be worn, wear them.
- 8. Be subjected to any disciplinary action, if having transgressed any of the requirements of the health and safety site rules, Eskom requirements, company requirements, or legislative requirements.
- 9. Avoid any act that may endanger their own health and safety or that of fellow employees, members of the public, or visitors who may be affected by their acts and/or omissions at work.
- 10. Have the right to obtain proper information from their employer regarding health and safety risks and measures related to the work processes.
- 11. Use facilities placed at their disposal and not misuse anything provided for their own protection or that of others.
- 12. Have the right to remove themselves from danger when they have good reason to believe that there is an imminent and serious danger to their health and safety and have the duty to inform their supervisor immediately of such danger.
- 13. Report to their supervisor (in the first instance), the principal contractor (in the second instance), and/or the Eskom project manager, any substandard acts and/or conditions that have come to their attention and that have not been rectified or acted on by their contractor management timeously.
- 14. Have the right and the duty at any workplace to participate in ensuring healthy and safe working conditions, to the extent of their control, over the equipment and methods of work adopted.
- 15. Maintain the surrounding area of the work site in a neat and tidy condition.
- 16. Have meaningful participation in regular health and safety meetings.
- 17. Have the right to refuse to perform or continue to perform any task/job on the grounds of health, safety, and environmental concerns.
- 18. When given instructions, understand the instructions and be permitted to clarify those instructions.

2.5.6 Contractor/ Construction Health and Safety officer (Full time SACPCMP accredited)

- 1. Promote a SHE culture within the organisations involved in the project / contract.
- 2. The contractor's safety and health officer shall assist in the control of all health and safety-related matters on the sites.
- 3. Be involved in the developing the project SHE plan and SHE policy.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879 Re	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 4. Be in constant liaison and cooperate with Eskom's SHE professionals responsible for providing them with a health and safety service.
- 5. Ensure that this SHE specification is adhered to by his/her principal contractor and is submitted to any appointed contractors.
- 6. Conduct audits and inspections of all work sites for the duration of the project.
- 7. Be involved in the organisations incident investigations when required.
- 8. Participate in the organisation's statutory and non-statutory health and safety committees meetings.
- 9. Conduct organisational, site and visitor induction training.
- 10. Stop any employee or contractor from performing construction work which is not in accordance with the principal contractor's and or appointed contractors health and safety plan which poses a threat to the health and safety of persons.
- 11. Ensure that no alcohol or other intoxicating substances are brought on to, or remains on, the premises / work sites and that no employee remains on site if he/she is under the influence. Furthermore, report such instances to contract management.
- 12. Make themselves available and ensure co-operation of employees under their control to undergo breathalyser and drug testing while entering and/or being on any Eskom work site by Eskom.
- 13. Carry out audits and or inspections on their contractors at least monthly and any appointed contractors on instructions of their contractor;
- 14. Carry out frequent behaviour observations of employees under their control at least monthly and any appointed contractors on instructions of their contractor.

2.6 Related/Supporting Documents

Eskom OHS Act section 37 (2) agreement to be signed at procurement during the signing of the NEC contract, it is the responsibility of the project manager to ensure that the 37(2) agreement is signed and a copy be kept in the contractor file at procurement.

3. Specification

3.1 Scope of work

External Work

Prepare ground , supply and install interlocking paving include (include river sand and plasting sheeting)

Construction of 14 steel carports with IBR roof including bases n labour see attached drawings

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Supply and install outdoor big blue water purification (5stages) Reverse osmosis filter with digital display

Trench excavation to accommodate electrical work and plumbing work trench not exceeding 1m deep but 200 width

Construction of steel PWD ramp and nutec IBR canopy at the main entrances, 1,5m width x 4,5m length 2,5 height labour inclusive

Demolish inside walls to create space (height 3m)

Construct new dry wall for toilets 6mX3m (two toilet cubicles) height 3m price includes labour and material

Supply prepare and seal and paint 1 coat roof with Eskom approved roof paint specifications supply paint and paint 2 coats on external walls with Eskom approved paint specifications Supply and installation of pwd female toilet (complete set).

Supply and installation of pwd male toilet complete set

Supply and installation of male toilet

Supply and installation of wooden doors and paint

Supply and installation of wash basin

Supply and install new aluminium sliding doors 2,5m

Supply and installation of interlocking rubber mats at the storage park home

Remove old laminated flooring and prepare floors

Supply and install Laminated flooring

Supply and install new window blinds (group E) classic blue

Repair existing kitchen unit doors and paint

Supply aluminium and install 2m one side sliding doors 2x2 including labour including

Demolish existing walls to be open plan design at the training centre park home

Supply and install new 150l kwik hot geyser class b labour inclusive

AIRCONDITIONING

Supply and Install new 14000 BTU Aircon, carrier

Supply and install new 12000 BTU Air conditioners carrier

Supply and install 24000btu aircons carrier

Electrical Work

Supply and Install outside lights, with daylight switch and at the parking area (industrial type), LED 500watts, size =60000 lm

Supply 3(25 mm)core cables and connect power cable from main DB to Park homes main DB BOX doule the length

Re -wiring of 2,5 mm ,1,5 mm cables and replacement all components and installation of led fluorescent light fittings and bulps light sensors (1200x600mm) recessed parbolic light Supply and Install new led lights and fittings , cool white (1200x600mm)

Test, Inspect installation, fix exiting faults and supply With CoC

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		·

Supply and Install new led lights and fittings, cool white (1200x600mm)

Test, Inspect installation, fix exiting faults and supply With CoC

all electrical accessories

supply and install projector screen (2650x1490)

Install new skirting /trunking for power sockets with 40 sockets

Construction of 30 000L septic tank, provision of a bore hole drilling

Remove rubble from site and supply dumping site certificate

A copy of the scope of works must be retained by the contractor.

Note: The contractor who will be awarded this contract will be known as the "principal contractor" and any contractor appointed by the principal contractor will be known as the "appointed contractor.

3.2 Legal Compliance

3.2.1 Section 37(2) (Legal) Agreement

A section 37(2) agreement must be signed between Eskom and the principal contractor at the time of awarding the contract. The principal contractor must ensure that a section 37(2) agreement is compiled between the principal contractor and all their appointed contractors for the contract.

The original copy of the section 37(2) Agreement must be retained by the contractor and a copy retained by the responsible project manager.

A copy of all the agreements must form part of the respective contractor's SHE file.

3.2.2 Hazardous work by children (Child Labour)

The constitution of the Republic of South Africa, in the "Bill of Rights" is clear on the rights of children, especially when it comes to:

- 1. being protected from exploitative labour practices;
- 2. not to be required or permitted to perform work or provide services that

i.are inappropriate for a person of that child's age; or

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

ii.place at risk the child's well-being, education, physical or mental health or spiritual, moral or social development;

and the Basic Conditions of Employment Act, Chapter six Section 43 "Prohibition of employment of children".

Before resorting to the use of child labour, due consideration must be given to the rights of the child in terms of the constitution. Where work is being performed which is not prohibited in terms of the constitution, then such work must be conducted in terms of the OHS Act "Regulations on Hazardous Work by Children in South Africa" with emphasis on paragraph 2 Purpose and Interpretation. Eskom does not condone the use of child labour and therefore all effort must be exercised and child labour should not be used.

3.2.3 OHS Act

The principal contractor and appointed contractors shall have an up to date copy of the OHS Act and regulations which will be available to all employees.

3.2.4 Legislative compliance

All contractors will comply with all the legislation pertaining to this contract being:

The principal contractor and all appointed contractors will comply with all the legislation pertaining to this project being:

- The Constitution of the Republic of South Africa (particularly Section 24 of the Bill of Rights).
- Occupational Health and Safety Act 1993 (Act 85 of 1993) and its Regulations.
- National Environmental Management Act 1998 (Act 107 of 1998).
- Environment Conservation Act 1989 (Act 73 of 1989).
- National Water Act 1998 (Act 36 of 1998).
- Civil and Building Work Act.
- National Road Traffic Act 93 of 1996.
- Compensation for Occupational Injures and Diseases Act.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879 Rev	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

• SANS Standards -Contractor shall use the relative standards applicable to the project.

3.3 Eskom Requirements

All contractors shall, before commencement of the project ensure that all their employees are familiar with the relevant Eskom SHE documentation that is applicable to contract services.

3.4 Construction Professional Registration (Awaiting clarity on SACPCMP registration for CR8 (1)

The principal contractor and all his/her appointed contractors shall be registered in their respective levels as professionals in terms of the requirements of the SACPCMP.

The SACPCMP web address is http://www.sacpcmp.org.za

- SHE professionals (which include Construction Safety Officers) are required to register as professionals with the SACPCMP.
- Construction Managers are required to register as professionals with the SACPCMP.
- Construction agents are required to register as a professional with the SACPCMP.

3.5 Notification of Construction Work (only on Construction Work Projects)

Unless otherwise contractually agreed upon, the principal contractor must notify the relevant provincial director of the Department of Labour of the intention of carrying out any construction work as defined in Construction Regulation 4 of the Act. The notification form of construction work is listed as an annexure to the construction regulations of the OHS Act. A copy of the notification letter sent to the DoEL shall be forwarded to the Project Manager on the same day as sent to the DoEL. A copy of the letter and their approval must be kept in the SHE file. When the DoEL provide a letter of approval, a copy of the approval must be sent to the Eskom Project Manager and a copy filed in the SHE file.

3.6 SHE Policy

SHE policy is a statement of intent and a commitment by the organisation's CE and senior management in relation to the relevant SHE roles and responsibilities, the achievement of their strategic objectives, values of integrity, customer satisfaction, excellence, and innovation.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

The principal contractor and all appointed contractors, if already not in place, will be required to compile an organisational SHE policy in line with their SHE responsibilities. The policy must be signed by the organisation's CE or the appointed assistant to the CE OHS Act Section 16(2). The policy must be displayed in a prominent place within the workplace. A copy of the policy must be filed in the contractor SHE files and attached as an annexure in the SHE Plan.

3.7 COID/ FEM

The principal contractor and all his/her appointed contractors shall be registered with an appropriate employment compensation commissioner and have available a valid letter of good standing (LoG) from such commissioner. The obligation lies with the contractors to ensure that the LoG remain valid throughout the contract period. A copy of the LoG must be filed in the contractor SHE files.

The nature of business on the LoG needs to be aligned with the scope of work for the project.

3.8 Costing for SHE within the Project

The costing for SHE must be itemised based on the overall scope of the project (i.e.) Training, provision of PPE, safety equipment purchases etc.

3.9 Statutory Appointments (Only include relevant appointments as per project requirements)

For the duration of the contract, the principal contractor and all appointed contractors shall appoint competent employees who will meet the requirements of the OHS Act. Where appointments are made, contractors shall ensure that the appointees have been suitably trained and or informed of their responsibilities before getting them to accept such appointment. The relevant statutory appointments shall be made in accordance with the requirements of the OHS Act which includes the requirement of a competent person being appointed in the relevant roles. The statutory appointments should include but not limited to the following:

- OHS Act Section 16.1 Chief Executive Officer
- OHS Act Section 16.2 Assistant to the Chief Executive Officer
- OHS Act Construction Regulation 8(1) Construction Manager (Full time)

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- OHS Act Construction Regulation 8(2) Assistant Construction Manager (Full time)
- OHS Act Construction Regulation 8(7) Construction Supervisor
- OHS Act Construction Regulation 8(8) Assistant Construction Supervisor
- OHS Act Construction Regulation 8(5) Construction Health and Safety Officer
- OHS Act General Administrative Regulation 9(2) Incident Investigator
- OHS Act Section 19 (3) Health and Safety Committee Member
- OHS Act Section 19(6)(a) Co-opted Health and Safety Committee member
- OHS Act Hazardous Chemical Substances Regulation 3(3) Hazardous Chemical Substances Co-coordinator
- OHS Act, Section 17 Health and Safety Representative.
- OHS Act General Machinery Regulation 2(1) Supervision of Machinery
- OHS Act Construction Regulation 7(1)(V) Appointment of a Contractor (if appointing subcontractors)
- OHS Act Construction Regulation 9(1) Person to Compile Risk Assessments
- OHS Act Construction Regulation 10(1) Competent Person to Compile Fall Protection Plan
- OHS Act: Pressure Equipment Regulations 11 & 12 Portable Gas Container Inspector
- OHS Act: Construction Regulations 13(1) Person to Supervise Excavation Work
- OHS Act: Construction Regulations 16(1) Scaffolding Supervisor
- OHS Act: Construction Regulations 23(1)(d)(i) Construction Vehicle and Mobile Plant Operator
- OHS Act: Construction Regulations 24(c) Electrical Installations Inspector
- OHS Act: Construction Regulations 24(d) Electrical Machinery Inspector

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879 Re	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- OHS Act: Construction Regulations 28(a) Stacking and Storage Supervisor on Construction sites
- OHS Act: Construction Regulations 29(h) Firefighting Equipment Inspector
- OHS Act General Safety Regulations 3(4) First Aider/s
- OHS Act General Safety Regulations 13(a) Ladder Inspector
- OHS Act Driven Machinery Regulations 18(10)(e) Lifting Tackle Inspector
- OHS Act Construction Regulations 22(a) Supervisor of Tower Cranes
- OHS Act Construction Regulations 12(2)(a) Temporary Works Supervisor

3.9.1 Non-statutory appointments

- Eskom requirement Emergency Planning Co-coordinator
- Eskom requirement Chairperson of Health and Safety Committee

3.10 Eskom Life-saving Rules

- 1. Eskom views health and safety in high esteem and encourages that any organisation who performs work for Eskom in Eskom adopt the same view.
- 2. Five Life-saving rules have been developed that will apply to all Eskom Employees, agents, consultants, and **contractors**. Failure to adhere to these rules by any Eskom employee or employee of a Principal Contractor or appointed contractor will be considered a serious transgression. These rules are being implemented to prevent serious injury or death of any employee, labour broker or contractor working in any area within Eskom.
- 3. If any contractual work will be performed on any Eskom premises (including delivery of any product), then the rules **shall be obeyed** by any contractor and their employees.

The rules are:

RULE	DESCRIPTION OF RULE

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Rule 1	OPEN, ISOLATE, TEST, EARTH, BOND, AND/OR INSULATE BEFORE TOUCH
	(That is plant, any plant operating above 1000 V)
	HOOK UP AT HEIGHTS
	Working at height is defined as any work performed above a stable work surface or where a person puts himself/herself in a position where he/she exposes himself/herself to a fall from or into.
	BUCKLE UP
Rule 3	No person may drive any vehicle on Eskom business and/or on Eskom premises:
	Unless the driver and all passengers are wearing seat belts.
	BE SOBER
	No person is allowed to be under the influence of intoxicating liquor or drugs while on duty
	PERMIT TO WORK
	Where an authorisation limitation exists, no person shall work without the required permit to work.

Eskom will take a stance of zero tolerance on these rules.

Non-compliance to a Life Saving rule will be considered serious misconduct and will lead to serious disciplinary action, which may include dismissal.

This is to ensure that **every person** who works on or visits an Eskom **returns home safely to his or her family.**

3.11 Substance Abuse

 Alcohol and substance abuse poses a significant threat to any business, more so in industrial incidents and the driving of vehicles. Eskom is therefore, entitled to take reasonable steps to ensure that intoxicated persons are identified and prevented from entering Eskom.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023	•	
Review Date	April 2024		

- 2. General Safety Regulation 2A is clear on the legal stance regarding intoxication.
- 3. The alcohol and drug permissible level is 0%.
- 4. All contractors shall comply with Eskom's procedure 32-37 ("Substance Abuse Procedure"), taking in to account that this is an Eskom Life-saving Rule number 4: BE SOBER"), this means anyone entering the Eskom will be subjected to ad hoc alcohol testing.
- 5. Contractors are encouraged to compile their own manual and to carry out regular alcohol testing of their own employees. The legislative alcohol level is deemed to be zero
- 6. Test records must be treated as "Confidential" and filed in the employees' personal file.

3.12 Contractor organisational Structure

3.12.1 Principal Contractor Organogram and Employee list

The principal contractor must provide an organisational organogram as well as an updated employee list related to this contract/project, depicting all the levels of responsibility from the CE down to the supervisors responsible for the contract. List the relevant positions held, names of appointees and legal appointments.

The principal contractor must ensure that all appointed contractors comply with this requirement. The principal contractor is responsible for keeping copies of all the organograms' as well as submitting them with the SHE plan. All organograms shall be updated timeously when appointments are changed.

This diagram must be kept up to date and filed in the project SHE files.

3.12.2 Appointed Contractor/s Organogram

- 1. Appointed contractors are required to compile their company organogram for the project, listing the reporting structure from their CE down to their project supervisors. The diagram must list the names, positions held and any appointments made.
- 2. This diagram must be kept up to date, a copy of which must be given to the principal contractor and a copy filed in the relevant project SHE files.
- 3. This diagram must be kept up to date and filed in the project SHE files.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

3.13 Risk assessment (refer to 32-520)

It is a legal requirement in terms of Section 8 (2)(d) of the OHS Act for an employer to carry out risk assessments, to establish which risks and hazards are attached to the health and safety of persons due to any work which is performed, any article or substance which is, handled, stored, transported. A risk assessment is defined as an identification of the hazards present in an organisation and an estimate of the extent of the risks involved, taking into account whatever precautions are already being taken.

It is essentially a three stage process:

- identification of all hazards;
- evaluation of the risks;
- Measures to control the risks.

Risk assessments are required to be maintained. This means that significant changes to a process or activity, or any new process or activity should be subjected to a risk assessment and that if new hazards come to light during the work process, then these should also be subjected to risk assessments. Risk assessments for long term processes should be periodically reviewed and updated. Method statements or written safe work procedures are an effective method as information and record of the way jobs / tasks must be performed. Daily or issue based or task specific or on the job risk assessments must be conducted at the place where work is to be performed/ conducted to allow managers and employees to assess any inherent risks that could have been overlooked during the initial risk assessment or any changes that might have occurred in a period of absence. For example if a job / task is extended over a day or halted due to inclement weather.

Guidelines for actual steps involved in a job/task specific risk assessment are:

- · Each activity is listed;
- Specific hazards are identified and listed against each activity;
- The magnitude of each risk is rated as Low. Medium or High;
- All known documentary and supervisory controls are listed. For instance: What safe work procedures exist for ladders;
- The relevance, effectiveness and sufficiency of these controls are assessed;
- In the event of insufficient or deficient controls for the particular activity, steps to be taken to rectify this shall be recorded, and safe working procedures drawn up;

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- Persons responsible for implementing and supervising the task shall be identified, nominated and duly assigned;
- Persons responsible for monitoring the task and carrying out the planned job observation must be nominated;
- Completed risk assessment shall be handed to the Eskom project manager representative for comment and approval.

The relevant section of the risk assessment shall be issued with a Transmittal Note to the Supervisor nominated as the responsible person; and the names of workmen who have received instruction on the work content and the sequence of the activities listed in the risk assessment shall be recorded, and their competence established. This instruction shall be done through an interpreter if required and recorded on the Pre-Job Brief (Daily Safe Task Instructions), with reference to applicable Risk Assessments.

3.14 Safe work procedures / method statements

Method statements / written safe work procedure are control measures used to prevent an incident from occurring during the execution of the project. A written safe work procedure/ method statements provide guidance how to execute the task safely. A safe working procedure should be written when:-

- a. Designing a new job or task;
- b. Changing a job or task;
- c. Introducing new equipment or substances; and

The safe working procedure should identify:

- d. The supervisor for the task or job and the employees who will undertake the task;
- e. The tasks that are to be undertaken that pose risks;
- f. The equipment and substances that are used in these tasks;
- g. The control measures that have been built into these tasks;
- h. Any training or qualification needed to undertake the task;
- i. The personal protective equipment to be worn;
- j. Actions to be undertaken to address safety issues that may arise while undertaking the task.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

3.15 Roof work (refer to 32-418)

Where roof work is to be performed, a risk assessment must be carried out prior to climbing on to the roof to determine the hazards (stability, suitability strength etc.), consequences of climbing and control measures that are required.

3.16 Construction/ Work Sites

Note1:No area is to be stripped of vegetation to create firebreaks, to prevent or make fires. No open fires are allowed on site. The contractor must ensure that operations are in compliance with statutory requirements at all times.

- The contractor must develop a fire safety procedure for the construction site prior to commencing work. The procedure must take into consideration the size of the site/s, the type of work performed and amount of combustible materials. Cognisance of OHS Act CR 29 must be made.
- 2. It must be developed in accordance with the hot work permit of the Eskom Plant Safety Regulations, Eskom Fire Risk Management requirements and all other applicable Regulations. All workers entering and working in the construction site need to be trained in fire safety and any duties they are required to perform.
- 3. A suitable fire warning system for alerting site personnel of fire shall be provided, and capable of being heard in all areas of the site.
- 4. Appropriate portable extinguishers must be available on the construction site and in cases of hot work, be readily available at the location.
- 5. Storage of combustible and flammable liquid in the construction site is not permitted unless stored in approved flammable cabinets or outdoors away from the buildings.
- 6. Site Smoking Restrictions must be enforced. No open flames are permissible and where hot work is performed, the work areas must be cleared of any combustibles prior to commencement of work.

3.17 Fire Equipment and maintenance

- 1. All firefighting equipment's that have been provided shall:
 - a.Be clearly labelled
 - b. Conspicuously numbered
 - c. Entered in a register

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

d.Inspected monthly by a competent person

- 2. Tested and serviced at recommended intervals by an accredited supplier
- 3. Results entered in the register and signed by competent person.

3.18 Flammable and Combustible Liquids

- Proposals to store fuel on site must have written approval from the Eskom Project Manager. The volumes of fuel allowed to be stored will depend on site conditions and Statutory Regulations.
- 2. A maximum storage of 40 litres of fuel is allowed to be stored. Anything greater than 40 litres to be stored in a flammable/combustible liquid store.
- 3. Adequate numbers of dry chemical fire extinguishers, each with a minimum capacity of 4.5 kg, shall be provided, installed and maintained.
- 4. All fuel storage areas must comply with the following requirements:
 - a. Storage should be well clear of buildings.
 - b. Storage areas must be kept free from all combustible materials.
 - c. All Safety signs must be prominently displayed i.e.
 - Flammable Liquid.
 - No Smoking.
 - No open flames.
 - d. Adequate firefighting equipment must be available.
- 5. Diesel tanks are to be installed in a bunded area; bunded area must be able to contain 110% of tank capacity.
- 6. Bunded area shall be of a concrete or steel construction and lined with a leak proof sealing material.
- 7. Bunded area shall have a drain valve.
- 8. No other material/equipment shall be stored in the bunded area.

3.18.1 Refuelling at the construction/ work site

With the exception of construction vehicles and mobile equipment, before a machine is refuelled, the motor must be stopped. Refuelling shall take place at designated safe areas and appropriate warning signs installed. Suitable drip trays must be used to prevent spillage at the filling nozzle.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023	•	
Review Date	April 2024		

3.19 First Aid and Equipment

- 1. The requirements of the OHS Act GSR 3 must be observed.
- 2. First aid appointments must be made to meet the requirements, this includes construction sites. Appointees must be trained to level 2. It is good practice for all employees to be trained to at least level 1.
- 3. When appointing employees for work sites, cognisance must be taken into account the type of work performed, the distance teams are working apart and the terrain to be covered if an emergency should arise.
- 4. A list of emergency numbers must be displayed on the notice boards and made accessible for all employees.
- 5. Principal Contractor must ensure that his /her employees and appointed contractor employees are familiar with the emergency numbers.
- 6. Contractors shall have one first aid box for the first 5 persons and thereafter one for every 50 or team of workers on site or part thereof, taking into account the type of work performed and the distance between teams.
- 7. More first aid boxes shall be provided in accordance with the risk assessment. Boxes must be available and accessible for the immediate treatment of injured persons at the workplace.
- 8. For offices, signs indicating where the first aid box or boxes are kept as well as the name and contact details of the First Aider of such first aid box or boxes shall be erected.
- 9. The Principal Contractor and appointed contractor shall ensure that alternative arrangements be made for incidents occurring after working hours.

3.19.1 Boxes and equipment

The following is a list of minimum contents of a first aid box:

- Item 1: Wound cleaner/antiseptic (100ml).
- Item 2: Swabs for cleaning wounds.
- Item 3: Cotton wool for padding (100 g).
- Item 4: Sterile gauze (minimum quantity 10).
- Item 5: 1 Pair of forceps (for splinters).

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- Item 6: 1 Pair of scissors (minimum size 100 mm).
- Item 7: 1 Set of safety pins.
- Item 8: 4 Triangular bandages.
- Item 9: 4 Roller bandages (75 mm X 5 m).
- Item 10: 4 Roller bandages (100 mm X 5 m).
- Item 11: 1 Roll of elastic adhesive (25 mm X 3 m).
- Item 12: 1 Non-allergenic adhesive strip (25 mm X 3 m).
- Item 13: 1 Packet of adhesive dressing strips (minimum quantity, 10 assorted sizes).
- Item 14: 4 First aid dressings (75 mm X 100 mm).
- Item 15: 4 First aid dressings (150 mm x 200 mm).
- Item 16: 2 Straight splints.
- Item 17: 2 Pairs large and 2 pairs medium disposable latex gloves.
- Item 18: 2 CPR mouth pieces or similar devices.

A content check list must be available with all boxes and boxes shall be checked on a regular basis, kept clean and dust free.

3.20 SHE Communication Systems

Principal Contractor/s and their appointed contractors must develop a communication strategy outlining how they intend to communicate SHE issues to their staff, the mediums they will employ and how they will measure the effectiveness of their SHE communication. Below is a brief on how communication should take place. Where project meetings are conducted on site, SHE shall be included as a standing agenda point and minutes of these meetings shall be available on site at all times. Minutes of meeting must be compiled and filed in the relevant SHE files. All employees shall have access to these minutes. Attendance register shall be kept for all the health and safety meetings.

3.20.1 Statutory Health and Safety Committees

1. The principal contractor shall establish statutory health and safety committee in terms of Section 19 of the OHS Act, Act. Similarly, appointed contractors shall establish their own statutory health and safety committee.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 2. All appointed contractors shall be members of the principal contractor's safety committee.
- 3. The Committee shall meet to discuss SHE issues concerning the current work being performed, training, upcoming work and SHE requirements, incidents and lessons learned specific SHE problems, safety performance, action plans and other relevant SHE issues. Listed below is a preferred agenda.
- 4. SHE representatives for a workplace shall be members of the relevant workplace safety committees (Refer to Section 19 (2) (a) of the OHS Act).
- 5. The number of persons nominated by employer must not be more than the Health and Safety Representatives on that specific statutory health and safety committee. (Refer to Section 19(2)(c) of the OHS Act)
- 6. A statutory health and safety committee meeting shall be held at least 3 monthly (where medium to high risk work is involved, more frequent if required), and all appointed members of the committee shall attend the meeting.
- 7. Statutory health and safety committees may make recommendations to the principal contractor and the project manager and the Inspector at DoEL.
- 8. All health and safety committees shall discuss all projects related OHS Act Section 24 and 25 incidents and other notified serious incidents.
- 9. Health and safety committees shall follow up on incident investigation recommendations and shall keep record of all recommendations made by the committee.
- 10. Statutory health and safety committees may make recommendations for the revision of current standards, procedures and practices.
- 11. The principal contractor and appointed contractors shall ensure that statutory and non-statutory health and safety committees carry out their duties.
- 12. The chairperson of the health and safety committees shall be selected and appointed by the contractor. The appointed chairperson must be competent to chair meetings and be able to make informed decisions.

3.20.2 Non-statutory health and safety committees

1. Where there are large worksites, then non-statutory sub-committee must be established within that worksite to assist with the communication of health and safety related matters between the statutory health and safety committee and the workplace.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

2. The duties and responsibilities of the non- statutory health and safety committees will be the same as the statutory safety committee

3.20.3 Agenda

- 1. The following serves as the guideline for the SHE Committee meeting agenda.
- List of agenda items:
- Matters arising from previous minutes
- Matters arising from Contractor's SHE meetings.
- Audit results and feedback
- Review Health and Safety Representative Inspection Reports
- Review
 - Incident investigation reports
 - Non-Conformances
 - Announcements (near miss/injury/damage)
 - Follow up on recommendations made by the employer in incident investigation reports
- Accident Prevention Safety Promotion
 - Planned Job Observations
 - SHE Training
 - o Protective clothing and equipment
 - Incident Announcements / Recall
- · Forthcoming High hazard activities.
- Non-conformances.
- Housekeeping.
- Work permits.
- Work procedures.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- Hazardous materials / substances.
- Fire Prevention
- Occupational Hygiene Assessments, Health Risks and Actions
- Security
- Construction vehicles and mobile equipment
- Rules, Instructions
- Public Safety
- Environmental Management
- Emergency Preparedness
- Statistics report
- Closure

3.20.4 Minutes and action items for all health and safety committee meetings

- 1. Minutes and record of action items shall be kept of all health and safety committee meetings.
- 2. Action column with target dates and responsible person shall be clearly visible on the minutes and shall be completed during the meeting.
- 3. Statutory health and safety committee meeting minutes and record of action items shall be kept for the duration of the project or a minimum period of three years.
- 4. Non-statutory health and safety committee meeting minutes shall be kept for the duration of the project or a minimum period of 12 months.
- 5. All other meeting minutes where SHE is on the agenda, shall be kept for a minimum period of 12 months.
- 6. The original copy of the minutes and record of the action items must be signed by the chairperson.
- 7. The relevant project manager and principal contractor shall endorse the relevant minutes with his/her recommendations and return the minutes to the relevant contractors chairperson within 14 calendar days of the meeting.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

3.20.5 Tool box talks / Daily team talks / pre job meetings

- 1. A meeting must be held prior to the commencement of the day's work with all relevant personnel associated with the work task in attendance. The job, relevant procedures, associated hazards, safety measures, i.e. the task risk assessments shall be discussed. Each employee who attends the briefing shall sign an attendance list of that pre-job brief form undertaking that they have an understanding of the tasks, risks and control measures required.
- 2. Where possible, tool box talks can be included in the pre-job brief meetings. If this does not occur, then weekly tool box talks must be conducted. The toolbox talk topics will be based on SHE issues pertaining to the construction site and or the project. The topic contents shall be in writing. Attendance registers with the topic listed shall be kept.

3.21 SHE Training

- The principal contractor, when making a bid for this project shall provide a breakdown list of the SHE training requirements and the costing of such requirements. Similarly, appointed contractor must provide the same requirements when bidding with the principal contractor.
- 2. The scope of training includes but is not limited to the type of work being performed and the relevant procedures. Additional to the requirements, will be that the principal contractor and appointed contractors must have the appropriate qualifications, certificates and employees should always be under competent supervision.
- 3. Where legislative and Eskom recommended appointments are made, the relevant training shall be given to those appointees prior to the acceptance of those appointments.
- 4. When there is an amendment to the Acts and/or to the regulations, SHE specification and SHE plan, all affected staff shall undergo the applicable refresher training.
- 5. Appropriate time must be set aside for training (induction and other) of all employees.
- 6. Records of all training and qualifications of all contractor employees must be kept on the SHE file.
- 7. Competent persons as per Construction Regulations 2014: "means a person who (a) has in respect of the work or task to be performed the required knowledge, training and experience and, where applicable, qualifications, specific to that work or task: Provided that where appropriate qualifications and training are registered I terms of

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

the provisions of the National Qualifications Framework Act, 2000 (Act No 67 of 2000), those qualifications and that training must be regarded as the required qualifications and training."

Relevant training requirements as per legislative and other requirements:

- 1. Construction Managers (CR8.1 and CR8.2) -
- 2. Construction Supervisors (CR8.7 and CR8.8) -
- 3. Risk Assessors
- 4. Ladder inspector
- 5. Vehicle mounted crane Operator
- 6. Drill Rig Operator
- 7. Working at heights US 229998
- 8. Rescue US 229995
- 9. Fall protection plan developer US 229994
- 10. First aider
- 11. Fire- fighting equipment inspector
- 12. Scaffolding
- 13. Construction Safety Officer
- 14. Safety representative
- 15. Incident Investigator
- 16. Electrical Machinery Inspector
- 17. Temporal Electrical Installation Inspector
- 18. Authorised/ Responsible persons ORHVS certificates and Authorisations

3.21.1 Induction training

- 1. The principal contractor shall ensure that all his / her employees, appointed contractors and their employees have undergone the Eskom Safety Contractor Management induction training prior to commencing work on site.
- 2. Attendance registers must be completed of any induction training given, which must indicate that they have received and understood the induction training.
- 3. Prior to attending the induction training, all employees must undergo a preemployment medical examination and found fit for duty. A copy of the certificate of fitness must be kept in the SHE file on site for the duration of the project.
- 4. All employees and visitors on site shall carry the proof of induction training.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

3.21.2 Site specific induction training

The principal contractor shall ensure that all his / her employees and appointed contractor employees undergo site specific work induction with regard to the approved project SHE plan, general hazards prevalent on the construction site, construction risk assessment, rules and regulations, and other related aspects. The induction training should also include identification of sensitive features such as wetlands/vlei areas, red data species, graves, etc.

3.21.3 Visitors to site induction

- 1. Visitors to the site shall be required to undergo and comply with the principal contractor's site-specific safety induction prior to being allowed access to site.
- 2. All visitors must remain in the care and custody of a person (host) who has been properly inducted. No visitors are permitted to undertake any work onsite, of any nature.
- 3. Visitors who have completed site induction must be provided with a record of proof of Induction training.

3.21.4 General training

The principal contractor will be required to ensure that before an employee commences work on the project, the respective supervisor informs the employee of his scope of authority, the hazards associated with work as well as the control measures to be taken. This will include man-job specifications, the discussion of any task procedures or hazardous operational procedures to be performed by the employee. The Principal Contractor is to ensure that the supervisor has satisfied himself that the employee understands the hazards associated with any work to be performed by conducting task/job observations.

3.22 Contractor Site Establishment

- 1. Principal contractor's site facilities should be managed at all times.
- 2. Prior to establishing a project site, a site plan is required to be drawn listing position of all buildings, amenities, storage and stacking areas. The appropriate colour coding and demarcation of storage and stacking areas must be carried out.
- 3. Where, working in the field and material is stored at the work sites, then proper stacking and storage shall be carried out.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

4. When compiling the site plan, cognisance must be taken to the establishment of the site camp, ablution facilities and dining area in relation to one another and away from stacking and storage areas.

3.22.1 Site roads

- 1. When planning, sufficient areas must be allocated for parking of construction vehicles and mobile equipment's as well as roadways for ease of manoeuvrability of these vehicles.
- 2. Sufficient width roads to be provided and adequate space is to be allowed for large vehicles traversing the sites.

3.22.2 Construction vehicle safety

- 1. It is the responsibility of the driver to ensure:
 - a. Their passengers wear seat belts whilst the vehicle is in motion.
 - b. Comply with all traffic road rules, safety, direction and speed signs.
 - c. Ensure that vehicle loads are properly secured prior to moving off.
 - d. Ensure that vehicles are not overloaded.
- 2. No drivers or operators may text, talk on cell phones or two way radios whilst driving, unless a hands free kit is used.
- 3. All drivers of construction vehicles are to have valid medical fitness certificates.
- 4. Each Project site that is enclosed by demarcation will have system/ process to manage vehicle access to site.
- 5. Contractor must maintain their vehicles in a roadworthy condition and a vehicle license must be valid at all times.
- 6. Drivers of light vehicles must avoid stopping or parking in the vicinity of machines. At least 30 (thirty) meters must be left clear between such a vehicle and such a machine
- 7. Contractor vehicles can be subject to inspections by the Client/Agent's representative. Vehicles which are not roadworthy will not be permitted to be used on the project.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

8. Drivers/operators shall be responsible for the travel-worthiness of all loads conveyed by them. Precautions shall be taken to secure all loads properly. Loads projecting from vehicles shall be securely loaded and in daytime a red flag and during darkness a red light or red reflective material shall be attached to the extreme end of such projecting material.

3.23 Housekeeping and Order

- 1. All contractors shall maintain a high standard of housekeeping within their sites and vehicles for the duration of the project.
- 2. Prompt disposal of waste materials, scrap and rubbish is essential.
- 3. Materials/objects shall not be left unsecured in elevated areas –falling objects may cause serious injuries/fatalities.
- 4. Nails protruding through timber shall be bent over or removed so as not to cause injury.
- 5. All packaging material including boxes, pallets, crates, etc. to be removed from the work area immediately.
- 6. On completion of his / her work, the contractor is responsible for clearing his / her work area of all materials, scrap, temporary buildings and building bases to the satisfaction of the client/agent.
- 7. In cases where an inadequate standard of housekeeping has developed, compromising safety and cleanliness, anyone has the responsibility to bring it to the attention of the principal contractor in the first instance and the Eskom project/site manager in the second instance.
- 8. The Eskom Project/Site Manager has the right to instruct the principal contractor and appointed contractors to cease work until the area has been tidied up and made safe. Neither additional costs nor extension of time to the contract shall be allowed as a result of such a stoppage. Failure to comply with this requirement will result into site cleaning by another cleaning contractor company at the cost of the principal contractor.
- 9. The principal contractor shall carry out regular safety/housekeeping inspections (at least weekly) to ensure maintenance of satisfactory standards. The principal contractor shall document the results of each inspection and shall maintain records for viewing.

3.23.1 Stacking and storage

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 1. Before stacking any material, the contractors or their employees must consult the contract manager for authorisation to use such an area for stacking purposes. This is to prevent haphazard arrangements.
- 2. Adequate care must be taken by the contractor to ensure that storage and stacking is carried out correctly and safely.
- 3. Correct shelve stacking must be carried out, heavy and bulky on the bottom, light and small on top.

3.24 Workplace Signage and Colour Coding

- 1. Symbolic safety signage shall be displayed where it is required by legislation.
- 2. All symbolic safety signage shall conform to the requirements of SANS standard 1186.
- 3. Signs shall be positioned to be seen from most positions within the work sites / areas.
- 4. All signage must be clear at all times and be replaced timeously when worn out.
- Contractors establishing sites must erect a company sign at their site offices to reflect the name and contact details of the: Construction Supervisor; Health and Safety Manager/Practitioner; First Aider; Health and Safety Representative and Evacuation warden.
- 6. The location of every first aid box; fire extinguisher and emergency exit is to be clearly indicated by means of a sign.
- 7. When using, an explosive power tool the appropriate signage shall be erected, warning people of its use.
- 8. Contractors shall provide signage where work is conducted and where unauthorised entry is prohibited and/or where alerting and cautioning passers-by to be aware of potential dangers.
- 9. The meanings of the appropriate symbolic signage must be discussed during induction training and toolbox talks.
- 10. Where possible, within workshops, work areas and established premises, the appropriate sign indicating the meaning of symbolic safety signs must be displayed.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023	•	
Review Date	April 2024		

3.25 Tools and Equipment

- 1. Contractors shall ensure that all tools and equipment are identified, safe to be used and is maintained in a good condition.
- Contractors shall ensure that all tools and equipment are listed on an inventory list, be regularly inspected at least monthly or as required by legislation and risk assessments. The equipment should be numbered or tagged so that it can be properly monitored and inspected.
- 3. Where applicable, tools and equipment must have the necessary approved test or calibration documentation prior to being brought onto the project and the records shall form part of the SHE plan. Maintenance calibration shall be undertaken in terms of the manufacturer's requirements.
- 4. All fuel driven equipment must be properly maintained in accordance with the manufacturer's recommendations and legal requirements.
- 5. Eskom reserves the right to inspect tools or items of equipment brought to site by contractors for use on this project.
- 6. Should Eskom personnel find any item that is inadequate, faulty, unsafe or in any other way unsuitable for the safe and satisfactory execution of the work for which it is intended, the Eskom personnel shall advise the contractor in writing and the contractor shall forthwith remove the item from site and replace it with a safe and adequate substitute.

Note: In such cases, the contractor shall not be entitled to extra payments or extensions of time in respect of delay caused by Eskom's instructions.

- 7. Where defective tools and equipment's are identified, such tools and equipment shall be removed out of site immediately, locked away to prevent further use until such time as the tool or piece of equipment has been repaired.
- 8. Contractors shall ensure that the appropriate records are kept for all tools and equipment used on the project. Such tools and equipment's shall be subjected to regular inspections.

3.25.1 Hand tools

- All hand tools (hammers, chisels, spanners, etc.) must be recorded on a register and inspected by the construction supervisor on a monthly basis as well as by users prior to use.
- 2. Tools with sharp points in tool boxes must be protected with a cover.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 3. All files and similar tools must be fitted with handles.
- 4. No make shift tools are permissible on the project.

3.26 Ladders

- Ladders used shall conform to the requirements of GSR 13A and used in terms of GSR
 6.
- 2. The appropriate head protection, with chin strap shall be worn by employees working from a ladder or with climbing irons.
- 3. The ladder wheels, brakes and platform must be in good condition.
- 4. All metal parts to be in good condition, no cracks.
- 5. Non-slip devices must be in good condition and no paint to be on wooden ladders
- 6. Climbing irons are permitted to be used in place of ladders on condition that the requirements of GSR 6 are not compromised and from an electrical point of view not damage any cabling. The working at heights risk assessment must indicate the use of climbing irons.
- 7. Employees using climbing irons shall be suitably trained in the use, care and maintenance of such climbing irons.
- 8. When using climbing irons, the appropriate rope grab fall prevention system shall be used.
- 9. The correct fall protection equipment shall be worn and used whilst climbing up, working from and climbing down ladders.
- 10. The appropriate head protection, with chin strap shall be worn by employees working from a ladder or with climbing irons.
- 11. A detailed inspection of all ladders shall be conducted monthly by a competent person and every time prior to climbing by employees using such ladders. The inspection check lists must be filed in the site SHE files.

3.27 Scaffolding

1. Scaffolding use shall conform to the requirements of CR 14, Eskom procedure 32-418 and used in terms of GSR 6.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 2. The requirements for using a scaffold platform shall be determined by the work at heights risk assessment.
- 3. All scaffolding that will be used shall conform to the SANS standard 10085 and the requirements of CR 16 shall be carried out.
- 4. Scaffolding shall be erected and inspected by the competent personnel.
- 5. The appropriate training for scaffold users shall be conducted prior to climbing on to the scaffold.
- 6. The correct fall protection equipment shall be worn and used whilst climbing up, working from and climbing down the scaffolds.
- 7. A detailed inspection of all scaffolding shall be conducted monthly by a competent person and every time prior to climbing by employees using such scaffolding. The inspection check lists must be filed in the site SHE files.

3.28 Auditing

3.28.1 Approval and compliance of principal contractor SHE plan

The Contractor's SHE Plan will be audited against compliance checklist so as to verify compliance to the requirements of the Eskom SHE specifications. Once there is compliance only then will the principal contractors SHE plan be approved by the project manager or an appointed Eskom contract custodian. The implementation of the SHE Plan shall be assessed / audited by Eskom personnel on a regular basis. This will include physical conditions evaluation.

3.28.2 Eskom SHE audits

Eskom shall evaluate all contractors' SHE performance on an ongoing basis against the legal, Eskom requirements, SHE specification and the contractors SHE plans.

Note: Eskom reserves the right to conduct unannounced audits on contractors

There will be monthly audits conducted by Eskom on the principal contractor/s and/or appointed contractors. These audits shall be attended by the contractor's site manager or his representative.

If there are any findings / non-compliance identified as serious in these audits, an activity will be stopped for that specific Principal Contractor and appointed contractor. Refer to section on "Work Stoppage" in this SHE Specification.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023	•	
Review Date	April 2024		

3.28.3 Contractor audits

Principal Contractors are required to conduct internal audits on both their employees and their appointed contractors on the implementation of their SHE Plan on a monthly basis or when the scope of work changes. A summary of the findings and the proposed corrective actions shall be submitted to Eskom project manager within one week after completion of the audit. Where appointed contractors are audited by the principal contractor a copy of the audit report shall be submitted to the appointed contractor within 7 days of the audit.

3.29 Smoking

The Tobacco products control act 83 of 1993 must be observed and smoking is permitted in designated areas only (Eskom Smoking Procedure 32-36).

3.30 Cellular Phones

The national requirements regarding the use of cellular phones must be observed, in particular when driving and or operating mobile equipment and or machinery.

3.31 Occupational Health, Hygiene and Rehabilitation

All contractors are required to develop an Occupational Health, Hygiene and Rehabilitation program. The program is intended to ensure that the risks to health are identified and controlled.

3.31.1 Medicals

Note: Eskom will only accept medical surveillances conducted by an Occupational Health Practitioner who holds a qualification in occupational health.

- 1. Principal contractors must ensure that their employees and their appointed contractor employees have a medical surveillance program whereby their employees under go entry, periodic and exit medical fitness examinations.
- In order for the appropriate medical examinations to be conducted, each employee
 must have a man job specification, which must indicate the description of work, list of
 hazards and potential occupational exposure limits, physical hazards and required
 physical attributes.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 3. Medical fitness certificates shall be renewed annually for employees who are working on site. This shall be maintained until completion of the contract.
- 4. The Principal Contractor must ensure that his / her employees and appointed contractor employees have undergone pre-entry medical examination before starting work on the contract.
- 5. The principal contractor shall provide a documented process for managing those employees who are issued with a conditional certificate of fitness.

3.32 Working at Heights

3.32.1 General Requirements

Wherever reasonably practicable, preference is given to the performance of work at ground level as opposed to the elevated position. Where work in an elevated position is necessary, preference is given to fall prevention measures such as, but not limited to, effective barricading and the use of work platforms. Persons may only work from a fall risk position if a site-specific fall protection plan is in place and correctly implemented and consists of the following:

- 1. All appointments for the fall protection plan developer and implementer are in place.
- 2. Baseline risk assessment, which is specific and incorporates the working at height risk assessment, as well as the site-specific risk assessment, has been completed for the work to be conducted.
- 3. Safe working procedure/task analysis and work instructions, approved by a competent person, are in place.
- 4. A fall rescue plan, along with necessary equipment and trained rescuers, is in place.
- 5. Appropriate training, as determined by the risk assessment, has been provided.
- 6. Appropriate height safety equipment and personal protective equipment have been issued to the individual.
- 7. There are equipment inspection procedures and up-to-date inspection records.
- 8. Individuals are medically fit to work at height, and records of this are kept.
- 9. A site-specific risk assessment is performed.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

While work is in progress, adequate warning signs and/or barricades shall be used in all areas where there is a risk of persons being injured by materials or equipment falling from the work area. Barricades should be continuous and easily visible.

A drop zone shall be established with appropriate warning signs and barricading, warning personnel below of workers above and potential falling objects.

Every employer shall ensure that work at height is:

- 1. properly planned;
- 2. appropriately supervised; and
- 3. carried out in a manner that is, as far as is reasonably practicable, safe and that its planning includes the selection of work equipment.

3.33 Risk Assessments

It is a legal requirement in terms of Section 8 (2)(d) of the OHS Act for an employer to carry out risk assessments, to establish which risks and hazards are attached to the health and safety of persons due to any work which is performed, any article or substance which is, handled, stored, transported. A risk assessment is defined as an identification of the hazards present in an organisation and an estimate of the extent of the risks involved, taking into account whatever precautions are already being taken. It is essentially a three stage process:

- · identification of all hazards;
- evaluation of the risks;
- Measures to control the risks.

Risk assessments are required to be maintained. This means that significant changes to a process or activity, or any new process or activity should be subjected to a risk assessment and that if new hazards come to light during the work process, then these should also be subjected to risk assessments. Risk assessments for long term processes should be periodically reviewed and updated. Method statements or written safe work procedures are an effective method as information and record of the way jobs / tasks must be performed. Daily or issue based or task specific or on the job risk assessments must be conducted at the place where work is to be performed/ conducted to allow managers and employees to assess any inherent risks that could have been overlooked during the initial risk assessment or any changes that might have occurred in a period of absence. For example if a job / task is extended over a day or halted due to inclement weather.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

3.34 Safe Work Procedures and Practices / Safe Operating

There must be written safe work procedures for all activities, the safe work procedures must be aligned with the risk assessments and scope of work for the project.

3.35 Personal Protective Equipment Requirements

- The Principal contractor must provide a detailed programme that includes the issuing, maintenance and replacement of PPE for all his employees and appointed contractors on site.
- 2. All contractors shall comply with the requirements of GSR 2 of the OHS Act.
- 3. The risk based PPE matrix must be compiled detailing the types of PPE that is required to be issued to employees performing the respective tasks.
- 4. Where there are unusual instances where particular activities require additional type of PPE, then a risk assessment must be conducted where such PPE requirements will be identified and the issuing be carried out.
- 5. All contractors shall ensure that their visitors wear and use the correct PPE whilst on worksites.
- 6. Where PPE is required and visitors are not in possession of, then it is the individual contractor's responsibility to provide the PPE.
- 7. All PPE purchased and used by all contractor employees including visitors must comply with the relevant SANS standards.
- 8. Where deemed as a requirement, then high visibility vests shall be worn.

3.36 Incident Investigation

All incidents shall be investigated in terms of OHS Act General Administrative Regulations 8 and 9, using Eskom Procedure 32-95 as a reference, and where injuries as contemplated in sections 24 and 25 have been sustained, be reported to the Department of Labour.

Contractors shall use the standard General Administrative Regulation Annexure 1 "Recording of an Incident" form for all incident investigation reports. The objective of incident investigation, should not only be a legal requirement, but should establish why and how the incident occurred and find out the real root cause of the incident and to decide on precautionary measures that

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

are required to address the root cause to prevent any further recurrences of the same or similar incidents.

The contractor incident management procedure need to be aligned to Eskom's 32-95 incident management procedure and timeline must be strictly adhered to.

The high level steps of the incident management procedure are as follows:

- 1. Incident identification
- 2. Initiation and Execution of Emergency Response
- 3. Notification and Reporting
- 4. Incident prioritisation
- 5. Classification and Recording of Incidents
- 6. Incident investigation
- 7. Management of Corrective Actions (Safety Measures)
- 8. Incident close-out
- 9. Incident Communication

Timelines with regards to incident management need to be strictly adhered to as per 32-95 Occupational Health and Safety Incident Management Procedure and 240-131838225 Occupational Health and Safety Incident Management Definitions and Classification Parameters.

Failure to comply with these requirements will be seen as the contractor not fulfilling their contractual obligations and the relevant consequence management actions will be taken against contractors who do not comply.

Timelines include:

- 1. Notification of incident to relevant Eskom SHEQS department should be done before the end of shift or within 24 hours of the incident occurring.
- 2. Investigation process to be initiated within 48 hours and concluded within 30 calendar days. The onus is on the contractor manager to provide evidence for the reasons why the Internal OHS Investigation could not be completed within 30 days and should be submitted to the relevant SHEQS department.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

In the case of incidents involving contractor employees, the contractor must investigate those incidents as an employer in his/her own right (employer's investigation) and generate a report. The report and Annexure 1 must be submitted to the applicable OU/BU or on request to the Department of Labour by the contractor. Eskom may participate during these investigations.

3.37 Emergency Management

The art of emergency preparedness and response is to minimise the effects of any emergency and to restore normal activities as soon as practical. The contractor must familiarise themselves with the Eskom emergency response plan and procedure. Periodic emergency drills must be undertaken to test the effectiveness of the plan. This must be recorded and provided to the Eskom SHEQS department for evaluation in the site specific safety file.

The emergency management procedure to be submitted has to include emergency contact numbers relevant to the area worked in for the site supervisor, hospital, fire brigade, first aider and ER24 (010 205 3400 and 084 124).

If no cellular phone reception is present for example in remote areas, an adequate process must be put in place to have adequate alternative communication.

3.38 Non-Conformance and Compliance

- 1. Any non-compliance to any health and safety requirement in this SHE specification is subject to discipline in terms of the Eskom Procurement and Supply Management Procedure.
- 2. Principal contractors are required to implement a non-conformance procedure (if not already in place) for issuing to contractors for transgressions. The procedure can include "quality" related non-conformance issues. Similarly, appointed contractors must implement a non-conformance procedure.
- 3. The procedure for the issuing and closing off of non-conformance reports shall be strictly adhered to.
- 4. Contractor project management must monitor the close out non-conformances issued, in not doing so; any recommendations made may not be implemented.
- 5. Where non-conformances are issued by Eskom then one of the close-out steps of the procedure will be for the offender to be called by the responsible project manager to explain the non-conformance issued and what plan is in place to prevent a recurrence of the non-conformance.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 6. Should the contractor fail to provide adequate PPE to their employees for the tasks being performed and/or to visitors; failure to enforce the wearing of such PPE will be viewed as a transgression of the legislative and Eskom requirements.
- 7. Add section for Issuing of site instructions, capturing of SAP QIM Quality Issues and process for close out.
- 8. After a contractor has been appointed the Project Manager should submit the relevant SHE Specification to the principal contractor. The Principal contractor then develops a site specific safety file in terms of the SHE Specification submitted for the project, this safety file needs to be developed and submitted to the Eskom SHEQS department for evaluation. No contractor may commence with work before the site specific safety file is accepted by Eskom SHEQS department and the relevant Project manager, as well as that the site specific procedures are adhered to.
- Eskom reserves the right to stop any contractor performing unsafe work/conditions and can apply consequence management if any contractor fails to comply with any Legislative requirements as well as any Eskom Requirements, Standards and Procedures. Refer to 32-726 Contract and Contractor OHS management Section 3.4.4.4.
- 10. Should Eskom personnel find that the site specific safety file is unsatisfactory, the process in Section 3.7 of 32-726 Contract and Contractor OHS management shall be initiated. Check and review

3.39 SHE File

- 1. A SHE file means a file or other record in permanent form, containing the information about the safety and health management system during construction and all information relating to the post-construction phase after handover to the client, so that the client can maintain the works in a healthy and safe way.
- 2. All contractors are required to keep a SHE file on every project site. If there is more than one site per project, a file per site shall be kept at that site. Contractors may keep additional files at their head office as additional records. The SHE file shall be maintained by all the contractors on their construction sites and shall be available on request for audit and inspection purposes.
- 3. The SHE file shall consist of the requirements in terms of the project's safety specification, the contractor's safety and health plans.
- 4. The sequence of filing the documentation must be kept in the same sequence as listed in this SHE specification and the SHE plan.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- 5. Each record shall be separated by partitions to afford easy identification and access. Each partition must be labelled.
- 6. On completion of the construction work/project, the principal contractor must hand over a consolidated health and safety file to the project manager. The principal contractor must also hand over all drawings, designs, lists of materials used, and other applicable information about the completed structure, as well as the list of subcontractors, the agreement, and the type of work completed.
- 7. In case where the project is extended, should the documentation in the SHE files become cumbersome, the older documentation must be archived in boxes which shall be correctly labelled and be available for auditing purposes. The archived documentation must be handed over at the completion of the project.

3.40 Work Stoppage

- Any person may stop any activity where an unsafe act or unsafe condition that poses or may pose an imminent threat to the safety and health of an individual or create a risk of degradation of the environment. This includes any unauthorised work or service performed by, or legally or contractually non-compliant acts or omissions by, any contractor contracted to work at that site.
- 2. Work stoppages that are initiated due to SHE concerns, non-compliance, or poor performance related to the contractor's works or services shall not warrant any financial compensation claim lodged against Eskom where the contractor has not met the requirements defined legally or contractually.
- 3. Where stoppages are carried out, the required non-conformance report shall be raised.
- 4. All work stoppages ideally should be investigated and documented by contract custodians.

3.41 Hours of Work

The requirements of the Basic Conditions of Employment Act, Chapter Two "Regulation of Working Time" must be adhered to. All contractors are required to maintain an accurate record of time worked by each employee.

3.41.1 Normal work

All work conducted on site shall fall within the legal requirements in accordance with the Basic Conditions of Employment Act. Contractors will notify their Eskom Supervisor or project manager of any work that needs to be performed after hours according to the agreed

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

arrangements. (The application needs to be submitted timeously). Where applicable, the notification should include proof of application, for overtime, to the Department of Labour and /or the letter of approval from the Department of Labour.

3.41.2 Night work

When night work is to be performed; contractors shall provide sufficient lighting to enable the entire work site to be illuminated to a degree that employees will not work in dark (unilluminated) or dimly lit areas. Care must be exercised as not to use few lights with high light intensives as this will cause night blindness.

If work is continuing from day light into night, at dusk, a tool box talk must be held where all employees will be advised of the hazards of night work and the extra precautions which require to be taken, i.e. poor housekeeping, stepping on uneven ground, stepping into holes etc.

3.41.3 Overtime

When overtime is required to be performed, the appointed contractors shall inform the principal contractor of such action. The principal contractor shall inform the Eskom project manager of such function. Contractors shall be aware of the effects of human fatigue and regulate overtime accordingly. The baseline risk assessment must be reviewed to include the management of overtime work.

3.42 Omissions from Safety and Health Requirements Specification

By drawing up this SHE specification Eskom has endeavoured to address the most critical aspects relating to SHE issues in order to assist the contractor to adequately provide for the health and safety of employees on site.

Should Eskom not have addressed all SHEQ aspects pertaining to the work that is tendered for, the contractor needs to include it in the SHE plan and inform Eskom of such issues when signing the contract.

3.43 Contract Sign-Off

On completion of the project, all appointed contractors shall close out their project documentation; SHE files and forward such to the principal contractor. The principal contractor shall likewise close out his/her project documentation and SHE files and forward such to the Eskom project manager.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023	•	
Review Date	April 2024		

3.44 Project Statistics

The following information should be submitted by the 1st of each month to the Contract Manager/ Custodian:

- Contractor manpower numbers and hours worked for the purpose of calculating the contractor lost-time injury (LTIR) and total recordable injury (TRIR) rates
- Contractor incidents per month (fatalities, lost time, medicals, first aid and near-misses).
- Contractor confirmation that incident case studies were discussed and recommendations implemented.
- Contractor confirmation that all issues findings against them has been addressed as required.
- Contractor will submit their statistics every month using the latest 240-140441286
 Contractor Manpower/Man-hours and OHS stats reporting form.

3.45 Weather Extremes

Contractors should after conducting a site specific baseline risk assessment establish what weather extremes are occurring in the area and make provision for control measures to prevent or reduce exposure to their employees to an acceptable level.

3.46 Dismantling, Assembly and Erecting of Structures

Construction Regulations 10, 11 and 14 needs to be strictly adhered to.

A competent person needs to be appointed to supervise demolition work in terms of Construction Regulation 14(1).

Contractors need to take all reasonable steps to prevent the uncontrolled collapse of any new or existing structure or any part of the said structure that may become unstable or which might be in a temporary state of weakness or might be unstable due to carrying out construction work.

No structure or part of any structure may be loaded in such a manner that it would be deemed as unsafe.

A contractor needs to appoint a competent person in writing to supervise and control all demolition work on site.

Before any demolition work is being carried out a competent person need to develop a detailed structural engineering survey of the structure to be demolished in order to identify the order in which the structure needs to be demolished. The competent person who

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

develops the structural engineering survey also needs to provide a method statement on the procedure to be followed in demolishing the structure.

The appointed competent person on supervising demolition work must check the structural integrity of the structure being dismantled at regular intervals determined by the method statement in order to prevent any premature collapse.

Contractors involved with demolition work need to take steps to ensure that no person works under overhanging material or a structure which has not been adequately supported, shored or braced. Steps should be taken by contractors to ensure all other services in the vicinity that may be affected are rendered safe for all persons involved.

Where demolition work includes working at heights and there is a risk of falling objects the following needs to be in place: (32-418)

- 1. A drop zone must be established and demarcated.
- 2. Suitable steps must be taken to prevent any material or objects from falling that could cause harm to people or property.
- 3. Where it is not reasonably practicable to comply with the requirements of paragraph **2** every employer must take suitable and sufficient steps to prevent any person from being struck by any falling material or object that is liable to cause personal injury.
- 4. No material or object shall be thrown or tipped from height in circumstances where it is likely to cause injury to any person.
- 5. Materials and objects must be stored in such a way as to prevent risk to any person arising from the collapse, overturning or unintended movement of such materials or objects.

Where demolition work includes working at a fall risk position a site specific fall protection plan needs to be developed and implemented by a competent person as per Construction Regulation 10.

The fall protection plan should make provision for the following information:

- 1. a risk assessment of all work carried out from a fall risk position and the procedures and methods used to address all the risks identified per location;
- 2. the processes for the evaluation of the employees' medical fitness necessary to work at a fall risk position and the records thereof;
- 3. a programme for the training of employees working from a fall risk position and the records thereof;
- 4. the procedure addressing the inspection, testing and maintenance of all fall protection equipment;

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

5. A rescue plan detailing the necessary procedure, personnel and suitable equipment required to affect a rescue of a person in the event of a fall incident to ensure that the rescue procedure is implemented immediately following the incident.

Contractors to ensure that the Fall Protection Plan is site specific as well as scope of work specific and that all required legislation as well as the Eskom requirements are adequately met.

3.47 Excavation Work

As per the scope of this project excavation will take place and as a result strict adherence to Eskom and legislative requirements need to be adhered to pertaining excavations.

As per Construction Regulation 13 – Excavations:

- (1) A contractor must-
- (a) ensure that all excavation work is carried out under the supervision of a competent person who has been appointed in writing for that purpose; and
- (b) evaluate, as far as is reasonably practicable, the stability of the ground before excavation work begins.
- (2) A contractor who performs excavation work-
- (a) must take reasonable and sufficient steps in order to prevent, as far as is reasonably practicable, any person from being buried or trapped by a fall or dislodgement of material in an excavation;
- (b) may not require or permit any person to work in an excavation which has not been adequately shored or braced: Provided that shoring and bracing may not be necessary where-

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- (i) the sides of the excavation are sloped to at least the maximum angle of repose measured relative to the horizontal plane; or
- (ii) such an excavation is in stable material: Provided that-
- (aa) permission has been given in writing by the appointed competent person contemplated in sub regulation (1) upon evaluation by him or her of the site conditions; and
- (bb) where any uncertainty pertaining to the stability of the soil still exists, the decision from a professional engineer or a professional technologist competent in excavations is decisive and such a decision must be noted in writing and signed by both the competent person contemplated in sub regulation (1) and the professional engineer or technologist, as the case may be;
- (c) must take steps to ensure that the shoring or bracing contemplated in paragraph (b) is designed and constructed in a manner that renders it strong enough to support the sides of the excavation in question;
- (d) must ensure that no load, material, plant or equipment is placed or moved near the edge of any excavation where it may cause its collapse and consequently endangers the safety of any person, unless precautions such as the provision of sufficient and suitable shoring or bracing are taken to prevent the sides from collapsing;
- (e) must ensure that where the stability of an adjoining building, structure or road is likely to be affected by the making of an excavation, steps are taken to ensure the stability of such building, structure or road and the safety of persons;
- (f) must cause convenient and safe means of access to be provided to every excavation in which persons are required to work, and such access may not be further than six meters from the point where any worker within the excavation is working;

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- (g) must ascertain, as far as is reasonably practicable, the location and nature of electricity, water, gas or other similar services which may in any way be affected by the work to be performed, and must before the commencement of excavation work that may affect any such service, take the steps that are necessary to render the circumstances safe for all persons involved;
- (h) must ensure that every excavation, including all bracing and shoring, is inspected-
- (i) daily, prior to the commencement of each shift;
- (ii) after every blasting operation;
- (iii) after an unexpected fall of ground;
- (iv) after damage to supports; and
- (v) after rain,

by the competent person contemplated in sub regulation (1), in order to ensure the safety of the excavation and of persons, and those results must be recorded in a register kept on site and made available on request to an inspector, the client, the client's agent, any other contractor or any employee;

- (i) must cause every excavation which is accessible to the public or which is adjacent to public roads or thoroughfares, or whereby the safety of persons may be endangered, to be-
- (i) adequately protected by a barrier or fence of at least one metre in height and as close to the excavation as is practicable; and
- (ii) provided with warning illuminants or any other clearly visible boundary indicators at night or when visibility is poor, or have resort to any other suitable and sufficient precautionary measure where subparagraphs (i) and (ii) are not practicable;

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- (j) must ensure that all precautionary measures stipulated for confined spaces as determined in the General Safety Regulations, 2003, are complied with by any person entering any excavation;
- (k) must, where the excavation work involves the use of explosives, appoint a competent person in the use of explosives for excavation, and must ensure that a method statement is developed by that person in accordance with the applicable explosives legislation; and
- (I) must cause warning signs to be positioned next to an excavation within which or where persons are working or carrying out inspections or tests.

3.48 COVID-19 Requirements

Code of Practice: Managing exposure to SARS-COV-2 in the workplace, 2022 published in GG46596, on 24 June 2022, GNR 2191.

As a result of the global COVID-19 pandemic the following requirements have to be put in place to ensure adequate control measures are present in workplaces:

Chapter 2 of GNR 2191:

1. Risk assessment and plan

Every employer must -

- a. Undertake a risk assessment to give effect to its obligations under the OHSA and the HBA Regulations;
- b. On the basis of the risk assessment develop or amend its existing plan to include
 - Any measures to be implemented in respect of the vaccination of its employees and, taking into account the intervals between vaccinations, the dates by which the employees must be fully vaccinated; and
 - ii. Any other protective measures contemplated section 6(1) and (2);
- c. Consult on the risk assessment and plan with -
 - i. Any representative trade union as contemplated by section 14(1) of the LRA; and
 - ii. Any health and safety committee established in terms of section 19 of the OHSA or, in the absence of such committee, a health and safety

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

representative designated in terms of section 17(1) of the OHSA or employee representative; and

d. Make the risk assessment and plan available for inspection by the trade union and committee contemplated in paragraph (c) and an inspector.

2. Contents of risk assessment and plan

- The risk assessment and plan referred to in section 5(1)(b) must include
 - a. The identification of the employees contemplated in paragraph(i) of that section;
 - The reporting of symptoms by employees and isolation of employees who are diagnosed with COVID-19 and are symptomatic;
 - The workplace protective measures required to be taken in terms of HBA Regulations including personal protective equipment and ventilation;
 - d. A procedure to resolve any issue that may arise from the HRA by an employee of the right to refuse to work in the circumstances contemplated in section 15(1); and
 - e. The process by which the obligations under this Code will be complied with.
- 2. The risk assessment and plan referred to in section 5(1)(b) may include
 - a. Social distancing measures including minimising the number of workers in the workplace through rotation, staggered working hours, shift and remote working arrangement's;
 - b. PPE measures contemplated in section 11:
 - Personal hygiene measures such as the wearing of facecloth masks, barriers hand washing, sanitisers and surface disinfectants;
 - d. Any special measures to mitigate the risk of infection or serious illness or death in respect of individual employees at increased risk such as reducing the numbers in and the duration of occupancy in meeting rooms.

In developing and implementing a plan in terms of subsection (1)(b)(i), an employer must comply with section 12.

3.49 Working near or crossing National, Provincial and local roads

Principal contractors must at all times ensure that all relevant legislation and best practices are followed when working near or crossing roads.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Ensuring that an adequate risk assessment is conducted and control measures implemented when work is conducted near or close to roads, where required relevant national as well as provincial and local authorities should be notified of any work being carried out over roads. Control measures including but not limited to relevant safety signage, traffic control by the use of flagmen as well as barricading should be in place.

3.50 Existing Infrastructure and Services

Before any work commences the Principal contractor should ensure that all existing infrastructure (Live overhead feeders, underground networks such as water pipes electrical cables etc.) are known to their employees and the risks pertaining to these infrastructure as well as what control measures are in place to ensure that no employees is injured or infrastructure damaged as a result of their activities.

The relevant existing infrastructure hazards and risks should be identified and included in the project specific baseline risk assessment together with the relevant control measures.

3.51 Working in close proximity to large bodies of water

Principal contractors must at all times ensure that all relevant legislation and best practices are followed when working near large bodies of water

Ensuring that an adequate risk assessment is conducted and control measures implemented when work is conducted near or close to bodies of water. Control measures including but not limited to relevant barricading and terrain stability assessment should be put in place.

3.52 Asbestos Work (Working in a naturally occurring asbestos area)

The Northern Cape is known for the prevalence of asbestos, contractors/ Eskom employees need to take precaution when working in such areas. The following towns and surrounding areas are known to be Asbestos affected.

- Kuruman
- Danielskuil
- Lime Acres
- Kathu
- Hotazel

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023	•	
Review Date	April 2024		

- Prieska
- Marydale

Client shall ensure that Contractor:

(a) Prior to work commencing -

Is performed by Registered Asbestos Contractor;

All asbestos materials likely to become airborne are identified;

Plan of work is submitted for approval, at least 30 day prior to work commencing, to an approved asbestos inspection authority;

A copy of the plan of work, approved by approved asbestos inspection authority, is submitted to the provincial director at least 14 days prior to commencement of demolition work. The approved plan of work shall be signed by Approved Asbestos Inspection Authority, employer and mandatory of employer

Copies of approved standardised procedure for demolition work is submitted to provincial director 14 days prior to work commencing

(b) During and after completion of demolition work -

All asbestos and material containing asbestos are handled and disposed of according to Asbestos Regulation 20;

All persons exposed to or likely to be exposed to asbestos is issued with appropriate Personal Protective Equipment and that such equipment is used properly.

The premise, area or structure is thoroughly checked to ensure that all asbestos waste has been removed

Contractor shall ensure:

Where roof work / Work from fall risk position are performed it is done in accordance to Construction Regulation 10.

Written work procedures are established and followed to prevent release of asbestos dust in the environment and approval therefore obtained from Approved Asbestos Inspection Authority and Provincial Director of D.O.L. Plan of work is submitted for approval, at least 30 day prior to work commencing, to an approved asbestos inspection authority;

A copy of the plan of work, approved by approved asbestos inspection authority, is submitted to the provincial director at least 14 days prior to commencement of demolition work. The

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

approved plan of work shall be signed by Approved Asbestos Inspection Authority, employer and mandatory of employer

Respirators:

The employer shall—

- (a) Provide employees with respirators approved by the chief inspector for use when working with asbestos. A sufficient quantity of respirator filters approved for asbestos shall be provided so those employees can change filters during the workday. A filter should preferably not be used for a period longer than one workday. The respirators shall be issued on a personal basis and arrangements shall be made for the regular inspection and servicing of the respirators;
- (b) Instruct and train employees in proper respirator use and ensure that filters and respirators are protected from exposure to asbestos prior to use; and
- (c) Ensure that employees wear respirators in the workplace at all times, and that respirators are properly fitted.

Protective clothing:

The employer shall-

- (a) Provide suitable protective clothing for his employees. Suitable clothing comprises overalls or similar full-body protective clothing with head covering and gumboots. Such clothing may be disposable, washable for re-use or may alternatively be suitable wet weather gear that can be hosed down;
- (b) Undertake or arrange for the disposal or laundering of protective clothing. Where a contract laundry is employed, care shall be taken that the contractor fully understands the precautions necessary for handling asbestos-contaminated clothing; and
- (c) Ensure that protective clothing is removed from the premises only for laundering or disposal and then only if suitably packed in a sealed impermeable container, and that it is clearly labelled with a warning label as containing asbestos-contaminated clothing.

Decontamination facilities and personal hygiene:

The employer shall set up decontamination facilities outside the workplace for the exclusive use of employees exposed to asbestos. These facilities shall consist of a "clean" changeroom, toilet/shower facilities and a "dirty" decontamination change-room

All employees without exception shall—

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- (i) remove personal clothes in the "clean" change- room and put on clean protective clothing, gum-boots and respirators before entering the work- place; and
- (ii) Use the vacuum-cleaning to de-dust before the protective clothing and gumboots are removed in the "dirty" decontamination change room when leaving the workplace. While still wearing their respirators, the employees should proceed to the showers and only remove their respirators while showering. All showering must be done using soap and water.
- (iii) Employees shall not eat, drink or smoke in the workplace. Before eating, drinking or smoking, employees shall first comply with paragraph (ii), and before re-entering the workplace employees shall comply with paragraph (i).

All other persons entering the workplace shall wear approved respirators for asbestos as well as protective clothing and footwear. Before leaving the workplace they must comply with paragraph (ii).

All contaminated clothing and footwear shall be left in the decontamination change-room and should be immediately stored in suitable containers prior to disposal or laundering. Contaminated respirators that are removed in the showers must be removed after being washed down and stored for disposal or made good for re-use. The collection of protective clothing, footwear and respirators shall be strictly controlled.

Disposal of waste

Work procedures shall be applied to small sections of the workplace at a time. Before beginning the next section all asbestos waste shall be collected from the section where work is currently in progress and placed in impermeable plastic bags or similarly effective containers.

- (a) Before leaving the workplace all containers shall be cleaned on the outside and labelled, and, in the case of bags, the bag containing the waste shall be placed in another clean bag, sealed and labelled.
- (b) All plastic sheeting, tape, cleaning material, clothing and all other disposable items used in the workplace shall be placed into impermeable plastic bags or similarly effective containers, Before leaving the workplace all containers and bags containing asbestos-contaminated materials or items shall be dealt with as in paragraph (a) above,
- (c) The detailed arrangements for asbestos disposal shall be agreed upon with the appropriate local authority. The waste shall be disposed of only on waste disposal sites

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023	•	
Review Date	April 2024		

specifically designated for this purpose in terms of the Environment Conservation Act, 1989 (Act 73 of 1989). Waste shall be deposited in such a manner as to minimise dust dispersal as well as the need for further disturbance of the waste. The waste should be covered with at least 200 mm of sand or other suitable material capable of forming a seal to prevent the dispersal of dust. No waste should be left uncovered at the end of a workday.

- (d) Liquids or sludge containing asbestos shall be collected in collecting-tanks from where it may be pumped into sealable drums or closed type tanker for transit to the waste disposal site. Transport and disposal must take place in such a way that there is no risk of the material drying out before it has been disposed of and covered as provided for in (c) above.
- (e) High density materials such as asbestos cement, plastic materials containing asbestos, etc. are not likely to release asbestos dust when tipped.

All vehicles, re-usable receptacles and covers, which have been in contact with asbestos waste, shall be cleaned by a dust-free method.

The employer concerned with the collection, transport and disposal of asbestos waste is responsible for complying with the provisions of the Occupational Health and Safety Act, 1993, and the regulations.

The contractor shall ensure that the relevant training and information procedures are in place and relayed to all workers. Proof of such training and information sharing shall be available on site at all times.

All exposed asbestos shall be coated – holes, cracks, damaged asbestos surfaces prior to removal from steel structure. The contractor shall ensure that OEL for Asbestos is not exceeded if Asbestos dust becomes airborne. The contractor shall ensure that measures are put in place to determine that OEL for Asbestos is not exceeded.

The contractor shall ensure that all records relating to assessment results, air monitoring, medical surveillance, Training etc. is kept for periods as specified in AR 16

Any water containing asbestos dust as a result of dismantling asbestos cement sheeting shall be treated according to Asbestos Regulation 13 (2) (b) and (c). Asbestos removal work is done in accordance to Asbestos Regulation 11 and 13.

Cutting or drilling is performed under controlled conditions according to Asbestos Regulation 11 and 13. This shall include the use of wet methods where possible, suitable slow speed cutter is used and a respirator used by operator and other at risk of exposure.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Asbestos waste of any form, including dust, is collected and disposed of according to Asbestos Regulation 20.

Contractor shall ensure adherence to all sections of Asbestos Regulations.

Summary of documentation required for Asbestos Work – To be read in conjunction with Asbestos Abatement Regulation:

- 1. Letter of good standing Valid Prior to work commencing
- 2. Mandatory (37.2) Agreement between Principal Contractor and Contractor Prior to work commencing
- 3. Notification of Asbestos Work Prior to work commencing
- 4. Risk assessment, Safe Work Procedure, Fall Protection Plan Prior to work commencing
- 5. D.O.L registration as an Asbestos Contractor Valid -Prior to work commencing, At tender stage
- 6. Plan of work submitted to AIA signed copy Prior to work commencing
- 7. Plan of work submitted to Provincial director (D.O.L) signed copy Prior to work commencing
- 8. Copies of all waste manifest slips (Certificate of safe disposal) from approved dumpsite After each load taken to dumpsite
- 9. Weigh bridge / delivery note indicating how much waste was disposed of in kg After each load taken to dumpsite
- 10. Proof of Principal Contractor acceptance of Contractor H&S documentation Prior to work commencing.

3.53 Vegetation Management

Vegetation contractors to ensure accredited Pest control operator is on site when herbicide application is being performed. When hazardous substances are being used on site ensure to also refer to Hazardous substances section of SHE Specification for requirements and guidance.

Relevant training needs to be provided to operators of machinery used in the operations of vegetation management such as Chainsaws and Brushcutters.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

A PPE matrix that includes all relevant vegetation management PPE needs to be submitted to Eskom contractor safety department together with safety file documentation for evaluation purposes.

Safe work procedures needs to be discussed and made available to employees for referencing purposes.

When working in close proximity to large bodies of water or working in wetlands and in danger of drowning, a relevant safe work procedure needs to be submitted to contractor safety management for evaluation.

3.54 Live Work

The Contractor or his delegate shall ensure that persons are trained, assessed and authorised in writing to perform Live Work.

The Person in charge of Live work shall ensure that all work is carried out as required by live work

standards and Task Manual and shall exercise the required level of Supervision.

Before any Live Work is conducted determine if site conditions at substation are suitable for the task to be carried out safely.

Supporting equipment must be inspected, tested and certified as serviceable.

Check that all live work authorizations are valid and suitable to task at hand.

Check and verify whether relevant PPE is available, in a serviceable and usable condition.

Gloving method basic principles:

- a. Double insulation
- b. Cover on approach
 - Cover primary conductors first then second points of contact
- c. If you can touch it, cover it
 - When working on one potential, the other potential(s) within the MAD will be covered
 - All covers to overlap by 150mm
- d. Work at chest height or
- e. Gloves and sleeves to be worn when leaving ground and only removed when back on ground

Risks associated with Live Work:

These risks that are identified below are not the only risks associated with this task and must not be

discussed in isolation.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023	•	
Review Date	April 2024		

- a) Maintain minimum approach distance to other potentials.
- b) Access route needs to be determined before driving the vehicle into sub. If the vehicle cannot
- c) access the work area safely alternative access must be considered.
- d) Ensure that when any vehicles are used in vicinity of live apparatus that the minimum approach distances are observed and maintained.
- e) Ensure that all vehicles on work site are earthed to the structures.
- f) DC supply and yard inspections must be performed before any task is attempted.
- g) Current carrying capacity of jumper to be adequate for task.
- h) Non-live work staff is not allowed access during any live work activity.

Note: No Live work can be performed unless there is an approved Task Manual which has been designed from a Task Analysis highlighting the associated hazards and risks at each stage of the activity.

3.55 Security Management

When making use of security services on a contractor worksite adherence to Sectoral Determination 6: Private Security Sector published under Government Gazette No. 35633 of 28 August 2012, needs to be adhered to.

Security contractor companies and Security officers should be in possession of their respective PSIRA registrations.

Security officers need to be provided with adequate Uniform (Including bullet proof vests), Lighting, Shelter, Ablutions, Drinking water, Communication devices and Panic buttons.

An adequate Threat risk assessment needs to be conducted before any Security services can be provided.

3.56 Access to farms, rural areas, private property, public and Governmental land

When there is a need to access private property Eskom standard 240-80605256 ACCESS TO PRIVATE PROPERTY (INCLUDES STRATEGY ON ACCESSING GAME RESERVES / FARMS / SMALLHOLDINGS) needs to be followed. For any other Government owned land the necessary authorities should be contacted and arrangements to be made.

Be aware that various hazards might be present when accessing private land, for example wild animals, domestic animals and public members themselves can also pose risks.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

3.57 Hazardous substances

Scope of application

- (1) Subject to the provisions of sub regulation (2), these Regulations shall apply to an employer or a self-employed person who carries out work at a workplace which may expose any person to the intake of an HCS at that workplace.
- (2) The provisions of regulations 3(1), 6 and 7 shall not apply to—
- (a) a self-employed person; or
- (b) a person who visits a workplace as contemplated in sub regulation (1).
- (3) The provisions of these Regulations shall not apply in the case where the Lead Regulations or Asbestos Regulations apply.

Information and training

- (1) An employer shall, before any employee is exposed or may be exposed, after consultation with the health and safety committee established for that section of the workplace, ensure that the employee is adequately and comprehensively informed and trained, as well as thereafter informed and trained at intervals as may be recommended by that health and safety committee, with regard to—
- (a) the contents and scope of these Regulations;
- (b) the potential source of exposure;
- (c) the potential risks to health caused by exposure;
- (d) the potential detrimental effect of exposure on his or her reproductive ability;
- (e) the measures to be taken by the employers to protect an employee against any risk from exposure;
- (f) the precautions to be taken by an employee to protect himself or herself against the health risks associated with the exposure, including the wearing and use of protective clothing and respiratory protective equipment;
- (g) the necessity, correct use, maintenance and potential of safety equipment, facilities and engineering control measures provided;
- (h) the necessity of personal air sampling and medical surveillance;
- (i) the importance of good housekeeping at the workplace and personal hygiene;
- (j) the safe working procedures regarding the use, handling, storage and labelling of the HCS at the workplace; and
- (k) procedures to be followed in the event of spillages, leakages or any similar emergency situation which could take place by accident.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- (2) An employer or a self-employed person shall give written instructions of the procedures contemplated in paragraph (k) of sub regulation (1) to the drivers of vehicles carrying the HCS.
- (3) An employer or a self-employed person shall ensure that he himself or she herself or any person who in any manner assists him or her in the carrying out or the conducting of his or her business, have the necessary information and has undergone sufficient training in order for him or her to identify the potential risks and the precautions which should be taken.

Medical surveillance

- (1) An employer shall ensure that an employee is under medical surveillance if—
- (a) the employee may be exposed to a substance listed in Table 3 of Annexure 1;
- (b) the exposure of the employee to any substance hazardous to his or her health is such that an identifiable disease or adverse effect to his or her health may be related to the exposure, there is a reasonable likelihood that the disease or effect may occur under the particular conditions of his or her work and there are techniques to diagnose indications of the disease or the effect as far as is reasonably practicable; or
- (c) the occupational health practitioner recommends that the relevant employee should be under medical surveillance in which case the employer may call on an occupational medicine practitioner to ratify the appropriateness of such recommendation.
- (2) In order to comply with the provisions of sub regulation (1), the employer shall, as far as is reasonably practicable, ensure—
- (a) that an initial health evaluation is carried out by an occupational health practitioner immediately before or within 14 days after a person commences employment, where any exposure exists or may exist, which comprises—
- (i) an evaluation of the employee's medical and occupational history;
- (ii) a physical examination; and
- (iii) any other essential examination which in the opinion of the occupational health practitioner is desirable in order to enable the practitioner to do a proper evaluation.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- (b) that subsequent to the initial health evaluation contemplated in paragraph (a), the relevant employee undergoes examinations as contemplated in paragraph (a)(ii) and (iii), at intervals not exceeding two years, or at intervals specified by an occupational medicine practitioner.
- (3) An employer shall not permit an employee who has been certified unfit for work by an occupational medicine practitioner to work in a workplace or part of a workplace in which he or she would be exposed: Provided that the relevant employee may be permitted to return to work which will expose him or her if he or she is certified fit for that work beforehand by an occupational medicine practitioner.
- (4) The employer shall record and investigate the incident contemplated in sub regulation (3) in compliance with regulation 8 of the General Administrative Regulations.

Respirator zone

An employer shall ensure—

- (a) that any workplace or part of a workplace under his or her control, where the concentration of an HCS in the air is, or may be, such that the exposure of employees working in that workplace exceeds the recommended limit without the wearing of respiratory protective equipment, is zoned as a respirator zone;
- (b) that a respirator zone is clearly demarcated and identified by notice indicating that the relevant area is a respirator zone and that respiratory protective equipment as contemplated in regulation 11 must be worn there; and
- (c) that no person enters or remains in a respirator zone unless he or she is wearing the required respiratory protective equipment.

Records

An employer shall—

(a) keep records of the results of all assessments, air monitoring, and medical surveillance reports required by regulations 5, 6 and 7, respectively: Provided that personal medical records shall only be made available to an occupational health practitioner;

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- (b) subject to the provisions of paragraph (c), make the records contemplated in paragraph
- (a), excluding personal medical records, available for inspection by an inspector;
- (c) allow any person subject to formal written consent of an employee, to peruse the records with respect to that particular employee;
- (d) make the records of all assessments and air monitoring available for perusal by the relevant health and safety representative or relevant health and safety committee;
- (e) keep all records of assessments and air monitoring for a minimum period of 30 years;
- (f) keep all medical surveillance records for a minimum period of 30 years and if the employer ceases activities, all those records shall be handed over or forwarded by registered post to the relevant regional director; and
- (g) keep a record of the investigations and tests carried out in terms of regulation 12(1)(b) and of any repairs resulting from these investigations and tests, and the records shall be kept for at least three years.

Handling of hazardous chemical substances

- (1) Subject to section 10(3) of the Act, every person who manufactures, imports, sells or supplies any hazardous chemical substance for use at work, shall, as far as is reasonably practicable, provide the person receiving such substance, free of charge, with a material safety data sheet in the form of Annexure 1, containing all the information as contemplated in either ISO 11014 or ANSIZ400.1.1993 with regard to—
- (a) product and company identification;
- (b) composition / information on ingredients;
- (c) hazards identification;
- (d) first-aid measures;
- (e) fire-fighting measures;
- (f) accidental release measures;

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024	•	·

- (g) handling and storage;
- (h) exposure control / personal protection;
- (i) physical and chemical properties;
- (j) stability and reactivity;
- (k) toxicological information;
- (I) ecological information;
- (m) disposal considerations;
- (n) transport information;
- (o) regulatory information; and
- (p) other information:

Provided that, where it is not reasonably practicable to provide a material safety data sheet, the manufacturer, importer, seller or supplier shall supply the receiver of any hazardous chemical substance with sufficient information to enable the user to take the necessary measures as regards the protection of health and safety.

- (2) Every employer who uses any hazardous chemical substance at work, shall be in possession of a copy of Annexure 8 or a copy of sufficient information, as contemplated in sub regulation (1).
- (3) Every employer shall make Annexure 8 or sufficient information, as contemplated in sub regulation (1), available at the request of any interested or affected person.

Control of exposure to HCS

- (1) An employer shall ensure that the exposure of an employee is either prevented or, where this is not reasonably practicable, adequately controlled: Provided that—
- (a) where there is exposure for which there is a recommended limit, the control of the exposure shall be regarded as adequate if the level of exposure is below that limit or if the

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

relevant area is zoned and the level of exposure is reduced to below that recommended limit by means of adequate personal protective equipment only after the level has been reduced to as low as is reasonably practicable by any other means than personal protective equipment; or

- (b) where there is exposure for which there is a control limit, the control of the exposure shall be regarded as adequate if the exposure is at a level as low as is reasonably practicable below that control limit: Provided that in the case of temporary excursions above the control limit, the employer shall ensure—
- (i) that the excursion is without a significant risk from exposure;
- (ii) that the excursion is not indicative of a failure to maintain adequate control;
- (iii) that during the excursion, the area is temporarily demarcated as prescribed in regulation 8 (b); and
- (iv) the provisions of regulation 11 are complied with.
- (2) Where reasonably practicable, the employer shall control the exposure of an employee—
- (a) by limiting the amount of an HCS used which may contaminate the working environment;
- (b) by limiting the number of employees who will be exposed or may be exposed;
- (c) by limiting the period during which an employee will be exposed or may be exposed;
- (d) by using a substitute for an HCS;
- (e) by introducing engineering control measures for the control of exposure, which may include the following—
- (i) Process separation, automation or enclosure;
- (ii) the installation of local extraction ventilation systems to processes, equipment and tools for the control of emissions of an airborne HCS;
- (iii) use of wet methods; and

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- (iv) separate workplaces for different processes;
- (f) by introducing appropriate work procedures which an employee must follow where materials are used or processes are carried out which could give rise to exposure of an employee and that procedures shall include written instructions to ensure—
- (i) that an HCS is safely handled, used and disposed of;
- (ii) that process machinery, installations, equipment, tools and local extraction and general ventilation systems are safely used and maintained;
- (iii) that machinery and work areas are kept clean; and
- (iv) that early corrective action can be readily identified.
- (3) An employer shall ensure that the emission of an HCS into the atmosphere comply with the provisions of the Atmospheric Pollution Prevention Act, 1965 (Act 45 of 1965).

Personal protective equipment and facilities

- (1) If it is not reasonably practicable to ensure that the exposure of an employee is adequately controlled as contemplated in regulation 10, the employer shall—
- (a) in the case of an airborne HCS, provide the employee with suitable respiratory protective equipment and protective clothing; and
- (b) in the case of an HCS which can be absorbed through the skin, provide the employee with suitable non-HCS impermeable protective equipment.
- (2) Where respiratory protective equipment is provided, the employer shall ensure—
- (a) that the relevant equipment is capable of controlling the exposure to below the OEL for the relevant HCS;
- (b) that the relevant equipment is correctly selected and properly used;
- (c) that information, instructions, training and supervision which is necessary with regard to the use of the equipment is known to the employees; and

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023	•	
Review Date	April 2024		

- (d) that the equipment is kept in good condition and efficient working order.
- (3) An employer shall, as far as is reasonably practicable—
- (a) issue no used personal protective equipment to an employee, unless the relevant protection equipment is decontaminated and sterilised;
- (b) provide separate containers or storage facilities for personal protective equipment when not in use; and
- (c) ensure that all personal protective equipment not in use is stored only in the place provided therefor.
- (4) An employer shall as far as is reasonably practicable, ensure that all contaminated personal protective equipment is cleaned and handled in accordance with the following procedures—
- (a) Where the equipment is cleaned on the premises of the employer, care shall be taken to prevent contamination during handling, transport and cleaning;
- (b) where the equipment is sent off the premises to a contractor for cleaning purposes—
- (i) the equipment shall be packed in impermeable containers;
- (ii) the containers shall be tightly sealed and have clear indication thereon that the contents thereof are contaminated; and
- (iii) the relevant contractor shall be fully informed of the requirements of these Regulations and the precautions to be taken for the handling of the contaminated equipment.
- (5) Subject to the provisions of sub regulation (4) (b), an employer shall ensure that no person removes dirty or contaminated personal protective equipment from the premises: Provided that where contaminated personal protective equipment has to be disposed of, it shall be treated as HCS waste as contemplated in regulation 15.
- (6) Subject to the provisions of the Facilities Regulations, an employer shall, where reasonably practicable, provide employees using personal protective equipment as contemplated in sub regulation (1), with—

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		·

- (a) adequate washing facilities which are readily accessible and located in an area where the facilities will not become contaminated, in order to enable the employees to meet a standard of personal hygiene consistent with the adequate control of exposure, and to avoid the spread of an HCS;
- (b) two separate lockers separately labelled "protective clothing" and "personal clothing", and ensure that the clothing is kept separately in the locker concerned; and
- (c) separate "clean" and "dirty" change rooms if the employer uses or processes an HCS to the extent that the HCS could endanger the health of persons outside the workplace.

Maintenance of control measures

An employer shall ensure—

- (a) that all control equipment and facilities provided in terms of regulations 10 and 11, are maintained in good working order; an
- (b) that thorough examinations and tests of engineering control measures are carried out at intervals not exceeding 24 months by an approved inspection authority or by a person whose ability to do the measurements and tests is verified by an approved inspection authority.

Prohibitions

No person shall as far as is reasonably practicable—

- (a) use compressed air or permit the use of compressed air to remove particles of an HCS from any surface or person; or
- (b) smoke, eat, drink or keep food or beverages in a respirator zone or permit any other person to smoke, eat, drink or keep food or beverages in that zone.

Labelling, packaging, transportation and storage

An employer shall, in order to avoid the spread of contamination of an HCS, take steps, as far as is reasonably practicable, to ensure—

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- (a) that the HCS in storage or distributed are properly identified, classified and handled in accordance with SABS 072 and SABS 0228;
- (b) that a container or a vehicle in which an HCS is transported, is clearly identified, classified and packed in accordance with SABS 0228 and SABS 0229; and
- (c) that any container into which an HCS is decanted, is clearly labelled with regard to the contents thereof.

Disposal of hazardous chemical substances

An employer shall as far as is reasonably practicable—

- (a) recycle all HCS waste;
- (b) ensure that all collected HCS waste is placed into containers that will prevent the likelihood of exposure during handling;
- (c) ensure that all vehicles, re-usable containers and covers which have been in contact with HCS waste are cleaned and decontaminated after use in such a way that the vehicles, containers or covers do not cause a hazard inside or outside the premises concerned;
- (d) ensure that all HCS waste which can cause exposure, is disposed of only on sites specifically designated for this purpose in terms of the Environmental Conservation Act, 1989 (Act 73 of 1989), in such a manner that it does not cause a hazard inside or outside the site concerned;
- (e) ensure that all employees occupied in the collection, transport and disposal of HCS waste, who may be exposed to that waste, are provided with suitable personal protective equipment; and
- (f) ensure that if the services of a waste disposal contractor are used, a provision is incorporated into the contract stating that the contractor shall also comply with the provisions of these Regulations.

Offences and penalties

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Any person who contravenes or fails to comply with any provision of regulation 3, 4, 5, 6, 7, 8, 9, 9A, 10, 11, 12, 13, 14 or 15 shall be guilty of an offence and liable on conviction to a fine or to imprisonment for a period not exceeding six months and, in the case of a continuous offence, to an additional fine of R200 for each day on which the offence continues or additional imprisonment of one day for each day on which the offence continues: Provided that the period of such additional imprisonment shall in no case exceed 90 days.

3.58 Working in close proximity to live apparatus

Principal contractors must at all times ensure that all relevant legislation and best practices are followed when working near large bodies of water

Ensuring that an adequate risk assessment is conducted and control measures implemented when work is conducted near or close to bodies of water. Control measures including but not limited to relevant barricading and terrain stability assessment should be put in place.

3.59 Routine on job observations

In line with Eskom requirements the Principal contractor site supervisor is responsible to conduct routine on site job observations.

Eskom will confirm if this requirement is adhered to through site visits and audits.

Requirements:

- 1. Have at least 4 job observations been done per month?
- 2. Has a task observation for operation of specialized vehicle mounted equipment taken place within the last 3 months?
- 3. Has all staff who "Work at heights" been observed at least once a vear?
- 4. Have all staff who perform critical tasks been observed at least once a year whilst performing a critical task?

4. Acceptance

GEMMA Cluster Contractor safety department

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

5. Revisions

Date	Rev.	Compiler	Remarks
August 2015	0	F Pooe	This provides the initial SHE specification requirements that must be met by the relevant contractors who have been awarded a contract for the work to be performed for Eskom.
April 2023	1	GEMMA Cluster Contractor safety department	Reviewed to include all site specific requirements

ANNEXURE 1 – FLASH REPORT

ACCIDEN	NT / INCIDEI	NT REGISTER NO :				
PART 1 -	- TO BE CO	MPLETED FOR ALL	ACCIDENTS	S / INCIDENTS:		
ESKOM		PUBLIC		CONTRACTOR	CASUAL/TEMP	
POOL		COMPANY CAR		SCHEME	HIRED/PRIVATE	
				Public		

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

FIRST AID		ELECTRICAL CONTACT	
MEDICAL		EQUIPMENT DAMAGE	
FATAL		THEFT	
LOST TIME INJURY		ENVIRONMENTAL	
OCCUPATIONAL DISEASE		FIRE	
VEHICLE ACCIDENT		NEAR MISS	
STORM DAMAGE		ON DUTY	
OTHER		OFF DUTY	
CRIME RELATED INCIDENTS			
PRIORITISATION BY LINE & SHE USING			
THE MATRIX			
POF			
Matrix.pdf			
Piatrix.pui			
NAME OF PERSON INVOLVED			
UNIQUE NUMBER OR IDENTITY NUMBER			
NATURE OF INJURIES SUSTAINED			
UNIT/SECTION/DEPARTMENT			
DATE OF ACCIDENT/INCIDENT			
LOCATION OF INCIDENT/ACCIDENT			
MANAGER/SUPERVISOR			
TELEPHONE NUMBER			
FULL DESCRIPTION OF ACCIDENT/INCID	ENT:		
WHAT IMMEDIATE ACTION IS TAKEN TO	PREVENT S	IMILAR INCIDENT IN FUTURE?	
LESSON LEARNT (GENERAL)			
IMMEDIATE PRELIMINARY FINDINGS OB	5ERVED		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

SUBSTANCE ABUSE TEST DONE	YES	NO	

PART 2 - TO BE COMPLETED FOR PUBLIC / CONTRACTOR / LIVESTOCK ACCIDENTS

LOW HANGING CONDUCTOR / CONDUCTOR ON GROUND	OTHER	
IRRIGATION PIPE INTO LINE	OTTEN	
TELKOM LINE INTO ESKOM LINE		
EXTERNAL / SUB-CONTRACTOR		
UNLAWFUL ENTRY / VANDALISM CRANE INTO LINE		
TREE ON LINE		
ESKOM VEHICLE INVOLVED		

PART 3 – TO BE COMPLETED FOR ALL VEHICLE ACCIDENTS

ESKOM DRIVER & UNIQUE NUMBER	
ESKOM VEHICLE REGISTRATION NUMBER	
DAMAGES TO ESKOM VEHICLE	
THIRD PARTY REGISTRATION NUMBER	
DRIVER OF 3 RD PARTY VEHICLE	
TELEPHONE NUMBER OF 3 RD PARTY	
NAME OF WITNESS	
WITNESS TELEPHONE NUMBER	

PART 4 - TO BE COMPLETED FOR ALL ELECTRICAL CONTACTS

DD SHEET NUMBER	
LINE CLEARANCE	
SUB STATION AND NETWORK	
SECTION BREAKERS	
TEE LINE	
ESKOM VOLTAGE	
BEFORE THE METER	
BEYOND THE METER	

PART 5 – TO BE COMPLETED FOR ALL CRIME RELATED INCIDENTS

NAME OF INVESTIGATING OFFICER	
DATE , TIME REPORTED TO INVESTIGATING OFFICER	
ESTIMATED VALUE INVOLVED	
DESCRIPTION OF PROPERTY DAMAGE	
NAME OF POLICE STATION REPORTED TO	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

DATE, TIME REPORTED TO SAPS	
PERSON REPORTING TO SAPS	

PART 6 - TO BE COMPLETED FOR ALL MEDICAL AND LOST TIME INJURIES

NAME OF ATTENDING DOCTOR	
NAME HOSPITAL TAKEN TO	
TELEPHONE NUMBER OF DOCTOR / HOSPITAL	
FAX NUMBER OF DOCTOR / HOSPITAL	
DATE OF TREATMENT RECEIVED	
TIME OF TREATMENT RECEIVED	

PART 7 - TO BE COMPLETED FOR ALL INCIDENTS / ACCIDENTS

FULL NAME OF PERSON REPORTING INCIDENT	
NAME OF SAFETY REP REPORTED TO	
TELEPHONE NUMBER	
FAX NUMBER	
DATE OF REPORTING INCIDENT / ACCIDENT	
TIME OF INCIDENT / ACCIDENT	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		·

Annexure 2 – Transportation of people at the back of open vehicles

DISTRIBUTION TECHNICAL INSTRUCTION

15 December 2011

Enquiries: Moniwa Mahlangu Tel: (012) 421 6625

TECHNICAL INSTRUCTION: 11TI-027

ART: 21 - RISK MANAGEMENT

TRANSPORTATION OF PEOPLE AT THE BACK OF OPEN VEHICLES (BAKKIES)

Background

In the past years we have experienced fatalities where people were being transported at the back of open vehicles, this has had a major impact since these vehicles are not meant for the conveyance of people but material and tools instead and furthermore it is against existing laws in the country. It was also communicated through a technical instruction (10TI-012) issued on 26 March 2010 that the practice should be stopped, it was however observed that this practice still persists in the organization.

It is further expressed that all Eskom employees and contractors should ensure Zero Harm to employees whilst performing work and even travelling on a daily basis.

Instruction

In order to prevent these incidents and similar consequences, it is decided that no person will be transported in a vehicle that is not intended for the conveyance of people at all times. Therefore no one will be transported at the back of an LDV regardless of whether it is covered with a canopy.

This instruction should be implemented with immediate effect and be communicated to all the relevant parties.

This Technical Instruction is in accordance with Eskom's Policies & Procedure and applicable legislation.

Your commitment to Zero Harm to all is appreciated.

A Noah

APPROVED BY:

Chairperson - Distribution SHEQ Committee

ESKOM COPYRIGHT PROTECTED



Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

ANNEXURE 3 - TRAINING NEEDS ANALYSIS/ MATRIX

₩	skom
----------	------

CORE SAFETY, HEALTH AND ENVIRONMENT COMPETENCY TRAINING MATRIX

Template Identifier	240-43921898	Rev	4
Document Identifier	240-89306315	Rev	1
Authorisation Date	December 2019		
Review Date	December 2024		

Introduction:

This training matrix is to be read in conjunction with 32-477 (SHE Training and Development Procedure)

OU/BU		18	10	19	23	23	23	23	23	22	23	23	23	2 3	22	23	23	23	23	2 3
GM/PSM		4	1	1	0	0	0	0	0	1	0	0	0	0	1	0	0	0	0	0
Required Training		22	11	20	23	23	23	23	23	23	23	23	23	2 3	23	23	23	23	23	2 3
Training Compliance	99.0%	81.8%	90.9	95.0	100.0	100.0	100.0	100.0%	100.0	95.7%	100.0	100.0%	100.0	100.0	95.7%	100.0	100.0	100.0	100.0	100.0

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879 Rev		2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

			%	%	%	%	%		%		%		%	%		%	%	%	%	%
EMPLOYEE (Name and surname)	DESIGNATION	Safety Ind	uctionTraining		SHE Sys	stems Train	ning	Gen	eral Hea	ith and	safety	Construc Training		Management		Othe	OHS TI	raining F	Requiren	nents:
		Site Specific SHE Induction	Task Specific SHE Induction	ISO 14001 Environmental management system standard awareness	Occupational Health and Safety Assessment Series Awareness – OHSAS 18001: 2007	Occupational Health and Safety Assessment Series Implementation- OHSAS 18001: 2007	ISO 45001 Occupational Health and Safety Standard Awareness	General Health and Safety Awareness/ Introduction to Basic	Office Health and Safety	NEBOSH Occupational Healthand Safety	SHE Training for Supervisors	Contracts Health and SafetyManagement Training for Tender	Contracts Health and SafetyManagement Training for Procurement	Contracts Health and Safety Management Training for Construction Clerk-of-works, Project Curponicon Manager	First Aid	Fire Fighting	Safety representative	FAS and FAS Rescue	Fall Protection Planner	ETC.
		Done	Req	Req	Done	Done	Done	Done	Done	Req	Done	Done	Done	Done	Req	Done	Done	Done	Done	Done
		Req	Done		Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done
		Req	Done		Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done
		Req	Done		Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done
		1	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done
		Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done
		Done		Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done	Done

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	-
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Annexure 4 – Site Specific Evaluation Template

SITE SPECIFIC CONTRACTOR EVALUATION TEMPLATE								
PRINCIPAL CONTRACTOR DETAILS								
Site Name & Address	Telephone:							
Project Manager (Client)	Telephone: Cell No :							
Principal Contractor	Telephone: Cell No :							
Contractors	Telephone:							
Construction /Site Manager(Principal Contractor)	Cell:							
Construction H&S Manager (Principal	Cell:							

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Construction H&S Officer(Principal	Cell:
Contractor)	
Scope of Work	
Project Commencement Date:	
Project Completion Date:	

Codes	Legal Requirements	Legal Ref	STATUS		S	What to look for??	Actions & Comments
			Y	N	N/A		
A1	SHE Policy	Sec. 07				SHE Policy must be signed by the CEO	
		OHS ACT				of the company and dated.	
A2	Mandatory Agreement	Sec. 37(2)				A signed 37-2 agreement (new) by	
						Client and Principal Contractor and if	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template	240-73416879	Rev	2
Identifier	240-73410079	Kev	
Document	High/Constr 1	Rev	1
Identifier	riigii/Consti i	IVEA	•
Effective Date	April 2023		
Review Date	April 2024		

			applicable between their appointed contractors
		Section 10 (4)	Is there an agreement of Client and/ or Supplier using third party equipment/ machinery on site as well as security contracts
		32-726 (Annexure B)	Signed Annexure B Acknowledge of Eskom SHE rules and other requirements
A3.1	Construction Work Permit OR	CR 3(6)	Annexure 1- Proof of Construction Work Permit from Department of Employment and Labour
A3.2	Notification of Construction Work	CR 4(1)	Completed & Signed Annexure 2 (by both parties). Proof of stamped Annexure 2 from Department of Employment and Labour

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879 Rev				
Document Identifier	High/Constr 1	Rev	1		
Effective Date	April 2023				
Review Date	April 2024				

A4	H&S specification and Baseline Risk	CR 5(b)	Client Issued H&S Specification and	
	Assessment for the project	CR5(1)(a)	Baseline Risk Assessment to be	
			included in file	
A5	Total Number of employees on site	CR 5(1)(h)	Employee list site specific to the project	
A6	Letter of Good Standing	CR 5(1)(j)	A valid current FEM/COID letter of Good	
		- ()()	Standing, Number and expiry date/	
			Nature of Business must reflect the	
			scope of work of that specific project.	
A7	H&S Plan	CR7 (1)(a)	H&S Plan to be aligned to Clients H&S	
			Specification/ scope specific to the	
			project	

(Codes	Appointments & Competencies	Legal Ref	Status	What to look for?	Actions & Comments

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template	240-73416879	Rev	2
Identifier	240-73410073	Kev	
Document	High/Constr 1	Rev	1
Identifier	riigii/Collsti 1	Kev	
Effective Date	April 2023		
Review Date	April 2024		

			Y	N	N/A	
B1	CEO	Sec.16(1)				Letter of Appointment/ Letter of resolution
B2	CEO Assignee	Sec. 16(2)				Letter of Appointment
В3	H&S Rep.	Sec. 17				Letter of appointment and proof of competency
B4	H&S Committee Members	Sec. 19(3)				Letters of appointment(Management appointees as well as employee representatives)
B5	First Aider	GSR 3(4)				Letter of appointment and proof of competency
B6	Ladder Inspector	GSR 13A				Letter of Appointment & proof of competence
B7	Incident Investigator	GAR 9(2)				Letter of appointment and a certificate in incident investigation e.g. RCAT

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template	240-73416879	Rev	2
Identifier	240-73410079	Kev	
Document	High/Constr 1	Rev	4
Identifier	riigii/Colisti i	Kev	•
Effective Date	April 2023		
Review Date	April 2024		

B8	Appointment of Principal Contractor	CR 5(1) (k)	Letter of Appointment of Principal Contractor and competency
B9	Construction Manager	CR (8) (1)	Letter of Appointment, proof of competency in Construction/ Project Management
B10	Assistant Construction Manager	CR (8) (2)	Letter of Appointment & proof of competency
B11	Construction H&S Officer (either Full- time, part-time)	CR 8(5)	Letter of Appointment &SACPCMP Registration
B12	Construction Work Supervisor	CR 8(7)	Letter of Appointment & proof of competence
B13	Assistant Constr. Work Supervisor	CR 8(8)	Letter of Appointment & proof of competence
B14	Risk Assessor	CR 9(1)	Letter of appointment & proof of formal Risk Assessment course/training attended- Institution name
B15	Fall Protection Planner	CR -10(1)(a)	Letter of appointment and proof of training

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template				
Identifier	240-73416879	Rev	2	
Document	High/Constr 1	Rev	4	
Identifier	High/Collsti 1	Kev	•	
Effective Date	April 2023			
Review Date	April 2024		·	

			US:229994
B16	Temporary Work Supervisor	CR 12(2)	Letter of appointment and proof of competency
B17	Crane supervisor (Tower Cranes)	CR22(a)	Letter of appointment and proof of competency
B18	Training of Lifting Machine operator	DMR 18(11)	TETA accredited Certificates & permit to operate, Licences and Prdp's Class e.g. C32
B19	Construction Vehicle & Mobile Plant operator	CR 23(1)(d)(i)	Letter of appointment and course certificates/ Nationals driver licence (Check road worthiness of the construction vehicles on site) TLB's Drill rigs, Truck Mounted Cranes, MEWP's and LDV's

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template				
Identifier	240-73416879	Rev	2	
Document	High/Constr 1	Rev	4	
Identifier	High/Collsti 1	Kev	•	
Effective Date	April 2023			
Review Date	April 2024		·	

B20	Temporal Electrical Installation Inspector	CR24(d)	Letter of appointment and proof of competency Wire Licence	
B21	Electrical Machinery Inspector	CR 24(e)	Letter of appointment and proof of competency, Electrical Trade test	
B22	Stacking & Storage	CR 28(a)	Letter of Appointment & proof of competence - Formal training certificate	
B23	Fire Equipment Inspector	CR29 (h)	Letter of appointment and proof of competency	
B24	Mobile Elevated Working platforms, Skyjacks: Operating certificates on file	SANS 1887:2007	Operating Training certificates	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2	
Document Identifier	High/Constr 1	Rev	1	
Effective Date	April 2023			
Review Date	April 2024			

B25	Inspector of Lifting Machines &Tackle	DMR- 18 (5)	Proof of competency LMI &LME (DOEL and ECSA/ LEEASA) Accreditation Scope of approval
B26	Load Test certificate	DMR- 18 (5)	Load Test certificate for Lifting machines and hand held powered lifting devices(lever hoists)Safe working load at 110% to be tested
B27	Lifting machinery attaching devices and Lifting tackle 6 monthly examinations	DMR-18(6)	Proof of valid 6 monthly examination
B28	Lifting tackle	DMR- 18(10)(e)	3 Monthly inspection reports by the Lifting tackle inspector (Not ECSA accredited person)

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template	240-73416879	Rev	2	
Identifier	240-73410079	Kev	2	
Document	High/Constr 1	Rev	1	
Identifier	riigii/Consti i	IZEA		
Effective Date	April 2023			
Review Date	April 2024			

B29	Lifting tackle inspector	DMR- 18(10)(e)				Appointment and Competence approved ECSA accredited training	
B30	HCS Controller	HCS Regulations				Letter of appointment and proof of competence for Hazardous chemicals (Valid PCO for Vegetation Management)	
B31	Excavation Supervisor	CR13				Appointment and Competence	
Codes	Risk Assessment	Legal Ref	Stat	us		What to look for?	
			Υ	N	N/A		
C1	Risk Identification	CR 9(1)(a)				Risk Assessment template -Site specific risk identification	
						Copy of Baseline Risk Assessment	
C2	Risk Analysis	CR 9(1)(b)				A documented method on how hazards and risks are evaluated and analysed e.g.	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template	240-73416879	Rev	2
Identifier			
Document	High/Constr 1	Rev	1
Identifier	riigii/Colisti i		
Effective Date	April 2023		
Review Date	April 2024		

C3	Risk Control	CR 9(1)(c)	Documented Risk Mitigation/ Control plan List safe work procedures to mitigate, reduce or control the risks on the BRA
C4	Monitoring Plan/Mechanism	CR 9(1)(d)	A monitoring plan- How are risks monitored. Note: during execution phase planned task observation at 4 per month by the supervisor, Working at Heights & Specialized Vehicle equipment
C5	Monitoring /Observations	CR 9(1)(d	Schedule of observations 4 observations per month on the following Working at Elevated positions for all staff w@h annually, in the last 3 months Specialized vehicles Critical/High/ Extreme task

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document	High/Constr 1	Rev	1
Identifier		1164	•
Effective Date	Effective Date April 2023		
Review Date	April 2024		

C6	Review Plan	CR9(1)(e)				A review plan demonstrating the frequency of review of Baseline RA's(Date of review of the plan if terms of incident occurs)
C7	Task Manuals and Safe Work Procedures					Check for Review dates of Safe Work Procedures/ Task manuals
Codes	Fall Protection	Legal Ref	Stati	ıs		What to look for?
			Y	N	N/A	
D1	Fall Protection Plan	CR 10(2) CR 10(2) (a)				Proof of: a risks assessment that includes Hazards and risks associated with all work carried out at positions of elevation and procedures and methods used to address all the risks identified per location.
D2	Risk Assessment	32-418				Risks to be considered refer to 3.3.2 (b) pg. 8&9 of 32-418: Working at Heights

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2	
Document Identifier	High/Constr 1	Rev	1	
Effective Date	April 2023			
Review Date	April 2024			

			Procedure. Risk assessment to include the Rescue plan and methods used
D3	Inspection, testing and maintenance of all Fall Protection Equipment	CR10(2)(d)	Procedure outlining the Inspection, testing and maintenance of all Fall Protection Equipment
D4	Rescue Plan	CR10(2)(e)	Rescue Plan- procedure
D5	Certificate of medical fitness	CR10(2)(b	Procedure for employees medical surveillance for working at Fall risk position
D6	FAS and Rescue Training	CR 10(2)(c)	Programme for the training of employees working from a Fall Risk position & records thereof. US:229995&229998
D7	Work at height and rescue training must be provided by SETA approved instructors and service providers	32-418	Check training records against SETA approved service providers

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

D8	3.5.11 At least two persons per team have to be able to perform rescues if work at height is involved. All personnel trained to perform rescues will be trained to first aid Level 2.	32-418				Two rescuers per team &Proof of first aid level two training of rescuers.
Codes	Induction Training	Legal Ref	State	us N	N/A	What to look for?
E1	Proof of Eskom's Induction Training on file.					Proof of Eskom Induction conducted
E2	Was Induction done by the Company?					Proof of Company Induction (Attendance register) & Contractor Induction Curriculum Content
E3	OHS Training program /matrix					Procedure/ Program /IDP's/Matrix

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024	•	

Codes	Medical Surveillance	Legal Ref	Stat	Status		What to look for?	
			Υ	N	N/A		
FI	Crane operator's medical certificate of fitness	CR 22(f)				Medical Fitness certificates by OHP &OHNP	
F2	Construction Vehicle & Mobile Plant Operator's medical certificate of Fitness	CR 23(1)(d)(ii)				Medical Fitness Certificate by OHP &OHNP	
F3	Medical certificates for all employees	CR 7(8)				Medical Certificates of all employees in the project by OHP &OHNP	
F4	Certificate of medical fitness	CR10(2)(b)				Evaluation of medical fitness of employees working at heights by OHP &OHNP	
Codes	Procedures	Legal Ref			<u> </u>	What to look for?	
			Y	N	N/A		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document	High/Constr 1	Rev	1
Identifier		IXCV	•
Effective Date	April 2023		
Review Date	April 2024		

G6 G7	Procedure for prevention of Fall into water & rescue plan of persons in	32-345 CR26(1)(a)		Vehicle Safety Management Procedure to be aligned to Eskom 32-345 Procedure & Rescue Plan	
G6	performed at elevation to be contained in SHE plan. Vehicle Safety Management	, ,		Vehicle Safety Management Procedure to be	
G5	Safe Work Procedures for all work	32-418 Ref 3.3.2 (c)		Safe work procedure/s	
G2	Effective Evacuation Plan	CR 29(1)(i)		Evacuation Plan (e.g. Check emergency number, appointments letters and Fire extinguisher handling awareness etc.)	
G1	Incident Management Procedure	32-95		Incident Management procedure to be aligned to 32-95, wrt reporting, recording, classification and investigation	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template	240-73416879	Rev	2
Identifier	240-73410079	Kev	2
Document	High/Constr 1	Rev	1
Identifier	riigii/Collsti 1	Kev	
Effective Date	April 2023		
Review Date	April 2024		

			Υ	N	N/A		
Н	Copies of Valid ORHVS certificates and Authorizations if work is to be done in any Eskom HV yard, substation or servitude authorized by the GMR 2(1)					Copies of valid ORHVS certificates and Authorisations	
Codes	Security	Legal Ref	Statu	Status Y N N/A		What to look for?	
			•	14	IN/A		
l1	PSIRA Registration	Sectoral Determinatio n 6				Company PSIRA Registration	
12	PSIRA Registration	Sectoral Determinatio n 6				Employee/ Security officer PSIRA Registration	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

13	PPE and Equipment	Sectoral				PPE Equipment signed issue Register	
		Determinatio				(uniforms, bullet proof vest, panic buttons,	
		n 6				two way radios etc.)	
Codes	Consultation and Participation	Legal Ref	Stat	us		What to look for?	
			Υ	N	N/A		
J1	Statutory meetings/ Inspections	Sec 19, 17				Previous records of meetings from other	
	reports					projects, she representative reports	
Codes	Principal Contractor to inform the client regarding use of	Legal Ref	Status			What to look for?	
	contractors		V	N	N/A		
	Contractors			14	IN/A		
K1	Is the Principal Contractor using contractors?	32-136	•	N	N/A	List of contractors	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Other SHE Specification Requirements									
% Compliance to SHE Specification	100% co	mpliant		Below 100% compliant					
Function Representative	Name & Signature		Date						
	Surname								
Signature of Eskom SHE Officer									
Signature of Project Co-ordinator									
Signature of Principal Contractor Health and Safety Officer / Representative									

(100% requirements met) - The file is FULLY compliant in all respects and the contractor may access the site and commence work.

(Less than 100% requirements met) - The file is non-compliant – The contractor may not have access to site or commence work. The contractor must rectify the deviations as listed on the following page and the file is re-viewed and a new assessment form is completed achieving full compliance

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Annexure 5 – 37(2) Agreement Template

⊗ Eskom	
----------------	--

Occupational Health and Safety Act: Section 37(2) Agreement -Form

Template	240-43921804	Rev	5
Identifier	240-43921004	Kev	3
Document	240-77037682	Rev	6
Identifier	240-77037662		О
Effective Date	December 2020		
Review Date	December 2025		

SECTION 37(2) AGREEMENT CONCLUDED BETWEEN

[insert name of subsidiary or Eskom Holdings SOC Limited]
AND
(Name of contractor/supplier)
I,
85 of 1993 ("the Act"), as amended, and agree to ensure that all work will be performed and/or machinery or plant used in accordance with the provisions of the Act.
I undertake that [insert name of contractor/supplier] shall
strictly adhere to, and ensure that his/her employees adhere to, the provisions of the Occupational Health and Safety Act, 1993 (Act 85 of 1993).
I have been provided with SHE specifications for project/service[insert brief
details of project/service, for example, name, contract/project number]
and will comply with the requirements set out in these.
Dublic

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Occupational Health and Safety Act: Section 37(2)	Document	240-77037682	Day	c
Agreement - Form	Identifier	240-77037682	Rev	О

I accept and agree that the SHE specifications constitute arrangements and procedures between

						(insert nar	ne of co	ntracto	r/supplier	and [insert n	ame
of	subsidiary	or	Eskom	Holdings	SOC	Limited]	which	will	ensure	compliance	by
				[insert nai	me of c	ontractor/s	upplier] v	with th	e provisio	ons of the Ac	t, as
cont	templated in	sectio	on 37(2) o	f the Act.							
wai\ mar varia	ver of any of oner, be of a	the particular three thr	orovisions orce or eff , waiver, o	of this agr fect, unless or consent sl	eement confirn hall be e	or consent ned in writi ffective onl	to any ng and	departı signed	ure from t by both	n, modification these shall, in parties, and s and for the spe	any such
This	agreement i	is sig	ned on be	ehalf of the	parties,	each signa	atory to t	his wa	rranting th	nat he/she has	s the
requ	isite authorit	y to d	lo so.								
Sigr	ned this			day of			20		at		
				(I	Place)						
(Ful	I name)					(Signatur	œ)			on	
beh	alf of					(Con	tractor/s	upplie	r)		
	nesses 1		beh	alf of the co	ntractor		er (resp	onsible	for signii	ng the contrac	ct on

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Occupational Health and Safety Act: Section 37(2)	Document	240-77037682	Rev	6	Ī
Agreement - Form	Identifier	240-77037682	Kev	0	

2	
Signed this day of	20 at (<i>Place</i>)
(Full name	(Signature) on
behalf of [insert name of subsidiary or Eskom Ho (Contracts and/or Project Manager or Repres	<u> </u>
Witnesses	
1	
2	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Annexure 6 - Principal Contractor 5(1)(k) Template



Principal Contractor 5(1)(k)
Construction Regulations 2014
Appointment Letter

()()			
Document	240-64729708	Rev	7
Identifier	240-04/29/00		1
Effective Date	Aug 2021		
Review Date	September 2026		

I, (Name & Surname of the appointer) the (Designation of the appointer*) for (Site name) hereby appoint you (Add Appointee Name & Surname) being the Contractor's Representative for (Add full company Name) as Principal Contractor for (Scope of work) as per Construction Regulations 2014, Regulation 5(1)(k); to perform the following duties as prescribed by Construction Regulations 2014, Regulation 7(1);

Designated Functional Responsibilities and Authority

In particular you are required amongst others, to ensure the following -

- provide and demonstrate to the client sufficient documented Health and Safety Plan based on clients documented health and safety specification contemplated in regulation 5(1)b of CR 2014
- open and keep on site a health and safety file, which must include all documentation required in terms of the Act, which must be available on request to an inspector; the client, the client agent or a contractor;
- on appointing of any other contractor and ensure compliance with the provision of the Act as contemplated on regulation 7(1)c;
- ensure health and safety plan contemplated in regulation 7(1)(a) as well as contractors health and safety plan is available on request to an employee, inspector, a contractor; the client or client's agent
- hand over a consolidated health and safety file to the client upon completion of the construction work;
- include and make available a comprehensive and updated list of all contractors on site accountable to the principal contractor, the agreements between the parties and the type of work being done
- ensure that all his or her employees have a valid medical certificate of fitness specific to the construction work to be performed and issued by an occupational health practitioner in the form of Annexure 3.
- stop any contractor from performing a construction activity which poses a threat to the health and safety of persons and which is not in accordance with the client's health and safety specifications and the Contractor's Health and Safety Plan for the site.

You are required to report any deviations from the above-mentioned instructions to me.

You shall submit a written weekly report on all shortfalls that have not been met in terms of these regulations.

This appointment is effective from (Add Start Date Here) until withdrawn by the (Designation of the appointer*).

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

(Designation of the appointer*)	Date
Acceptance of Designation	
, , , , , , , , , , , , , , , , , , , ,	Add Unique number or ID number), hereby acknowledge and accept the above-mentioned a conversant with the relevant provisions of the Occupational Health and Safety Act No. 85 of
Principal Contractor CR 5 (1)((k) Date

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		·

Annexure 7 – Annexure B: Eskom Acknowledgement Form for OHS legal and other requirements

(4)	Eskom
	C3 (O111

Annexure B: Eskom Acknowledgement Form for OHS legal and other requirements

Template Identifier	240-43921804	Rev	5
Document Identifier	240-77471499	Rev	3
Effective Date	May 2021		

Annexure B: Acknowledgement Form for Eskom OHS legal and other requirements

NOTE: the supplier/contractor/tenderer has to ensure that he/she understands the OHS requirements listed hereunder.

- 1. The **supplier/contractor/tenderer** is expected to comply to the following documents when working at/rendering a service to Eskom but not limited to the following:
 - a. Eskom contractor Health and Safety requirements standards 32-136
 - b. OHS specification/requirements provided
 - c. Occupational Health and Safety Act 85 of 1993
 - d. Compensation for Occupational Diseases and Illnesses Act 130 of 1993

Note: Please note that after contract award, it is your responsibility to fully align the company's processes to Eskom's OHS requirements (policies, procedures, standards etc).

- 2. Penalties shall be enforced on the main supplier for non-conformance/s (identified for the main supplier and/o its contractor and/or supplier) pertaining to Eskom and/or Statutory OHS requirement/s.
- 4. Ensure that all employees (contractors/suppliers) undergo the relevant Eskom induction and the company's
- 5. Management of Contractors/ Suppliers

The main contractor/supplier:

- a) Has to demonstrate to Eskom the process and selection criteria applied when appointing contractors and suppliers.
- **b)** Has to provide notification to Eskom, prior to the appointment of contractors or suppliers for the commencement of work.
- c) Has to ensure that contractors/ suppliers have adequate resources and competencies.
- d) Is accountable for the management of its contractors/ suppliers in order to ensure that the applicable legal and Eskom requirements (that are applicable to the main supplier during contract execution) are complied with by the contractors or suppliers.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

- **e)** The main supplier shall monitor contractors or suppliers through audits and assessments with regard to OHS compliance during the execution of the work.
- f) The grounds for the termination of work done by contractors/suppliers shall be provided by the main supplier.
- **g)** All non-conformances/non-compliance by the contractors/suppliers (all tiers) to the main supplier shall be dealt with directly with the main contractor/supplier in terms of performance and penalty processes.
- h) Eskom reserves the right to verify this when deemed necessary. The contractor may be instructed to provide copies of testimonials/references and the contact detail of clients (including Eskom) for whom the Company has done previous work of a similar nature

I, the undersigned, hereby acknowledge that I have obtained that I fully understand them and the consequences of non-content in the consequences of non-content in the consequences.	
Signed at on day of	20
Company/Supplier Name:	
Name of Authorised person (CEO/Director/ Managing Director	or)
Signature	Date
Witness 1	
Witness 2	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Annexure 8 - Behavioural Observation Form

			Behavioural Observation Form - S	tandard			
Observer's Deta	ils						
Name of Observer: Date of Observation:							
Duration of Observation (min): Task Grading of Observer:							
Operation Unit: Observer's Dept./Area:							
Dept. observed:			Location/Area/PS/Unit:				
	People Observ	/ed	Group Obse	rved			
Number of people	a observed:		Employee:			Co-Observers	
Number of people			Principal Contractor:		Co-Obs	server:	
			Sub-Contractor:		Co-Obs	erver:	
Number of people	e working unsafe	ly:	Visitor:		Co-Obs	erver:	
Type of activity	Observed						
Type of activity	Observed:	S	afe behaviours and Safe Conditions	Observed			
	Safe		(If block is selected - describe safe beh	aviours and	condition	s in above block)	
Activity is:	Unsafe		(If block is selected - Please identify th	e unsafe acti	ions in th	e categories below)	
			Unsafe Categories				
	PPE		Positions of Peopl	е		Reactions of People	
□ Ears			☐ Striking against or getting struck by	against or getting struck by		□ Adjust PPE	
□ Eyes and fac	e		□ Caught in or between objects		☐ Change position		
☐ Feet and Leg	js .		□ Fall/could fall			□ Rearrange job	
□ Hands and A	ırms		□ Contacting extreme temperatures	Contacting extreme temperatures		□ Stop activity	
□ Head			☐ Inhaling or swallowing hazardous se	ubstances		Orderliness/Housekeeping	
□ Respiratory S	System		□ Repetitive motion	Repetitive motion		□ Not understood	
□ Trunk			□ Awkward positions			□ Not known	
			☐ Electrical contact			□ Not followed	
Tools	and Equipment	:		Procedure	s		
□ In bad, unsaf	e condition		□ Not adequate		□ Not	followed	
□ Not used co	rrectly		□ Not known		□ Not	understood	
☐ Wrong for job)						
			Reasons for Unsafe Behaviou	ırs			
□ Not available □ Knowled		vledge (training)					
□ Unaware of risk □		□ Not	□ Not practical				
□ Uncomfortable		□ Time	☐ Time pressure				
□ Cost		☐ Uncle	□ Unclear responsibility				
□ Forgetting							
Comments/Follo	ow-up Actions:	_					

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Annexure 9 – Annexure D OHS KPI SHE Post-contract Reviews



Annexure D: OHS KPI's and Post-Contract Reviews

Template Identifier	240-43921804	Rev	5
Document Identifier	240-77472561	Rev	3
Effective Date	May 2021		

The objectives and outcome of the OHS post-contract review shall be reflected in the contractual requirements for the supplier so that the supplier is aware of this exercise.

An evaluation will be conducted and will be supported by the objective evidence documented during the term of the contract. The evaluation report must be filed in the contract documents.

The following criteria (but not limited to) shall be considered for the review:

- Accident and injury data for the contract.
- OHS non-conformances.
- Duration and effectiveness in addressing and closing out OHS deficiencies/corrective actions.
- Legal compliance with OHS requirements.
- Number of behavioural safety observations conducted by contract manager and the contractor supervisors.
- · Close-out of Incident Investigations.
- No. of staff members (incl. subcontractors and suppliers) who contravened the Eskom Lifesaving rules.
- Prohibition and contravention notices issued by Department of Labour/Dept. of Mineral Resources notices, Department of Environmental affairs etc.
- · Contributions and effort made to improve OHS performance
- Contractor /Supplier (including its contractor) total number of incidents:
 - Fatalities,
 - Lost-time injuries,
 - reportable incidents (Department of Labour/Department of Mineral Resources/Department Environmental affairs)

The following matrix shall be used to assess the performance against the identified criteria. The OU/BU may add or remove KPI's to ensure practicality:

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024	•	



Annexure D: OHS KPI's and Post-Contract Reviews

Template Identifier	240-43921804	Rev	5
Document Identifier	240-77472561	Rev	3
Effective Date	May 2021		

1. Contractor OHS KPI (Business units or Operating units must ensure alignment to the business KPI's)

Supplier's name: Project Ref number:

Scope of work:

Ceiling Weighting Floor Kick Target Stretch 1. Fatalities 1.) No of fatalities experienced for the fiscal year or the duration of the project if less than 40% 2 0 -1 -2 12 months 1.) Lost time incidents/LTIR for the fiscal year the duration of the project less than 12 30% 2. Lost time incidents 3 2 0 / LTIR months

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

3. OHS compliance	Supplier average audit rating for the fiscal year the duration of the project less than 12 months	20%	1	2	3	4	5
	2.) Supplier has closed out audit findings/non-conformances within a specified period.		80%	85%	90%	95%	10%
	3.) Eskom Safety rules violation for the fiscal year the duration of the project less than 12 months		40%	20%	0%	-20%	-40%
4. OHS improvement programme	Supplier has implemented OHS interventions or initiatives to improve on the Health and Safety of employees	10%	60%	70%	80%	90%	100%
	Supplier participate in Eskom's OHS interventions and programmes (Safety stand offs, OHS campaigns/events, cooperation, provide the required feedback or information etc)		60%	70%	80%	90%	100%

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		



Annexure D: OHS KPI's and Post-Contract Reviews

Template Identifier	240-43921804	Rev	5
Document Identifier	240-77472561	Rev	3
Effective Date	May 2021		

2. Post Contract Evaluation Report:

Unacceptable	Satisfactory		Good		Exceptional
Comments:					
Decision:					
Will this Supplier be Recomn	nended for Future	Work With	in Eskom? Tick App	icable Co	<u>lumn</u>
Yes, With Reservations		Yes		No	
Substantiate the reasons for	reservation (if app	licable):			
Name and Jackson Paragraph			and the Late of the second second		
Names and designations and c	ontact details of per	rsons that c	onducted the post cor	itract revie	eW:

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



REFURBISHMENT OF PARK HOMES NCOU

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Unacceptable	Satisfactory	Good	Exceptional
Administrative:			
	ation data on this form have be	on completed by	
Performance record and evalua	ation data on this form have be	en completed by:	
Client representative:			
Name:	Title:		
Signature:	Date:		
Additional comments:			

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Annexure 10 – TASK OBSERVATION FORM

					Template 2		240-43921804		Rev	6			
Œ	Task Observation Tem		€Skom		emp	late	Docume Identifie		240-114	350002	Rev	2	
							Effective	e Date	Novemb	oer 2020			
							Review	Date	May 202	25			
	Task Observer Name:					Task C	bserved / Sco	pe of Wor	k:				
1.	Section / Department:					Location	on:						
	Occupation:					Is ther task?	e a procedure for this						
	Date:					Proced	dure Ref. No.:						
	Time with task:					Work	Order No.:						
2.	REASON FOR THE	OBSI	RVATION										
	Planned	Ad	ccident Repeater		Expe	rienced	Worker	Ri	sk Taker	Foll	ow-up		
3.	TASK OBSERVATION	ON											
	Did employee adhere to t requirements?	he pro	cedure / practise			Could S	ubstandard A	acts and Co	nditions obs	erved lead t	o:		
	Did the employee use the	presc	ribed PPE			- In	jury						
	Did the employee adhere per activity performed at					- O	ccupational H	ealth Illne	sses				
	Tools & Equipment:					- C	osts (Delays)						
	- Used correctly					- Po	oor Quality (N	on-confor	mance)				
	- In good and safe co	nditio	n			- Er	nvironment ([Damage, Po	ollution, Wild	life)			

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

	- Test certificates valid and available			- Public Liability	
	Pre-task Planning (Toolbox Talk):			- Work Site (Clean and Tidy)	
	- Work Instruction / Task Manual used			- Live saving Rules (Transgression)	
	- Complete workers register				
	Risk assessment been done				
	Valid work permit available				
4.	NON COMPLIANCE PRACTICES OBSERVA	ATION			
	Working at unsafe speed			Failure to warn	
	Using unsafe equipment			Taking chances	
	Using equipment unsafely			Failure to identify hazards	
	Unsafe loading, placing & lifting			Failure to secure / lock-out	
	Taking unsafe position			Safety sign ignored	
	Safety rules ignored				
5.	NOTE: ALL OBSERVED CLASS HAZARDS SHALL REQUIR OBSERVED DEVIATIONS / NON-CONFORM			NTERVENTION	
J.	OBSERVED DEVIATIONS / NON-CONTOL	VIAIVIA	CLJ		
6.	AT RISK BEHAVIOURS				
7.	PROPOSED CONTROLS				
	Compile a procedure for this task			Issue a standing instruction	
	Revise present procedure			Change work methods	
	Retrain employees			Professional referral	
	Engineering revision			Coaching	
8.	ANALYSIS				

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

	IAC – Inadequate capability		alcohol	g or N	AIN – Inadequate maintenance	
	KNO – Lack of knowledge		NAT – Natural factors	E	QU – Inadequate equipment	
	SKI – Lack of skill		LEA – Inadequate leadership		TA – Inadequate work / training andards	
	STR - Stress		ENG – Inadequate engineering	W	/EA – Wear and tear	
	MOT – Improper motivation		PUR – Inadequate purchasing	C	ON – Inadequate control	
9.	DISCUSSION BETWE	EN SUPERVISO	R / OBSERVER AND EMPLOY	/EE		
	EMPLOYEE EXPLANATION F					
	A CREENIENT TO CHANGE A	T DICK DELIAN (IOUD				
	AGREEMENT TO CHANGE A	I KISK BEHAVIOUK				
10	FOLLOW/ LID ACTION				14/1/501 / 14/1/0	
10.	FOLLOW-UP ACTION				WHEN / WHO	
11.	SIGNATURES				•	
Perso	on being observed			Date		
Task	Observer			Date		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Annexure 11 - Contractor SHE File Hand Back Record

₩ Eskom	CONTRACTOR	SHE FILE HAND BACK	Identifier	240-76755865	Rev	
Z A €2KOLLI		RECORD	Authorisation Date	01 March 2014		
Delete not applicable	:					
*Contract / Project : _						
*Contract / Project N	umber:					
l,		in my capacity as _				
have received the SHI	E File for the abo	ove mentioned Contract	/ Project from:			
Details of Contractor						
Trading N	lame					
Company Registra	ation Number					
Contact P	erson					
Contact No	umber					
Addre	ss					

The contents of the file include:

Note: member receiving to ✓ requirement for inclusion in file for project specific

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Requirement	Minimum	In file
All drawings photographs designs	Requirement ✓	
All drawings, photographs, designs	✓	
Copy SHE policy	V	
Copy Letter of Good Standing	∀	
Sect 16(2) Appointment	,	
Project / Contract scope of work	✓	
Project / Contract SHE plan	✓	
Principal Contractor Appointment	√	
H & S Representative appointment	√	
Safety Officer appointment	✓	
Construction Notification application	✓	
Construction Work Permit approval	✓	
Approved copy of specific SHE plan	✓	
Project Organisational Organogram	✓	
Breakdown for costing for SHE	✓	
Scope of Work	✓	
Competency Training records	✓	
Incident investigation records	✓	
Base Line Risk Assessments	✓	
Fall protection plan	✓	
Medical Certificates	✓	
Emergency Management plans	✓	
Fire Risk Management plans	✓	
First Aid Management	✓	
SHE Communication System	✓	
Pre start job assessment / talk	✓	
Relevant Equipment check lists	✓	
Audit reports		
•		
•		
•		
•		
•		
•		
•		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

• Assessor to add additional project / contract specific requirements

Template	240-73416879	Rev	2
Identifier	240-73410073		_
Document	High/Constr 1	Rev	1
Identifier	riigii/Colisti i	IZEA	•
Effective Date	April 2023		
Review Date	April 2024		

Comments by member receiving file:	
SHE File handed in by:	
Name:	Signed:
Date of Handover:	
SHE File received by:	
Name:	Signed:
Date Receiving:	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024	•	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template	040 70440070	Rev	
Identifier	240-73416879		2
Document	High/Constr 1	Rev	1
Identifier	High/Collsti 1	IVEA	
Effective Date	April 2023		
Review Date	April 2024	•	

Annexure 12 – OHS Tender Evaluation Template



Annexure C 4: OHS Tender Evaluation Template (Construction work)

Template Identifier	240-43921898	Rev	5
Document Identifier	240-106084699	Rev	2
Effective Date	May 2021		

1.	Tenderer's / Supplier's name:	Tender Ref number:
	Scope of work:	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template	240-73416879	Rev	2
Identifier	240-73410079		2
Document	High/Constr 1	Rev	1
Identifier	riigii/Colisti i	IZEA	
Effective Date	April 2023		
Review Date	ew Date April 2024		

Ref.	OHS Tender Returnable	Submission Y = Yes N= No	<u>Comments</u>
		NI/A — NI - 4	
		N/A = Not applicable	
1	Annexure B		
	Is the acknowledgement of Eskom's OHS legal and other requirements form signed and submitted by the tenderer?		
2	OHS plan (Must address the project /scope of work OHS risk(s) and aligned with the health and safety specification or requirements)		
3	Costing for Health and Safety management		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template	240-73416879	Rev	2
Identifier	240-73410073	1164	4
Document	High/Constr 1	Rev	1
Identifier	riigii/Collsti i	IZEA	•
Effective Date	April 2023		
Review Date	v Date April 2024		

Ref.	OHS Tender Returnable	Submission Y = Yes N= No N/A = Not applicable	<u>Comments</u>
	Has the tenderer submitted detailed costing for SHE (the cost should be broken down not provided as a lump sum)?		
	 The costing must be based on the overall scope of work/service to be performed; The scope of work and the risk assessment may serve as a guideline. 		
4	Baseline Risk Assessment (BRA)		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template	240-73416879	Rev	2
Identifier	240-73410073	IVEA	_
Document	High/Constr 1	Rev	4
Identifier	riigii/Collsti i	IZEA	•
Effective Date	April 2023		
Review Date	te April 2024		

Ref.	OHS Tender Returnable	Submission Y = Yes N= No N/A = Not applicable	<u>Comments</u>
	Identification, assessment and management of OHS and COVID-19 risks related to the scope of work. The methoDoELogy and applicable risk matrix used for the risk assessment must be provided together with the BRA		
5	Valid Letter of Good Standing (COIDA or equivalent)		
6	OHS policy signed by CEO		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template	240-73416879	Rev	2
Identifier	240-73410079		2
Document	High/Constr 1	Rev	1
Identifier	riigii/Colisti i	IZEA	
Effective Date	April 2023		
Review Date	ew Date April 2024		

Ref.	OHS Tender Returnable	Submission Y = Yes N= No N/A = Not applicable	<u>Comments</u>
	The submitted policy document must comply to OHS Act Section 7		
7	OHS Competency (Consider scope of work, risks, SHE plan and applicability) CV,s and qualifications / certificates (List competencies required) - First aiders - Fire fighters - Construction Supervisor - Safety officer (SACPCMP registered)		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template	240-73416879	Rev	2
Identifier	240-73410079		2
Document	High/Constr 1	Rev	1
Identifier	riigii/Colisti i	IZEA	
Effective Date	April 2023		
Review Date	ew Date April 2024		

Ref.	OHS Tender Returnable	Submission Y = Yes N= No N/A = Not applicable	<u>Comments</u>
	 SHE Representative HCS Controller Incident investigator Fall Protection Plan Developer Truck Mounted Crane Operator 		
8	Medical Fitness Certificates - by Occupational Health Practitioner for any two employees or Medical Program		
	Recommendation		Recommended or Not recommended.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

*NOTE: For explanatory notes for the listed items (SHE requirements) please refer to 240 - 77433139 Annexure A: Supplier Risk Category

1. Other requirements

Annotation: Populate additional OHS tender returnable(s) that are applicable to the scope of work and need to be evaluated prior to contract award. This section must be deleted if not applicable.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Ref.	OHS Tender Returnable	Submission Y = Yes N= No	<u>Comments</u>
1	COVID-19 requirements: 1. COVID-19 risk assessment 2. COVID-19 Workplace plan		
	Recommendation		Recommended /Not Recommended

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Eskom OHS Representative Designation Signature Date

Development Team

Diane Maunatlala

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION **PROJECT**

WORK AT HEIGHT ON JOB

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

240-43921804

Rev

6

Annexure 13 - Working at Height On Job Observation Form Template

Identifier

€ Skom		OBS	OBSERVATION FORM				Document Identifier		240-141493501		Rev	1	
76 C21	CITI							ctive Da		January			
							Rev	iew Dat	е	January	y 2023		
Unit/Area/S	ection:												
	ng observed: _												
Observation													
	rect task/activ				000	1100.							
TICK LITE COI	Tect task/activ	ity iii one oi	file nove2 n	GIOW. V									
Planne	ed /	Ad hoc	Risk tak	er		perie			cident		Follow-up		
						work	er	rep	eater				
Suspecte	d use of dru	gs/alcohol?	Yes	No									
Working	Working	Working	Working	Climbi	ing	Clin	nbing	Climbin	g V	Vorking	Working	on	
from a	from	from a	from a	and	_	and		and		n top of			
Ladder	Scaffolding	Cherry Picker	Crane in attached		working on Lattice		king Steel	working on	,	truck's ad	transform	ier	
			basket	Structi						ody			
Visual ins	spection of F	AS Unit			YE	ES	NO	N/A		Comme	nts or obs	ervatio	n
•	nents of the F		l be examine	ed:									
	Full Body Harn		ب م ماه م با										
•	win Lanyard \	VILLI SUOCK A	osorder										

Public

Work Positioning Lanyard

Attachment Slings

Hooks

D-ring Carabiners

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Is the climber in possession of a FAS Rescue Kit?		
Is the climber working under the supervision of the rope		
access lead?		
Fitting/Adjusting FAS		
Locate and pick up by the dorsal D-ring and put the		
shoulder straps on from behind the shoulders		
Couple together the male and female parts of the		
quick-lock on chest strap and adjust tension		
Fit the waist belt and adjust to the correct waist size		
Fit the leg straps		
Connect the twin lanyard to the dorsal D-ring of the		
harness		
Fit the one connector of the work positioning lanyard to		
the left D-ring and the other connector to the right D-ring		
of the harness belt		
Co-worker/s check if the FAS is securely		
fastened around the wearer's body		
Not too tight and not too loose – measure		
between legs using 2 fingers Working from a ladder/PML		
Has the ladder been inspected before use?		
Has the ladder been secured at the bottom before		
climbing?		
Is the ladder on a ladder register?		
When ascending or descending from a ladder, the user		
shall hook the pylon hooks alternately onto the ladder		
rungs		
The user shall use the centre of the ladder to ensure		
proper balancing on the ladder		
Does the user secure the ladder at the top?		
Working on transformers – ground level		
When ascending/descending from the transformer		
using a short ladder – the ladder shall be secured at the		
bottom by another person		
If an anchoring point is available; ensure that the two		
big pylon hooks are hooked to the anchor point so that		
the user is anchored at all times		
If there are no suitable anchoring points, create one by		
using the attachment sling/s		
Attach the pylon hooks onto the sling/s		

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Alternatively; an approved portable lifeline can be used	
Working with climbing shoes/irons	
Check pole for rot	
Carry out a visual inspection of the climbing shoes or	
irons:	
Hook (not bent)	
 Sharpness of spikes 	
 Leather straps (not damaged) 	
 Buckles (not damaged) 	
No cracks in the metal	
Take the climbing shoes/irons to the bottom of the pole.	
Put one foot on the footplate and fasten the leather	
straps around the foot and then repeat with the other	
foot	
Stand as close as possible to the pole, then loop the	
work positioning lanyard of the FAS Unit twice around	
the pole, keeping it crossed (Figure 8)	
Attach the connectors of the work positioning lanyard to	
the left and right D-rings of the waist belt Place the first climbing shoe hook around the pole as	
low as possible and place the second shoe hook around	
the pole above the first hook	
Use thumbs to move the crossed loop of the work	
positioning lanyard upwards, taking care to keep the	
loop crossed and as small as possible	
Is the user in possession of a rope-grab system and has	
a suitable anchor point been identified to anchor it on?	
When reaching the work position, ensure that the two	
big pylon hooks are hooked at all times to an anchor	
point	
To descend; slowly move down the pole in the same	
way you moved up	
Lattice Structures	
Is the steel structure fitted with climbing pegs?	
Is there safe access at the anti-vandal devices?	
Is the structure sound enough to be climbed?	
Does the climber have the correct PPE? i.e.:	
Hat with short peak and chin strap	
Safety glasses	

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template	240-73416879	Rev	2	
Identifier	240-73410079	Kev	_	
Document	High/Constr 1	Rev	4	
Identifier	riigii/Colisti i	Kev	•	
Effective Date	April 2023			
Review Date	April 2024			

Gloves				
 Shoes 				
 Are all tools attached with lanyards? 				
Correct thermal underwear for climate of the				
day				
Has the correct method been adhered to for fastening				
the climbing hooks?				_
Is there a device that controls the rate of descent?				
Emergency Plan and Rescue Plan				
Does the climber have or know of the site-specific				
approved Fall Prevention Plan?				
Does the climber know of the Emergency Plan?				
Is an active system being operated by another				
employee for the purpose of arresting the fall of a rope				
access worker?				_
Access zone				
Has the area been determined where employees are at				
risk of falling, such as near a working edge?				_
Deviations/Comments/Feedback:				
Training needs identified:				
· ·				
SIGNATURE :	DA	TE:	 	
Person being observed				
-				
SIGNATURE :	DA	TE:	 	
Observer				
SIGNATURE :	DA	TE:	 	

Annexure 14 - Costing for OHS

Chairman of H & S Committee

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Health and Safety Costing

	Health and Safety Costing						
ITEM	DESCRIPTION	Reference	UNIT	QUANTITY	PRICE PER UNIT	TOTAL	
				(1)	(2)	(1)*(2)	
1.	Supply of all items of Personal Protective Clothing/Equipment & ensure use thereof for full compliance						
1.1	Steel toe capped safety boots						
1.2	Appropriate protective clothing						
1.3	Gloves						
1.4	Colour coded hardhats [Blue for labourer, Red for First Aider, Green for						
1.5	SHE Reps and White for Supervisors and Managers] Ear protection (earplugs etc)						
1.6	Eye protection appropriate to task performed	<u> </u>					
1.7	Induction tags/cards	General Safety Regulation 2: Personal Safety Equipment and Facilities					
1.8	Dust masks						
1.0	Asbestos PPE						
1,10	Covid 19 PPE						
1.11	Luminous high visibility safety vests						
	Any other: Contractor to specify:Rain coats						
1.12	PPE						
2.		Performing work in a Fall Risk Position					
2.1	Fall Protection Plan developer						
2.2	Fall Protection Plan						
2.3	Fall protection equipment (Safety Harness)						
2.4	Fall Prevention equipment (Gaurdrails, barricading, achors)	Construction Regulation 10: Fall Protection					
2.5	Evaluation of physical fitness of personnel working at heights	Conditional regulation 10.1 all 1 releasion					
	Any other: Contractor to specify:						
2.6							
•		Bandardina and Olaman					
3	Supply & install, including removal upon completion to ensure full	Barricading and Signage		1			
3.1	compliance to legislation						
3.2	Rigid type barricading	Construction Regulation 13: Excavataion					
3.3	Temporary fence barricading along perimeter of excavated area	Oonstruction regulation to: Excertatation					
3.4	Appropriate equipment/tools for excavation.						
3.5	Provision of all signage for all relevant activities in terms of latest revision of legislation	General Safety Regulation 2B: Display of substituted notices and signs					
	Any other: Contractor to specify :						
3.5	,						
4		Related Training					
4.1	Induction Training						
4.2	First Aid Training						
4.3	Health and Safety Representative training			1			
4.4	Incident Investigator Training Hazard Identification & Risk Assessment Training			1			
4.6	Training of Personnel working at heights			1			
4.6				<u> </u>			
4.7	Operating for High Voltage systems Ladder Inspector Training	Construction Regulations, General Safety Regulations, ORHVS, Driven		1			
4.8	Crane Operator Training	Machinery Regulations					
4.9	Construction vehicle & Mobile plant Operator e.g. trucks, drills bakkies etc						
	· · · · · · · · · · · · · · · · · · ·						
4.11	Training to operate Jackhammer, etc						
4.12	Fire Fighting Training						
4.13	Any other: Contractor to specify:						
5		Safety Management System					
5.1	Implementation of Health and Safety Management System on site as detailed in OHS Plan and associated documentation						
5.2	Availability of Principal Contractor resources & systems. Provision of monthly audits to ensure compliance to Client and Legaslative requirements. Submission of monthly statistical data and audit reports to Client	Construction Regulation 7: Duties of Principal Contractor and contractor, 32-726: SHE Commercial Process, PLCM					
5.3	Site close out and OHS file submission	_					
ე.ქ	Site close out and OHS file submission						

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

HEALTH AND SAFETY WORKS Cont.

ITEM	DESCRIPTION		UNIT	QUANTITY	PRICE PER UNIT	TOTAL
				(1)	(2)	(1)*(2)
6		Occupational Hygiene				
6.1	Health Risk Assessment					
6.2	Occupational Hygiene Surveys					
6.2.1	Ergonomics	Naise Indused Heaving Less Devulations, Ashetese Devulations, Herordeus				
6.2.2	Dust survey (asbestos analysis and reporting to DoL	Noise Induced Hearing Loss Regulations, Asbetsos Regulations, Hazardous Chemical Substances Regulations				
6.2.3	Noise survey for all noise generating equpment	Chemical Gubstances Regulations				
6.2.4	Structural Engineer Survey					
6.2.5	Any other: Contractor to specify:					
7	Medical Screeining					
7.1	Medical Screeining (pre, post and during) done by Occupational Health Practitioner	Construction Regulation 7(8), Noise Induced Hearing Loss Regulations, Asbetsos Regulations, Hazardous Chemical Substances Regulations				
8		Transport				
8.1	Transportation of employees in compliance with the Transportation of employees procedure	Construction Regulation 23(2) (i) & (j): Construction Vehicles and Mobile Plant				
9		Human Resources				
9.1	Appointment of a Full-Time Construction Safety Officer	Construction Regulation8(5): Management and Supervision of Construction				
9.2	Structural Engineer (For any dismantling/ demolition activities)					
9.3	Any other: Contractor to specify:	work				
	•	<u> </u>			TOTAL	

Annexure 15 – Live Work Task Observation Template

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		



Live Work Task Observation (FOR GLOVING, STICK & BAREHAND)

	LIVE WORKING TASK OBSERVATION FOR GLOVING, STICK & BAREHAND			
NO.	Activity	Yes	No	N/A
1.	Source breaker off ARC and panel labels applied? (According to HV Live Working Standard) Compulsory for S&B, ladder, Substation Live Work and scaffolding without kick boards			
2.	Was job planned? All equipment and material on site.(All documentation to be available)			
3.	Is an approved task manual on site and was it used when the task was discussed?			
4.	Are equipment tested, inspected and cleaned?			
5.	Were the tools and equipment properly transported? Are the tools and equipment in an acceptable condition? (clean/no scratches)			
6.	Team talk held – LW declaration, risk identification and step by step procedure communicated, completed and signed?			
7.	Is the structure on either side of the work place inspected as per HV Live Working Standard?			
8.	Is the task manual(s) followed? Are there sufficient workers to do the task safely and according to the task manual?			
9.	Is the team authorised for the task manual(s) they are using and are their authorisations valid?			
10.	Line equipment: - Was the following considered or calculated? - Conductor size, Span lengths and Conductor weight / displacement or tension. Is the lifting equipment suitable for the task?			
11.	Vehicle positioned, earthed and checked for hazards?			
12.	Is the 2m Vehicle clearance observed and demarcated?			
13.	Is the FAS attached to work platform and are workers wearing the required protective equipment.			
14.	Is communication adequate between PiC and workmen, as well as work-team and control?			
15.	Did the worker use conductive gloves when disconnecting strain insulators? (S&BH)			
16.	Are workmen observed by ground workers?			
17.	Were leather gloves used when handling ropes and slings including the ground level workers?			
18.	Were adequate measures taken to avoid equipment damage and did all workers concentrate on the task?			
19.	Were distractions dealt with and was supervision adequate?			
20.	Were weather conditions favourable and was this monitored?			
21.	Blankets, liners and insulated boom inspected and cleaned? Blankets, gloves and sleeves covered up when not in use? (Gloving)			
22.	Are basic principles applied correctly?			
23.	Is line equipment / covers correctly applied? Is work carried out on one potential at a time?			

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

	Correct use of all equipment and lifting gear – Snubbing bracket, hand lines and Rope Blocks? Do		
24.	they remove and lower the equipment to ground level safely?		
25.	Were risks discussed and taken into account? Did the workers position themselves out of the way of possible falling objects?		
26.	Does the team follow the task manual(s) and step by step procedure as discussed beforehand?		
27.	Are the sticks and equipment marked with SWL and unique numbers where applicable?		
	Are the sticks marked to indicate the correct minimum approach distance? Did any worker		
28.	encroach on the minimum approach distance?		
	Is the access equipment in a good working condition and clean? Is the access equipment		
29.	inspected and certificates up to date?		
	Is the inspection file checked and up to date? (Tools daily and monthly etc.) (Personnel certificates		
30.	valid)		
31.	Are sticks packed on racks, the equipment and vehicles correctly positioned?		
32.	Was work area demarcated as per HV Live Working Standard		

TEAM OBSERVED					
Name	U/No. / ID No.	Designation (PiC/PtP)	Signature		
	REMARKS/COMME	ENTS			
PLACE:					

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.



HIGH RISK / CONSTRUCTION PROJECT

Template Identifier	240-73416879	Rev	2
Document Identifier	High/Constr 1	Rev	1
Effective Date	April 2023		
Review Date	April 2024		

Work Order number:				
Task Manual number:				
Declaration Number:				
Details of work carried out:				
OE	BSERVED BY			
Name:	Designation:			
Signature:	Date:			

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.