| Item No | | Quantity | Rate | Amount |
|------------|--|----------|------|--------|
| | SECTION 1 | | | |
| | BILL NO. 1 | | | |
| | PRELIMINARIES | | | |
| | BUILDING AGREEMENT AND PRELIMINARIES | | | |
| | MEANING OF TERMS "TENDER / TENDERER" | | | |
| | Any reference to the words "Tender" or "Tenderer" herein and/or in any other documentation shall be construed to have the same meaning as the words "Bid" or "Bidder" | | | |
| | PRELIMINARIES | | | |
| | The JBCC Preliminaries Code 2103, May 2005 edition for use with the JBCC Principal Building Agreement Edition 4.1 Code 2101, March 2005 is taken to be incorporated herein. The tenderer is deemed to have referred to these documents for the full intent and meaning of each clause. These clauses are referred to by number and heading only. Where standard clauses or options are not applicable to the contract such modifications or corrections as are necessary are given under each relevant clause. Where an item is not relevant to this specific contract such item is marked "N/A" signifying "Not Applicable" | | | |
| | PRICING OF PRELIMINARIES | | | |
| | Should Option A, as set out in clause B10.3.1 hereinafter be used for the adjustment of preliminaries then each item priced is to be allocated to one or more of the three categories Fixed, Value Related or Time Related and the respective amounts entered in the spaces provided under each item | | | |
| | Items not priced in these Preliminaries shall be deemed to be included elsewhere in these Bills of Quantities | | | |
| | Carried Forward | | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

THE MVULA TRUST

| | Brought Forward | R | |
|--|--|---|--|
| SECTION A: JBCC PRINCIPA | AL BUILDING | | |
| <u>AGREEMENT</u> | | | |
| <u>DEFINITIONS</u> | | | |
| A1.0 DEFINITIONS AND INTE | RPRETATION | | |
| Clause 1.0 | | | |
| Clause 1.1 Definition of "Commer added: | ncement Date" is | | |
| "COMMENCEMENT DATE" mean working days after site hand over. | | | |
| Clause 1.1 Definition of "Constru amended by replacing it with the f | | | |
| "CONSTRUCTION GUARANTEE at call obtained by the contractor approved by the employer in term construction guarantee form as se schedule | r from an institution ns of the employer's | | |
| Clause 1.1 Definition of "Constru amended by replacing it with the f | | | |
| "CONSTRUCTION PERIOD" mea commencing on the commencem on the date of practical completi | nent date and ending | | |
| Clause 1.1 Definition of "Corrupt | Practice" is added: | | |
| "CORRUPT PRACTICE" means to receiving or soliciting of anything of the action of a public official in the or in contract execution | of value to influence | | |
| Clause 1.1 Definition of "Fraudule | ent Practice" is added: | | |
| | | | |
| Section No. 4 | Carried Forward | R | |
| Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

THE MVULA TRUST

| В | Brought Forward | ļ i | ₹ |
|---|--|-----|---|
| "FRAUDULENT PRACTICE" means a m of facts in order to influence a procureme the execution of a contract to the detrime tenderer and includes collusive practice a tenderers (prior to or after the tender subdesigned to establish tender prices at articompetitive levels and to deprive the tender benefits of free and open competition | nispresentation ent process or ent of any among emission) ificial non- | | |
| Clause 1.1 Definition of "Interest" is ame replacing it with the following: | ended by | | |
| "INTEREST" means the interest rates ap contract, whether specifically indicated in clauses or not, will be in terms of the legi- Republic of South Africa, and in particular | the relevant islation of the | | |
| (a) in respect of interest owed by the empiriterest rate as determined by the Minister and Constitutional Development from time terms of section 1(2) of the Prescribed Ract, 1975 (Act No. 55 of 1975), will apply | er of Justice e to time, in ate of Interest | | |
| and | | | |
| (b) in respect of interest owed to the empinterest rate as determined by the Minister from time to time, in terms of section 80(1) Public Finance Management Act, 1999 (A) 1999), will apply | er of Finance, 1)(b) of the | | |
| Clause 1.1 Definition of "Principal Agent by replacing it with the following: | t " is amended | | |
| "PRINCIPAL AGENT" means the person appointed by the employer and named ir In the event of a principal agent not beir then all the duties and obligations of a pr as detailed in the agreement shall be fulf representative of the employer as named schedule | n the schedule . ng appointed, rincipal agent filled by a | | |
| Clause 1.1 Definition of " Security " is ame replacing it with the following: | ended by | | |
| | Carried Forward | F | 2 |
| Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

| | R | |
|------|------|------|
| | | |
| | | |
| | | |
| | | |
| Item | | |
| | | |
| | | |
| | | |
| Item | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| Item | | |
| | R | |
| | | |
| | Item | Item |

| 4 A4.0 DESIGN RESPONSIBILITY Clause 4.0 Clause 4.3 is amended by replacing it with the following the company of the company | | | |
|---|---------------|---|--|
| Clause 4.3 is amended by replacing it with the follo | | | |
| | | | |
| No clause | Time | | |
| | Time | | |
| Fixed:Value related:related: | lioni | | |
| 5 A5.0 EMPLOYER'S AGENTS | | | |
| Clause 5.0 | | | |
| Clause 5.1.2 is amended to include clauses 32.6.3 and 34.4 in terms of which the employer has retain authority and has not given a mandate to the princ agent and in terms of which the employer shall sig documents. | ed its pal | | |
| Fixed:Value related:related: | Time Item | | |
| 6 A6.0 SITE REPRESENTATIVE | | | |
| Clause 6.0 | | | |
| Fixed:Value related:related: | Time | | |
| 7 A7.0 COMPLIANCE WITH REGULATIONS | ileni | | |
| Clause 7.0 | | | |
| Fixed:Value related:related: | Time Item | | |
| 8 A8.0 WORKS RISK | | | |
| Clause 8.0 | | | |
| Fixed:Value related:related: | Time Item | | |
| | | | |
| Carried F | orward | R | |
| Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

| | Brought Forward | | R | |
|----|---|------|---|--|
| 9 | A9.0 INDEMNITIES | | | |
| | Clause 9.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| 10 | A10.0 WORKS INSURANCES | | | |
| | Clause 10.0 | | | |
| | Clause 10.0 is amended by the addition of the following clauses: | | | |
| | 10.5 Damage to the Works | | | |
| | (a) Without in any way limiting the contractor's obligations in terms of the contract, the contractor shall bear the full risk of damage to and/or destruction of the works by whatever cause during construction of the works and hereby indemnifies and holds harmless the employer against any such damage. The contractor shall take such precautions and security measures and other steps for the protection and security of the works as the contractor may deem necessary | | | |
| | (b) The contractor shall at all times proceed immediately to remove or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works | | | |
| | (c) The employer shall carry the risk of damage to or destruction of the works and materials paid for by the employer that is the result of the excepted risks as set out in 10.6 | | | |
| | (d) Where the employer bears the risk in terms of this contract, the contractor shall, if requested to do so, reinstate any damage or destroyed portions of the works and the costs of such reinstatement shall be measured and valued in terms of 32.0 hereof | | | |
| | Carried Forward | | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

| | Brought Forward | R |
|---------|--|---|
| | Injury to Persons or loss of or damage to erties | |
| (a) | The contractor shall be liable for and hereby indemnifies the employer against any liability, loss, claim or proceeding whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever arising out of or in the course of or caused by the execution of the works unless due to any act or negligence of any person for whose actions the employer is legally liable | |
| (b) | The contractor shall be liable for and hereby indemnifies the employer against any liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the site , whether belonging to or under the control of the employer or any other body or person, arising out of or in the course of or by reason of the execution of the works unless due to any act or negligence of any person for whose actions the employer is legally liable | |
| (c) | The contractor shall, upon receiving a contract instruction from the principal agent, cause the same to be made good in a perfect and workmanlike manner at his own cost and in default thereof the employer shall be entitled to cause it to be made good and to recover the cost thereof from the contractor or to deduct the same from amounts due to the contractor | |
| (d) | The contractor shall be responsible for the protection and safety of such portions of the premises placed under his control by the employer for the purpose of executing the works until the issue of the certificate of practical completion | |
| | | |
| Section | Carried Forward on No. 1 | R |

EMIS NO. 200100375

| risk of removal of or interference with support to adjoining properties including land or structures or any structures to be altered or added to, the contractor shall obtain adequate insurance and will remain adequately insured or insured to the specific limit stated in the contract against the death of or injury to persons or damage to such property consequent on such removal or interference with the support until such portion of the works has been completed | | | E1 | VIIS INC. 20010 | 03/3 |
|--|--|--|----|-----------------|------|
| risk of removal of or interference with support to adjoining properties including land or structures or any structures to be altered or added to, the contractor shall obtain adequate insurance and will remain adequately insured or insured to the specific limit stated in the contract against the death of or injury to persons or damage to such property consequent on such removal or interference with the support until such portion of the works has been completed f) The contractor shall at all times proceed immediately at his own cost to remove or dispose of any debris and to rebuild, restore, replace and/or repair such property and to execute the works 10.7 High risk insurance In the event of the project being executed in a geological area classified as a "High Risk Area", that is an area which is subject to highly unstable subsurface conditions that might result in catastrophic ground novement evident by sinkhole or dolline formation the ollowing will apply: 10.7.1 Damage to the works The contractor shall, from the commencement date of the works until the date of the certificate of practical completion bear the full risk of and hereby indemnifies and holds harmless the employer against any damage of and/or destruction of the works consequent upon a atastrophic ground movement as mentioned above. The contractor shall take such precautions and security measures and other steps for the protection of the works as he may deem necessary When so instructed to do so by the principal agent, the contractor shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the works, at the contractor's own costs Carried Forward R Section No. 1 | | Brought Forward | R | | |
| immediately at his own cost to remove or dispose of any debris and to rebuild, restore, replace and/or repair such property and to execute the works 10.7 High risk insurance In the event of the project being executed in a geological area classified as a "High Risk Area", that is an area which is subject to highly unstable subsurface conditions that might result in catastrophic ground movement evident by sinkhole or doline formation the ollowing will apply: 10.7.1 Damage to the works The contractor shall, from the commencement date of the works until the date of the certificate of practical completion bear the full risk of and hereby indemnifies and holds harmless the employer against any damage of and/or destruction of the works consequent upon a catastrophic ground movement as mentioned above. The contractor shall take such precautions and security measures and other steps for the protection of the works as he may deem necessary When so instructed to do so by the principal agent, the contractor shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the works, and to rebuild, restore, replace and/or repair the works, at the contractor's own costs Carried Forward R Section No. 1 | (e) | risk of removal of or interference with support to adjoining properties including land or structures or any structures to be altered or added to, the contractor shall obtain adequate insurance and will remain adequately insured or insured to the specific limit stated in the contract against the death of or injury to persons or damage to such property consequent on such removal or interference with the support until such portion | | | |
| n the event of the project being executed in a geological area classified as a "High Risk Area", that is an area which is subject to highly unstable subsurface conditions that might result in catastrophic ground movement evident by sinkhole or doline formation the ollowing will apply: 10.7.1 Damage to the works The contractor shall, from the commencement date of the works until the date of the certificate of practical completion bear the full risk of and hereby indemnifies and holds harmless the employer against any damage to and/or destruction of the works consequent upon a catastrophic ground movement as mentioned above. The contractor shall take such precautions and security measures and other steps for the protection of the works as he may deem necessary When so instructed to do so by the principal agent, the contractor shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works, at the contractor's own costs Carried Forward R Section No. 1 | (f) | immediately at his own cost to remove or dispose of any debris and to rebuild, restore, replace and/or repair such property and to | | | |
| geological area classified as a "High Risk Area", that is an area which is subject to highly unstable subsurface conditions that might result in catastrophic ground movement evident by sinkhole or doline formation the ollowing will apply: 10.7.1 Damage to the works The contractor shall, from the commencement date of he works until the date of the certificate of practical completion bear the full risk of and hereby indemnifies and holds harmless the employer against any damage of and/or destruction of the works consequent upon a catastrophic ground movement as mentioned above. The contractor shall take such precautions and security measures and other steps for the protection of the works as he may deem necessary When so instructed to do so by the principal agent, the contractor shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the works, at the contractor's own costs Carried Forward R Section No. 1 | 10.7 | High risk insurance | | | |
| The contractor shall, from the commencement date of the works until the date of the certificate of practical completion bear the full risk of and hereby indemnifies and holds harmless the employer against any damage of and/or destruction of the works consequent upon a catastrophic ground movement as mentioned above. The contractor shall take such precautions and security measures and other steps for the protection of the works as he may deem necessary When so instructed to do so by the principal agent, the contractor shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works, at the contractor's own costs Carried Forward R Section No. 1 | geolo an ar condi move | ogical area classified as a "High Risk Area", that is rea which is subject to highly unstable subsurface itions that might result in catastrophic ground ement evident by sinkhole or doline formation the | | | |
| the works until the date of the certificate of practical completion bear the full risk of and hereby indemnifies and holds harmless the employer against any damage of and/or destruction of the works consequent upon a catastrophic ground movement as mentioned above. The contractor shall take such precautions and security measures and other steps for the protection of the works as he may deem necessary When so instructed to do so by the principal agent, the contractor shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works, at the contractor's own costs Carried Forward R Section No. 1 | 10.7. | 1 Damage to the works | | | |
| contractor shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works, at the contractor's own costs Carried Forward R Section No. 1 | the w comp and h to and catas The c meas | pletion bear the full risk of and hereby indemnifies holds harmless the employer against any damage ad/or destruction of the works consequent upon a strophic ground movement as mentioned above. contractor shall take such precautions and security sures and other steps for the protection of the | | | |
| Section No. 1 | conti dispo destri | ractor shall proceed immediately to remove and/or ose of any debris arising from damage to or ruction of the works and to rebuild, restore, replace | | | |
| Section No. 1 | | Carried Forward | R | | + |
| Bill No. 1 | PREL | on No. 1 LIMINARIES AND GENERAL | | | |

THE MVULA TRUST

| Brought Forward | | R | |
|--|------|---|--|
| 10.7.2 Injury to persons or loss of or damage to property | | | |
| The contractor shall be liable for and hereby indemnifies and holds harmless the employer against any liability, loss, claim or proceeding arising at any time during the period of the contract whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever resulting from, arising out of, or caused by a catastrophic ground movement as mentioned above The contractor shall be liable for and hereby indemnifies the employer against any and all liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the site , whether belonging to or under the control of the employer or any | | | |
| other body or person whomsoever arising out of or caused by a catastrophic ground movement, as mentioned above, which occurred during the period of the contract | | | |
| 10.7.3 It is the responsibility of the contractor to ensure that he has adequate insurance to cover his risk and iability as mentioned in 10.7.1 and 10.7.2. Without imiting the contractor's obligations in terms of the contract, the contractor shall, within twenty-one (21) calendar days of the commencement date but before commencement of the works, submit to the employer proof of such insurance policy, if requested to do so | | | |
| and all losses and/or damages of whatever nature suffered or incurred consequent upon the contractor's default of his obligations as set out in 10.7.1; 10.7.2 and 10.7.3. Such losses or damages may be recovered from the contractor or by deducting the same from any amounts still due under this contract or under any other contract presently or hereafter existing between the employer and the contractor and for this purpose all these contracts shall be considered one indivisible whole | | | |
| Fixed: Value related: Time related: | Item | | |
| Carried Forward | | R | |
| Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

| | Brought Forward | | R | |
|----|--|------|---|--|
| 11 | A11.0 LIABILITY INSURANCES | | | |
| | Clause 11.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| 12 | A12.0 EFFECTING INSURANCES | | | |
| | Clause 12.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| 13 | A13.0 No clause | N/A | | |
| 14 | A14.0 SECURITY | | | |
| | Clause 14.0 | | | |
| | Clauses 14.1 - 14.8 are amended by replacing them with the following: | | | |
| | 14.1 The security to be submitted by the contractor to the employer will be as a payment reduction of up to ten per cent (10%) of the value certified in the payment certificate (excluding VAT) | | | |
| | 14.1.1 The payment reduction of the value certified in a payment certificate shall be <i>mutatis mutandi</i> in terms of 31.8(A) | | | |
| | 14.1.2 The employer shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the payment reduction security or portions thereof to the contractor | | | |
| | 14.2 Where security as a payment reduction of ten per cent (10%) of the value certified in the payment certificate (excluding VAT) has been selected: | | | |
| | Carried Forward | | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

| | Brought Forward | | R | | |
|----|---|------|---|---|--|
| 1 | 14.2.1 The payment reduction of the value certified in a payment certificate shall be <i>mutatis mutandi</i> in terms of 31.8(B) | | | | |
| | 14.2.2 The employer shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the payment reduction security or portions thereof to the contractor | | | | |
| | 14.9 Should the contractor fail to furnish the security in terms of 14.2, the employer , in his sole discretion and without notification to the contractor , is entitled to change the contractor's selected form of security to that of a ten per cent (10%) payment reduction of the value certified in the payment certificate (excluding VAT), whereafter 14.7 shall be applicable | | | | |
| | Fixed: Value related: Time related: | Item | | | |
| | EXECUTION | | | | |
| 15 | A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS | | | | |
| | Clause 15.0 | | | | |
| | Clause 15.1.1 is amended by replacing it with: | | | | |
| | No clause | | | | |
| | Clause 15.1.2 is amended by replacing it with: | | | | |
| | The security selected in terms of 14.0 | | | | |
| | Clause 15.1 is amended by the addition of the following clause: | | | | |
| | 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within fourteen (14) calendar days of commencement date | | | | |
| | | | | | |
| | Carried Forward Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | R | | |
| | | l . | ı | ı | |

| | Brought Forward | | R | |
|----|---|------|---|--|
| 20 | A20.0 NOMINATED SUBCONTRACTORS | | | |
| | Clause 20.0 | | | |
| | Clause 20.1.3 is amended by replacing it with the following: | | | |
| | No clause | | | |
| | Note: See item B9.1 hereinafter for adjustment of attendance on nominated subcontractors executing work allowed for under provisional sums | | | |
| | Fixed: Value related: Time related: | Item | | |
| 21 | A21.0 SELECTED SUBCONTRACTORS | | | |
| | Clause 21.0 | | | |
| | Clause 21 is amended by replacing it with: | | | |
| | No clause | | | |
| | Fixed: Value related: Time related: | Item | | |
| 22 | A22.0 EMPLOYER'S DIRECT CONTRACTORS | | | |
| | Clause 22.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| 23 | A23.0 CONTRACTOR'S DOMESTIC SUBCONTRACTORS | | | |
| | Clause 23.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | Carried Forward Section No. 1 | | R | |
| | PRELIMINARIES AND GENERAL Bill No. 1 | | | |
| | | | | |

| | Brought Forward | | R | |
|----|--|------|---|---|
| | COMPLETION | | | |
| 24 | A24.0 PRACTICAL COMPLETION | | | |
| | Clause 24.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| 25 | A25.0 WORKS COMPLETION | | | |
| | Clause 25.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| 26 | A26.0 FINAL COMPLETION | | | |
| | Clause 26.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| 27 | A27.0 LATENT DEFECTS LIABILITY PERIOD | | | |
| | Clause 27.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| 28 | A28.0 SECTIONAL COMPLETION | | | |
| | Clause 28.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | Carried Forward | | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |
| | | | | l |

| | Brought Forward | | R | |
|----|--|------|---|--|
| 29 | A29.0 REVISION OF DATE FOR PRACTICAL COMPLETION | | | |
| | Clause 29.0 | | | |
| | Clause 29.2.5 is amended by replacing it with: | | | |
| | No clause | | | |
| | Fixed: Value related: Time related: | Item | | |
| 30 | A30.0 PENALTY FOR NON-COMPLETION | | | |
| | Clause 30.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| | PAYMENT | | | |
| 31 | A31.0 INTERIM PAYMENT TO THE CONTRACTOR | | | |
| | Clause 31.0 | | | |
| | Clause 31.5.2 is amended by replacing "14.7.1" with "14.0 and 31.8" | | | |
| | Clause 31.8 is amended by replacing it with the following two alternative clauses: | | | |
| | Alternative A | | | |
| | 31.8(A) Where a security is selected in terms of 14.1; the value of the works in terms of 31.4.1 and materials and goods in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments: | | | |
| | 31.8(A).1 Ninety-five percent (95%) of such value in interim payment certificates issued up to the date of practical completion | | | |
| | 31.8(A).2 Ninety-seven and half percent (97.5%) of such value in interim payment certificates issued on the date of practical completion and up to but excluding the date of final completion | | | |
| | Carried Forward | | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

| | | Brought Forward | | R | |
|---|---|---|------|---|--|
| interim paymen | y-nine percent (99%) of t certificates issued or If up to but excluding the rms of 34.6 | n the date of final | | | |
| the final payme where the amount in such an even | undred percent (100%) nt certificate in terms of the certified is in favour the payment reduction evel applicable to the fi | of 34.6 except of the employer . n shall remain at | | | |
| Clause 31.12 is | amended by deleting t | he following: | | | |
| | e subject to the emplo x invoice for the amoun | | | | |
| Fixed: related: | Value related: | Time | Item | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | Carried Forward | | R | |
| Section No. 1 PRELIMINARIE Bill No. 1 | S AND GENERAL | | | | |
| | | | | | |

| | Brought Forward | | R | |
|----|---|------|---|--|
| 32 | A32.0 ADJUSTMENT TO THE CONTRACT VALUE | | | |
| | Clause 32.0 | | | |
| | Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence: | | | |
| | "due to no fault of the contractor " | | | |
| | Add the following clauses: 33.2.9 to 33.2.13: | | | |
| | 33.2.9 the contractor 's failure or neglect to commence with the works on the dates prescribed in the contract | | | |
| | 33.2.10 the contractor's failure or neglect to proceed with the works in terms of the contract | | | |
| | 33.2.11 the contractor's failure or neglect for any reason to complete the works in accordance with the contract | | | |
| | 33.2.12 the contractor's refusal or neglect to comply strictly with any of the conditions of contract or any contract instructions and/or orders in writing given in terms of the contract | | | |
| | 33.2.13 the contractor's estate being sequestrated; liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa. | | | |
| | Fixed: Value related: Time related: | Item | | |
| 33 | A33.0 RECOVERY OF EXPENSE AND LOSS | | | |
| | Clause 33.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | Carried Forward | | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |
| | | | | |

| | Brought Forward | | R | |
|----|---|------|---|--|
| 34 | A34.0 FINAL ACCOUNT AND FINAL PAYMENT | | | |
| | Clause 34.0 | | | |
| | Clause 34.1 is amended by removing "#" next to 34.1 | | | |
| | Clause 34.2 is amended by inserting "#" next to 34.2 | | | |
| | Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due" | | | |
| | Fixed: Value related: Time related: | Item | | |
| 35 | A35.0 PAYMENT TO OTHER PARTIES | | | |
| | Clause 35.0 | | | |
| | Fixed: Value related: Time related: | Item | | |
| | CANCELLATION | | | |
| 36 | A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT | | | |
| | Clause 36.0 | | | |
| | Clause 36.1 is amended by the addition of the following clauses: | | | |
| | 36.1.3 refuses or neglects to comply strictly with any of the conditions of contract | | | |
| | 36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa | | | |
| | 36.1.5 in the judgement of the employer , has engaged in corrupt or fraudulent practices in competing for or in executing the contract | | | |
| | Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer" | | | |
| | Carried Forward | | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

| | Brought Forward | | R | |
|----|--|------|---|--|
| | Clause 36.0 is amended by the addition of the following clause: | | | |
| | 36.3 Remove reference to "No clause", and replace "principal agent" with "employer" | | | |
| | 36.7 Notwithstanding any clause to the contrary, on cancellation of this agreement either by the employer or the contractor ; or for any reason whatsoever, the contractor shall on written instruction, discontinue with the works on a date stated and withdraw himself from the site . The contractor shall not be entitled to refuse to withdraw from the works on the grounds of any lien or right of retention or on the grounds of any other right whatsoever | | | |
| | Fixed: Value related: Time related: | Item | | |
| 37 | A37.0 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE | | | |
| | Clause 37.0 | | | |
| | Clause 37.3.5 is amended by replacing "ninety (90)" with "one hundred and twenty (120)" | | | |
| | Clause 37.0 is amended by the addition of the following clause: | | | |
| | 37.3.5 Replace "ninety (90)" with "one hundred and twenty (120) and 38.5.4 | | | |
| | Fixed: Value related: Time related: | Item | | |
| 38 | A38.0 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT | | | |
| | Clause 38.0 | | | |
| | Clause 38.5.4 is amended by replacing "ninety (90)" with "one hundred and twenty (120)" | | | |
| | Clause 38.0 is amended by the addition of the following clause: | | | |
| | Carried Forward | | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |
| | | | | |

| | Brought Forward | | R | |
|----|--|------|---|--|
| | 38.7 Notwithstanding any clause to the contrary, on cancellation of this agreement either by the employer or the contractor ; or for any reason whatsoever, the contractor shall on written instruction, discontinue with the works on a date stated and withdraw himself from the site . The contractor shall not be entitled to refuse to withdraw from the works on the grounds of any lien or right of retention or on the grounds of any other right whatsoever | | | |
| | Fixed: Value related: Time related: | Item | | |
| 39 | A39.0 CANCELLATION - CESSATION OF THE WORKS | | | |
| | Clause 39.0 | | | |
| | Clause 39.3.5 is amended by the addition of the following at the end of the sentence: | | | |
| | "within one hundred and twenty (120) working days of completion of such a report" | | | |
| | Fixed: Value related: Time related: | Item | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | Carried Forward | | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |
| | | | | |

| | Brought Forward | | R | | |
|----|---|------|-----|-----|--|
| | DISPUTE | | | | |
| 40 | A40.0 DISPUTE SETTLEMENT | | | | |
| | Clause 40.0 | | | | |
| | Clause 40.2.2 is amended by replacing "one (1) year" with "three (3) years" | | | | |
| | Clause 40.6 is amended by removing the reference to: | | | | |
| | No clause | | | | |
| | Clause 40.7.1 is amended by replacing "(10)" with "(15)" and by the addition of the following: | | | | |
| | Whether or not mediation resolves the dispute, the parties shall bear their own costs concerning the mediation and equally share the costs of the mediator and related costs | | | | |
| | Fixed: Value related: Time related: | Item | | | |
| | SUBSTITUTE PROVISIONS | | | | |
| 41 | A41.0 STATE CLAUSES | | | | |
| | Clause 41.0 | | | | |
| | Fixed: Value related: Time related: | Item | | | |
| | CONTRACT VARIABLES | | | | |
| 42 | A42.0 THE SCHEDULE (C1.2) | | | | |
| | Clause 42.0 | | | | |
| | Tenderers are referred to the C1.2 CONDITIONS OF CONTRACT AND CONTRACT VARIABLES for variables pertaining to this contract | | | | |
| | Fixed: Value related: Time related: | Item | | | |
| | related | пеш | | | |
| | | | | | |
| | Carried Forward | | R | | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | | |
| | | | i l | i l | |

| | Brought Forward | | R | |
|----|---|------|---|--|
| | SECTION B: JBCC PRELIMINARIES | | | |
| | B1.0 DEFINITIONS AND INTERPRETATION | | | |
| 43 | B1.1 Definitions and interpretation | | | |
| | See also clause A1.0 of Section A for additional and/or amended definitions which shall apply equally to this Section | | | |
| | Fixed: Value related: Time related: | Item | | |
| | B2.0 DOCUMENTS | | | |
| 44 | B2.1 Checking of documents | | | |
| | Fixed: Value related: Time related: | Item | | |
| 45 | B2.2 Provisional bills of quantities | | | |
| | Fixed: Value related: Time related: | Item | | |
| 46 | B2.3 Availability of construction documentation | | | |
| | Fixed: Value related: Time related: | Item | | |
| 47 | B2.4 Interests of agents | | | |
| | Fixed: Value related: Time related: | Item | | |
| 48 | B2.5 Priced documents | | | |
| | Fixed: Value related: Time related: | Item | | |
| | | | | |
| | | | | |
| | | | | |
| | | | _ | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | R | |

| | Brou | ght Forward | | R |
|----------------------|-----------------------------------|-------------|------|---|
| 9 B2.6 Te | ender submission | | | |
| Clause 2.6 | is amended by replacing "JBCC F | orm of | | |
| Tender" w 07(EC)" | ith "Form of Offer and Acceptance | DPW- | | |
| Fixed: | Value related: | Time | | |
| related: | | | Item | |
| B3.0 TI | HE SITE | | | |
| 0 B3.1 D | efined works area | | | |
| Fixed: | Value related: | Time | | |
| related: | | | Item | |
| 1 <i>B3.2 G</i> | eotechnical investigation | | | |
| Fixed: | Value related: | Time | | |
| related: | | | Item | |
| 2 B3.3 In | spection of the site | | | |
| Fixed: | Value related: | Time | | |
| related: | | | Item | |
| 3 B3.4 Ex | risting premises occupied | | | |
| Fixed: | Value related: | Time | | |
| related: | | | Item | |
| 4 B3.5 Pi | evious work - dimensional accui | racy | | |
| Fixed: | Value related: | Time | | |
| related: | | | Item | |
| 5 B3.6 P i | revious work - defects | | | |
| Fixed: | Value related: | Time | | |
| related: | | | Item | |
| 6 B3.7 S 6 | ervices - known | | | |
| Fixed: | Value related: | Time | 14 | |
| related: | | | Item | |
| | | | | |
| | | | | |
| Section No | | ied Forward | | R |
| PRELIMIN | ARIES AND GENERAL | | | |
| Bill No. 1 | | | | |

| | Brought Forward | | R | |
|----|--|------|---|--|
| 57 | B3.8 Services - unknown | | | |
| | Fixed: Value related: Time | | | |
| | related: | Item | | |
| 58 | B3.9 Protection of trees | | | |
| | Fixed: Value related: Time | | | |
| | related: | Item | | |
| 59 | B3.10 Articles of value | | | |
| | Fixed: Value related: Time | | | |
| | related: | Item | | |
| 60 | B3.11 Inspection of adjoining properties | | | |
| | Fixed: Value related: Time | | | |
| | related: | Item | | |
| | B4.0 MANAGEMENT OF CONTRACT | | | |
| 31 | B4.1 Management of the works | | | |
| | Fixed: Value related: Time | | | |
| | Fixed: Value related: Time related: R | Item | | |
| 62 | B4.2 Programme for the works | | | |
| | Fixed: Value related: Time | | | |
| | related: | Item | | |
| 3 | B4.3 Progress meetings | | | |
| | Fixed: Value related: Time | | | |
| | related: | Item | | |
| 64 | B4.4 Technical meetings | | | |
| | Fixed: Value related: Time | | | |
| | related: | Item | | |
| 35 | B4.5 Labour and plant records | | | |
| | Fixed: Value related: Time | | | |
| | related: | Item | | |
| | | | | |
| | Carried Forward | | R | |
| | Section No. 1 | | | |
| | PRELIMINARIES AND GENERAL | | | |
| | Bill No. 1 | | | |
| | | | | |

| | Brought Forward | R | |
|----|---|------|--|
| 1 | B5.0 SAMPLES, SHOP DRAWINGS AND MANUFACTURERS' INSTRUCTIONS | | |
| 66 | B5.1 Samples of materials | | |
| | Fixed: Value related: Time related: | Item | |
| 67 | B5.2 Workmanship samples | | |
| | Fixed: Value related: Time related: | Item | |
| 88 | B5.3 Shop drawings | | |
| | Fixed: Value related: Time related: | Item | |
| 69 | B5.4 Compliance with manufacturers' instructions | | |
| | Fixed: Value related: Time related: | Item | |
| | B6.0 TEMPORARY WORKS AND PLANT | | |
| 70 | B6.1 Deposits and fees | | |
| | Fixed: Value related: Time related: | Item | |
| '1 | B6.2 Enclosure of the works | | |
| | Fixed: Value related: Time related: | Item | |
| 72 | B6.3 Advertising | | |
| | Fixed: Value related: Time related: | Item | |
| 73 | B6.4 Plant, equipment, sheds and offices | | |
| | Fixed: Value related: Time related: | Item | |
| | | | |
| | Carried Forward | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | |

| Brought Forward | R | |
|--|------|--|
| B6.5 Main notice board | | |
| Fixed: Value related: Time | | |
| related: | Item | |
| B6.6 Subcontractors' notice board | | |
| Fixed: Value related: Time | | |
| related: | Item | |
| B7.0 TEMPORARY SERVICES | | |
| B7.1 Location | | |
| Fixed: Value related: Time | | |
| related: | Item | |
| B7.2 Water | | |
| Fixed: Value related: Time | | |
| related: | Item | |
| B7.3 Electricity | | |
| Fixed: Value related: Time | | |
| related: | Item | |
| B7.4 Telecommunication facilities | | |
| Fixed: Value related: Time | | |
| related: | Item | |
| B7.5 Ablution facilities | | |
| Fixed: Value related: Time | | |
| related: | Item | |
| B8.0 PRIME COST AMOUNTS | | |
| B8.1 Responsibility for prime cost amounts | | |
| Fixed: Value related: Time | | |
| related: | Item | |
| | | |
| | | |
| | | |
| Carried Forward | R | |
| Section No. 1 | | |
| PRELIMINARIES AND GENERAL Bill No. 1 | | |
| | | |

| | Brought Forward | R |
|----|---|------|
| | B11.0 GENERAL | |
| 89 | B11.1 Protection of the works | |
| | Fixed: Value related: Time related: | Item |
| 90 | B11.2 Protection / isolation of existing / sectionally occupied works | |
| | Fixed: Value related: Time related: | Item |
| 91 | B11.3 Security of the works | |
| | Fixed: Value related: Time related: | Item |
| 92 | B11.4 Notice before covering work | |
| | Fixed: Value related: Time related: | Item |
| 93 | B11.5 Disturbance | |
| | Fixed: Value related: Time related: | Item |
| 94 | B11.6 Environmental disturbance | |
| | Fixed: Value related: Time related: | Item |
| 95 | B11.7 Works cleaning and clearing | |
| | Fixed: Value related: Time related: | Item |
| 96 | B11.8 Vermin | |
| | Fixed: Value related: Time related: | Item |
| | | |
| | | |
| | Carried Forward | R |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | |
| | | |

| | Brought Forward | | R | ì |
|-----|--|------|---|---|
| 97 | B11.9 Overhand work | | | ı |
| | Fixed: Value related: Time related: | Item | | |
| 98 | B11.10 Instruction manuals and guarantees | | | ı |
| | Fixed: Value related: Time related: | Item | | |
| 99 | B11.11 As built information | | | 1 |
| | Fixed: Value related: Time related: | Item | | 1 |
| 100 | B11.12 Tenant installations | | | ı |
| | Fixed: Value related: Time related: | Item | | |
| | B12.0 SCHEDULE OF VARIABLES | | | 1 |
| 101 | B12.1 Schedule of variables | | | ı |
| | Fixed: Value related: Time related: | Item | | |
| | This schedule contains all variables referred to in this document and is divided into pre-tender and post-tender categories. The pre-tender category must be completed in full and included in the tender documents. Both the pre-tender and post-tender categories form part of these Preliminaries | | | |
| | Spaces requiring information must be filled in, shown as "not applicable" or deleted and not left blank. Where choices are offered, the non-applicable items are to be deleted. Where insufficient space is provided the information should be annexed hereto and cross-referenced to the applicable clause of the schedule . Key cross reference clauses are italicised in [] brackets | | | |
| | Carried Forward Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | R | |

| | Brought Forward | R | |
|-------------------------------|--|---|--|
| 12.1 | PRE-TENDER INFORMATION | | |
| | Provisional bills of quantities The quantities are provisional | | |
| | YES | | |
| | Availability of construction documentation Construction documentation is complete | | |
| | YES | | |
| 12.1.3 <i>[2.4]</i> | Interests of agents Details: | | |
| | Defined works area Details: | | |
| | Geotechnical investigation Details: | | |
| | Existing premises occupied Specific requirements: | | |
| | Previous work - dimensional accuracy Details: | | |
| | Previous work - defects Details: | | |
| | Services - known Details: | | |
| | Protection of trees Specific requirements: | | |
| | | | |
| | Carried Forward | R | |
| Section PRELIM Bill No. | No. 1 INARIES AND GENERAL | | |

| Broug | ht Forward | R |
|---|--|---|
| 12.1.11 <i>Inspection of adjoining properties</i> [3.11] Specific requirements: | | |
| 12.1.12 <i>Enclosure of the works</i> [6.2] Specific requirements: | | |
| 12.1.13 <i>Offices</i> [6.4.3] Specific requirements: The contractor shall provide, maintai remove on completion of the works ar the exclusive use of the principal age minimum size 4 x 3 x 3m high interna insulated and ventilated, provided with lighting and fitted with boarded floor, of chair, drawing stool, drawing board ar drawers for drawings. The office shall clean and fit for use at all times | n office for ent, lly, suitably n electric desk, nd lock-up | |
| 12.1.14 <i>Main notice board</i> [6.5] Specific requirements: The contractor shall provide, erect w directed, maintain and remove on conthe works a notice board size 3 x 3m Drawing GEN 063, constructed of suit boarding with flat smooth surface and edging bead 19mm thick round outer projecting 12mm from face of boarding rounded on front edge. The board sha securely fixed to hoarding, where hoa provided, or fixed to and including a s supporting structure of timber or tubul and braces. The board is to be painte white and the bead and 12mm wide d lines dark green. All wording shall be in dark green as per the coat of arms wording shall be inscribed in dark greens and serif lettering | as type able with edges and g and all be rding is uitable ar posts d ivory ividing inscribed for SA. All | |
| 12.1.15 Subcontractors' notice board [6.6] A notice board is required | | |
| Specific requirements: | NO | |
| Carri Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | ed Forward | R |

| | Brought Forward | R | |
|---|-----------------|---|--|
| 12.1.16 <i>Water</i> [7.2] Option A (by contractor) | | | |
| | NO | | |
| Option B (by employer - free | of charge) | | |
| | NO | | |
| Option C (by employer - mete | ered) | | |
| | YES | | |
| 12.1.17 <i>Electricity</i> [7.3] Option A (by contractor) | | | |
| | NO | | |
| Option B (by employer - free | of charge) | | |
| | NO | | |
| Option C (by employer - mete | ered) | | |
| | YES | | |
| 12.1.18 <i>Telecommunications</i> [7.4] Telephone | | | |
| YES | | | |
| Facsimile | | | |
| | YES | | |
| E-mail | | | |
| | YES | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | Carried Forward | R | |
| Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | Carried Forward | K | |
| | | | |

| Brought Forward | R | |
|---|---|--|
| 12.1.19 <i>Ablution facilities</i> [7.5] Option A (by contractor) | | |
| YES | | |
| Option B (by employer) | | |
| NO | | |
| 12.1.20 Protection of existing/sectionally occupied | | |
| works [11.2] Protection is required | | |
| | | |
| NO | | |
| 12.1.21 Special attendance [9.2] Subcontractor (1) details: | | |
| Subcontractor (2) details: | | |
| Subcontractor (3) details: | | |
| Subcontractor (4) details: | | |
| 12.1.22 Protection of the works [11.1] Specific requirements: | | |
| 12.1.23 <i>Disturbance</i> [11.5] Specific requirements: The contractor shall keep the site, structures, etc well watered during operations to prevent dust and shall provide and erect and remove on completion of the works all necessary temporary dust screens all to the satisfaction of the principal agent | | |
| 12.1.24 <i>Environmental disturbance</i> [11.6] Specific requirements: | | |
| 12.2 POST-TENDER INFORMATION | | |
| Carried Forward Section No. 1 PRELIMINARIES AND GENERAL | R | |
| Bill No. 1 | | |

| | | Brought Forward | R | |
|-------------------------------|---|-----------------|---|--|
| 12.2.1 [10.2] | Payment of preliminaries Option A (prorated) | | | |
| | | NO | | |
| | Option B (calculated) | | | |
| | | YES | | |
| 12.2.2 [10.3] | Adjustment of preliminaries Option A (three categories) | | | |
| | | NO | | |
| | Option B (detailed breakdown |) | | |
| | | YES | | |
| 12.2.3 | Additional agreed prelimina Details: | ries items | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | Carried Forward | R | |
| Section PRELII Bill No. | MINARIES AND GENERAL | Gairieu Forward | K | |
| 101 | | | | |

| | Brought Forward | | R | |
|-----|---|------|---|--|
| l | SECTION C: SPECIFIC PRELIMINARIES | | | |
| | Section C contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item | | | |
| 102 | C1.0 CONTRACT DRAWINGS | | | |
| | The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the works and the manner in which they are to be executed | | | |
| | Should any part of the drawings not be clearly understood by the tenderer he shall, before submitting his tender, obtain clarification in writing from the principal agent | | | |
| | Fixed: Value related: Time related: | Item | | |
| 103 | C2.0 GENERAL PREAMBLES | | | |
| | The document "Specification of Materials and Methods to be used - PW371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014)." is obtainable on the Department's website (http://www.publicworks.gov.za/ under "Consultants Guidelines"), and shall be read in conjunction with the bills of quantities / lump sum document and be referred to for the full descriptions of work to be done and materials to be used | | | |
| | Fixed: Value related: Time related: | Item | | |
| | | | | |
| | Carried Forward | | R | |
| | Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

| | Brought Forward | | R | |
|-----|--|------|---|--|
| 104 | C3.0 TRADE NAMES | | | |
| | Wherever a trade name for any product has been described in the bills of quantities / lump sum document , the tenderer's attention is drawn to the fact that any other product of equal quality may be used subject to the written approval of the principal agent being obtained prior to the closing date for submission of tenders | | | |
| | If prior written approval for an alternative product is not obtained, the product described shall be deemed to have been tendered for | | | |
| | Fixed: Value related: Time related: | Item | | |
| 105 | C4.0 HIV/AIDS AWARENESS | | | |
| | It is required of the contractor to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document . Provision for pricing of HIV/AIDS awareness is made under items C10.1 to C10.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained | | | |
| | The contractor must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment | | | |
| | Carried Forward Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | R | |

| Brought Forward | | R | |
|---|------|---|--|
| C4.1 AWARENESS CHAMPION Selection, appointment, briefing and making available of an Awareness Champion including provision of all relevant services, all in accordance with the HIV/AIDS Specification Fixed: | Item | | |
| C4.2 AWARENESS WORKSHOPS Selection and appointment of a competent Service Provider approved by the principal agent, provision of a Service Provider Workshop Plan and a suitable venue, conducting of awareness workshops by means of traditional and/or modern multi- media techniques, including follow-up courses, making available all tuition material and performing assessment procedures, all in accordance with the HIV/AIDS Specification Fixed: | ltem | | |
| C4.3 POSTERS, BOOKLETS, VIDEOS, ETC. Provision, displaying, maintaining and replacing when necessary of four plastic laminated posters, booklets and educational videos, etc. for the duration of the construction period, all in accordance with the HIV/AIDS Specification | | | |
| Fixed: | Item | | |
| Fixed: Value related: Time related: | Item | | |
| Carried Forward Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | R | |

| Brought Forward | | R | |
|---|------|---|--|
| C4.5 MONITORING Monitoring HIV/AIDS awareness of workers, providing the principal agent with access to information including making available all reports, thoroughly completed and reflecting the correct information, for the duration of the construction period and close out, all in accordance with the HIV/AIDS Specification | | | |
| Fixed:Value related: | Item | | |
| | | | |
| | | | |
| Carried to Cluster Summary | | R | |
| Section No. 1 PRELIMINARIES AND GENERAL Bill No. 1 | | | |

| Item No | | Unit | Quantity | Rate | Amount |
|------------|--|------|----------|------|--------|
| | SECTION 2 | | | | |
| | BILL NO.1 | | | | |
| | <u>REFURBISHMENTS</u> | | | | |
| | SUPPLEMENTARY PREAMBLES | | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | | |
| | SUPPLEMENTARY PREAMBLES | | | | |
| | <u>View site</u> | | | | |
| | Before submitting his tender the contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained | | | | |
| | | | | | |
| | Carried Forward Section No. 2 BUILDING WORKS Bill No. 1 | | | R | |

THE MVULA TRUST

| Brought Forward | R | |
|--|---|--|
| Eviating atwest-week taking days and removing | | |
| Existing structuresIn taking down and removing existing work, the utmostcare shall be observed | | |
| to prevent any structural or otherdamage to the | | |
| remaining portions of the building and | | |
| theContractor shall provide all shoring, | | |
| needling, strutting,etc. to ensure the stability of | | |
| all structures during thealteration work. Any | | |
| damage to the structure and/orbuilding as well | | |
| as the rectification of same will be forthe | | |
| Contracor's account.SUPPLEMENTARY | | |
| PREAMBLESServicesSpecial care shall be | | |
| exercised during the progress ofthe work to | | |
| ensure that electrical installation, watersupply | | |
| pipes, gas and oxygen supply pipes, | | |
| telephoneand other services which may be | | |
| encountered are notinterfered with and notice | | |
| shall be given to theRepresentative Agent if any | | |
| disconnection or alterationsbecome | | |
| necessary.Dust and noiseThe Contractor is to | | |
| take all necessary precautions tothe | | |
| satisfaction of the Representative Agent to | | |
| preventany nuisance from the dust and/or noise | | |
| whilst carryingout the work.Disposal of | | |
| debrisThe Contractor shall be responsible for | | |
| the removal fromsite of all materials, debris and | | |
| rubbish resulting fromthe work and the removal | | |
| is deemed to be included inthe rates unless | | |
| otherwise specified. | | |
| Explosives | | |
| No explosives whatsoever may be used for demolition purposes unless otherwise stated | | |
| General | | |
| The contractor shall come out the whole of the works | | |
| The contractor shall carry out the whole of the works with as little mess and noise as possible and with a | | |
| minimum of disturbance to adjoining premises and their | | |
| tenants. He shall provide proper protection and provide, | | |
| erect and remove when directed, any temporary | | |
| tarpaulins that may be necessary during the progress of | | |
| the works, all to the satisfaction of the principal agent | | |
| | | |
| | | |
| | | |
| | | |
| Carried Forward | R | |
| Section No. 2 | | |
| BUILDING WORKS | | |
| Bill No. 1 | | |
| | | |
| | | |

THE MVULA TRUST

| | Brought Forward | R | |
|--|---|---|--|
| Water supply pipes and other piping encountered and found necessary to shall be effectually stopped off or gremoved, and any new connections necessary shall be made with proper satisfaction of the principal agent | o disconnect or cut, rubbed up and that may be | | |
| Doors, fanlights, fittings, frames, lin be re-used shall be thoroughly over refixing including taking off, easing cramping up, re-wedging as require cramps, dowels, etc, and easing, oi repairing ironmongery as necessary damaged in removal or subsequent all nail and screw holes with tinted match timber, unless otherwise desor re-varnishing is given separately | rhauled before and rehanging, and and making good ling, adjusting and and replacing any glass and stopping up collastic wood to cribed. Re-painting | | |
| Prices for taking out of doors, windo for removal of all beads, architraves | | | |
| Prices for taking out and removing of shall include for removing door stop and making good floor and wall finishexisting | os, cabin hooks, etc | | |
| With regard to building up of opening cement screeds and pavings, grand etc, shall be levelled and prepared brickwork | olithic, tops of walls, | | |
| Making good of finishes shall include the brick and concrete surfaces ont finishes are applied, where necessary | o which the new | | |
| The contractor will be required to ta affecting the existing buildings on the held solely responsible for the accudimensions where used in the manu (doors, windows, fittings, etc) | ne site and he will be racy of all such | | |
| Alterations to the roof and roof truss with the carpentry and joinery and t | | | |
| LOCATIONS | | | |
| A - Girls Ablution Blocks | | | |
| B - Boys Ablution Blocks | | | |
| C - Staff Ablution Blocks | | | |
| Section No. 2 BUILDING WORKS Bill No. 1 | Carried Forward | R | |

| | Brought Forward | | | R | |
|---|---|----|----|---|----------|
| | Old materials to become the property of theContractorOld materials from the alterations, except wheredescribed to be re-used or handed over, become theproperty of the Contractor who must allow credit forsame in the Final Summary.Old materials to be carted awayOld materials from the alterations, except wheredescribed to be re-used or handed over, as well as allrubbish, etc. must regularly be carted away from siteand not be allowed to accumulate on or around the site.Old materials not to be re-usedNone of the old materials are to be re-used for newwork, except where specifically described as being setaside for re-use.Handing over of materialsWhere certain materials or articles from demolitions oralterations are described as to be handed over by theContractor to the Representative/ Agent, such materialsor articles shall be properly stored by the Contractor must obtain official receipt listing materials or articles and datesof handing over. If the Contractor fails to submit thereceipt when requested, it shall be deemed that thematerials or articles are still in his possession and hewill be held liable to the Department for the fullreplacement value thereof, which amount will bededucted from any monies due to the Contractor. REMOVAL OF EXISTING WORK Taking out, removing doors, windows, etc including | | | | |
| 1 | thresholds Timber single door A:5 B:3 C:5 | No | 13 | | |
| | Taking down and removing ceilings including cornices, timber brandering etc | | | | |
| 2 | Ceilings, cornices etc A: 19 B: 19 C: 19 | m2 | 58 | | |
| | INSPECTING, SERVICING, REMOVING OF EXISTING TOILET SEAT COVERS | | | | |
| | | | | | |
| | | | | _ | <u> </u> |
| | Section No. 2 BUILDING WORKS Bill No. 1 | | | R | |

| | Brought Forward | | | R | _ |
|----|---|----|------|---|---|
| | Inspect existing galvanised metal roof coverings for leaks, remove loose roof screws and replace with new 100mm long screws with and including new domed roof washer with sealant attached: | | | | |
| 3 | Existing roof coverings A: 19 B: 19 C: 18 | m2 | 56 | | |
| | <u>SUNDRIES</u> | | | | |
| 4 | Allowance cleaning and clearing before work commences on ablution block A: 0.00 B: 0.00 C: 1.00 | | Item | | |
| 5 | Allowance for oil treatment of existing timber trusses, purlins and wall plates | | Item | | |
| | A: 0.00 B: 0.00 C: 1.00 | | | | |
| 6 | Allowance for isolated roof leaks A: 0.00 B: 0.00 C: 1.00 | | Item | | |
| 7 | Service and repair all pivot and locking mechanisms of existing steel windows | No | 13 | | |
| | A:5 B:3 C:5 | | | | |
| | Breaking down and removing brickwork etc | | | | |
| 8 | One brick walls A: 48 B: 48 C: 45 | m2 | 140 | | |
| | Take out and remove doors, etc, including thresholds, set aside for handing over to the employer and prepare frame to receive new doors in similar position (doors measured elsewhere) | | | | |
| 9 | Timber single door and frame not exceeding 2,5m ² A:5 B:3 C:5 | No | 13 | | |
| 10 | Burglar bars: 1500 x 2100mm high A:1 B:1 C:1 | No | 3 | | |
| 11 | Steel window frame | No | 13 | | |
| | A:5 B:3 C:5 | | | | |
| | Carried Forward Section No. 2 BUILDING WORKS Bill No. 1 | | | R | |

| | Brought Forward | | | R | | _ |
|----|---|----|------|---|---|---|
| | Take out and remove broken window panes from steel windows and prepare frame to receive new glazing in similar position (glazing measured elsewhere) | | | | | |
| 12 | Window glass panes | m2 | 12 | | | |
| | A:5 B:3 C:5 | | | | | |
| | Taking out and removing ironmongery | | | | | |
| 13 | Mortice lockset from timber door A:5 B:3 C:5 | No | 13 | | | |
| 14 | Door closer from timber door and frame | No | 2 | | | |
| | A:0 B:0 C:2 | | | | | |
| 15 | Toilet paper holder from wall A:5 B:3 C:5 | No | 13 | | | |
| | Hacking up/off and removing granolithic, screeds, plaster, etc from concrete or brickwork and preparing surfaces for new screed, plaster, tile finishes, etc | | | | | |
| 16 | 80mm Screed from floors | m2 | 56 | | | |
| | A:19 B:19 C:18 | | 4.40 | | | |
| 17 | Internal plaster from walls and columns A: 48 B: 48 C: 45 | m2 | 140 | | | |
| | Hacking up/off and removing ceramic tiles including removing mortar bed or adhesive from concrete or brickwork and preparing surfaces for new screed, plaster, tile finish, etc | | | | | |
| 18 | Tiles to floors A: 19 B: 19 C: 18 | m2 | 56 | | | |
| 19 | Tiles to walls | m2 | 128 | | | |
| | A: 26 B: 26 C: 76 | | | | | |
| | Taking out and removing piping, including cutting off as necessary, holderbats and making good floor and wall finishes (making good tiling and paintwork elsewhere) | | | | | |
| 20 | UPVC piping not exceeding 110mm internal diameter A: 22 B: 19 C: 0 | m | 41 | | | |
| | | | | | | |
| | Carried Forward Section No. 2 BUILDING WORKS Bill No. 1 | | | R | | |
| | | | | | 1 | |

| | Brought Forward | | | R | |
|----|---|----|------|---|--|
| | Taking out and removing sanitary fittings, tanks, geysers, etc, including disconnecting from pipes, traps, etc and making good floor and wall finishes (making good tiling and paintwork elsewhere) | | | | |
| 21 | Stainless steel wash hand basin A:1 B:2 C:1 | No | 4 | | |
| 22 | Vitreous china WC pan with cistern and flush pipe A:5 B:3 C:5 | No | 13 | | |
| 23 | Vitreous china wall hung urinal with flush valve and flush pipe A:0 B:1 C:0 | No | 1 | | |
| | MAKING GOOD OF FINISHES ETC | | | | |
| | Making good face brickwork | | | | |
| 24 | Cleaning of the facebrick on the outside and inside A: 51 B: 51 C: 91 | m2 | 193 | | |
| | Making good paint work | | | | |
| 25 | Internal walls A: 48 B: 48 C: 45 | m2 | 140 | | |
| | <u>SUNDRIES</u> | | | | |
| 26 | Allowance for unblocking existing blocked sewer A: 0.00 B: 0.00 C: 1.00 | | Item | | |
| 27 | Allowance for testing, servicing and repair all Mechanical equipment on site A: 0.00 B: 0.00 C: 1.00 | | Item | | |
| 28 | Allow for detection of all services A: 0.00 B: 0.00 C: 1.00 | | Item | | |
| | Carried Forward to Summary of Section No. 2 Section No. 2 | | | R | |
| | BUILDING WORKS Bill No. 1 | | | | |

| Item No | | Unit | Quantity | Rate | Amount |
|------------|--|------|----------|------|--------|
| | SECTION 2 | | | | |
| | BILL NO.2 | | | | |
| | BRICKWORK | | | | |
| | SUPPLEMENTARY PREAMBLES | | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | | |
| | <u>BRICKWORK</u> | | | | |
| | Sizes in descriptions | | | | |
| | Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick | | | | |
| | Hollow walls etc | | | | |
| | Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole. | | | | |
| | Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats "Brixeal" bitumen emulsion waterproofing coating. | | | | |
| | User note: The above preamble generally applies for works in hot and humid coastal areas | | | | |
| | Face bricks | | | | |
| | Bricks shall be ordered timeously to obtain uniformity in size and colour | | | | |
| | <u>Pointing</u> | | | | |
| | Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc | | | | |
| | | | | | |
| | | | | | |
| | Carried Forward | | | R | |
| | Section No. 2 BUILDING WORKS Bill No. 2 | | | | |

| | Brought Forward | | | R | |
|---|---|----|----|---|---|
| | SAMPLES | | | | |
| | Samples of all masonry building units, except those for walls units. Samples of building units to be used in walls described as "load bearing" shall consist of 30 units from every 30 000 units delivered to site described as "load bearing", shall consist of a minimum of 6 | | | | |
| | LOCATIONS | | | | |
| | A - Girls Ablution Blocks | | | | |
| | B - Boys Ablution Blocks | | | | |
| | C - Staff Ablution Blocks | | | | |
| | <u>SUPERSTRUCTURE</u> | | | | |
| | Brickwork of NFP bricks in class II mortar | | | | |
| 1 | Half brick walls A:8 B:8 C:6 | m2 | 22 | | |
| | Joint forming material in movement joints | | | | |
| 2 | Vertical separation joint between brick- and/or concrete surfaces formed with 13mm bitumen impregnated softboard joint filler not exceeding 300mm high including raking out for a depth 12mm and finish off with 12 x 13mm bituminous filling. A:1 B:2 C:13 | m | 16 | | |
| | BRICKWORK SUNDRIES | | | | |
| | Brick reinforcement | | | | |
| 3 | 75mm Wide reinforcement built in horizontally A: 12 B: 12 C: 7 | m | 31 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | _ |
| | Carried Forward to Summary of Section No. 2 | | | R | |
| | Section No. 2 BUILDING WORKS Bill No. 2 | | | | |
| | | | | | |

| | Quantity | Rate | Amount |
|---|----------|------|--------|
| SECTION 2 | | | |
| BILL NO.3 | | | |
| CARPENTRY AND JOINERY | | | |
| SUPPLEMENTARY PREAMBLES | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| SUPPLEMENTARY PREAMBLES | | | |
| Particle board: | | | |
| Particle board shall comply with the following specifications: | | | |
| a) SABS 1300 Particle board: exterior and flooring type | | | |
| b) SABS 1301 Particle board: interior type | | | |
| Joinery: | | | |
| Descriptions of frames shall be deemed to include frames, transoms, mullions, rails, etc | | | |
| Descriptions of hardwood joinery shall be deemed to include pelleting of bolt holes | | | |
| Fixing | | | |
| Items described as "nailed" shall be deemed to be fixed with hardened steel nails or shot pins to brickwork or concrete | | | |
| ROOFS ETC | | | |
| Plate nailed timber roof truss construction | | | |
| The following is applicable in respect of roof trusses: | | | |
| Trusses are at maximum 760mm centres | | | |
| The dimensions in the descriptions of the trusses are nominal and actual measurements are to be obtained from the Employer's Agent and/or the site before design or fabrication commences | | | |
| | | | |
| Section No. 2 BUILDING WORKS Bill No. 3 | d | R | |

THE MVULA TRUST

| Brought Forward | R | |
|---|---|--|
| DESCRIPTIONS | | |
| The term "planted on" shall mean the nailing of one timber member to another | | |
| The term "screwed on" shall mean the countersunk screwing of one timber member to another The term "plugged" shall mean the countersunk screwing of a timber member to and including plastic plugs in brickwork or concrete | | |
| Descriptions of floors, ceilings, joinery, etc. shall be deemed to include for all square cutting. Descriptions of items given in linear metre shall be deemed to include for mitres, stopped ends, fitted intersections, etc. Descriptions of rounded angles, rebates, grooves, chamfers, moulded edges, etc. shall be deemed to include for angles, ends, etc. | | |
| PREFABRICATED ROOFS, ETC. | | |
| a) The design, manufacture and transportation of the roof trusses, bracing, etc. shall be under the control of a registered Engineer in accordance with SABS 0243. It shall be required from the manufacturer of the trusses to lodge a written guarantee that his construction has been designed by a qualified Structural Engineer and that he is in possession of a capability certificate issued by the Institute for Timber Construction and approved by the Representative/Agent. | | |
| b) Erection must be carried out as described in "The Erection and Bracing of Timber Roof Trusses" published by the Truss Plate Association of South Africa Ltd. and the National Timber Research Institute, CSIR. | | |
| c) Descriptions of roof trusses shall be deemed to include for design, manufacture, supply, hoisting and fixing in position, trimming ends, notching, etc. and for any temporary and permanent bracing. | | |
| Prefabricated plate nailed timber roof truss construction | | |
| <u>LOCATIONS</u> | | |
| A - Girls Ablution Blocks | | |
| B - Boys Ablution Blocks | | |
| C - Staff Ablution Blocks | | |
| Carried Forward | R | |
| Section No. 2 BUILDING WORKS | | |

| | Brought Forward | | | R | |
|---|--|----|----|---|--|
| | Sawn softwood trusses | | | | |
| 1 | Roof construction to pitched roof with 10 degree pitch approximately 11500 x 3000mm x 2 and 2900mm x 2700mm on plan sloping with 1000mm eaves overhang one one end, including wall plates, trusses, jack rafters, hip rafters, permanent bracing and purlins. Exposed rafters to be treated with approved creasote wood treatment A: 24 B: 24 C: 44 | m2 | 92 | | |
| | DOORS, ETC. | | | | |
| | Wrought hardwood flushback doors with sapele veneer hung to steel frames | | | | |
| 2 | 44mm "TDM" Framed and ledged door 813 x 2 032mm high A:5 B:3 C:5 | No | 13 | | |
| | Semi Solid doors with "Masonite" 3mm standard hardboard covering on both sides suitable for painting hung to steel frames | | | | |
| 3 | 40mm x 813 x 2032mm Standard meranti door A:1 B:1 C:2 | No | 4 | | |
| | EAVES, VERGES, ETC | | | | |
| | Pressed-fibre cement | | | | |
| 4 | Fascias and barge boards A: 19 B: 19 C: 17 | m | 54 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | Carried Forward to Summary of Section No. 2 | | | R | |
| | Section No. 2 BUILDING WORKS Bill No. 3 | | | | |
| | | | | | |

| Item No | | Quantity | Rate | Amount |
|------------|--|----------|------|--------|
| | SECTION 2 | | | |
| | BILL NO. 4 | | | |
| | CEILINGS, PARTITIONS AND ACCESS FLOORING | | | |
| | PREAMBLES | | | |
| | For preambles, refer to "Model Preambles for Trades", for specification of materials and methods to be used - refer to public works document no. PW371 | | | |
| | SUPPLEMENTARY PREAMBLES | | | |
| | Proprietary items or materials Proprietary items or materials where specified are to be of the brand specified - or other approved - by the Employer's Agent | | | |
| | Descriptions Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs in brickwork or concrete at not exceeding 600 mm centres, and where described as "bolted" the bolts have been given elsewhere | | | |
| | LOCATIONS | | | |
| | A - Girls Ablution Blocks | | | |
| | B - Boys Ablution Blocks | | | |
| | C - Staff Ablution Blocks | | | |
| | CEILINGS | | | |
| | "Aerolite" insulation | | | |
| 1 | 75mm Insulation closely fitted and laid on top of brandering between roof timbers etc m2 A: 19 B: 19 C: 18 | 56 | | |
| | NAILED UP AND SCREW UP CEILINGS | | | |
| | Carried Forward Section No. 2 BUILDING WORKS Bill No. 4 | | R | |

| | Brought Forward | t | | R | |
|----------|---|----|----|---|--|
| white m | Everite Nutec" plain boards screw fixed with etal H-profile jointing strips over joints, centres with cross brandering at joints, ends and at light fittings, etc | | | | |
| branderi | including 38 x 50mm sawn softwood ng A:19 B:19 C:18 | m2 | 56 | | |
| Gypsum | plasterboard cornices | | | | |
| | oved cornice fixed to walls A: 18 B: 18 C: 17 | m | 52 | | |
| Trap do | <u>or</u> | | | | |
| Extra ov | er ceiling for 600 x 600mm trap door comprising A:1 B:1 C:1 | No | 3 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| Section | Carried Forward to Summary of Section No. 2 No. 2 IG WORKS | 2 | | R | |

| Item No | | Quantity | Rate | Amount |
|------------|--|----------|------|--------|
| | SECTION 2 | | | |
| | BILL NO. 5 | | | |
| | IRONMONGERY | | | |
| | PREAMBLES | | | |
| | For preambles, refer to "Model Preambles for Trades", for specification of materials and methods to be used - refer to public works document no. PW371 | | | |
| | LOCATIONS | | | |
| | A - Girls Ablution Blocks | | | |
| | B - Boys Ablution Blocks | | | |
| | C - Staff Ablution Blocks | | | |
| | BATHROOM FITTINGS | | | |
| | "Kimberly Clark" or similar approved | | | |
| 1 | Standard vandalproof toilet roll holder A:5 B:3 C:5 | о 13 | | |
| | LOCKS | | | |
| | "Union" | | | |
| 2 | "682-24-52 SC" three lever lockset A:5 B:3 C:5 | o 13 | | |
| 3 | Padlock, 50mm Viro with two keys A:1 B:1 C:1 | 0 3 | | |
| | PUSH PLATES AND KICKING PLATES | | | |
| | "Dorma" | | | |
| 4 | | o 13 | | |
| | A:5 B:3 C:5 | | | |
| | LETTERS, NAMEPLATES, ETC | | | |
| | | | | |
| | | | | |
| | Carried Forward | | R | |
| | Section No. 2 BUILDING WORKS Bill No. 5 | | | |
| | | | | |

| | Brought Forward | | | R | | |
|---|---|----|----|---|---|---|
| | "Union" | | | | | |
| 5 | "AL5066-06ASE08" 152 x 152mm anodised aluminium plate with directional pictogram A:5 B:3 C:5 | No | 13 | | | |
| | SUNDRIES | | | | | |
| 6 | 30mm Diameter rubber door stop plugged & screwed to floor | No | 13 | | | |
| | A:5 B:3 C:5 "Kimberley-Clark"or Simlilar | | | | | |
| 7 | Stainless steel female she-bin plugged to wall A:1 B:0 C:0 | No | 1 | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | Carried Forward to Summary of Section No. 2 | | | R | | |
| | Section No. 2 BUILDING WORKS Bill No. 5 | | | | | |
| | | l | | | I | I |

| Item No | | Quantity | Rate | Amount |
|------------|---|----------|------|--------|
| | SECTION 2 | | | |
| | BILL NO.6 | | | |
| | <u>METALWORK</u> | | | |
| | PREAMBLES | | | |
| | For preambles, refer to "Model Preambles for Trades", for specification of materials and methods to be used - refer to public works document no. PW371 | | | |
| | SUPPLEMENTARY PREAMBLES | | | |
| | <u>Descriptions</u> | | | |
| | Descriptions of bolts shall be deemed to include nuts and washers | | | |
| | Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete | | | |
| | Metalwork described as holed for bolt(s) shall be deemed to exclude the bolts unless otherwise described | | | |
| | LOCATIONS | | | |
| | A - Girls Ablution Blocks | | | |
| | B - Boys Ablution Blocks | | | |
| | C - Staff Ablution Blocks | | | |
| | MILD STEEL DOOR FRAMES | | | |
| | 1.6mm thick mild steel double rebated frame for 220mm wall | | | |
| 1 | Frame for door, size 813 x 2032mm high A:5 B:3 C:5 | 13 | | |
| 2 | Frame for door 900 x 2032mm high A:1 B:1 C:1 | 3 | | |
| | GALVANISED STEEL WINDOWS, DOORS, ETC | | | |
| | Carried Forward Section No. 2 BUILDING WORKS | | R | |
| | Bill No. 6 | | | |

| | Brought Forward | | | R | |
|---|--|----|------|---|-----------|
| | Steel gates and frames | | | | |
| 3 | Purpose made square hallow section mild steel security gate, size 813 x 2032mm High A:1 B:1 C:1 | No | 3 | | |
| | Gate frame to consist of 50 x 50 x 2.5mm rectangular tubing sections metre 45 degrees at corners before welded and secured against wall with 50 x 50 x 5mm with brackeets welded to frame and bolted to wall with 10mm (m10) raw bolts | | | | |
| 4 | Door burglar bars for door size 1500 x 2100mm high complete with lock A:1 B:1 C:1 | No | 3 | | |
| | Protective SHE-BIN cages (female toilets only) | | | | |
| 5 | Allow the Provisional Amount of R12 800.00 (Twelve Thousand Eight Hundred Rand) for supply and installation of protective steel cage to female she-bins A: 0.00 B: 0.00 C: 1.00 | | Item | | 12,800.00 |
| | 71.0.00 2.0.00 0.1.00 | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | Carried Forward to Summary of Section No. 2 Section No. 2 | | | R | |
| | BUILDING WORKS Bill No. 6 | | | | |
| | | | | | |

| | | Quantity | Rate | Amount |
|--|---|---|--|-----------|
| SECTION 2 | | | | |
| BILL NO. 7 | | | | |
| PLASTERING | | | | |
| SUPPLEMENTARY PREAMBLES | | | | |
| For preambles see "Specifications of materials and methods to be used - PW 371" | | | | |
| LOCATIONS | | | | |
| A - Girls Ablution Blocks | | | | |
| B - Boys Ablution Blocks | | | | |
| C - Staff Ablution Blocks | | | | |
| SCREEDS | | | | |
| 3:1 Cement screeds wood floated on concrete | | | | |
| 25mm Thick on floors A: 19 B: 19 C: 26 | m2 | 65 | | |
| INTERNAL PLASTER | | | | |
| Cement plaster on brickwork | | | | |
| On walls A:14 B:62 C:30 | m2 | 106 | | |
| On narrow widths A: 13 B: 13 C: 16 | m2 | 41 | | |
| RHINOLITE | | | | |
| Cement plaster rendering coat with gypsum skim plaster finishing coat, on concrete | | | | |
| On Ceilings A: 19 B: 19 C: 45 | m2 | 84 | | |
| | | | | |
| | | | | |
| Carried Forward to Summary of Section No. 2 | | | R | |
| Section No. 2 BUILDING WORKS Bill No. 7 | | | | |
| | BILL NO. 7 PLASTERING SUPPLEMENTARY PREAMBLES For preambles see "Specifications of materials and methods to be used - PW 371" LOCATIONS A - Girls Ablution Blocks B - Boys Ablution Blocks C - Staff Ablution Blocks SCREEDS 3:1 Cement screeds wood floated on concrete 25mm Thick on floors | BILL NO. 7 PLASTERING SUPPLEMENTARY PREAMBLES For preambles see "Specifications of materials and methods to be used - PW 371" LOCATIONS A - Girls Ablution Blocks B - Boys Ablution Blocks C - Staff Ablution Blocks SCREEDS 3:1 Cement screeds wood floated on concrete 25mm Thick on floors m2 A:19 B:19 C:26 INTERNAL PLASTER Cement plaster on brickwork On walls m2 A:14 B:62 C:30 On narrow widths m2 A:13 B:13 C:16 RHINOLITE Cement plaster rendering coat with gypsum skim plaster finishing coat, on concrete On Ceilings m2 A:19 B:19 C:45 Carried Forward to Summary of Section No. 2 Section No. 2 BUILDING WORKS | SECTION 2 BILL NO. 7 PLASTERING SUPPLEMENTARY PREAMBLES For preambles see "Specifications of materials and methods to be used - PW 371" LOCATIONS A - Girls Ablution Blocks B - Boys Ablution Blocks C - Staff Ablution Blocks SCREEDS 3:1 Cement screeds wood floated on concrete 25mm Thick on floors A: 19 B: 19 C: 26 INTERNAL PLASTER Cement plaster on brickwork On walls A: 14 B: 62 C: 30 On narrow widths A: 13 B: 13 C: 16 RHINOLITE Cement plaster rendering coat with gypsum skim plaster finishing coat, on concrete On Ceilings A: 19 B: 19 C: 45 Carried Forward to Summary of Section No. 2 Section No. 2 BUILDING WORKS | SECTION 2 |

| Item No | | | Quantity | Rate | Amount |
|------------|--|----|----------|------|--------|
| | SECTION 2 | | | | |
| | BILL NO. 8 | | | | |
| | TILING | | | | |
| | PREAMBLES | | | | |
| | For preambles, refer to "Model Preambles for Trades", for specification of materials and methods to be used - refer to public works document no. PW371 | | | | |
| | LOCATIONS | | | | |
| | A - Girls Ablution Blocks | | | | |
| | B - Boys Ablution Blocks | | | | |
| | C - Staff Ablution Blocks | | | | |
| | WALL TILING | | | | |
| | 150 x 150 x 8mm "Johnson Matisse Code AS 002" or other approved Gloss white tiles fixed with adhesive to plaster (plaster elsewhere)and flush pointed with TAL light grey Epoxy grouting | | | | |
| 1 | On walls | m2 | 275 | | |
| | A:102 B:102 C:71 | | | | |
| | FLOOR TILING 300 x 300mm Ceramic tiles fixed with an approved adhesive on prepared screeded floors with 3mm wide joints and flush pointed with tinted jointing compound and sealed with approved sealer | | | | |
| 2 | On floors and landings A: 19 B: 19 C: 35 | m2 | 74 | | |
| 3 | On skirtings not exceeding 150mm high A: 55 B: 55 C: 0 | m | 110 | | |
| | Carried Forward to Summary of Section No. 2 Section No. 2 BUILDING WORKS Bill No. 8 | | | R | |

| Item No | | Quantity | Rate | Amount |
|------------|--|----------|------|--------|
| | SECTION 2 | | | |
| | BILL NO. 8 | | | |
| | PLUMBING AND DRAINAGE (PROVISIONAL) | | | |
| | PREAMBLES | | | |
| | For preambles, refer to "Model Preambles for Trades", for specification of materials and methods to be used - refer to public works document no. PW371 | | | |
| | NOTE: | | | |
| | All prices/rates to be net, excluding Value Added Tax | | | |
| | SUPPLEMENTARY PREAMBLES | | | |
| | uPVC pipes and fittings: | | | |
| | Soil, waste and vent pipes and fittings shall be solvent weld jointed | | | |
| | Copper pipes: | | | |
| | Pipes shall be hard drawn and half-hard pipes of the class stated. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), class 2 (half-hard) and class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground | | | |
| | Fixing of pipes | | | |
| | Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls etc, casting in, building in or suspending not exceeding 1m below suspension level | | | |
| | | | | |
| | | | | |
| | Carried Forward | | R | |
| | Section No. 2 BUILDING WORKS Bill No. 9 | | | |

| Brought Forward | R |
|--|---|
| Reducing fittings | |
| Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm only the largest end or branch size is given. Should the contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm all sizes are given and no claim for extra bushes, reducers, etc will be entertained | |
| Wire gratings | |
| Descriptions of gutter outlets etc shall be deemed to include wire balloon gratings | |
| Exposed concrete surfaces | |
| Exposed surfaces of concrete stormwater channels, cover slabs, inspection eye marker slabs, gulley tops, cleaning eye tops, catchpits, inspection chambers, etc shall be finished smooth with plaster | |
| <u>Excavations</u> | |
| No claim for rock excavation will be entertained unless the contractor has timeously notified the quantity surveyor thereof prior to backfilling | |
| Soft rock and "hard rock" shall be as defined in "Earthworks" | |
| Laying, backfilling, bedding, etc. of pipes | |
| Pipes shall be laid and bedded and trenches shall be carefully backfilled in accordance with manufacturers' instructions | |
| Where no manufacturers' instructions exist pipes shall be laid in accordance with clauses 5.1 and 5.2 of each of the following: SABS 1200 L: Medium-pressure pipelines LD: Sewers LE: Stormwater drainage Pipe trenches etc shall be backfilled in accordance with clauses 3, 5.5, 5.6, 5.7 and 7 of SABS 1200 DB: Earthworks (Pipe trenches) Pipes shall be bedded in accordance with clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SABS 1200 LB: Bedding (Pipes). Unless otherwise described bedding of rigid pipes shall be class B bedding | |
| Carried Forward | R |
| Section No. 2 BUILDING WORKS Bill No. 9 | |

| | | | | Brought Forward | | | R | |
|---|---|---|---|--|----|----|---|--|
| | Flush pans | | | | | | | |
| | Flush pans shall "S" traps as nece | | ght or side o | utlets and "P" or | | | | |
| | Stainless steel betc. | oasins, sir | nks, wash tr | oughs, urinals, | | | | |
| | Units shall have s and tiling keys ag | | | | | | | |
| | Waste unions | | | | | | | |
| | Descriptions of w rubber or vulcanit | | | | | | | |
| | LOCATIONS | | | | | | | |
| | A - Girls Ablution | Blocks | | | | | | |
| | B - Boys Ablution | Blocks | | | | | | |
| | C - Staff Ablution | Blocks | | | | | | |
| | RAINWATER D | ISPOSA | <u>L</u> | | | | | |
| | Mr Gutter Ogee similar seamles: | | approved p | ore-coated | | | | |
| 1 | 100 x 100 x 0.6m including matchin (measured elsew mastic, hung by rhangers at 800m | ng rivet fixe here) inter nail fixed to | ed mitres and nally sealed o internal pre | d end caps using silicon e-painted | m | 44 | | |
| | A : 14 | B : 14 | C : 16 | | | | | |
| 2 | 100 x 76 x 0.5mm pre-painted down fixings | | | | m | 44 | | |
| | A : 14 | B : 14 | C : 16 | | | | | |
| 3 | Extra over 125 x 50mm pipe | 100mm ea | aves gutter fo | or outlet for 75 x | No | 6 | | |
| | A : 4 | B : 2 | C:0 | | | | | |
| 4 | Extra over 75 x 1 offset 750mm pro | | vn pipe for e | aves or plinth | No | 6 | | |
| | A : 4 | B:2 | C:0 | | | | | |
| | | | | | | | | |
| | Section No. 2 BUILDING WORK | KS | | Carried Forward | | | R | |

| | Brought F | orward | | R | |
|----|---|--------|----|---|--|
| 5 | Extra over 75 x 100mm down pipe for shoe A:4 B:2 C:0 | No | 6 | | |
| | SUBSOIL DRAINAGE | | | | |
| | uPVC Pipes underground | | | | |
| 6 | 110mm pipes laid in and including trenches not exceeding 1m deep A: 12 B: 11 C: 13 | m | 36 | | |
| | SANITARY PLUMBING (SOIL AND WASTE) | | | | |
| | uPVC Pipes | | | | |
| 7 | 110mm Diameter pipes A:12 B:9 C:0 | m | 21 | | |
| 8 | 50mm Diameter pipes A: 10 B: 23 C: 0 | m | 33 | | |
| | Extra over for uPVC for fittings | | | | |
| 9 | 50mm Inspection eye junction A:4 B:4 C:0 | No | 8 | | |
| 10 | 50mm - pipe fitting | No | 4 | | |
| | A:2 B:2 C:0 | | | | |
| 11 | 50mm GI two way vent valve A:1 B:1 C:0 | No | 2 | | |
| 12 | 110mm-50mm concentric/eccentric reducers A: 2 B: 1 C: 0 | No | 3 | | |
| 13 | 110mm bends fitting 45/90° A: 2 B: 1 C: 0 | No | 3 | | |
| 14 | 110mm Pan connector A:2 B:2 C:0 | No | 4 | | |
| | SANITARY FITTINGS | | | | |
| | | | | | |
| | Carried F Section No. 2 BUILDING WORKS Bill No. 9 | orward | | R | |

| | Brought Forward | | | R | _ |
|----|--|----|----|---|---|
| | Vaal or other approved | | | | |
| 15 | Code 750200 Vaal "Protea" or similar low level WC suite comprising vitreous china washdown pan (Code 750100) and matching 9 litre cistern (Code 710533) complete with lid and fitments, and purpose made CP side-flush lever mounted to wall. A:5 B:3 C:5 | No | 13 | | |
| 16 | Springbok white glazed porcelain WHB | No | 13 | | |
| | A:5 B:3 C:5 | | | | |
| 17 | TU102 Flat Back Wall Mounted Trough Urinal Right- hand Outlet 1830x780x300mm as supplied or equal approved | No | 1 | | |
| 18 | A:0 B:1 C:0 Vitreous china wallmounted "flatback" urinal (code 7053) supplied with 38mm c.p. domical grating (code 8787),c.p. spreader (code 8543) and two hanger brackets (code 8127), with "cobra watertech flushmaster junior" urinal flush valve (fj6.000) A:0 B:2 C:0 | No | 2 | | |
| | WASTE UNIONS ETC | | | | |
| | Cobra Watertech or other approved | | | | |
| 19 | 38mm basin or sink waste union A:5 B:3 C:5 | No | 13 | | |
| | TRAPS ETC | | | | |
| | Cobra Watertech or other approved | | | | |
| 20 | 40mm 'Flexitrap' flexible rubber reseal 'S' or 'P' trap with clips complete A:5 B:3 C:5 | No | 13 | | |
| | TAPS, VALVES, ETC | | | | |
| | Cobra Watertech or other approved | | | | |
| 21 | Cobra no 401 CP Basin set with 31mm chromium plated whb outlet A:5 B:3 C:5 | No | 13 | | |
| | | | | | |
| | Carried Forward | | | R | _ |
| | Section No. 2 BUILDING WORKS Bill No. 9 | | | | |

| | Brought Forwar | d | | R | _ |
|----|--|----|------|---|---|
| 22 | 22mm Code FJ6.000 "Flushmaster Junior" urinal flushvalve complete with connector, spray rose (Code FJT 5.4) and wallplate. | No | 1 | | |
| | A:0 B:1 C:0 | | | | |
| | SANITARY PLUMBING | | | | |
| | <u>Sundries</u> | | | | |
| 23 | Testing waste pipe system A: 0.00 B: 0.00 C: 1.00 | | Item | | |
| | WATER SUPPLIES | | | | |
| | Galvanised steel pipes | | | | |
| 24 | 25mm Pipes chased into brick walls A: 15 B: 14 C: 0 | m | 29 | | |
| 25 | 15mm Pipes chased into wall A: 19 B: 21 C: 0 | m | 40 | | |
| | Extra over galvanised steel pipes for steel fittings | | | | |
| 26 | 25mm Fittings A:5 B:3 C:5 | No | 13 | | |
| | Class "O" copper pipes, chase into walls and make good for wall to receive paint | | | | |
| 27 | 15mm Pipes A:0 B:25 C:4 | m | 29 | | |
| 28 | 15mm Fittings A:5 B:3 C:5 | No | 13 | | |
| | Extra over class "O" copper pipes for capillary | | | | |
| | <u>fittings</u> | | | | |
| 29 | 15mm Fittings A:7 B:5 C:0 | No | 12 | | |
| | <u>Sundries</u> | | | | |
| | | | | | |
| | | | | | |
| | Carried Forwar | d | | R | _ |
| | Section No. 2 BUILDING WORKS Bill No. 9 | | | | |

| | Brought Forward | | R | |
|----|---|------|---|----------|
| | BUDGETARY ALLOWANCES | | | |
| 30 | Allow the Budgetary Allowance of R 5 000.00 for builders work in connection with the commissioning and servicing of decommissioned water supply services to be expanded in part or whole as directed by Principal Agent A:0.00 B:0.00 C:1.00 | Item | | 5,000.00 |
| | 71.0.00 2.0.00 0.1.00 | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | Carried Forward to Summary of Section No. 2 | | R | |
| | Section No. 2 BUILDING WORKS | | | |
| | Bill No. 9 | | | |
| | | | | |

| Item No | | Quantity | Rate | Amount |
|------------|---|----------|------|--------|
| | SECTION 2 | | | |
| | BILL NO. 9 | | | |
| | GLAZING | | | |
| | SUPPLEMENTARY PREAMBLES | | | |
| | For preambles see "Specifications of materials and methods to be used - PW 371" | | | |
| | MIRRORS | | | |
| | NOTE: | | | |
| | Mirrors shall be of 6mm thick silvered GG quality polished float glass with rounded and polished edges and splayed corners. | | | |
| | Unless otherwise described, mirrors shall have four holes for and be screwed to and including approved patent plugs in plastered or tiled wall with countersunk steel screws tap-threaded for and including screw type chromium plated dome-headed caps and felt washers. | | | |
| | LOCATIONS | | | |
| | A - Girls Ablution Blocks | | | |
| | B - Boys Ablution Blocks | | | |
| | C - Staff Ablution Blocks | | | |
| 1 | 800 x 600mm mirror with polished edges fixed to wall or over tiles with silicone and double sided tape, with silicone bead all around to seal gap between mirror and wall/tiles A:5 B:3 C:5 | 13 | | |
| | GLAZING TO STEEL WITH PUTTY | | | |
| | 4 mm Rough cast glass | | | |
| 2 | Panes exceeding 0,5m2 and not exceeding 2m2 m2 A: 17 B: 10 C: 17 | 44 | | |
| | Carried Forward Section No. 2 BUILDING WORKS Bill No. 10 | | R | |

| | Brought Forward | | R | |
|---|---|------|---|----------|
| | SUNDRY ITEMS | | | |
| 3 | Allow the some of R5 000.00 to assess, service and replace (where necessary) window stays to all windows to be used in part or in whole as directed by the Principal Agent. | Item | | 5,000.00 |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | Carried Forward to Summary of Section No. 2 Section No. 2 BUILDING WORKS Bill No. 10 | | R | |

| Item No | | Quantity | Rate | Amount |
|------------|--|----------|------|--------|
| | SECTION 2 | | | |
| | BILL NO. 10 | | | |
| | PAINTWORK | | | |
| | PREAMBLES | | | |
| | For preambles, refer to "Model Preambles for Trades", for specification of materials and methods to be used - refer to public works document no. PW371 | | | |
| | SUPPLEMENTARY PREAMBLES | | | |
| | PREPARATORY WORK TO EXISTING WORK | | | |
| | Previously painted plastered surfaces | | | |
| | Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth | | | |
| | Previously painted metal surfaces | | | |
| | Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal | | | |
| | Previously painted wood surfaces | | | |
| | Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth | | | |
| | LOCATIONS | | | |
| | A - Girls Ablution Blocks | | | |
| | B - Boys Ablution Blocks | | | |
| | C - Staff Ablution Blocks | | | |
| | PAINTWORK ETC TO PREVIOUSLY PAINTED WORK ON FLOATED | | | |
| | | | | |
| | | | | |
| | Carried Forward | | R | |
| | Section No. 2 BUILDING WORKS Bill No. 11 | | | |
| | | | | |

| | | Brought Forward | | | R | |
|---|---|--|----|-----|---|--|
| One coat unive | | oat and three coats super | | | | |
| 1 On internal walls | | C: 144 | m2 | 348 | | |
| ON METAL | D . 102 | C . 144 | | | | |
| Wash down wit to remove all tr rust, loose and areas with synt | aces of soar flaking pain hetic metal r Indercoat ar | p, rinse with clean water p, remove all traces of t. Spot prime bare metal primer coat, apply one nd apply two coats | | | | |
| 2 On window fram | es B:9 | C:0 | m2 | 25 | | |
| 3 On door burglar | bars B:9 | C:0 | m2 | 17 | | |
| 4 On door frames | B:9 | C:0 | m2 | 17 | | |
| ON FIBRE-CE | | | | | | |
| | | pats interior quality PVA | | | | |
| 5 On ceilings and A: 19 | cornices B : 19 | C:35 | m2 | 74 | | |
| ON WOOD Prepare, stop a oil based wood | | ee coats "Plascon" clear | | | | |
| On doors A: 19 | B : 19 | C:22 | m2 | 61 | | |
| Prepare and ap | oly two coat | s of carbolineum | | | | |
| 7 On exposed root | timbers B : 19 | C:35 | m2 | 74 | | |
| | | | | | R | |

| | Section No. 2 | | | |
|------------|--|------------|---|--------|
| | BUILDING WORKS | | | |
| | SECTION SUMMARY - BUILDING WORKS | | | |
| Bill No | | Page No | | Amount |
| 1 | REFURBISHMENTS | 45 | | |
| 2 | MASONRY | 47 | | |
| 3 | CARPENTRY AND JOINERY | 50 | | |
| 4 | CEILINGS, PARTITIONS AND ACCESS FLOORING | 52 | | |
| 5 | IRONMONGERY | 54 | | |
| 6 | METALWORK | 56 | | |
| 7 | PLASTERING | 57 | | |
| 8 | TILING | 58 | | |
| 9 | PLUMBING AND DRAINAGE | 65 | | |
| 10 | GLAZING | 67 | | |
| 11 | PAINTWORK | 69 | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | Carried to Cluster Summary | | R | |
| | Section No. 2 BUILDING WORKS | | | |
| | | | | |
| | | | | |

| Item No | | Unit | Quantity | Rate | Amount | _ |
|------------|---|------|----------|------|--------|---|
| | SECTION 3 | | | | | |
| | BILL NO. 1 | | | | | |
| | EXTERNAL WORKS (PROVISIONAL) | | | | | |
| | Note: | | | | | |
| | For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014). | | | | | |
| | TEMPORARY BARRIERS, SCREENS,ECT. | | | | | |
| | TEMPORARY HOARDING | | | | | |
| | Note: Contractor to price for the taking down and carting away hoarding on completion. | | | | | |
| | Site clearance | | | | | |
| 1 | Allow for clearing site for the width of 1000mm where fencing runs are to be erected including removing trees, shrubs, etc., not exceeding 200mm girth, grubbing up roots and roughly levelling. | m | 53 | | | |
| 2 | External barricade screen, 1800mm high overall, comprising 100-125mm diameter tanalith treated gumpoles planted 650mm deep in ground at 3000mm centres comprising of six strands of 4mm galvanised straining wires (evenly spaced) secured to posts with doubled 2mm galvanised wire inserted through hole in post and turned a minimum of four turns around straining wire and yellow and orange barrier shade cloth fixed to straining wires with 20Mpa mass concrete base size 400 x 400 x 550mm thick with sloping top surface including all processors are supported by a leftling size of | | | | | |
| | including all necessary excavations, backfilling, risk of collapse and carting away surplus material, etc. | m | 53 | | | |
| | Section No. 3 EXTERNAL WORKS Bill No. 1 | | | R | | |

| Brought Forward | | | R | | _ |
|--|--|--|---|--|---|
| Hot dipped galvanised steel gates | | | | | |
| Security fence double gate, size 3000mm wide x 1800mm high, formed of 80 x 40 x 4mm wall thickness rectangular section framing all round with mitred and welded angles and diagonal cross brace, the gate covered with mesh security fencing secured with "Howgring" clips applied with "Howgring" pliers at 300mm centres to and including six rows of straining wires and yellow/orange barrier shade cloth. | No | 1 | | | |
| THE FOLLOWING IN WALKWAYS | | | | | |
| <u>EARTHWORKS</u> | | | | | |
| Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away | | | | | |
| Reduced levels between buildings, retaining walls, etc. | m3 | 38 | | | |
| Carting away of excavated material | | | | | |
| Extra over all excavations for loading surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. | m3 | 38 | | | |
| BASECOURSES | | | | | |
| G7 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings. | m3 | 34 | | | |
| <u>Sundries</u> | | | | | |
| Rip reduced platform level and recompact to 93% Mod. A.A.S.H.T.O. density. | m2 | 117 | | | |
| Prescribed Testing | | | | | |
| Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed. | No | 12 | | | |
| Carried Forward Section No. 3 EXTERNAL WORKS Bill No. 1 | | | R | | _ |
| | Security fence double gate, size 3000mm wide x 1800mm high, formed of 80 x 40 x 4mm wall thickness rectangular section framing all round with mittred and welded angles and diagonal cross brace, the gate covered with mesh security fencing secured with "Howgring" clips applied with "Howgring" pliers at 300mm centres to and including six rows of straining wires and yellow/orange barrier shade cloth. THE FOLLOWING IN WALKWAYS EARTHWORKS Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Reduced levels between buildings, retaining walls, etc. Carting away of excavated material Extra over all excavations for loading surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. BASECOURSES G7 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings. Sundries Rip reduced platform level and recompact to 93% Mod. A.A.S.H.T.O. density. Prescribed Testing Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed. Carried Forward Section No. 3 EXTERNAL WORKS | Security fence double gate, size 3000mm wide x 1800mm high, formed of 80 x 40 x 4mm wall thickness rectangular section framing all round with mitred and welded angles and diagonal cross brace, the gate covered with mesh security fencing secured with "Howgring" clips applied with "Howgring" pliers at 300mm centres to and including six rows of straining wires and yellow/orange barrier shade cloth. THE FOLLOWING IN WALKWAYS EARTHWORKS Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Reduced levels between buildings, retaining walls, etc. Carting away of excavated material Extra over all excavations for loading surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. BASECOURSES G7 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings. Sundries Rip reduced platform level and recompact to 93% Mod. A.A.S.H.T.O. density. Prescribed Testing Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed. Carried Forward Section No. 3 EXTERNAL WORKS | Security fence double gate, size 3000mm wide x 1800mm high, formed of 80 x 40 x 4mm wall thickness rectangular section framing all round with mitted and welded angles and diagonal cross brace, the gate covered with mesh security fencing secured with "Howgring" clips applied with "Howgring" pilers at 300mm centres to and including six rows of straining wires and yellow/orange barrier shade cloth. THE FOLLOWING IN WALKWAYS EARTHWORKS Excavate in earth not exceeding 2m deep including trimming sides. levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Reduced levels between buildings, retaining walls, etc. m3 38 Carting away of excavated material Extra over all excavations for loading surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. m3 38 BASECOURSES G7 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings. m3 34 Sundries Rip reduced platform level and recompact to 93% Mod. A.A.S.H.T.O. density. m2 117 Prescribed Testing Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed. No 12 | Security fence double gate, size 3000mm wide x 1800mm high, formed of 80 x 40 x 4mm wall thickness rectangular section framing all round with mitred and welded angles and diagonal cross brace, the gate covered with mesh security fencing secured with "Howgring" clips applied with "Howgring" pliers at 300mm centres to and including six rows of straining wires and yellow/orange barrier shade cloth. THE FOLLOWING IN WALKWAYS EXCAVATE IN EXCAVATION IN WALKWAYS EXCAVATE IN EXCAVATE IN THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE IN EACH TO SECURITY OF THE FOLLOWING SIN WALKWAYS EXCAVATE AND SECURE OF THE FOLLOWING SIN WALKWAYS EXCAVATE AND SECURE OF TH | Security fence double gate, size 3000mm wide x 1800mm high, formed of 80 x 40 x 4mm wall thickness rectangular section framing all round with mitred and welded angles and diagonal cross brace, the gate covered with mesh security fencing secured with "Howgring" clips applied with "Howgring" pliers at 300mm centres to and including six rows of straining wires and yellow/orange barrier shade cloth. THE FOLLOWING IN WALKWAYS EXEXUAGE in searth not exceeding 2m deep including trimming sides. levelling and ramming bottoms and depost in spoil heaps for later re-use or cart away Reduced levels between buildings, retaining walls, etc. Carting away of excavated material Extra over all excavations for loading surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. m3 38 BASECOURSES G7 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings. Sundries Rip reduced platform level and recompact to 93% Mod. A.A.S.H.T.O. density. prescribed Testing Provide and have filling compaction check tested by a Consulting Engineer's Laboratory and deliver the results to the Architect within 24 hours of the tests being completed. Carried Forward Section No. 3 EXTERNAL WORKS |

| Brought Forward | ı l | R | |
|------------------------------|-----|---|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| Section No. 3 | | R | |
| EXTERNAL WORKS Bill No. 1 | | | |
| | | | |

| | Brought Forward | | | R | |
|----|--|----|-----|---|--|
| | Weedkillers, insecticides, etc. | | | | |
| | Soil insecticide in accordance with SANS 5859 | | | | |
| 9 | Under paving, etc. | m2 | 53 | | |
| | PRECAST CONCRETE PAVERS | | | | |
| | Grey interlocking precast concrete pavers type S-A laid in herringbone pattern with header course perimeter margin | | | | |
| 10 | 50mm Thick laid on and including 25mm sand bed treated with weed killer and cement/sand mixture swept into joints on completion. | m2 | 53 | | |
| | <u>Sundries</u> | | | | |
| 11 | Circular cutting on 50mm thick non bevelled concrete pavers. | m | 21 | | |
| | Channelling, kerbing, edging, etc. | | | | |
| | Precast concrete kerbing | | | | |
| 12 | Precast semi-mountable concrete Fig 8B edge kerb size 300 x 175mm high cast in lengths not exceeding 1m and with expansion joints at not exceeding 10m centres finished smooth off the mould on all exposed surfaces bedded on and including minimum 50mm thick mass concrete 15 MPa base and backing including all necessary excavation, formwork, expansion joints, etc. | m | 102 | | |
| 13 | Ditto, but circular on plan to not exceeding 4m radius. | m | 38 | | |
| | THE FOLLOWING IN WATER SUPPLY | | | | |
| | ALTERATIONS TO EXISTING | | | | |
| 14 | Locate, cut into and temporarily stop off 40mm diameter water pipe for insertion of stop end (elsewhere). | No | 1 | | |
| 15 | Locate, cut into and temporarily stop off 54mm diameter water pipe for insertion of Tee Junction (elsewhere). | No | 1 | | |
| | | | | | |
| | Carried Forward Section No. 3 EXTERNAL WORKS Bill No. 1 | | | R | |

| | Brought Forward | | | R | |
|----|---|----|-----|---|--|
| 16 | Locate, cut into and temporarily stop off 63mm diameter water pipe for insertion of Tee Junction (elsewhere). | No | 1 | | |
| | PIPEWORK, ETC. | | | | |
| | Pipes, pipe fittings, etc. | | | | |
| | Class 12 uPVC water supply pipe with bedding and filling in accordance with SABS 1200 | | | | |
| 17 | 32mm Pipe and laying in ground not exceeding 1000mm deep. | m | 126 | | |
| 18 | 40mm Pipe and laying in ground not exceeding 1000mm deep. | m | 118 | | |
| | Extra over uPVC pipes for the following fittings | | | | |
| 19 | 32mm bend. | No | 24 | | |
| 20 | 40mm bend. | No | 12 | | |
| 21 | 32mm Tee junction. | No | 9 | | |
| 22 | 40mm Tee junction. | No | 6 | | |
| 23 | 32 x 40 x 32mm Reducing tee. | No | 1 | | |
| 24 | 32 x 54 x 32mm Reducing tee. | No | 1 | | |
| 25 | 40 x 63 x 40mm Reducing tee. | No | 1 | | |
| | Water supply valve or meter chambers | | | | |
| 26 | Excavate for and build valve chamber size 460 x 460 x not exceeding 1000mm deep internally, formed of 300mm thick layer of well backfilling, 200mm high half brick corbelled sides with 75mm brickforce between each course including Type 3A cast iron valve cover and frame size 100 x 230 x 300 encased in a 300mm thick 25mpa mass concrete base. | No | 3 | | |
| | Taps, valves, etc. | | | | |
| 27 | 32mm Gate valve. | No | 3 | | |
| | Carried Forward | | | R | |
| | Section No. 3 EXTERNAL WORKS Bill No. 1 | | | | |

| | | | | | i |
|---|---|---|--|---|---|
| 32mm Non return valve. | No | 1 | | | |
| Testing | | | | | |
| Allow for testing the water supply installation in accordance with the National Building Regulations. | | Item | | | |
| THE FOLLOWING IN SOIL DRAINAGE | | | | | |
| Pipe depth categories and manholes, catchpits, etc. have been measured to the designed invert levels of same. The Contractor is to allow for in his rates for any additional excavation, bedding, backfilling, making up levels, etc. he deems necessary to make up any difference to actual depth. | | | | | |
| EXISTING SERVICES | | | | | |
| Jet or high pressure cleaning to be carried out on subsurface piping, rodding eyes, manholes, etc. to be carried out to the complete satisfaction of the Engineer. | | | | | |
| <u>Pipes</u> | | | | | |
| 110mm Pipe fixed to walls. | m | 8 | | | |
| 110mm Pipe not exceeding 1000mm deep. | m | 18 | | | |
| 110mm Pipe exceeding 1000mm not exceeding 2000mm deep. | m | 14 | | | |
| Rodding eyes | | | | | |
| 110mm Diameter PVC rodding eye. | No | 15 | | | |
| Brick manholes | | | | | |
| Manhole not exceeding 1000mm deep. | No | 4 | | | |
| Manhole exceeding 1000mm not exceeding 2000mm deep. | No | 2 | | | |
| ALTERATIONS TO EXISTING | | | | | |
| Cut into and stop off temporarily 110mm soil pipe for new manhole construction (elsewhere). | No | 1 | | | |
| Carried Forward Section No. 3 EXTERNAL WORKS Bill No. 1 | | | R | | |
| | Allow for testing the water supply installation in accordance with the National Building Regulations. THE FOLLOWING IN SOIL DRAINAGE Pipe depth categories and manholes, catchpits, etc. have been measured to the designed invert levels of same. The Contractor is to allow for in his rates for any additional excavation, bedding, backfilling, making up levels, etc. he deems necessary to make up any difference to actual depth. EXISTING SERVICES Jet or high pressure cleaning to be carried out on subsurface piping, rodding eyes, manholes, etc. to be carried out to the complete satisfaction of the Engineer. Pipes 110mm Pipe fixed to walls. 110mm Pipe exceeding 1000mm not exceeding 2000mm deep. Rodding eyes 110mm Diameter PVC rodding eye. Brick manholes Manhole not exceeding 1000mm deep. Manhole exceeding 1000mm not exceeding 2000mm deep. ALTERATIONS TO EXISTING Cut into and stop off temporarily 110mm soil pipe for new manhole construction (elsewhere). Carried Forward Section No. 3 EXTERNAL WORKS | Allow for testing the water supply installation in accordance with the National Building Regulations. THE FOLLOWING IN SOIL DRAINAGE Pipe depth categories and manholes, catchpits, etc. have been measured to the designed invert levels of same. The Contractor is to allow for in his rates for any additional excavation, bedding, backfilling, making up levels, etc. he deems necessary to make up any difference to actual depth. EXISTING SERVICES Jet or high pressure cleaning to be carried out on subsurface piping, rodding eyes, manholes, etc. to be carried out to the complete satisfaction of the Engineer. Pipes 110mm Pipe fixed to walls. m 110mm Pipe exceeding 1000mm deep. m Rodding eyes 110mm Diameter PVC rodding eye. No Brick manholes Manhole not exceeding 1000mm deep. No Manhole exceeding 1000mm not exceeding 2000mm deep. ALTERATIONS TO EXISTING Cut into and stop off temporarily 110mm soil pipe for new manhole construction (elsewhere). No Carried Forward Section No. 3 EXTERNAL WORKS | Allow for testing the water supply installation in accordance with the National Building Regulations. THE FOLLOWING IN SOIL DRAINAGE Pipe depth categories and manholes, catchpits, etc. have been measured to the designed invert levels of same. The Contractor is to allow for in his rates for any additional excavation, bedding, backfilling, making up levels, etc. he deems necessary to make up any difference to actual depth. EXISTING SERVICES Jet or high pressure cleaning to be carried out on subsurface piping, rodding eyes, manholes, etc. to be carried out to the complete satisfaction of the Engineer. Pipes 110mm Pipe fixed to walls. m 8 110mm Pipe not exceeding 1000mm deep. m 18 110mm Pipe exceeding 1000mm not exceeding 2000mm deep. Rodding eyes 110mm Diameter PVC rodding eye. No 15 Brick manholes Manhole exceeding 1000mm not exceeding 2000mm deep. No 4 Manhole exceeding 1000mm not exceeding 2000mm deep. ALTERATIONS TO EXISTING Cut into and stop off temporarily 110mm soil pipe for new manhole construction (elsewhere). Carried Forward Section No. 3 EXTERNAL WORKS | Allow for testing the water supply installation in accordance with the National Building Regulations. THE FOLLOWING IN SOIL DRAINAGE Pipe depth categories and manholes, catchpits, etc. have been measured to the designed invert levels of same. The Contractor is to allow for in his rates for any additional excavation, bedding, backfilling, making up levels, etc. he deems necessary to make up any difference to actual depth. EXISTING SERVICES Jet or high pressure cleaning to be carried out on subsurface piping, rodding eyes, manholes, etc. to be carried out to the complete satisfaction of the Engineer. Pipes 110mm Pipe fixed to walls. m 8 110mm Pipe exceeding 1000mm deep. m 18 110mm Pipe exceeding 1000mm not exceeding 2000mm deep. Rodding eyes 110mm Diameter PVC rodding eye. No 15 Brick manholes Manhole not exceeding 1000mm deep. No 4 Manhole exceeding 1000mm not exceeding 2000mm deep. No 2 ALTERATIONS TO EXISTING Cut into and stop off temporarily 110mm soil pipe for new manhole construction (elsewhere). Carried Forward Section No. 3 EXTERNAL WORKS | Allow for testing the water supply installation in accordance with the National Building Regulations. THE FOLLOWING IN SOIL DRAINAGE Pipe depth categories and manholes, catchpits, etc. have been measured to the designed invert levels of same. The Contractor is to allow for in his rates for any additional excavation, bedding, backfilling, making up levels, etc. he deems necessary to make up any difference to actual depth. EXISTING SERVICES Jet or high pressure cleaning to be carried out on subsurface piping, rodding eyes, manholes, etc. to be carried out to the complete satisfaction of the Engineer. Pipes 110mm Pipe fixed to walls. m 8 110mm Pipe not exceeding 1000mm deep. m 18 110mm Pipe exceeding 1000mm not exceeding 2000mm deep. Rodding eyes 110mm Diameter PVC rodding eye. No 15 Brick manholes Manhole not exceeding 1000mm deep. No 4 Manhole exceeding 1000mm not exceeding 2000mm deep. No 2 ALTERATIONS TO EXISTING Cut into and stop off temporarily 110mm soil pipe for new manhole construction (elsewhere). No 1 Carried Forward Section No. 3 EXTERNAL WORKS |

| | Brought Forward | | | R | _ |
|----|---|----|----|---|---|
| 37 | Cut into and stop off temporarily 110mm soil pipe for insertion of Tee junction (elsewhere). | No | 1 | | |
| | NEW WORKS | | | | |
| | Class 34 Rigid uPVC socketed soil piping with bedding and filling in accordance with SABS 1200 | | | | |
| 38 | 110mm Pipe and excavation not exceeding 1000mm deep. | m | 18 | | |
| 39 | 110mm Pipe and excavation exceeding 1000mm not exceeding 2000mm deep. | m | 8 | | |
| | Extra over uPVC pipes for fittings | | | | |
| 40 | 110mm 90 Degree bend. | No | 9 | | |
| 41 | 110mm Junction. | No | 2 | | |
| | Rodding eyes, etc. | | | | |
| 42 | PVC Rodding eye and frame and joint to top of 110mm uPVC pipe. | No | 2 | | |
| | Sundries | | | | |
| 43 | 300 x 300 x 75mm Precast concrete inspection eye marker slab set in position including excavations, carting away, ect. | No | 3 | | |
| | MANHOLES, ETC. | | | | |
| 44 | Excavate for and build manhole size 1440 x 1440 x not exceeding 1000mm deep internally, formed of 150mm thick reinforced concrete (25MPa) bottom projecting 150mm all round with welded mesh Ref. 245 both top and bottom, one brick sides, 150mm high precast reinforced concrete (25MPa) cover slab and lid with welded mesh Ref. 245 both top and bottom laid loose on top of brickwork, finished on all exposed surfaces in 3.1 cement plaster and bottom graded to outlets in 3.1 cement mortar. | No | 1 | | |
| | Carried Forward Section No. 3 EXTERNAL WORKS Bill No. 1 | | | R | |

| | Brought Forward | | | R | |
|----|--|----|------|---|--|
| 45 | Excavate for and build manhole size 1440 x 1440 x exceeding 1000mm not exceeding 2000mm deep internally, formed of 150mm thick reinforced concrete (25MPa) bottom projecting 150mm all round with welded mesh Ref. 245 both top and bottom, one brick sides, 150mm high precast reinforced concrete (25MPa) cover slab and lid with welded mesh Ref. 245 both top and bottom laid loose on top of brickwork, finished on all exposed surfaces in 3.1 cement plaster and bottom graded to outlets in 3.1 cement mortar. | No | 2 | | |
| | Cast iron covers and frames | NO | 2 | | |
| 46 | Type 2A cast iron manhole cover and frame size 620mm diameter bedded on top of concrete slab in cement mortar. | No | 3 | | |
| | <u>Testing</u> | | | | |
| 47 | Allow for testing the soil drainage and sewer plumbing installation in accordance with the National Building Regulations. | | Item | | |
| | THE FOLLOWING IN RAINWATER TANKS AND TANKSTANDS (ALL TRADES) | | | | |
| | Rainwater harvesting (Labour intensive) | | | | |
| | Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away | | | | |
| 48 | Reduced levels under solid floors. | m3 | 1 | | |
| 49 | Surface trenches. | m3 | 15 | | |
| | Excavations in earth of more difficult character | | | | |
| 50 | Extra over excavations in earth for excavation in soft rock. | m3 | 2 | | |
| 51 | Extra over excavations in earth for excavation in hard rock. | m3 | 1 | | |
| | | | | | |
| | Carried Forward Section No. 3 EXTERNAL WORKS | | | R | |
| | Bill No. 1 | | | | |

| | Brought Forward | | | R | Γ |
|----|---|----|------|---|---|
| | Carting away of excavated material | | | | |
| 52 | Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. | m3 | 9 | | |
| | Risk of collapse of excavations | | | | |
| 53 | Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc. | m2 | 43 | | |
| | Keeping excavations free of water | | | | |
| 54 | Allow for keeping the excavations free from water. | | Item | | |
| | Filling, layerworks, etc. | | | | |
| 55 | Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 95% Mod AASHTO dry density. | m3 | 7 | | |
| 56 | Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density to trenches, bases, etc. | m3 | 7 | | |
| | Compaction of surfaces | | | | |
| 57 | Scarify in-situ material to a depth of 150mm and compact to 95% Mod AASHTO density. | m2 | 16 | | |
| | <u>Tests</u> | | | | |
| 58 | Allow for Mod AASHTO density tests on filling. | No | 4.00 | | |
| | Reinforced concrete 25MPa in: | | | | |
| 59 | Strip foundations cast against excavated surfaces. | m3 | 5 | | |
| 60 | Surface beds cast in panels including temporary formwork. | m3 | 2 | | |
| | <u>Sundries</u> | | | | |
| 61 | Float surface of concrete to a wood float finish. | m2 | 16 | | |
| | Carried Forward | | | R | _ |
| | Section No. 3 EXTERNAL WORKS Bill No. 1 | | | | |

| | Brought Forward | | | R | | |
|----|---|------|----|---|------|---|
| | Rough formwork (use and waste) to concrete to: | | | | | |
| 62 | Edge, riser, etc not exceeding 300mm high. | m | 32 | | | |
| | High tensile welded steel mesh reinforcement : | | | | | |
| 63 | Ref: 395 cast into concrete surfaces. | m2 | 14 | | | |
| 64 | Ref: 395 cast into concrete strip footings. | m2 | 29 | | | |
| | Brickwork in stock bricks in 5:1 cement mortar : | | | | | |
| 65 | One brick wall. | m2 | 15 | | | |
| 66 | One brick wall in foundations. (Provisional) | m2 | 15 | | | |
| | Brickwork sundries : | | | | | |
| 67 | Galvanised brick reinforcement 150mm wide built horizontally into brickwork. | m | 86 | | | |
| | | "" | 00 | | | |
| | "Rustgold FBS / Qunu Travertine " or other equal approved FBX quality face bricks including jointing and square recess pointing 6 x 10mm joints | | | | | |
| 68 | Extra over ordinary brickwork for facing and pointing in stretcher bond. | m2 | 15 | | | |
| 69 | Extra over ordinary brickwork for facing and pointing in | 1112 | 10 | | | |
| 09 | stretcher bond in foundations. (Provisional) | m2 | 5 | | | |
| | Face brick copings, lintols, cills, etc. | | | | | |
| 70 | Extra over brickwork for brick-on-edge header course coping including pointing to both faces and top. | m | 32 | | | |
| | Movement joints | | | | | |
| 71 | 10mm Thick bitumen impregnated softboard built vertically between concrete and concrete or brickwork | | | | | |
| | surfaces. | m2 | 10 | | | |
| 72 | Rake out 10mm wide softboard for a depth of 10mm and seal with an approved 2 part polysulphide sealant. | m | 18 | | | |
| | | | | | | |
| | | | | | | |
| | Carried Forward | | | R | | |
| | Section No. 3 EXTERNAL WORKS | | | | | |
| | Bill No. 1 | | | | | |
| | ı | | 1 | · | II . | 1 |

| | Brought Forward | | | R | |
|----|--|----|----|---|--|
| | <u>Ties, cramps, etc.</u> | | | | |
| 73 | 38 x 1,6mm Galvanised hoop iron strap around tank, both ends fitted with once holed 30 x 30 x 3mm thick galvanised flat plate and bolted together with and including M8 bolt and nut. | No | 4 | | |
| 74 | 38 x 1,6mm Galvanised hoop iron tie down, 1200mm long, one end wrapped around tank strap and twice bolted, the other end folded over and bolted to top of concrete with and including 8 x 60mm masonry anchor. | No | 16 | | |
| | 250 Micron "Gunplas USB" green polyethylene sheeting : | | | | |
| 75 | Laid flat under solid floor and over walls. | m2 | 14 | | |
| | Rainwater tanks: | | | | |
| 76 | 5000 Litre polyethylene rotomoulded vertical water storage tank provided complete with lid and overflow outlet, fitted with suitable adaptor and setting in position on concrete tankstand (elsewhere measured). (The tanks are to be filled with water for the Practical Completion inspection) | No | 1 | | |
| 77 | Hole through top of tank lid for 100mm diameter pipe. | No | 2 | | |
| | THE FOLLOWING IN ELEVATED TANKS AND GROUND STORAGE (ALL TRADES) | | | | |
| | EXCAVATIONS, FILLING, ETC. | | | | |
| | Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away | | | | |
| 78 | Reduced levels under solid floors. | m3 | 11 | | |
| | Excavations in earth of more difficult character | | | | |
| 79 | Extra over excavations in earth for excavation in soft rock. | m3 | 1 | | |
| | | | | | |
| | Section No. 3 EXTERNAL WORKS Bill No. 1 | | | R | |

| | Brought Forward | | | R | |
|----|--|----|------|---|--|
| | Carting away of excavated material | | | | |
| 80 | Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. | m3 | 12 | | |
| | Risk of collapse of excavations | | | | |
| 81 | Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc. | m2 | 10 | | |
| | Keeping excavations free of water | | | | |
| 82 | Allow for keeping the excavations free from water. | | Item | | |
| | Foundation courses | | | | |
| 83 | Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density under solid floors. | m3 | 4 | | |
| 84 | Imported G5 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density under solid floors. | m3 | 4 | | |
| | Compaction of surfaces | | | | |
| 85 | Scarify in-situ material to a depth of 150mm and compact to 93% Mod AASHTO density. | m2 | 27 | | |
| | <u>Tests</u> | | | | |
| 86 | Allow for Mod AASHTO density tests on filling. | No | 2.00 | | |
| | CONCRETE (Labour intensive) | | | | |
| | Reinforced concrete 30MPa (19mm stone) in: | | | | |
| 87 | Rafter slabs cast against excavated surfaces. | m3 | 8 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | Section No. 3 EXTERNAL WORKS Bill No. 1 | | | R | |

| | Brought Forward | | | R | |
|----|---|------|----|---|--|
| | Testing | | | | |
| 88 | Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional) | Sets | 2 | | |
| | Surface treatment | | | | |
| 89 | Float surface of concrete to a wood float finish. | m2 | 27 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | Carried Forward | | | R | |
| | Section No. 3 | | | K | |
| | EXTERNAL WORKS Bill No. 1 | | | | |
| | | | | | |

| | Brought Forward | | | R | |
|-----|---|----|----|---|--|
| | <u>FORMWORK</u> | | | | |
| | Edges, risers, ends and reveals | | | | |
| 90 | Edge, riser, etc exceeding 300mm high. | m2 | 11 | | |
| | Projections, grooves, etc. | | | | |
| 91 | Labour and material in forming 25 x 25mm chamfer to exposed top edge of concrete. | m | 24 | | |
| | REINFORCEMENT (PROVISIONAL) | | | | |
| | High tensile welded steel mesh reinforcement : | | | | |
| 92 | Ref: 395 cast into concrete surfaces. | m2 | 27 | | |
| | PLUMBING AND DRAINAGE | | | | |
| | ALTERATIONS TO EXISTING | | | | |
| 93 | Locate, cut into and temporarily stop off 63mm diameter water pipe for insertion of reducing fitting (elsewhere). | No | 2 | | |
| | Pipes, pipe fittings, etc. | | | | |
| | Class 12 uPVC water supply pipe with bedding and filling in accordance with SABS 1200 | | | | |
| 94 | 40mm Pipe. | m | 90 | | |
| 95 | 50mm Pipe. | m | 12 | | |
| 96 | 40mm Pipe and laying in ground not exceeding 1000mm deep. | m | 10 | | |
| | Extra over uPVC pipes for the following fittings | | | | |
| 97 | 40mm Bend. | No | 27 | | |
| 98 | 50mm Bend. | No | 5 | | |
| 99 | 40mm Tee junction. | No | 2 | | |
| 100 | 63 x 40mm Straight reducer | No | 2 | | |
| | | | | | |
| | Section No. 3 EXTERNAL WORKS Bill No. 1 | | | R | |

| | Brought Forward | | | R | _ |
|-----|--|----|---|---|---|
| | Taps, valves, etc. | | | | |
| 101 | 40mm float valve kit fitted inside of tank. | No | 3 | | |
| 102 | 40mm In-line strainer. | No | 2 | | |
| 103 | 40mm Brass gate valve. | No | 3 | | |
| 104 | 40mm Brass non return valve. | No | 1 | | |
| 105 | 40mm Flanged resilient seal gate valve with cap top. | No | 2 | | |
| 106 | 40mm Flanged pressure reducing valve. | No | 1 | | |
| | <u>Switch</u> | | | | |
| 107 | Float switch fitted inside of tank. | No | 2 | | |
| | <u>Connections</u> | | | | |
| | Connection of new to existing pipes | | | | |
| 108 | Connection of 40mm diameter HDPE to 40mm diameter galvanised pipes including all necessary reducers, saddles, etc. | No | 2 | | |
| 109 | Connection of 40mm diameter HDPE to 0.75kw water pump including all necessary reducers, saddles, etc. | No | 2 | | |
| 110 | Connection of 63mm diameter HDPE to 40mm diameter galvanised pipes including all necessary reducers, saddles, etc. | No | 1 | | |
| | Rainwater tanks: | | | | |
| 111 | 20 000 Litre polyethylene rotomoulded vertical water storage tank provided complete with lid and overflow outlet, fitted with suitable adaptor and setting in position on concrete tankstand (elsewhere measured). (The tanks are to be filled with water for the Practical Completion inspection) | No | 3 | | |
| 112 | Hole through side of tank for 40mm diameter pipe including adaptor. | No | 6 | | |
| | Carried Forward Section No. 3 EXTERNAL WORKS Bill No. 1 | | | R | |

| | Brought Forward | | | R | |
|-----|---|----|------|---|-----------|
| | <u>Ties, cramps, etc.</u> | | | | |
| 113 | 38 x 1,6mm Galvanised hoop iron strap around tank, both ends fitted with once holed 30 x 30 x 3mm thick galvanised flat plate and bolted together with and including M10 bolt and nut. | No | 3 | | |
| 114 | 38 x 1,6mm Galvanised hoop iron tie down, 2500mm long, one end wrapped around tank strap and twice bolted, the other end folded over and bolted to top of concrete with and including 8 x 60mm masonry anchor. | No | 12 | | |
| | Water supply valve or meter chambers | | | | |
| 115 | Excavate for and build valve chamber size 565 x 665 x 550mm deep overall formed of precast concrete valve chamber units 1, 2, 3 and 4 with valve box lid-V and 19mm thick layer of 19mm stone in bottom including filling in and ramming. | No | 2 | | |
| | Pump and Pumphouse | | | | |
| 116 | Allow the Budgetary Allowance of R 15 000,00 (Fifteen Thousand Rand) for the installation of a 0.75kw water pump including housing, etc. | | Item | | 15,000.00 |
| | ELECTRICAL CONNECTION | | | | |
| | Elevated Tank Electrical Works | | | | |
| 117 | Allow the Budgetary Allowance of R 50 000,00 (Fifty Thousand Rand) for the electrical supply to the water pumps, float switches, ect. | | Item | | 50,000.00 |
| | PROVISION OF TEMPORARY TOILETS DURING THE CONSTRUCTION PERIOD | | | | |
| | Portable toilets | | | | |
| 118 | Supply and erecting of the portable chemical toilet during the duration of the contract. | No | 5 | | |
| 119 | Servicing and maintain the five portable chemical toilets on a weekly basis during duration of the contract. (No = week) | No | 20 | | |
| | | | | | |
| | Carried Forward | | | R | |
| | Section No. 3 EXTERNAL WORKS Bill No. 1 | | | | |

| | Brought Forward | | | R | |
|-----|--|----|---|---|--------------|
| 120 | Removal of the portable chemical toilet on completion of the contract. | No | 5 | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | _ |
| | Carried to Cluster Summary Section No. 3 EXTERNAL WORKS | | | R | |
| | Bill No. 1 | | | | |

| | FINAL SUMMARY | | | |
|---------------|---|------------|---|-----------|
| Section No | | Page No | | Amount |
| 1 | PRELIMINARIES AND GENERAL | 38 | | |
| 2 | BUILDING WORKS | 70 | | |
| 3 | EXTERNAL WORKS | 87 | | |
| | SUB TOTAL (A) | | R | |
| | Allow the sum as indicated for Contingencies 10% | | R | |
| | COMMUNITY LIAISON OFFICER (CLO) | | | |
| | Provide the sum of R 39 000.00 (Thirty Nine Thousand Hundred Rand) for the employment of a CLO.(R 6 500.00 per month x contract period allowance) | Item | | 39,000.00 |
| | Add for profit on the above if required. | Item | | |
| | SUB TOTAL (B) | | R | |
| | Add VAlue Added Tax @ 15% | | R | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | Openial to Final Forms of Tonder | | | |
| | Carried to Final Form of Tender | | R | |
| | | | | |
| | | | | |