



- NOTES ON ERECTION DETAIL:
1. THE HOLES FOR TIMBER POSTS SHALL BE OF SUFFICIENT SIZE TO PERMIT PROPER SETTING OF THE POST AND TO ALLOW SUFFICIENT ROOM FOR BACKFILLING.
 2. AT LEAST 1.0 m OF POST SHALL BE EMBEDDED IN THE GROUND.
 3. HOLES FOR TIMBER POST SHALL BE SPACED TO SUIT THE STANDARDS LENGTH OF GUARDRAIL SUPPLIED.
 4. HOLES SHALL BE BACKFILLED WITH (12:1) SOIL: CEMENT MIXTURE AT OPTIMUM MOISTURE CONTENT IN COMPACTED LAYERS NOT EXCEEDING 100 mm.
 5. WHERE JOINED, THE END OF THE GUARDRAIL WHICH OVERLAPS ON THE SIDE OF THE TRAFFIC SHALL BE POINT IN THE DIRECTION OF THE TRAFFIC MOVEMENT.

- THE ABOVE CRITERIA ARE TO BE APPLIED WITH DISCRETION AND THE POSITION OF ALL GUARDRAILS MUST BE CONFIRMED BY THE ENGINEER PRIOR TO THE ERECTION THEREOF.

[illegible]