

Item No		Quantity	Rate	Amount
	<p><u>SECTION 1 - PRELIMINARIES</u></p> <p><u>BILL NO. 1</u></p> <p><u>PRELIMINARIES</u></p> <p style="text-align: center;">-----</p> <p><u>BUILDING AGREEMENT AND PRELIMINARIES</u></p> <p>The JBCC Series 2000 Principal Building Agreement (March 2005 edition 4.1) prepared by the Joint Building Contracts Committee shall be the applicable building agreement, amended as hereinafter described together with the associated documentation as prepared by the Joint Building Contracts Committee</p> <p>The JBCC Preliminaries (May 2005 edition) published by the Joint Building Contracts Committee for use with the said JBCC Principal Building Agreement shall be deemed to be incorporated in these bills of quantities</p> <p>The Contractor is deemed to have referred to the abovementioned documents for the full intent and meaning of each clause thereof</p> <p>These clauses are hereinafter referred to by clause number and heading only. Where standard clauses or alternatives are not entirely applicable to this contract such modifications, corrections or supplements as will apply are given under each relevant clause heading and such modifications, corrections or supplements shall take precedence notwithstanding anything contrary contained in the abovementioned documents</p> <p>Where any item is not relevant to this specific contract such item is marked N/A, signifying "not applicable"</p> <p>The Bills of Quantities have been drawn up in accordance with the "Standard System of Measuring Building Work Seventh Edition (Revised 2015)" published by The South African Association of Quantity Surveyors</p>			
	Carried Forward		R	
	<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>			

Brought Forward			R	
<p>The quantities or specifications contained in these bills of quantities are not to be used for the calculation or ordering of materials.</p> <p><u>PREAMBLES FOR TRADES</u></p> <p>The General Preambles for Trades (2017 edition) as published by The Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said Model Preambles will be entertained</p> <p>Where Architect's or Engineer's specifications or drawings (where issued) are in conflict with the above Preambles, etc, the Architect's or Engineer's specification and drawings, as the case may be, are to take preference</p> <p>Where the drawings and Architect's or Engineer's specifications are in conflict, the Contractor is to obtain written clarification from the Principal Agent prior to the closing of tenders</p> <p>The Contractor's prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the said Model Preambles and in any supplementary preambles</p>				
Carried Forward			R	
<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>				

	Brought Forward		R
<u>PRICING OF PRELIMINARIES</u>			
If option A as set out in clause B10.3.1 hereinafter is to be used for the adjustment of the preliminaries each item priced is to be allocated to one or more of the three categories "F", "V" or "T" as the case may be below such item, where:			
F -	An amount which shall not be varied (Fixed)		
V -	An amount which shall be varied in proportion to the contract value as compared with the contract sum (Value)		
T -	An amount which shall be varied in proportion to the construction period as compared to the initial construction period excluding revisions to the construction period for which the Contractor is not entitled to adjustment of the contract value in terms of the agreement (Time)		
Items not priced in these Preliminaries shall be deemed to be included elsewhere in these Bills of Quantities			

		Carried Forward	R
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

Brought Forward

R

SECTION A: JBCC PRINCIPAL BUILDING AGREEMENT

DEFINITIONS

1 1.0 Definitions and Interpretation

1.0 Clause

1.1 Definition of "**Commencement Date**" is added:

"**COMMENCEMENT DATE**" means the date that the **agreement**, made in terms of the Form of Offer and Acceptance, comes into effect

Clause 1.1 Definition of "**Construction Period**" is amended by replacing it with the following:

"**CONSTRUCTION PERIOD**" means the period commencing on the commencement date and ending on the date of practical completion

Clause 1.1 Definition of "**Interest**" is amended by replacing it with the following:

"**INTEREST**" means the interest rates applicable on this contract, whether specifically indicated in the relevant clauses or not, will be in terms of the legislation of the Republic of South Africa, and in particular:

- (a) In respect of interest owed by the **employer**, the interest rate as determined by the Minister of Justice and Constitutional Development, from time to time, in terms of section 1(2) of the Prescribed Rate of Interest Act, 1975 (Act No. 55 of 1975), will apply; and
- (b) in respect of interest owed to the **employer**, the interest rate as determined by the Minister of Finance, from time to time, in terms of section 80(1)(b) of the Public Finance Management Act, 1999 (Act No. 1 of 1999), will apply.

Carried Forward

R

Section No. 1
 Preliminaries
 Bill No. 1
 PRELIMINARIES
Diatho Consulting (PTY) LTD

	Brought Forward		R
	<p>Clause 1.6.4 is amended by replacing it with the following:</p> <p>No clause</p> <p>F: V: T: </p>	Item	
	<p><u>OBJECTIVE AND PREPARATION</u></p>		
2	<p>2.0 Offer, Acceptance and Performance</p> <p>F: V: T: </p>	Item	
3	<p>3.0 Documents</p> <p>3.7 is amended by the addition of the following:</p> <p>The Contractor shall supply and keep a copy of the JBCC Series 2000 Principal Building Agreement and Preliminaries applicable to this contract on the site, to which the Employer, Principal Agent and agents shall have access at all times</p> <p>F: V: T: </p>	Item	
4	<p>4.0 Design Responsibility</p> <p>F: V: T: </p>	Item	
5	<p>5.0 Employer's Agent</p> <p>5.1.2 is amended to include clauses 32.6.3, 34.3 and 34.4</p> <p>F: V: T: </p>	Item	
	Carried Forward		R
	<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>		

	Brought Forward		R	
6	<p>6.0 Site Representative</p> <p>F: V: T: </p>	Item		
7	<p>7.0 Compliance with Regulations</p> <p>Note: The provisions herein include inter alia, compliance with all the requirements set out in the Construction Regulations, 2003 issued under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993), and in particular with Regulation 5(1) requiring the compilation of a health and safety plan, as well as Regulation 6(1) requiring the appointment of a construction supervisor</p> <p>See also clause C10 of Section C - Specific Preliminaries</p> <p>F: V: T: </p>	Item		
8	<p>8.0 Works Risk</p> <p>F: V: T: </p>	Item		
9	<p>9.0 Indemnities</p> <p>F: V: T: </p>	Item		
10	<p>10.0 WORKS INSURANCES</p> <p>Clause 10.0 is amended by the addition of the following clauses:</p>			
	Carried Forward		R	
	<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>			

Brought Forward	R
<p>10.5 Damage to the Works</p> <p>(a) Without in any way limiting the contractor's obligations in terms of the contract, the contractor shall bear the full risk of damage to and/or destruction of the works by whatever cause during construction of the works and hereby indemnifies and holds harmless the employer against any such damage. The contractor shall take such precautions and security measures and other steps for the protection and security of the works as the contractor may deem necessary</p> <p>(b) The contractor shall at all times proceed immediately to remove or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works</p> <p>(c) The employer shall carry the risk of damage to or destruction of the works and material paid for by the employer that is the result of the excepted risks as set out in 10.6</p> <p>(d) Where the employer bears the risk in terms of this contract, the contractor shall, if requested to do so, reinstate any damage or destroyed portions of the works and the costs of such reinstatement shall be measured and valued in terms of 32.0 hereof</p> <p>10.6 Injury to Persons or loss of or damage to Properties</p> <p>(a) The contractor shall be liable for and hereby indemnifies the employer against any liability, loss, claim or proceeding whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever arising out of or in the course of or caused by the execution of the works unless due to any act or neglect of any person for whose actions the employer is legally liable</p>	R
Carried Forward	R
<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>	

	Brought Forward	
<p>(b) The contractor shall be liable for and hereby indemnifies the employer against any liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the site, whether belonging to or under the control of the employer or any other body or person, arising out of or in the course of or by reason of the execution of the works unless due to any act or neglect of any person for whose actions the employer is legally liable</p> <p>(c) The contractor shall, upon receiving a contract instruction from the principal agent, cause the same to be made good in a perfect and workmanlike manner at his own cost and in default thereof the employer shall be entitled to cause it to be made good and to recover the cost thereof from the contractor or to deduct the same from amounts due to the contractor</p> <p>(d) The contractor shall be responsible for the protection and safety of such portions of the premises placed under his control by the employer for the purpose of executing the works until the issue of the certificate of practical completion</p> <p>(e) Where the execution of the works involves the risk of removal of or interference with support to adjoining properties including land or structures or any structures to be altered or added to, the contractor shall and will remain adequately insured or insured against the death of or injury to persons or damage to such property consequent on such removal or interference with the support until such portion of the works has been completed</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>	R	

Brought Forward			R
<p>(f) The contractor shall at all times proceed immediately at his own cost to remove or dispose of any debris and to rebuild, restore, replace and/or repair such property and to execute the works</p> <p>10.7 High risk insurance</p> <p>In the event of the project being executed in a geological area classified as a "High Risk Area", that is an area which is subject to highly unstable subsurface conditions that might result in catastrophic ground movement evident by sinkhole or doline formation the following will apply:</p> <p>10.7.1 Damage to the works</p> <p>The contractor shall, from the commencement date of the works until the date of the certificate of practical completion bear the full risk of and hereby indemnifies and holds harmless the employer against any damage to and/or destruction of the works consequent upon a catastrophic ground movement as mentioned above. The contractor shall take such precautions and security measures and other steps for the protection of the works as he may deem necessary</p> <p>When so instructed to do so by the Principal Agent, the Contractor shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works, at the contractor's own costs</p> <p>10.7.2 Injury to persons or loss of or damage to property</p> <p>The contractor shall be liable for and hereby indemnifies and holds harmless the employer against any liability, loss, claim or proceeding arising at any time during the period of the contract whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever resulting from, arising out of or caused by a catastrophic ground movement as mentioned above</p>			
Carried Forward			R
<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>			

	Brought Forward		R
	<p>The contractor shall be liable for and hereby indemnifies the employer against any and all liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the site, whether belonging to or under the control of the employer or any other body or person whomsoever arising out of or caused by a catastrophic ground movement, as mentioned above, which occurred during the period of the contract</p> <p>10.7.3 It is the responsibility of the contractor to ensure that he has adequate insurance to cover his risk and liability as mentioned in 10.7.1 and 10.7.2. Without limiting the contractor's obligations in terms of the contract, the contractor shall, within twenty-one (21) calendar days of the commencement date but before commencement of the works, submit to the employer proof of such insurance policy, if requested to do so</p> <p>10.7.4 The employer shall be entitled to recover any and all losses and/or damages of whatever nature suffered or incurred consequent upon the contractor's default of his obligations as set out in 10.7.1; 10.7.2 and 10.7.3. Such losses or damages may be recovered from the contractor or by deducting the same from any amounts still due under this contract or under any other contract presently or hereafter existing between the employer and the contractor and for this purpose all these contracts shall be considered one indivisible whole</p> <p>F: V: T: </p>		
11	<p>11.0 Liability Insurances</p> <p>F: V: T: </p>	Item	
12	<p>12.0 Effecting Insurances</p> <p>F: V: T: </p>	Item	
	Carried Forward		R
	<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>		

	Brought Forward		R
13	13.0 <i>No clause</i>	N/A	
14	14.0 SECURITY Clauses 14.1 - 14.8 are amended by replacing them with the following: 14.1 In respect of contracts with a contract sum up to R1 million, the security to be submitted by the contractor to the employer will be as a payment reduction of five per cent (5%) of the value certified in the payment certificate (excluding VAT) 14.1.1 The payment reduction of the value certified in a payment certificate shall be <i>mutatis mutandi</i> in terms of 31.8(A) 14.1.2 The employer shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the payment reduction security or portions thereof to the contractor 14.2 In respect of contracts with a contract sum above R1 million, the contractor shall have the right to select the security to be provided in terms of 14.3, 14.4, 14.5, 14.6, or 14.7 as stated in the schedule . Such security shall be provided to the employer within twenty-one (21) calendar days from commencement date . Should the contractor fail to select the security to be provided or should the contractor fail to provide the employer with the selected security within twenty-one (21) calendar days from commencement date , the security in terms of 14.7 shall be deemed to have been selected. 14.3 Where security as a cash deposit of ten per cent (10%) of the contract sum (excluding VAT) has been selected:		
	Carried Forward		R
	Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD		

Brought Forward			R
<p>14.3.1 The contractor shall furnish the employer with a cash deposit equal in value to ten per cent (10%) of the contract sum (excluding VAT) within twenty-one (21) calendar days from commencement date</p> <p>14.3.2 Within twenty-one (21) calendar days of the date of practical completion of the works the employer shall reduce the cash deposit to an amount equal to three per cent (3%) of the contract value (excluding VAT), and refund the balance to the contractor</p> <p>14.3.3 Within twenty-one (21) calendar days of the date of final completion of the works the employer shall reduce the cash deposit to an amount equal to one per cent (1%) of the contract value (excluding VAT) and refund the balance to the contractor</p> <p>14.3.4 On the date of payment of the amount in the final payment certificate, the employer shall refund the remainder of the cash deposit to the contractor</p> <p>14.3.5 The employer shall be entitled to recover expense and loss from the cash deposit in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the cash deposit security or portions thereof to the contractor</p> <p>14.3.6 The parties expressly agree that neither the employer nor the contractor shall be entitled to cede the rights to the deposit to any third party</p> <p>14.4 Where security as a variable construction guarantee of ten percent (10%) of the contract sum (excluding VAT) has been selected:</p> <p>14.4.1 The contractor shall furnish the employer with an acceptable variable construction guarantee equal in value to ten per cent (10%) of the contract sum (excluding VAT) within twenty-one (21) calendar days from commencement date</p>			
Carried Forward			R
<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
14.4.2 The variable construction guarantee shall reduce and expire in terms of the Variable Construction Guarantee form included in the invitation to tender			
14.4.3 The employer shall return the variable construction guarantee to the contractor within fourteen (14) calendar days of it expiring			
14.4.4 Where the employer has a right of recovery against the contractor in terms of 33.0, the employer shall issue a written demand in terms of the variable construction guarantee			
14.5 Where security as a fixed construction guarantee of five per cent (5%) of the contract sum (excluding VAT) and a five per cent (5%) payment reduction of the value certified in the payment certificate (excluding VAT) has been selected:			
14.5.1 The contractor shall furnish a fixed construction guarantee to the employer equal in value to five per cent (5%) of the contract sum (excluding VAT)			
14.5.2 The fixed construction guarantee shall come into force on the date of issue and shall expire on the date of practical completion			
14.5.3 The employer shall return the fixed construction guarantee to the contractor within fourteen (14) calendar days of it expiring			
14.5.4 The payment reduction of the value certified in a payment certificate shall be in terms of 31.8 (A) and 34.8			
14.5.5 Where the employer has a right of recovery against the contractor in terms of 33.0, the employer shall be entitled to issue a written demand in terms of the fixed construction guarantee or may recover from the payment reduction or may do both			
Carried Forward			R
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

Brought Forward			R
<p>14.6 Where security as a cash deposit of five per cent (5%) of the contract sum (excluding VAT) and a payment reduction of five per cent (5%) of the value certified in the payment certificate (excluding VAT) has been selected:</p> <p>14.6.1 The contractor shall furnish the employer with a cash deposit equal in value to five per cent (5%) of the contract sum (excluding VAT) within twenty-one (21) calendar days from commencement date</p> <p>14.6.2 Within twenty-one (21) calendar days of the date of practical completion of the works the employer shall refund the cash deposit in total to the contractor</p> <p>14.6.3 The payment reduction of the value certified in a payment certificate shall be <i>mutatis mutandi</i> in terms of 31.8(A)</p> <p>14.6.4 Where the employer has a right of recovery against the contractor in terms of 33.0, the employer may issue a written notice in terms of 33.4 or may recover from the payment reduction or may do both</p> <p>14.7 Where security as a payment reduction of ten per cent (10%) of the value certified in the payment certificate (excluding VAT) has been selected:</p> <p>14.7.1 The payment reduction of the value certified in a payment certificate shall be <i>mutatis mutandi</i> in terms of 31.8(B)</p> <p>14.7.2 The employer shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the payment reduction or portions thereof to the contractor</p> <p>14.8 Payments made by the guarantor to the employer in terms of the fixed or variable construction guarantee shall not prejudice the rights of the employer or contractor in terms of this agreement</p>			
Carried Forward			R
<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>			

	Brought Forward		R
	<p>14.9 Should the contractor fail to furnish the security in terms of 14.2, the employer, in his sole discretion and without notification to the contractor, is entitled to change the contractor's selected form of security to that of a ten per cent (10%) payment reduction of the value certified in the payment certificate (excluding VAT), whereafter 14.7 shall be applicable</p> <p>F: V: T:</p> <p><u>EXECUTION</u></p>	Item	
15	<p>15.0 PREPARATION FOR AND EXECUTION OF THE WORKS</p> <p>Clause 15.1.1 is amended by replacing it with:</p> <p>No Clause</p> <p>Clause 15.1 is amended by the addition of the following clause: 15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty-one (21) calendar days of commencement date</p> <p>Clause 15.2.1 is amended by replacing it with the following clause:</p> <p>Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.2 and 15.1.4</p> <p>F: V: T:</p>	Item	
16	<p>16.0 Access to the Works</p> <p>F: V: T:</p>	Item	
	Carried Forward		R
	<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>		

	Brought Forward			R
17	17.0 Contract Instructions F: V: T:	Item		
18	18.0 Setting out of the Works F: V: T:	Item		
19	19.0 Assignment F: V: T:	Item		
20	20.0 Nominated Subcontractors 20.1.3 is amended by replacing it with the following: Note: See item B9.1 hereinafter for adjustment of attendance on nominated subcontractors executing work allowed for under provisional sums F: V: T:	Item		
21	21.0 Selected Subcontractors 21 is amended by replacing it with: No Clause F: V: T:	N/A		
22	22.0 Employer's Direct Contractors F: V: T:	Item		
23	23.0 Contractor's Domestic Subcontractors F: V: T:	Item		
	Carried Forward			R
	Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

	Brought Forward			R
	<u>COMPLETION</u>			
24	24.0 Practical Completion F: V: T:	Item		
25	25.0 Work's Completion F: V: T:	Item		
26	26.0 Final Completion F: V: T:	Item		
27	27.0 Latent Defects Liability Period F: V: T:	Item		
28	28.0 Sectional Completion F: V: T:	Item		
29	29.0 Revision of Date for Practical Completion F: V: T:	Item		
30	30.0 Penalty for Noncompletion F: V: T:	Item		
	<u>PAYMENT</u>			
31	31.0 INTERIM PAYMENT TO THE CONTRACTOR 31.8 is amended by replacing it with the following two alternative clauses:			
	Carried Forward			R
	Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

Brought Forward				R
Alternative A				
31.8(A) Where a security is selected in terms of 14.1; 14.5 or 14.6, the value of the works in terms of 31.4.1 and materials and goods in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments:				
31.8(A).1 Ninety-five per cent (95%) of such value in interim payment certificates issued up to the date of practical completion				
31.8(A).2 Ninety-seven per cent (97%) of such value in interim payment certificates issued on the date of practical completion and up to but excluding the date of final completion				
31.8(A).3 Ninety-nine per cent (99%) of such value in interim payment certificates issued on the date of final completion and up to but excluding the final payment certificate in terms of 34.6				
31.8(A).4 One hundred per cent (100%) of such value in the final payment certificate in terms of 34.6 except where the amount certified is in favour of the employer . In such an event the payment reduction shall remain at the adjustment level applicable to the final payment certificate				
Alternative B				
31.8(B) Where security is a payment reduction in terms of 14.7 the value of the works in terms of 31.4.1 and materials and goods in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments:				
31.8(B).1 Ninety per cent (90%) of such value in interim payment certificates issued up to the date of practical completion				
Carried Forward				R
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD				

	Brought Forward		R
	<p>31.8(B).2 Ninety-seven per cent (97%) of such value in interim payment certificates issued on the date of practical completion and up to but excluding the date of final completion</p> <p>31.8(B).3 Ninety-nine per cent (99%) of such value in interim payment certificates issued on the date of final completion and up to but excluding the final payment certificate in terms of 34.6</p> <p>31.8(B).4 One hundred per cent (100%) of such value in the final payment certificate in terms of 34.6 except where the amount certified is in favour of the employer. In such an event the payment reduction shall remain at the adjustment level applicable to the final payment certificate</p> <p>Clause 31.12 is amended by deleting the following:</p> <p>Payment shall be subject to the employer giving the contractor a tax invoice for the amount due</p> <p>F: V: T: </p>		
32	<p>32.0 Adjustment to the Contract Value</p> <p>Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence:</p> <p>"due to no fault of the contractor"</p> <p>F: V: T: </p>	Item	
33	<p>33.0 RECOVERY OF EXPENSE AND LOSS</p> <p>Clause 33.2 is amended by adding the following clauses:</p> <p>33.2.9 the contractor's failure or neglect to commence with the works on the dates prescribed in the contract</p>	Item	
	Carried Forward		R
	<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>		

	Brought Forward		R
	33.2.10 the contractor's failure or neglect to proceed with the works in terms of the contract		
	33.2.11 the contractor's failure or neglect for any reason to complete the works in accordance with the contract		
	33.2.12 the contractor's refusal or neglect to comply strictly with any of the conditions of contract or any contract instructions and/or orders in writing given in terms of the contract		
	33.2.13 the contractor's estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa		
	F: V: T:	Item	
34	34.0 Final Account and Final Payment		
	Clause 34.13 is amended by replacing "seven (7) calendar days " with "twenty-one (21) calendar days " and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due"		
	F: V: T:	Item	
35	35.0 Payment to other Parties		
	F: V: T:	Item	
	Carried Forward		R
	Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD		

Brought Forward

R

CANCELLATION

36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT

36.3 is amended by removing the reference to "No clause" and replacing the words "**principal agent**" with "**employer**"

36.0 is amended by the addition of the following clause:

36.7 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

F: V: T:

36 **37.0 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE**

37.0 is amended by the addition of the following clause:

37.5 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

F: V: T:

Item

Carried Forward

R

Section No. 1
 Preliminaries
 Bill No. 1
 PRELIMINARIES
Diatho Consulting (PTY) LTD

	Brought Forward		R
37	<p>38.0 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT</p> <p>Clause 38.0 is amended by the addition of the following clause:</p> <p>38.7 Notwithstanding any clause to the contrary, on cancellation of this agreement either by the employer or the contractor; or for any reason whatsoever, the contractor shall on written instruction, discontinue with the works on a date stated and withdraw himself from the site. The contractor shall not be entitled to refuse to withdraw from the works on the grounds of any lien or right of retention or on the grounds of any other right whatsoever</p> <p>F: V: T: </p>		
38	<p>39.0 Cancellation - Cessation of the Works</p> <p>F: V: T: </p>	Item	
39	<p>40.0 Dispute Settlement</p> <p>40.2.2 is amended by replacing "one (1) year" with "three (3) years"</p> <p>40.6 is amended by removing the reference to: No clause</p> <p>40.7.1 is amended by replacing "(10)" with "(15)" and by the addition of the following:</p> <p>Whether or not mediation resolves the dispute, the parties shall bear their own cost concerning the mediation and equally share the costs of the mediator and related costs</p> <p>F: V: T: </p>	Item	
	Carried Forward		R
	<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>		

Brought Forward

R

SUBSTITUTE PROVISIONS

40 41.0 State Clauses

F: V: T:

Item

CONTRACT VARIABLES

THE SCHEDULE (DPW04EC)

41 42.0 E-TENDER INFORMATION

Tenderers are referred to section "C1.2 Contract Data"
 on page 56 for variables pertaining to this contract

F: V: T:

Item

Carried Forward

R

Section No. 1
 Preliminaries
 Bill No. 1
 PRELIMINARIES
Diatho Consulting (PTY) LTD

Brought Forward			R
<u>SECTION B: JBCC PRELIMINARIES</u>			
<u>1.0 DEFINITIONS AND INTERPRETATION</u>			
42	1.1 Definitions and interpretation F: V: T:	Item	
<u>2.0 DOCUMENTS</u>			
43	2.1 Checking of documents F: V: T:	Item	
44	2.2* Provisional bills of quantities F: V: T:	Item	
45	2.3* Availability of construction documentation F: V: T:	Item	
46	2.4* Interests of agents F: V: T:	Item	
47	2.5 Priced documents F: V: T:	Item	
48	2.6 Tender submission Clause 2.6 is amended by replacing “JBCC Form of Tender” with “Form of Offer and Acceptance (DPW07)” F: V: T:	Item	
Carried Forward			R
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

	Brought Forward		R	
	<u>3.0 THE SITE</u>			
49	3.*1 Defined works area F: V: T:	Item		
50	3.2* Geotechnical investigation F: V: T:	Item		
51	3.3 Inspection of the site Tenderers shall complete the Site Inspection Certificate (DPW16 EC) included in the tender documents and return the same with the tender submission. F: V: T:	Item		
52	3.4* Existing premises occupied F: V: T:	Item		
53	3.5* Previous work - dimensional accuracy F: V: T:	Item		
54	3.6 Previous work - defects F: V: T:	Item		
55	3.7* Services - known F: V: T:	Item		
	Carried Forward		R	
	Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

	Brought Forward		R	
56	3.8 Services - unknown F: V: T:	Item		
57	3.9* Protection of trees F: V: T:	Item		
58	3.10 Articles of value F: V: T:	Item		
59	3.11* Inspection of adjoining properties F: V: T:	Item		
<u>4.0 MANAGEMENT OF CONTRACT</u>				
60	4.1 Management of the works F: V: T:	Item		
61	4.2 Programme for the works F: V: T:	Item		
62	4.3 Progress meetings F: V: T:	Item		
63	4.4 Technical meetings F: V: T:	Item		
Carried Forward			R	
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD				

	Brought Forward		R
64	4.5 Labour and plant records F: V: T:	Item	
<u>5.0 SAMPLES, SHOP DRAWINGS AND MANUFACTURERS' INSTRUCTIONS</u>			
65	5.1 Samples of materials F: V: T:	Item	
66	5.2 Workmanship samples F: T: V:	Item	
67	5.3 Shop drawings F: V: T:	Item	
68	5.4 Compliance with manufacturers' instructions F: T: V:	Item	
<u>6.0 TEMPORARY WORKS AND PLANT</u>			
69	6.1 Deposits and fees F: V: T:	Item	
70	6.2* Enclosure of the works F: V: T:	Item	
71	6.3 Advertising F: V: T:	Item	
Carried Forward			R
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

	Brought Forward			R
72	<p>6.4* Plant, equipment, sheds and offices</p> <p>The contractor shall provide, maintain and remove on completion of the works an office for the exclusive use for meetings to be held on site. The minimum size of the office shall be 4 x 4 x 2,70m high internally with concrete floor, insulated ceiling and roof. The office shall be suitably ventilated, equipped with electric lighting and fitted with table, six (6) chairs, one (1) pinning board 2,40 x 1,20m high, one (1) writing board 2,40 x 1,20m high and a set of ten (10) aluminium "Ozafite" drawing hangers complete with stand. The office shall be kept clean and fit for use at all times</p> <p>F: V: T: </p>	Item		
73	<p>6.5* Main notice board</p> <p>The contractor shall provide, erect where directed, maintain and remove on completion of the works a notice board size 3 x 3m high, constructed of suitable boarding with flat smooth surface on a suitable square tubular steel sub-frame and fixed to and including a suitable supporting structure of timber or tubular posts and braces.</p> <p>F: V: T: </p>	Item		
74	<p>6.6* Subcontractors' notice board</p> <p>F: V: T: </p>	Item		
	<u>7.0 TEMPORARY SERVICES</u>			
75	<p>7.1 Location</p> <p>F: V: T: </p>	Item		
	Carried Forward			
	<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
76	7.2& Water F: V: T:	Item		
77	7.3& Electricity F: V: T:	Item		
78	7.4& Telecommunication facilities F: V: T:	Item		
79	7.5& Ablution facilities F: V: T:	Item		
	<u>8.0 PRIME COST AMOUNTS</u>			
80	8.1 Responsibility for prime cost amounts F: V: T:	Item		
	<u>9.0 ATTENDANCE ON N/S SUBCONTRACTORS</u>			
81	9.1 General attendance The schedule rates providing for attendance on nominated subcontractors and other contractors , will be adjusted only if the scope of the work has changed F: V: T:	Item		
82	9.2* Special attendance F: V: T:	Item		
	Carried Forward			R
	Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

	Brought Forward			R
83	9.3 Commissioning - fuel, water and electricity F: V: T:	Item		
	<u>10.0 FINANCIAL ASPECTS</u>			
84	10.1 Statutory taxes, duties and levies F: V: T:	Item		
85	10.2 & Payment for preliminaries F: V: T:	Item		
86	10.3 & Adjustment of preliminaries F: V: T:	Item		
87	10.4 Payment certificate cash flow F: V: T:	Item		
	<u>11.0 GENERAL</u>			
88	11.1* Protection of the works F: V: T:	Item		
89	11.2* Protection / isolation of existing / sectionally occupied works F: V: T:	Item		
90	11.3 Security of the works F: V: T:	Item		
	Carried Forward			R
	Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

	Brought Forward		R	
91	11.4 Notice before covering work F: V: T:	Item		
92	11.5* Disturbance F: V: T:	Item		
93	11.6* Environmental disturbance F: V: T:	Item		
94	11.7 Works cleaning and clearing F: V: T:	Item		
95	11.8 Vermin F: V: T:	Item		
96	11.9 Overhand work F: V: T:	Item		
97	11.10 Instruction manuals and guarantees F: V: T:	Item		
98	11.11 As built information F: V: T:	Item		
99	11.12 Tenant installations F: V: T:	Item		
	Carried Forward		R	
	Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

	Brought Forward		R
<u>12.0 SCHEDULE OF VARIABLES</u>			
12.1 PRE-TENDER INFORMATION			
12.1.1 Provisional bills of quantities [2.2]			
YES			
12.1.2 Availability of construction documentation [2.3]			
YES			
12.1.3 Interests of agents [2.4]			
N/A			
12.1.4 Defined works area [3.1]			
Give details and/or refer Architect's site plan drawing no where available			
12.1.5 Geotechnical Investigation [3.2]			
Geotechnical investigation report where available			
12.1.6 Existing premises occupied [3.4]			
The existing buildings on the site is occupied by school learners and staff			
12.1.7 Previous work - dimensional accuracy [3.5]			
N/A			
12.1.8 Previous work - defects [3.6]			
N/A			
		Carried Forward	R
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

	Brought Forward		R
12.1.9 Services - known [3.7]			
Not known			
12.1.10 Protection of trees [3.9]			
Trees not being removed must be protected.			
12.1.11 Inspection of adjoining properties [3.11]			
This also applies to roads and services, etc.			
12.1.12 Enclosure of the works [6.2]			
No specific requirements			
12.1.13 Offices [6.4.3]			
The Contractor shall provide, maintain and remove on completion of the works an office for the exclusive use of the Principal Agent, minimum size 6 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with boarded floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times			
Carried Forward			R
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD			

	Brought Forward		R
<p>12.1.14 Main notice board [6.5]</p> <p>Provide ONE (1) noticeboards, eg:</p> <p>The Contractor shall provide, erect where directed, maintain and remove on completion of the works a notice board size 3 x 3m, constructed of suitable boarding with flat smooth surface and with edging bead 19mm thick round outer edges and projecting 12mm from face of boarding and rounded on front edge. The board shall be securely fixed to hoarding, where hoarding is provided, or fixed to and including a suitable supporting structure of timber or tubular posts and braces. The board is to be painted ivory white and the bead and 12mm wide dividing lines dark green. All wording shall be inscribed in dark green as per the coat of arms for SA. All wording shall be inscribed in dark green painted "sans serif" lettering</p> <p>12.1.15 Subcontractors notice board [6.6]</p> <p>NO</p> <p>12.1.16 Water [7.2]</p> <p>Option A (by contractor)</p> <p>12.1.17 Electricity [7.3]</p> <p>Option A (by contractor)</p> <p>12.1.18 Telecommunications [7.4]</p> <p>Telephone - YES Facsimile - YES Email - YES</p> <p>12.1.19 Ablution facilities [7.5]</p> <p>Option A (by contractor)</p>			
	Carried Forward		R
<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
12.1.20 Protection of existing/sectionally occupied works [11.2] Protection is required YES				
12.1.21 Special attendance [9.2] N/A				
12.1.22 Protection of the works [11.1] No specific requirements				
Carried Forward				R
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD				

	Brought Forward			
<p>12.1.23 Disturbance [11.5]</p> <p>The Contractor shall be responsible for and take all precautions in controlling all forms of pollution during the contract period due to noise, artificial light, wind-blown sand, dust, etc in the dry season and deposits of mud etc in the wet season by whatever means necessary and daily removal of deposits etc, all to the satisfaction of the Principal Agent and any costs, claims, etc will be for the Contractor's account</p> <p>The surrounding buildings will be occupied and functioning during these works and the Contractor is to ensure that the works are carried out with as little mess and noise as possible and with a minimum of disturbance to adjoining and close buildings and properties and their occupants. The Contractor is to make use of appropriate plant and methods of execution which result in the least possible noise factors. All machinery shall be fully muffled</p> <p>The Contractor shall keep the site, structures and materials well watered during the operations to prevent dust and shall provide, erect and maintain all temporary tarpaulins, dust and weatherproof screens, barriers and temporary plumbing that may be necessary during the progress of the works</p> <p>The Contractor shall ensure that the functioning of the existing School is not disturbed or disrupted, except where special arrangements are made with the Principal Agent</p> <p>The Contractor may not carry out construction operations outside of normal working times without the permission of the Principal Agent</p> <p>12.1.24 Environmental disturbance [11.6]</p> <p>No specific requirements</p>	Brought Forward		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>	Carried Forward		R	

	Brought Forward			R
<u>12.2 POST-TENDER INFORMATION</u>				
12.2.1	Payment of preliminaries			
[10.2]	Option A or B (post tender)			
12.2.2	Adjustment of preliminaries			
[10.3]	Option A or B (post tender)			
12.2.3	Additional agreed preliminaries items			
Details: To be agreed post tender where relevant				
		Carried Forward		R
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD				

Brought Forward

R

SECTION C: SPECIFIC PRELIMINARIES

Section C contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item

C1: CONFIDENTIALITY

100 The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the **works** and the manner in which they are to be executed

Should any part of the drawings not be clearly intelligible to the tenderer he shall, before submitting his tender, obtain clarification in writing from the **principal agent**

F: V: T:

Item

C2: TRADE NAMES

101 Wherever a trade name for any product has been described in the **bills of quantities**, the tenderer's attention is drawn to the fact that any other product of equal quality may be used subject to the written approval of the **principal agent** being obtained prior to the closing date for submission of tenders

If prior written approval for an alternative product is not obtained, it shall be deemed that the tenderer the product described has been tendered for

F: V: T:

Item

Carried Forward

R

Section No. 1
 Preliminaries
 Bill No. 1
 PRELIMINARIES
Diatho Consulting (PTY) LTD

Brought Forward

R

C3: IMPORTED MATERIALS

102 Where imported items are listed in the tender documents, the tenderer shall provide all the information called for, failing which the price of any such item, materials or equipment shall be excluded from currency fluctuations.

Notwithstanding any provisions elsewhere regarding the adjustment of contract prices, the price of any item, material or equipment listed in terms of this clause shall be excluded from the Contract Price Adjustment Provisions (if applicable)

F: V: T:

Item

C4: SECURITY CHECK OF PERSONNEL

103 The **principal agent** may require the **contractor** to have his personnel and workmen, or a certain number of them, security classified

In the event of the **principal agent** requesting the removal of a person or persons from the **works** for security reasons, the **contractor** shall do so forthwith and shall thereafter ensure that such person or persons are denied access to the **works** and the **site** and/or to any document or information relating to the **works**

F: V: T:

Item

C5: CONTRACT INSTRUCTIONS

104 Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor

F: V: T:

Item

Carried Forward

R

Section No. 1
 Preliminaries
 Bill No. 1
 PRELIMINARIES
Diatho Consulting (PTY) LTD

Brought Forward		R
105	<p><u>C6: SITE LEVELS</u></p> <p>Before commencement of the works the Contractor shall carry out and provide the Principal Agent for approval a survey of the existing site levels in sufficient detail to enable the preparation of a final account</p> <p>F: V: T: </p>	Item
106	<p><u>C7: UNAUTHORISED PERSONS ON SITE</u></p> <p>The Contractor shall not permit unauthorised persons onto and workmen to lodge on the site</p> <p>F: V: T: </p>	Item
107	<p><u>C8: PLANT AND LABOUR RECORD</u></p> <p>At the end of each week the Contractor shall provide the Principal Agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day and the number, type and capacity of all plant, excluding hand tools, currently used on the works</p> <p>F: V: T: </p>	Item
108	<p><u>C9: USE OF LOCAL LABOUR FROM THE EMPLOYER'S AREAS OF OPERATION</u></p> <p>It is a requirement of the contract that the work be executed in such a manner as to maximise the use of local labour from the Employer's areas of operation in order to provide the local community with employment opportunities.</p> <p>The tenderer is to identify all activities for which it is intended to employ workers from the local community and full details thereof are to be provided in the tender documentation</p>	
Carried Forward		R
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD		

Brought Forward	R
<p>The total value of the work that is to be of a local labour nature may be a consideration in the adjudication process. Once a tender is accepted the activities and number of persons stated in the above-mentioned schedule shall become the minimum contractual commitment. In applying the principles set out above, it is a specific requirement of this tender that the successful tenderer employs, in consultation with the Employer's representative, unemployed persons from the ranks of the local communities and the immediate surroundings, who possess the appropriate skills required for a contract of this nature</p> <ul style="list-style-type: none"> - In order to achieve the recruitment of local labour, the Employer will establish, a database of unemployed persons, indicating their specialised training, previous experience and employment, etc. The successful tenderer will be required to directly employ suitable persons recruited from the employer's database and ensure that all legislative requirements regarding their employment are complied with and provide the Employer with the necessary documentary proof, if required - The Contractor is required to produce weekly records suitably detailed to enable the Employer's representative to monitor the achievement of the required local labour percentages. The Contractor is required to provide the Employer's database for the purposes of assessing skills transfer from informal skills training - The Contractor is required to provide informal skills training so that the required standard of workmanship is maintained - Any difficulty experienced by the tenderer/Contractor in the procurement of the required percentages of local labour is to be referred immediately to the Employer's representative 	R
Carried Forward	R
<p>Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD</p>	

Brought Forward			R	
- In respect to "Target Labour", the minimum rate for any and all workers contracted for this project shall be R120 per day				
F: V: T:	Item			
Carried Forward			R	
Section No. 1 Preliminaries Bill No. 1 PRELIMINARIES Diatho Consulting (PTY) LTD				

Brought Forward

R

C10: COMMUNITY LIASON OFFICER

109

It is a requirement of this Contract that a Community Liaison officer (CLO) be appointed for the area represented by the Tender. The function of the CLO shall be to represent the local community in matters concerning the use of local labour on the works and to assist with and facilitate communication between the Contractor, the Engineer and the local communities. The period of appointment of the CLO shall be as stated in the Contract for Temporary Employment as a Community Liaison officer referred to below. It must be noted that the date of commencement of temporary employment of the CLO shall be no later than the date of commencement of the Contract. The identification of the approved CLO to be appointed by the Contractor under the Contract shall be resolved by the Contractor, the particular Ward Councillors in collaboration with the Local Communities.

It will be required, therefore, that the successful Tenderer (i.e. the Contractor) enter into a contract for the employment of the above-mentioned CLO, the parties to which will be the Contractor, the RDP/Development Forum and the CLO. To this end a specimen Form of Contract for the Temporary Employment as a Community Liaison Officer is included in this document; this Form of Contract sets out, inter alia, the agreement between the parties, the duties and conditions of employment of the CLO (including the rate of remuneration to be paid).

As said contract will be between the Contractor and the CLO, all costs involved shall be borne by the Contractor and the tender shall be deemed to include for this.

F: T: V:

Item

Carried Forward

R

Section No. 1
 Preliminaries
 Bill No. 1
 PRELIMINARIES
Diatho Consulting (PTY) LTD

Brought Forward

R

C11: GUARANTEES

110

Where guarantees are called for, the Contractor shall obtain a written guarantee, addressed to the Employer, from the firm supplying the materials and/or doing the work and shall deliver same to the Principal Agent no later than the works completion date.

The guarantee shall state that workmanship, materials and installation are guaranteed for a specified period from the final completion dated and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice from the Principal Agent to do so. This guarantee will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the Contractor.

The Principal Agent shall be the sole judge of the cause responsible for defect of the works and his decision shall be final and binding in terms of clause 40.2 of the agreement

F: V: T:

.....

Item

Carried Forward

R

Section No. 1
 Preliminaries
 Bill No. 1
 PRELIMINARIES
Diatho Consulting (PTY) LTD

Brought Forward

R

C12: WARRANTIES FOR MATERIAL AND WORKMANSHIP

111

Where warranties for materials and/or workmanship are called for, the Contractor shall obtain a written warranty, addressed to the Employer, from the firm supplying the materials and/or doing the work and shall deliver same to the Principal Agent on the certified practical completion of the contract

The warranty shall state that workmanship, materials and installation are warranted for a specified period from the date of final completion and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice to do so. The warranty will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the Contractor

F: V: T:

.....

Item

C13: OVERTIME

112

Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the Contractor unless the Principal Agent has specifically authorised, in writing, prior to execution thereof, that costs for such overtime are to be borne by the Employer

F: V: T:

.....

Item

Carried Forward

R

Section No. 1
 Preliminaries
 Bill No. 1
 PRELIMINARIES
Diatho Consulting (PTY) LTD

Brought Forward

R

C14: CO-OPERATION OF CONTRACTOR FOR COST MANAGEMENT

113 It is specifically agreed that the Contractor accepts the obligation of assisting the agents in implementing proper cost management on this project. The Contractor will be advised by the Principal Agent of all cost management procedures which will be implemented to ensure that the final account does not exceed the budget

F: V: T:

Item

C15: FINANCIAL INVESTIGATION

114 Tenderers must be prepared to furnish the following documentation at own cost within seven (7) days of being called upon to do so:

- Audited financial statements for the past three financial years plus a certified financial statement covering the period from the end of the last financial year to date. If audited statements are not readily available provisional certified statements must be submitted
- A resolution of the board of directors authorising the signatory to certify such statements
- An extract of the relevant memorandum and article(s) of association from which it is clear that the company is empowered to issue such statement
- A list of all major shareholders indicating the percentage shareholding of each

F: V: T:

Item

Carried Forward

R

Section No. 1
 Preliminaries
 Bill No. 1
 PRELIMINARIES
Diatho Consulting (PTY) LTD

Brought Forward

R

C16:REINSTATEMENT OF DAMAGED AREAS ON THE SITE OR EMPLOYERS' PROPERTIES IN GENERAL CAUSED BY CONSTRUCTION OPERATIONS, ETC.

115

Before commencing the works, the Contractor shall arrange with the Principal Agent to inspect, among others, existing buildings, structures, roads, pavings, kerbs, channels and fences on the site or Employers' properties in general

The Contractor shall note in writing, all conditions that the works could affect and copy the Principal Agent accordingly. The Contractor should pay particular attention to cracks, defects and existing levels related to structures, roads, pavings, kerbs, channels and fences, which later could be claimed to have been caused or disturbed by the construction operations

Where instructed by the Principal Agent, levels and photographs shall be taken by the Contractor and the cost thereof shall be for the Employer's account. Certified copies shall be lodged with the Principal Agent

The Contractor will be held responsible for maintaining the above in its present condition during execution of the works and will be liable for all costs relating to the repairing or replacing of damaged areas caused by the construction operations

F: V: T:

.....

Item

SUMMARY OF CATEGORIES

Category : Fixed R.....

Category : Value R.....

Category : Time R.....

Carried to Final Summary

R

Section No. 1
 Preliminaries
 Bill No. 1
 PRELIMINARIES
Diatho Consulting (PTY) LTD

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 2</u></p> <p><u>BILL NO.1</u></p> <p><u>DEMOLITIONS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition), as published by the Association of South African Quantity Surveyors, shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items, fully described in the said General Preambles, will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>View Site:</u></p> <p>Before submitting his tender, the Contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished.</p> <p>No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained</p> <p><u>Old materials to become property of the Contractor:</u></p> <p>Old materials from demolitions, except where described as to be re-used or handed over, become the property of the Contractor, who must allow credit for same in the last item of the "Demolitions" trade</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 2 Demolitions Bill No. 1 DEMOLITIONS Diatho Consulting (PTY) LTD</p>			R

<p style="text-align: center;">Brought Forward</p> <p><u>Old materials to be re-used:</u></p> <p>None of the old materials are to be used for new work, except where specifically described as being set aside for re-use</p> <p><u>Old materials, debris, etc to be carted away:</u></p> <p>All old materials from the demolitions, except where described as to be re-used or handed over, as well as all rubbish, debris, etc must be regularly carted from the site and not be allowed to accumulate on or around the site</p> <p><u>Handing over of materials:</u></p> <p>Where certain materials or articles from demolitions are described as to be "handed over to the Employer", it shall be taken to mean "handed over by the Contractor to the Principal Agent" and such materials or articles shall be properly stored by the Contractor until handing over thereof and shall include all necessary transport</p> <p>The Contractor must obtain an official receipt from the Principal Agent listing the materials or articles and dates of handing over</p> <p>Should the Contractor fail to submit the receipt when requested to do so, it shall be deemed that the materials or articles are still in his possession and he will be held liable to the Employer for the full replacement value thereof, which amount will be deducted from any monies due to the Contractor</p> <p><u>Explosives:</u></p> <p>No explosives whatsoever may be used for demolition purposes, unless otherwise stated</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 2 Demolitions Bill No. 1 DEMOLITIONS Diatho Consulting (PTY) LTD</p>		R	

	Brought Forward			R
<p><u>General:</u></p> <p>The Contractor shall carry out the whole of the works with as little mess and noise as possible and with a minimum of disturbance to adjoining premises and their tenants. He shall provide proper protection and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the Principal Agent</p> <p>Water supply pipes and other piping that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the Principal Agent</p> <p><u>Hazardous materials:</u></p> <p>Demolitions of buildings, services, external works, site services, etc are to include for the safe removal and disposal of <u>asbestos or asbestos products or other hazardous materials</u> by approved Registered Specialists</p> <p style="text-align: center;">-----</p> <p><u>REMOVAL OF EXISTING WORK</u></p> <p><u>DEMOLITIONS, ETC</u></p> <p><u>DEMOLISH EXISTING TOILET STRUCTURES</u></p> <p>1 Demolish existing pit toilet structure overall size 6500 x 3900 x 3000mm high including desludging waste to municipality waste site, hacking and removing foundations, concrete surface beds, walls, doors, windows, door frames, ironmongery, zink, plumbing fittings complete, backfilling, compacting and clear debris and etc. Service Provider to submit relevant and valid permit of disposal to the municipal waste and all rubble's to be carted away from site.</p>	No	2		
	Carried Forward			R
<p>Section No. 2 Demolitions Bill No. 1 DEMOLITIONS Diatho Consulting (PTY) LTD</p>				

	Brought Forward			R
2	<p>Demolish existing pit toilet structure overall size 10500 x 3900 x 3000mm high including desludging waste to municipality waste site, hacking and removing foundations, concrete surface beds, walls, doors, windows, door frames, ironmongery, zink, plumbing fittings complete, backfilling, compacting and clear debris and etc. Service Provider to submit relevant and valid permit of disposal to the municipal waste and all rubble's to be carted away from site.</p> <p><u>TEMPORARY ABLUTIONS</u></p> <p><i>NOTE: Failure to complete new toilet blocks within the stipulated duration of contract due to contractor's default, additional months will be paid by the contractor</i></p>	No	1	
3	<p>Temporary chemical toilets (10No) for a period of original construction (site handover date to original practical completion date) up to approved extension of time including all servicing necessary as per standards. All servicing of the temporary chemical toilets on late completion of works by contractor till actual practical completion date, all costs will be on the contractor's account.</p>	Mnths	5	
Carried to Final Summary				R
Section No. 2 Demolitions Bill No. 1 DEMOLITIONS Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 3</u></p> <p><u>BILL NO.1</u></p> <p><u>ALTERATIONS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition), as published by the Association of South African Quantity Surveyors, shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items, fully described in the said General Preambles, will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>View site:</u></p> <p>Before submitting his tender, the Contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished.</p> <p>No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained</p> <p><u>Old materials to become property of the Contractor:</u></p> <p>Old materials from alterations, except where described as to be re-used or handed over, become the property of the Contractor, who must allow credit for same in the last item of the "Alterations" trade</p> <p style="text-align: right;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 1 ALTERATIONS Diatho Consulting (PTY) LTD</p>			R

	Brought Forward		R
<p><u>Old materials to be carted away:</u></p> <p>Old materials from the alterations, except where described as to be re-used or handed over, as well as all rubbish, etc must be regularly carted from the site and not be allowed to accumulate on or around the site</p> <p><u>Old materials to be re-used:</u></p> <p>None of the old materials are to be used for new work, except where specifically described as being set aside for re-use</p> <p><u>Handing over of materials:</u></p> <p>Where certain materials or articles from demolitions or alterations are described as to be "handed over to the Employer", it shall be taken to mean "handed over by the Contractor to the Principal Agent" and such materials or articles shall be properly stored by the Contractor until handing over thereof and shall include all necessary transport</p> <p>The Contractor must obtain an official receipt from the Principal Agent listing the materials or articles and dates of handing over</p> <p>Should the Contractor fail to submit the receipt when requested to do so, it shall be deemed that the materials or articles are still in his possession and he will be held liable to the Employer for the full replacement value thereof, which amount will be deducted from any monies due to the Contractor</p> <p><u>Explosives:</u></p> <p>No explosives whatsoever may be used for demolition purposes, unless otherwise stated</p>			
<p style="text-align: right;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 1 ALTERATIONS Diatho Consulting (PTY) LTD</p>			R

Brought Forward

R

GENERAL

The contractor shall carry out the whole of the work with as little mess and noise as possible and with a minimum of disturbance to adjoining premises and their tenants. He shall provide proper protection and provide and erect any temporary tarpaulins and temporary plumbing that may be necessary during the progress of the works, all to the satisfaction of the Architect, and remove when directed.

Any water supplies pipes and other piping that may be met with and found necessary to disconnect or cut, shall be effectually stopped or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the Architect.

Doors, fanlights, fittings, frames, linings, etc shall be thoroughly overhauled before re-fixing including taking off, easing and rehanging, cramping up, re-wedging as required and making good cramps, dowels, etc and easing, oiling, adjusting and repairing ironmongery if necessary, replacing any glass damaged in removal or subsequently and stopping up all nail and screw holes with tinted wood to match timber.

Where doors, windows, etc are described as taken out this shall be understood to include for removal of all beads, architraves, ironmongery, etc and doors which are re-fixed are to be provided with new architraves (elsewhere measured).

Prices for taking out and removing doors and frames shall include for removing door stops, cabin locks, etc and making good to match existing.

With regard to building up openings in existing walls, cement screeds and pavings, granolithic, etc, shall be levelled and prepared for raising of brickwork.

Allow for making good all existing plastered walls where damaged by furniture, etc, and stopping up all screw and holes before painting.

Carried Forward

R

Section No. 3
 Renovations - 4 seats (Enviroloo)
 Bill No. 1
 ALTERATIONS
Diatho Consulting (PTY) LTD

	Brought Forward			R
	<p><u>Making good finishes shall be deemed to include making good of the brick and concrete surfaces onto which new finishes are applied, where necessary.</u></p> <p><u>The contractor will be required to take all dimensions affecting existing building on the site and he will be held solely responsible for the accuracy of all such dimensions.</u></p> <p><u>Hazardous materials:</u></p> <p>Demolitions of buildings, services, external works, site services, etc are to include for the safe removal and disposal of <u>asbestos or asbestos products or other hazardous materials by approved Registered Specialists</u></p> <p style="text-align: center;">-----</p> <p><u>TEMPORARY BARRIERS, SCREENS, ETC</u></p> <p><u>Temporary barriers, screens, etc including removal:</u></p>			
1	"Joluka Orange/ Yellow" or similar approved safety barrier netting 1500mm high including suitable timber framing, corners, ends, etc	m	42	
	<p><u>REMOVAL OF EXISTING WORK</u></p> <p><u>Breaking up and removing reinforced concrete, including cutting off and removing reinforcement:</u></p>			
2	Concrete toilet seats	m2	4	
3	150mm Thick surface beds	m2	3	
	Carried Forward			R
	<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 1 ALTERATIONS Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
<p><u>Carefully taking out and handing over to the Employer doors, windows, etc including taking out and removing thresholds, sills, etc from brickwork and preparing openings to receive new similar doors, windows, etc (elsewhere measured) and making good cement plaster on both sides and into reveals:</u></p>			
4	Timber single door and frame not exceeding 2,5m ²	No	6
<p><u>Taking out/off and removing ironmongery:</u></p>			
5	Window stays	No	6
6	Window handles	No	4
<p><u>Taking out and removing piping, sanitary fittings, etc including cutting off as necessary, disconnecting piping from fittings and blocking off and making good damaged plasterwork to walls and screeds to floors (all redecoration work elsewhere):</u></p>			
7	Vitreous china wall hung urinal with flush valve	No	2
<p><u>Taking out/off and removing glass and mirrors:</u></p>			
8	Glass panes not exceeding 0,1m ² from steel windows with putty, including cleaning out rebates and preparing for new glass	m2	4
<p><u>MAKING GOOD OF FINISHES, ETC</u></p>			
<p><u>Making good untinted granolithic</u></p>			
9	25mm Thick on floors in patches	m2	13
<p><u>Making good internal/external cement plaster:</u></p>			
10	Walls in patches	m2	7
Carried Forward			R
<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 1 ALTERATIONS Diatho Consulting (PTY) LTD</p>			

		Brought Forward			R
11	<p><u>Wash down thoroughly with sugarsoap and remove all stains, paint marks, etc, repoint and re-mortar joints as required on existing</u></p> <p>Face brick work</p>	m2	48		R
<p>Carried Forward to Summary of Section No. 3</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 1 ALTERATIONS Diatho Consulting (PTY) LTD</p>					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 3</u></p> <p><u>BILL NO.2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Cost of tests:</u></p> <p>The costs of making, storing and testing of concrete test cubes as required under clause 7 "Tests" of SANS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the Principal Agent.</p> <p>The testing shall be undertaken by an independent firm or institution nominated by the Contractor to the approval of the Principal Agent. (Test cubes are measured separately)</p>			
<p>Carried Forward</p>		R	
<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Breeze concrete:</u></p> <p>Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated</p> <p><u>Lightweight concrete:</u></p> <p>Lightweight concrete shall have a density of 600kg/m³ for the top 50mm and 400kg/m³ for the remaining thickness. The minimum thickness at outlets, channels, etc shall be 50mm</p> <p><u>Waterproof concrete:</u></p> <p>"Waterproof concrete" shall have the same properties as normal concrete, but the following shall be modified to make the the concrete more water-tight:</p> <ol style="list-style-type: none"> 1. a cement/water ratio of minimum 1.9 and maximum 2.1 2. minimum OPC content of 300kg/m³ 3. Polypropolene micro fibres added to concrete at rate of 182 million per m³ <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>	R	

	Brought Forward			R
	Formwork to soffits of solid slabs, etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described			
	Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described			

	<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
	<u>25MPa/19mm concrete:</u>			
	Aprons cast in panels	m3	2	
	<u>TEST BLOCKS</u>			
1	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	Sets	3.0	
	<u>CONCRETE SUNDRIES</u>			
	<u>Finishing top surfaces of concrete smooth with a wood float:</u>			
2	Ramps to falls	m2	16	
	<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>			
	<u>Rough formwork to sides:</u>			
3	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	16	
	<u>MOVEMENT JOINTS, ETC</u>			
	Carried Forward			R
	Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD			

Brought Forward					
	<u>Expansion joints with 10mm softboard between vertical concrete and brick surfaces:</u>				R
4	Not exceeding 300mm high to edges of surface beds	m	4		
	<u>REINFORCEMENT (PROVISIONAL)</u>				
	<u>Fabric reinforcement:</u>				
5	Type 193 fabric reinforcement in concrete surface beds, slabs, etc	m2	13		
Carried Forward to Summary of Section No. 3					
Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD					
					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 3</u></p> <p><u>BILL NO.3</u></p> <p><u>WATERPROOFING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Waterproofing:</u></p> <p>Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets, etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs</p> <p style="text-align: center;">-----</p>			
<p>Carried Forward</p>		R	
<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 3 WATERPROOFING Diatho Consulting (PTY) LTD</p>			

Brought Forward

DAMPPROOFING OF WALLS AND FLOORS

One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape:

1	Under aprons	m2	13	
---	--------------	----	----	--

R

Carried Forward to Summary of Section No. 3

Section No. 3
 Renovations - 4 seats (Enviroloo)
 Bill No. 3
 WATERPROOFING
 Diatho Consulting (PTY) LTD

R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 3</u></p> <p><u>BILL NO.4</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing:</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given separately elsewhere</p> <p><u>Joinery:</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p>			
Carried Forward		R	
<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 4 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p>Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts</p> <p><u>Particle board</u></p> <p>All particle board shall comply with SANS 50312 having the required marking as per SANS 50312/EN 312</p> <p><u>Decorative thermosetting plastic laminate covering:</u></p> <p>Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish</p> <p><u>Sizes:</u></p> <p>Sizes are nominal and the Contractor shall make allowance in his prices for minor variances in stated finished sizes of timber doors, door members, door frames, architraves, etc</p> <p><u>Prices</u></p> <p>Prices for all joinery work are to include for general framing, housing and notching, arris rounded angles, glueing, blocking, planting on, screwing, adhesives, dowels, pellets, cross tongues, screws and nails and setting up complete and also for all square cutting and waste. Tops shall be secured with metal or hardwood buttons.</p> <p style="text-align: center;">-----</p> <p><u>ROOFS, ETC</u></p> <p><u>Sundries:</u></p> <p>1 Two coats creosote on sawn timbers m2</p> <p style="text-align: right; margin-right: 20px;">34</p> <p><u>EAVES, VERGES, ETC</u></p>			
	Carried Forward			R
	<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 4 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			

Brought Forward							
	<u>Medium density plain fibre-cement fascias and barge boards:</u>						R
2	19 x 235mm Fascias and barge boards, including aluminium H-profile jointing strips	m	28				
	<u>DOORS, ETC</u>						
	<u>Semi-solid core flush panel timber door with hardboard edging, face suitable for paint on both sides, hung to steel frames</u>						
3	44 x 762 x 1882mm high	No	4				
	<u>Wrought meranti doors hung to steel frames:</u>						
4	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard	No	1				
Carried Forward to Summary of Section No. 3							
Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 4 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD							
							R

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 3</u></p> <p><u>BILL NO.5</u></p> <p><u>IRONMONGERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p>			
	Carried Forward		R	
	<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 5 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

Brought Forward				R
<u>Locks:</u>				
Notwithstanding Clause 2, Item 3 of the "Ironmongery" trade of the Standard System (7th Edition, 2015) of Measuring Building Work, descriptions of locks shall be deemed to include two keys per lock				
<u>Finishes to ironmongery:</u>				
Where applicable, finishes to ironmongery are indicated by suffixes in accordance with the following list:				
BS Satin bronze lacquered				
CH Chromium plated				
SC Satin chromium plated				
SE Silver enamelled				
GE Grey enamelled				
AN Anodised natural				
AS Anodised silver				
AB Anodised bronze				
AG Anodised gold				
ABL Anodised black				
PB Polished brass				
PL Polished and lacquered				
PT Epoxy coated				
SD Sanded				
BBS Brushed stainless steel				

<u>CATCHES, CABIN HOOKS, ETC</u>				
1	150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	2	
<u>LOCKS</u>				
<u>Approved:</u>				
2	50mm Padlock	No	2	
3	Four lever lockset	No	2	
Carried Forward				R
Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 5 IRONMONGERY Diatho Consulting (PTY) LTD				

	Brought Forward				R
4	Indicator lockset	No	4		
	<u>DOOR CLOSERS</u>				
	<u>"Dorma" or similar approved:</u>				
5	"Dorma" TS73N/EN3-4 parallel arm door closer delayed closing-push side fitting.	No	3		
	<u>LETTERS, NAMEPLATES, ETC</u>				
	<u>"Union Assa Abloy" or similar approved:</u>				
6	75 x 150mm Natural anodised aluminium plate with male or female symbol	No	1		
7	"Ref. SS5066E-06SSE14" stainless steel pictogram engraved with a disabled sign	No	1		
	<u>SUNDRIES</u>				
8	25mm Diameter wall mounted door stop plugged	No	6		
	<u>BATHROOM FITTINGS</u>				
	<u>"Kimberley-Clark" or similar approved:</u>				
9	"Ref. SQ2 code 405607B" white lockable toilet roll holder	No	4		
10	Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc	No	3		
Carried Forward to Summary of Section No. 3					R
Section No. 3					
Renovations - 4 seats (Enviroloo)					
Bill No. 5					
IRONMONGERY					
Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 3</u></p> <p><u>BILL NO.6</u></p> <p><u>METALWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions of bolts, anchors, etc:</u></p> <p>Descriptions of bolts shall be deemed to include nuts and washers</p> <p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete</p> <p>Items described as "holed for bolt(s)" shall be deemed to exclude the bolts, unless otherwise described</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres</p>			
Carried Forward		R	
<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 6 METALWORK Diatho Consulting (PTY) LTD</p>			

Brought Forward			R	
<p><u>Fixing:</u></p> <p>Unless otherwise described, descriptions of items shall be deemed to include for fixing to brickwork or concrete</p> <p>Where items are described as "bolted", the bolts are measured elsewhere as stated in clause N.7 of the Model Preambles</p> <p><u>References:</u></p> <p>References in descriptions of windows, doors, gates, etc refer to the respective types of windows, doors, etc detailed in the Architect's window schedules numbered</p> <ul style="list-style-type: none"> • T-2002 • T-2003 • T-2004 • T-2005 <p>and bound into the back of these bills of quantities</p> <p>Tenderers are to price the following items in conjunction with the above Architect's drawings, etc and no claim arising from brevity of descriptions in these bills of quantities, of items shown on the Architect's drawings, etc shall be entertained</p> <p style="text-align: center;">-----</p>				
Carried Forward			R	
<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 6 METALWORK Diatho Consulting (PTY) LTD</p>				

	Brought Forward			
R				
<u>STEEL GATES, SCREENS, ETC</u>				
<u>Welded screens and gates, to walls:</u>				
1	Single gate and frame 813 x 2032mm high of 25 x 25 x 2mm hollow section frame and 25 x 25 x 2mm hollow section horizontal middle rail filled in with 12 x 12mm square section vertical rails at 75mm centers and fitted with a pair of suitable hinges welded to frame and with locking mechanism for padlock all in and including outer frame of 25 x 25 x 2mm hollow section welded frame bolted to brickwork	No	2	
R				
Carried Forward to Summary of Section No. 3				
Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 6 METALWORK Diatho Consulting (PTY) LTD				
R				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 3</u></p> <p><u>BILL NO.7</u></p> <p><u>PLASTERING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Moisture tests:</u></p> <p>Before any finishes, coverings, etc are applied to screeds, plastering, etc or any other in-situ finish, moisture tests are to be carried out to the complete satisfaction of the Project Manager to ensure that these surfaces have the correct moisture content for the finish to be applied</p> <p><u>Labours, etc</u></p> <p>Labours such as fair, rounded and chamfered edges, trowel cuts, throats, V-joints, angles, etc shall be deemed to be included in the descriptions</p>			
Carried Forward		R	
<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 7 PLASTERING Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Sample Panels</u></p> <p>A sample panel size 1m x1m, of each of the various plaster type wall and floor finishes in this contract, shall be prepared for the approval of the Project Manager and the cost of the sample panel(s) shall be deemed to be included in the overall costs of the <u>relevant</u> wall and floor finishes</p> <p><u>GRANOLITHIC</u></p> <p><u>Method:</u></p> <p>The method to be used shall be either the monolithic method or the bonded method</p> <p><u>Preparation:</u></p> <p>For granolithic applied monolithically, the concrete floor shall be swept clean after bleeding of the concrete has ceased and the slab has begun to stiffen; any remaining bleed water shall be removed and the granolithic applied immediately thereafter. For granolithic to be bonded to the floor slab after it has hardened, the slab surface shall be hacked (preferably by mechanical means) until all laitance, dirt, oil, etc is dislodged and swept clean of all loose matter. The slab shall then be wetted and kept damp for at least six hours before applying the granolithic</p> <p><u>Mix:</u></p> <p>Unless otherwise described, granolithic shall attain a compressive strength of at least 41MPa. The coarse aggregate shall comply with SANS 1083 and shall generally be capable of passing a 10mm mesh sieve. Where the thickness of the granolithic exceeds 25mm, the size of the coarse aggregate shall be increased to the maximum size compatible with the thickness of the granolithic</p>				R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 7 PLASTERING Diatho Consulting (PTY) LTD</p>				R

<p style="text-align: center;">Brought Forward</p> <p><u>Panels:</u></p> <p>Granolithic shall be laid in panels not exceeding 14m² for monolithic finishes, not exceeding 9,5m² for bonded finishes and not exceeding 6m² for all external granolithic. Wherever possible, panels shall be square but at no time should the length of the panel exceed 1,5 times its width</p> <p>Where possible joints between panels shall be positioned over joints in the floor slab and shall be at least 3mm wide through the full thickness of the finish, separated by strips of wood or fibreboard and finished with V-joints</p> <p><u>Laying:</u></p> <p>Monolithic granolithic shall be applied to the partially set slab and thoroughly compacted and lightly wood floated to the required levels</p> <p>Bonded granolithic shall be applied to the slab after applying a 1:1 sand-and-cement slurry brushed over the surface and allowed to partially set before applying the granolithic. The granolithic shall be thoroughly compacted and lightly wood floated to the required levels</p> <p>After wood floating, the monolithic and bonded granolithic shall remain undisturbed until bleeding has ceased and the surface has stiffened. Any remaining bleed water and laitance shall then be removed and the surface steel trowelled or power floated</p> <p><u>Curing, seasoning and protection:</u></p> <p>Granolithic shall be covered with clean hessian with waterproof building foil over and kept wet for at least seven days after laying</p> <p><u>Colour:</u></p> <p>Coloured granolithic shall be tinted with an approved colouring pigment mixed into a true and even colour</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 7 PLASTERING Diatho Consulting (PTY) LTD</p>	R	

Brought Forward

R

TINTED WHITE CEMENT SCREEDS

Tinted screed shall be composed of one bag White Portland Cement and two wheelbarrows "Malmesbury" sand. Surfaces shall be finished with a steel trowel to leave a smooth finish and coated with two coats "Earthcote S.I. Floorcote" two-pack polyurethane floor sealer applied as per the manufacturer's recommendations

NOTE: Tinted screeds are to be strengthened with "Primal Eccos" acrylic polymer (15% of the water volume is to be substituted with the acrylic polymer during the mixing process)

Coarse sand is to be used for these screeds

All tinting, finishing, strengthening, etc are to be mixed, applied, etc strictly in accordance with the manufacturer's instructions

CEMENT PLASTER

Unless otherwise described, cement plaster shall be taken to mean Class 1 cement plaster i.e. 1:4 cement:sand plaster (common cement)

FLOOR AND WALL SEALERS

Minimum two coats approved epoxy coat, on concrete:

1	On screed	m2	13	
---	-----------	----	----	--

Carried Forward to Summary of Section No. 3

Section No. 3
 Renovations - 4 seats (Enviroloo)
 Bill No. 7
 PLASTERING
Diatho Consulting (PTY) LTD

R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 3</u></p> <p><u>BILL NO.8</u></p> <p><u>PLUMBING AND DRAINAGE (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Wire gratings:</u></p> <p>Descriptions of gutter outlets, etc shall be deemed to include wire balloon gratings</p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p>			
<p>Carried Forward</p>		R	
<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 8 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>Stainless steel basins, sinks, wash troughs, urinals, etc:</u></p> <p>Stainless steel for economy basins, domestic sinks and worktops shall be Type 430 (17/0)</p> <p>Stainless steel for urinals, basins, quality sinks, wash troughs, institutional equipment, etc shall be Type 304 (18/8)</p> <p>Stainless steel for laboratory sinks, photographic equipment, etc shall be Type 316 (18/8)</p> <p>Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable</p> <p><u>Sealing of edges:</u></p> <p>Outer edges of sinks, basins, baths, urinals, etc are to be sealed against adjacent surfaces with approved mildew resistant silicone sealant and prices must include therefor</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 8 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

<p style="text-align: center;">Brought Forward</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPE) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 8 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claims for extra bushes, reducers, etc will be entertained</p> <p><u>Fixing of pipes:</u></p> <p>Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls, etc casting in, building in or suspending not exceeding 1m below suspension level</p> <p><u>Paper wrapping to pipes:</u></p> <p>Pipes chased into brickwork must be wrapped with two layers of stout brown paper tied with wire. Rates are to include for wrapping around joints and fittings</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 8 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SANS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SANS 1200L : Medium-pressure pipelines SANS 1200LD : Sewers SANS 1200LE : Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SANS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SANS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 8 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

Brought Forward	R
<p><u>General:</u></p> <p>Descriptions of cast iron roof outlets shall be deemed to include joints to pipes and casting into concrete (adaptors for joints to PVC pipes, etc are given separately)</p> <p>Descriptions of overflow pipes where measured in number, shall be deemed to include joints to cisterns and splay cut ends</p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site</p> <p>Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)</p> <p>Descriptions of WC pans, slop hoppers, etc shall be deemed to include for joints to soil pipes (pan connectors are separately measured) and shall have straight or side outlets and "P" or "S" traps as necessary</p> <p>Description of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.</p> <p><u>As-built drawings:</u></p> <p>Where required, the Contractor shall prepare an updated set of as-built drawings. At completion of the contract the Contractor shall hand these drawings to the Project Manager for reproducing onto the originals for handing over to the Employer (provision for allowance of as-built drawings elsewhere)</p>	R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 8 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R

	Brought Forward			R
<u>Proprietary items:</u>				
Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items				
Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.				
Prices are to be based on the specific products/articles specified.				
On request, returnable samples are to be provided to the Project Manager for consideration				

<u>SANITARY FITTINGS</u>				
<u>"Vaal" or similar approved:</u>				
1	455 x 290mm "Hibiscus" 7050 wash hand basin bolted to wall	No	3	
2	Flat back urinal overall size 295 x 315 x 415mm high with 40mm chromium plated domical grating (Code 878720) and top inlet spreader (Code 8543) with two hanger brackets with flushmaster junior (Code 812720) hung to wall	No	2	
Carried Forward				R
Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 8 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

Brought Forward									
									R
		<u>Supply and install "Enviroloo systems" or similar approved:</u>							
3	"Enviro Loo System FG-1040 STDCA/A Standard" strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvered inlets (PL.1), drying plate (PL.2), two x air inlets (PL.3), toilet pan, seat and lid (PL.4), 3500mm long outlet vent pipe (PL.5), ventilation extraction unit (PL.6) fixed to wall with vent wall bracket (PL.7), 1 bag mounting screws and organic starter, enzyme and toilet cleaner (PL.8) including all necessary interconnector piping between multiple tanks, emergency outlet piping, etc	No	4						
4	"Enviro Loo Urinal Evaporative Tank System code FG-862B " strictly in accordance with manufacturers instructions, unit comprising of urinal evaporative tank (PL.1), urinal bowl (PL.5), 3500mm long outlet vent pipe (PL.3), ventilation extraction unit (PL.3) fixed to wall with vent wall bracket (PL.4), 1 bag mounting screws and organic starter, enzyme and toilet cleaner (PL.8) including all necessary piping, traps, etc	No	1						
		<u>Precast concrete wash trough:</u>							
5	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, including all necessary pipework including soak away approximately 10 meters away from the wash trough, sized at 1000 x 1000 x 1000mm covered with "bidim" complete etc	No	1						
		<u>TRAPS, ETC</u>							
		<u>"Cobra Watertech" or similar approved:</u>							
6	50mm Code 365 CP bottle trap	No	5						
		<u>TAPS, VALVES, ETC</u>							
		Carried Forward							
									R
		Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 8 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD							

Brought Forward			R
<u>"Cobra Watertech" or similar approved:</u>			
7	19mm chrome plated push button taps to wash troughs	No	1
8	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No	5
9	15mm Code 503-21CP elbow action pillar tap	No	5
<u>SANITARY PLUMBING</u>			
<u>uPVC pipes:</u>			
10	50mm Pipes	m	20
11	50mm Diameter pipe laid in and including trenches not exceeding 1m deep	m	15
<u>Extra over uPVC pipes for fittings:</u>			
12	50mm Bend	No	20
13	50mm Junction	No	10
14	50mm Junction with cleaning eye and lid	No	10
15	110mm "GI Two-way" vent valve	No	4
<u>Testing:</u>			
16	Testing waste pipe system		Item
<u>WATER SUPPLIES</u>			
<u>Class 16 uPVC pressure pipes with solvent welded joints:</u>			
17	32mm Pipes laid in and including trenches not exceeding 1m deep	m	20
Carried Forward			R
Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 8 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Brought Forward			R
18	50mm Pipes laid in and including trenches not exceeding 1m deep	m	30
<u>Extra over class 16 uPVC pressure pipes for fittings with solvent welded joints:</u>			
19	32mm Bend	No	10
20	32mm Reducer	No	5
21	32mm Tee	No	5
22	50mm Bend	No	5
23	50mm Tee	No	5
<u>Class 1 copper pipes with capillary couplings:</u>			
24	15mm Pipe fixed to walls, in chases, etc	m	20
25	Ditto, but 22mm diameter	m	10
<u>Extra over Class 1 copper pipes for capillary fittings:</u>			
26	15mm Fittings	No	5
27	22mm Fittings	No	2
<u>Testing:</u>			
28	Testing water pipe system		Item
Carried Forward to Summary of Section No. 3			R
Section No. 3			
Renovations - 4 seats (Enviroloo)			
Bill No. 8			
PLUMBING AND DRAINAGE			
Diatho Consulting (PTY) LTD			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 3</u></p> <p><u>BILL NO.9</u></p> <p><u>GLAZING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Float glass:</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass:</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p style="text-align: center;">-----</p> <p><u>TOPS, SHELVES, DOORS, MIRRORS, ETC</u></p>			
<p>Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 9 GLAZING Diatho Consulting (PTY) LTD</p>		R	

Brought Forward				R
	<p><u>4mm Silvered float glass copper backed mirrors with 10mm bevelled and polished edges fixed with double sided adhesive tape:</u></p>			
1	Stainless steel mirror size 350 x 400m plugged to wall with chrome plated screws.	No	3	
	<p><u>GLAZING TO STEEL WITH PUTTY</u></p> <p><u>6,38mm Obscure safety glass:</u></p>			
2	Panes not exceeding 0,1m ²	m2	6	
<p>Carried Forward to Summary of Section No. 3</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 9 GLAZING Diatho Consulting (PTY) LTD</p>				R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 3</u></p> <p><u>BILL NO.10</u></p> <p><u>PAINTWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and minor cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces:</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 10 PAINTWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
<p><u>Previously painted wood surfaces:</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with "Plascon", etc specifications, unless otherwise described</p> <p><u>COLOURS</u></p> <p>When staining timber, the resultant colour or shade must be to the complete satisfaction of the Project Manager before any overcoating or preservative is applied</p> <p>Paintwork is classified in the following different colour groups: "White", "Pastel", "Deep" and "Transparent" in accordance with the "Natural Colour System" (NCS) adopted by the SA National Standards Unless otherwise described, all paintwork shall be deemed to be classified in the "White" colour group</p> <p style="text-align: center;">-----</p> <p><u>PAINTWORK, ETC TO NEW WORK</u></p> <p><u>ON FIBRE-CEMENT BOARD SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use, on:</u></p>				
<p>1 Fascias and barge boards, including priming metal jointing strips</p>	m2	14		
<p><u>METAL SURFACES WITH</u></p>				
	Carried Forward			R
<p>Section No. 3 Renovations - 4 seats (Enviroloo) Bill No. 10 PAINTWORK Diatho Consulting (PTY) LTD</p>				

	Brought Forward			R
	<u>One coat alkyd based zinc phosphate primer and two coats premium quality polyurethane enamel paint, on steel:</u>			
2	Gates, grilles, burglar screens, balustrades, etc (both sides measured over the full flat area)	m2	4	
3	Extra over for paintwork in the "Deep" colour group	m2	11	
	<u>ON WOOD SURFACES</u>			
	<u>One coat primer, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on:</u>			
4	Doors	m2	23	
5	Extra over for paintwork in the "Pastel" colour group	m2	23	
	<u>PAINTWORK, ETC TO PREVIOUSLY PAINTED WORK</u>			
	<u>One coat alkali resistant plaster primer and two coats PVA acrylic emulsion paint on</u>			
6	Walls	m2	93	
7	Extra over for paintwork in the "Pastel" colour group	m2	93	
	<u>ON METAL SURFACES</u>			
	<u>Spot priming bare metal surfaces, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on work in poor condition:</u>			
8	Door frames	m2	7	
9	Windows with burglar bars	m2	5	
10	Extra over for paintwork in the "Deep" colour group	m2	3	
	Carried Forward to Summary of Section No. 3			R
	Section No. 3			
	Renovations - 4 seats (Enviroloo)			
	Bill No. 10			
	PAINTWORK			
	Diatho Consulting (PTY) LTD			

Bill No	<u>SECTION SUMMARY - Renovations - 4 seats (Enviroloo)</u>	Page No	Amount
1	ALTERATIONS	57	
2	CONCRETE, FORMWORK AND REINFORCEMENT	61	
3	WATERPROOFING	63	
4	CARPENTRY AND JOINERY	66	
5	IRONMONGERY	69	
6	METALWORK	72	
7	PLASTERING	76	
8	PLUMBING AND DRAINAGE	86	
9	GLAZING	88	
10	PAINTWORK	91	
	Carried to Final Summary		R
	Section No. 3 Renovations - 4 seats (Enviroloo) Diatho Consulting (PTY) LTD		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 4</u></p> <p><u>BILL NO.1</u></p> <p><u>ALTERATIONS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition), as published by the Association of South African Quantity Surveyors, shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items, fully described in the said General Preambles, will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>View site:</u></p> <p>Before submitting his tender, the Contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished.</p> <p>No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained</p> <p><u>Old materials to become property of the Contractor:</u></p> <p>Old materials from alterations, except where described as to be re-used or handed over, become the property of the Contractor, who must allow credit for same in the last item of the "Alterations" trade</p> <p style="text-align: right;">Carried Forward</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 1 Alterations Diatho Consulting (PTY) LTD</p>			R

Brought Forward		R
<p><u>Old materials to be carted away:</u></p> <p>Old materials from the alterations, except where described as to be re-used or handed over, as well as all rubbish, etc must be regularly carted from the site and not be allowed to accumulate on or around the site</p> <p><u>Old materials to be re-used:</u></p> <p>None of the old materials are to be used for new work, except where specifically described as being set aside for re-use</p> <p><u>Handing over of materials:</u></p> <p>Where certain materials or articles from demolitions or alterations are described as to be "handed over to the Employer", it shall be taken to mean "handed over by the Contractor to the Principal Agent" and such materials or articles shall be properly stored by the Contractor until handing over thereof and shall include all necessary transport</p> <p>The Contractor must obtain an official receipt from the Principal Agent listing the materials or articles and dates of handing over</p> <p>Should the Contractor fail to submit the receipt when requested to do so, it shall be deemed that the materials or articles are still in his possession and he will be held liable to the Employer for the full replacement value thereof, which amount will be deducted from any monies due to the Contractor</p> <p><u>Explosives:</u></p> <p>No explosives whatsoever may be used for demolition purposes, unless otherwise stated</p>		
<p style="text-align: center;">Carried Forward</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 1 Alterations Diatho Consulting (PTY) LTD</p>		R

Brought Forward			R
<p><u>GENERAL</u></p> <p><u>The contractor shall carry out the whole of the work with as little mess and noise as possible and with a minimum of disturbance to adjoining premises and their tenants. He shall provide proper protection and provide and erect any temporary tarpaulins and temporary plumbing that may be necessary during the progress of the works, all to the satisfaction of the Architect, and remove when directed.</u></p> <p><u>Any water supplies pipes and other piping that may be met with and found necessary to disconnect or cut, shall be effectually stopped or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the Architect.</u></p> <p><u>Doors, fanlights, fittings, frames, linings, etc shall be thoroughly overhauled before re-fixing including taking off, easing and re-hanging, cramping up, re-wedging as required and making good cramps, dowels, etc and easing, oiling, adjusting and repairing ironmongery if necessary, replacing any glass damaged in removal or subsequently and stopping up all nail and screw holes with tinted wood to match timber.</u></p> <p><u>Where doors, windows, etc are described as taken out this shall be understood to include for removal of all beads, architraves, ironmongery, etc and doors which are re-fixed are to be provided with new architraves (elsewhere measured).</u></p> <p><u>Prices for taking out and removing doors and frames shall include for removing door stops, cabin locks, etc and making good to match existing.</u></p> <p><u>With regard to building up openings in existing walls, cement screeds and pavings, granolithic, etc, shall be levelled and prepared for raising of brickwork.</u></p> <p><u>Allow for making good all existing plastered walls where damaged by furniture, etc, and stopping up all screw and holes before painting.</u></p>			
Carried Forward			R
<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 1 Alterations Diatho Consulting (PTY) LTD</p>			

	Brought Forward				R
	<p><u>Making good finishes shall be deemed to include making good of the brick and concrete surfaces onto which new finishes are applied, where necessary.</u></p> <p><u>The contractor will be required to take all dimensions affecting existing building on the site and he will be held solely responsible for the accuracy of all such dimensions.</u></p> <p><u>Hazardous materials:</u></p> <p>Demolitions of buildings, services, external works, site services, etc are to include for the safe removal and disposal of <u>asbestos or asbestos products or other hazardous materials by approved Registered Specialists</u></p> <p style="text-align: center;">-----</p> <p><u>TEMPORARY BARRIERS, SCREENS, ETC</u></p> <p><u>Temporary barriers, screens, etc including removal:</u></p>				
1	"Joluka Orange/ Yellow" or similar approved safety barrier netting 1500mm high including suitable timber framing, corners, ends, etc	m		17	
	<p><u>REMOVAL OF EXISTING WORK</u></p> <p><u>Carefully taking out and handing over to the Employer doors, windows, etc including taking out and removing thresholds, sills, etc from brickwork and preparing openings to receive new similar doors, windows, etc (elsewhere measured) and making good cement plaster on both sides and into reveals:</u></p>				
2	Timber single door and frame not exceeding 2,5m ²	No		5	
	<p><u>Taking out/off and removing ironmongery:</u></p>				
3	Window stays	No		4	
	Carried Forward				R
	<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 1 Alterations Diatho Consulting (PTY) LTD</p>				

Brought Forward			R
4	Window handles	No	4
<u>Taking out and removing piping, sanitary fittings, etc including cutting off as necessary, disconnecting piping from fittings and blocking off and making good damaged plasterwork to walls and screeds to floors (all redecoration work elsewhere):</u>			
5	Vitreous china wall hung urinal with flush valve	No	2
6	Vitreous china wash hand basin	No	3
7	"Daisy Elite" 772403 close-coupled WC suite comprising pan with double flap heavy duty thermoset seat (Code: 8531Z0) and matching 9 litre cistern	No	4
<u>Taking out/off and removing glass and mirrors:</u>			
8	Glass panes not exceeding 0,1m ² from steel windows with putty, including cleaning out rebates and preparing for new glass	m2	4
<u>MAKING GOOD OF FINISHES, ETC</u>			
<u>Making good untinted granolithic</u>			
9	25mm Thick on floors in patches	m2	25
<u>Making good internal/external cement plaster:</u>			
10	Walls in patches	m2	9
<u>Wash down thoroughly with sugarsoap and remove all stains, paint marks, etc, repoint and re-mortar joints as required on existing</u>			
11	Face brick work	m2	49
Carried Forward to Summary of Section No. 4			R
Section No. 4			
Renovations 5 Seats (Water-borne)			
Bill No. 1			
Alterations			
Diatho Consulting (PTY) LTD			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 4</u></p> <p><u>BILL NO.2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Cost of tests:</u></p> <p>The costs of making, storing and testing of concrete test cubes as required under clause 7 "Tests" of SANS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the Principal Agent.</p> <p>The testing shall be undertaken by an independent firm or institution nominated by the Contractor to the approval of the Principal Agent. (Test cubes are measured separately)</p>			
	Carried Forward		R	
	<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Breeze concrete:</u></p> <p>Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated</p> <p><u>Lightweight concrete:</u></p> <p>Lightweight concrete shall have a density of 600kg/m³ for the top 50mm and 400kg/m³ for the remaining thickness. The minimum thickness at outlets, channels, etc shall be 50mm</p> <p><u>Waterproof concrete:</u></p> <p>"Waterproof concrete" shall have the same properties as normal concrete, but the following shall be modified to make the the concrete more water-tight:</p> <ol style="list-style-type: none"> 1. a cement/water ratio of minimum 1.9 and maximum 2.1 2. minimum OPC content of 300kg/m³ 3. Polypropolene micro fibres added to concrete at rate of 182 million per m³ <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>	R	

Brought Forward				R
Formwork to soffits of solid slabs, etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described				
Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described				

<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>25MPa/19mm concrete:</u>				
	Aprons cast in panels	m3	2	
<u>TEST BLOCKS</u>				
1	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	Sets	3.0	
<u>CONCRETE SUNDRIES</u>				
<u>Finishing top surfaces of concrete smooth with a wood float:</u>				
2	Ramps to falls	m2	17	
<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>				
<u>Rough formwork to sides:</u>				
3	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	17	
<u>MOVEMENT JOINTS, ETC</u>				
Carried Forward				R
Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD				

	Brought Forward				
	<u>Expansion joints with 10mm softboard between vertical concrete and brick surfaces:</u>				R
4	Not exceeding 300mm high to edges of surface beds	m	2		
	<u>REINFORCEMENT (PROVISIONAL)</u>				
	<u>Fabric reinforcement:</u>				
5	Type 193 fabric reinforcement in concrete surface beds, slabs, etc	m2	17		
	Carried Forward to Summary of Section No. 4				R
	Section No. 4				
	Renovations 5 Seats (Water-borne)				
	Bill No. 2				
	CONCRETE, FORMWORK AND REINFORCEMENT				
	Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 4</u></p> <p><u>BILL NO.3</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing:</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given separately elsewhere</p> <p><u>Joinery:</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p>			
Carried Forward		R	
<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 3 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			

	Brought Forward				R
	<p>Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts</p> <p><u>Particle board</u></p> <p>All particle board shall comply with SANS 50312 having the required marking as per SANS 50312/EN 312</p> <p><u>Decorative thermosetting plastic laminate covering:</u></p> <p>Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish</p> <p><u>Sizes:</u></p> <p>Sizes are nominal and the Contractor shall make allowance in his prices for minor variances in stated finished sizes of timber doors, door members, door frames, architraves, etc</p> <p><u>Prices</u></p> <p>Prices for all joinery work are to include for general framing, housing and notching, arris rounded angles, glueing, blocking, planting on, screwing, adhesives, dowels, pellets, cross tongues, screws and nails and setting up complete and also for all square cutting and waste. Tops shall be secured with metal or hardwood buttons.</p> <p style="text-align: center;">-----</p> <p><u>EAVES, VERGES, ETC</u></p> <p><u>Medium density plain fibre-cement fascias and barge boards:</u></p> <p>1 19 x 235mm Fascias and barge boards, including aluminium H-profile jointing strips</p> <p style="text-align: right; margin-right: 20px;">m 17</p> <p><u>DOORS, ETC</u></p>				
	Carried Forward				R
	<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 3 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>				

	Brought Forward			R
	<u>Semi-solid core flush panel timber door with hardboard edging, face suitable for paint on both sides, hung to steel frames</u>			
2	44 x 762 x 1882mm high	No	4	
	<u>Wrought meranti doors hung to steel frames:</u>			
3	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard	No	2	
	Carried Forward to Summary of Section No. 4			R
	Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 3 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 4</u></p> <p><u>BILL NO.4</u></p> <p><u>IRONMONGERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 4 IRONMONGERY Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
	<p><u>Locks:</u></p> <p>Notwithstanding Clause 2, Item 3 of the "Ironmongery" trade of the Standard System (7th Edition, 2015) of Measuring Building Work, descriptions of locks shall be deemed to include two keys per lock</p> <p><u>Finishes to ironmongery:</u></p> <p>Where applicable, finishes to ironmongery are indicated by suffixes in accordance with the following list:</p> <p>BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AN Anodised natural AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded BBS Brushed stainless steel</p> <p style="text-align: center;">-----</p> <p><u>CATCHES, CABIN HOOKS, ETC</u></p> <p>1 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged</p> <p><u>LOCKS</u></p> <p><u>Approved:</u></p> <p>2 50mm Padlock</p> <p>3 Four lever lockset</p>	No	2	
	Carried Forward			R
	<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 4 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

	Brought Forward				R
4	Indicator lockset	No	4		
	<u>DOOR CLOSERS</u>				
	<u>"Dorma" or similar approved:</u>				
5	"Dorma" TS73N/EN3-4 parallel arm door closer delayed closing-push side fitting.	No	2		
	<u>LETTERS, NAMEPLATES, ETC</u>				
	<u>"Union Assa Abloy" or similar approved:</u>				
6	75 x 150mm Natural anodised aluminium plate with male or female symbol	No	2		
7	"Ref. SS5066E-06SSE14" stainless steel pictogram engraved with a disabled sign	No	2		
	<u>SUNDRIES</u>				
8	25mm Diameter wall mounted door stop plugged	No	5		
	<u>BATHROOM FITTINGS</u>				
	<u>"Kimberley-Clark" or similar approved:</u>				
9	"Ref. SQ2 code 405607B" white lockable toilet roll holder	No	4		
10	Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc	No	2		
Carried Forward to Summary of Section No. 4					R
Section No. 4					
Renovations 5 Seats (Water-borne)					
Bill No. 4					
IRONMONGERY					
Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 4</u></p> <p><u>BILL NO.5</u></p> <p><u>METALWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions of bolts, anchors, etc:</u></p> <p>Descriptions of bolts shall be deemed to include nuts and washers</p> <p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete</p> <p>Items described as "holed for bolt(s)" shall be deemed to exclude the bolts, unless otherwise described</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres</p>			
Carried Forward		R	
<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 5 METALWORK Diatho Consulting (PTY) LTD</p>			

	Brought Forward		R
<p><u>Fixing:</u></p> <p>Unless otherwise described, descriptions of items shall be deemed to include for fixing to brickwork or concrete</p> <p>Where items are described as "bolted", the bolts are measured elsewhere as stated in clause N.7 of the Model Preambles</p> <p><u>References:</u></p> <p>References in descriptions of windows, doors, gates, etc refer to the respective types of windows, doors, etc detailed in the Architect's window schedules numbered</p> <ul style="list-style-type: none"> • T-2002 • T-2003 • T-2004 • T-2005 <p>and bound into the back of these bills of quantities</p> <p>Tenderers are to price the following items in conjunction with the above Architect's drawings, etc and no claim arising from brevity of descriptions in these bills of quantities, of items shown on the Architect's drawings, etc shall be entertained</p> <p style="text-align: center;">-----</p>			
<p style="text-align: right;">Carried Forward</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 5 METALWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			
R				
<u>STEEL GATES, SCREENS, ETC</u>				
<u>Welded screens and gates, to walls:</u>				
1	Single gate and frame 813 x 2032mm high of 25 x 25 x 2mm hollow section frame and 25 x 25 x 2mm hollow section horizontal middle rail filled in with 12 x 12mm square section vertical rails at 75mm centers and fitted with a pair of suitable hinges welded to frame and with locking mechanism for padlock all in and including outer frame of 25 x 25 x 2mm hollow section welded frame bolted to brickwork	No	2	
R				
Carried Forward to Summary of Section No. 4				
Section No. 4				
Renovations 5 Seats (Water-borne)				
Bill No. 5				
METALWORK				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 4</u></p> <p><u>BILL NO.6</u></p> <p><u>PLUMBING AND DRAINAGE</u> <u>(PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Wire gratings:</u></p> <p>Descriptions of gutter outlets, etc shall be deemed to include wire balloon gratings</p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p>			
<p>Carried Forward</p>		R	
<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 6 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>Stainless steel basins, sinks, wash troughs, urinals, etc:</u></p> <p>Stainless steel for economy basins, domestic sinks and worktops shall be Type 430 (17/0)</p> <p>Stainless steel for urinals, basins, quality sinks, wash troughs, institutional equipment, etc shall be Type 304 (18/8)</p> <p>Stainless steel for laboratory sinks, photographic equipment, etc shall be Type 316 (18/8)</p> <p>Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable</p> <p><u>Sealing of edges:</u></p> <p>Outer edges of sinks, basins, baths, urinals, etc are to be sealed against adjacent surfaces with approved mildew resistant silicone sealant and prices must include therefor</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 6 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

<p style="text-align: center;">Brought Forward</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPe) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 6 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claims for extra bushes, reducers, etc will be entertained</p> <p><u>Fixing of pipes:</u></p> <p>Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls, etc casting in, building in or suspending not exceeding 1m below suspension level</p> <p><u>Paper wrapping to pipes:</u></p> <p>Pipes chased into brickwork must be wrapped with two layers of stout brown paper tied with wire. Rates are to include for wrapping around joints and fittings</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 6 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SANS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SANS 1200L : Medium-pressure pipelines SANS 1200LD : Sewers SANS 1200LE : Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SANS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SANS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 6 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

Brought Forward		R
<p><u>General:</u></p> <p>Descriptions of cast iron roof outlets shall be deemed to include joints to pipes and casting into concrete (adaptors for joints to PVC pipes, etc are given separately)</p> <p>Descriptions of overflow pipes where measured in number, shall be deemed to include joints to cisterns and splay cut ends</p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site</p> <p>Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)</p> <p>Descriptions of WC pans, slop hoppers, etc shall be deemed to include for joints to soil pipes (pan connectors are separately measured) and shall have straight or side outlets and "P" or "S" traps as necessary</p> <p>Description of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.</p> <p><u>As-built drawings:</u></p> <p>Where required, the Contractor shall prepare an updated set of as-built drawings. At completion of the contract the Contractor shall hand these drawings to the Project Manager for reproducing onto the originals for handing over to the Employer (provision for allowance of as-built drawings elsewhere)</p>		
Carried Forward		R
<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 6 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		

	Brought Forward			R
<u>Proprietary items:</u>				
Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items				
Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.				
Prices are to be based on the specific products/articles specified.				
On request, returnable samples are to be provided to the Project Manager for consideration				

<u>SANITARY FITTINGS</u>				
<u>"Vaal" or similar approved:</u>				
1	455 x 290mm "Hibiscus" 7050 wash hand basin bolted to wall	No	4	
2	Flat back urinal overall size 295 x 315 x 415mm high with 40mm chromium plated domical grating (Code 878720) and top inlet spreader (Code 8543) with two hanger brackets with flushmaster junior (Code 812720) hung to wall	No	2	
<u>TRAPS, ETC</u>				
<u>"Cobra Watertech" or similar approved:</u>				
3	50mm Code 365 CP bottle trap	No	4	
<u>TAPS, VALVES, ETC</u>				
Carried Forward				
				R
Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 6 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>"Cobra Watertech" or similar approved:</u>			
4	19mm chrome plated push button taps to wash troughs	No	4
5	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No	4
6	15mm Code 503-21CP elbow action pillar tap	No	4
<u>SANITARY PLUMBING</u>			
<u>uPVC pipes:</u>			
7	50mm Pipes	m	10
8	50mm Diameter pipe laid in and including trenches not exceeding 1m deep	m	6
<u>Extra over uPVC pipes for fittings:</u>			
9	50mm Bend	No	7
10	50mm Junction	No	5
11	50mm Junction with cleaning eye and lid	No	4
12	110mm "GI Two-way" vent valve	No	5
<u>Testing:</u>			
13	Testing waste pipe system		Item
<u>WATER SUPPLIES</u>			
<u>Class 16 uPVC pressure pipes with solvent welded joints:</u>			
14	32mm Pipes laid in and including trenches not exceeding 1m deep	m	11
Carried Forward			R
Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 6 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Brought Forward				R
15	50mm Pipes laid in and including trenches not exceeding 1m deep	m	8	
<u>Extra over class 16 uPVC pressure pipes for fittings with solvent welded joints:</u>				
16	32mm Bend	No	5	
17	32mm Reducer	No	3	
18	32mm Tee	No	6	
19	50mm Bend	No	8	
20	50mm Tee	No	4	
<u>Class 1 copper pipes with capillary couplings:</u>				
21	15mm Pipe fixed to walls, in chases, etc	m	3	
22	Ditto, but 22mm diameter	m	4	
<u>Extra over Class 1 copper pipes for capillary fittings:</u>				
23	15mm Fittings	No	9	
24	22mm Fittings	No	7	
<u>Testing:</u>				
25	Testing water pipe system		Item	
Carried Forward to Summary of Section No. 4				R
Section No. 4				
Renovations 5 Seats (Water-borne)				
Bill No. 6				
PLUMBING AND DRAINAGE				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 4</u></p> <p><u>BILL NO.7</u></p> <p><u>GLAZING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Float glass:</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass:</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p style="text-align: center;">-----</p> <p><u>TOPS, SHELVES, DOORS, MIRRORS, ETC</u></p>			
<p>Carried Forward</p>		R	
<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 7 GLAZING Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>4mm Silvered float glass copper backed mirrors with 10mm bevelled and polished edges fixed with double sided adhesive tape:</u></p>			
1	Stainless steel mirror size 350 x 400m plugged to wall with chrome plated screws.	No	4	
	<p><u>GLAZING TO STEEL WITH PUTTY</u></p> <p><u>6,38mm Obscure safety glass:</u></p>			
2	Panes not exceeding 0,1m ²	m2	6	
<p>Carried Forward to Summary of Section No. 4</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 7 GLAZING Diatho Consulting (PTY) LTD</p>				
				R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 4</u></p> <p><u>BILL NO.8</u></p> <p><u>PAINTWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and minor cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces:</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p style="text-align: right; margin-right: 20px;">Carried Forward</p> <p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 8 PAINTWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
<p><u>Previously painted wood surfaces:</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with "Plascon", etc specifications, unless otherwise described</p> <p><u>COLOURS</u></p> <p>When staining timber, the resultant colour or shade must be to the complete satisfaction of the Project Manager before any overcoating or preservative is applied</p> <p>Paintwork is classified in the following different colour groups: "White", "Pastel", "Deep" and "Transparent" in accordance with the "Natural Colour System" (NCS) adopted by the SA National Standards Unless otherwise described, all paintwork shall be deemed to be classified in the "White" colour group</p> <p style="text-align: center;">-----</p> <p><u>PAINTWORK, ETC TO NEW WORK</u></p> <p><u>ON FIBRE-CEMENT BOARD SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use, on:</u></p>				
<p>1 Fascias and barge boards, including priming metal jointing strips</p>	m2	5		
<p><u>METAL SURFACES WITH</u></p>				
	Carried Forward			R
<p>Section No. 4 Renovations 5 Seats (Water-borne) Bill No. 8 PAINTWORK Diatho Consulting (PTY) LTD</p>				

Brought Forward			R
<u>One coat alkyd based zinc phosphate primer and two coats premium quality polyurethane enamel paint, on steel:</u>			
2	Gates, grilles, burglar screens, balustrades, etc (both sides measured over the full flat area)	m2	7
3	Extra over for paintwork in the "Deep" colour group	m2	10
<u>ON WOOD SURFACES</u>			
<u>One coat primer, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on:</u>			
4	Doors	m2	23
5	Extra over for paintwork in the "Pastel" colour group	m2	10
<u>PAINTWORK, ETC TO PREVIOUSLY PAINTED WORK</u>			
<u>One coat alkali resistant plaster primer and two coats PVA acrylic emulsion paint on</u>			
6	Walls	m2	32
7	Extra over for paintwork in the "Pastel" colour group	m2	15
<u>ON METAL SURFACES</u>			
<u>Spot priming bare metal surfaces, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on work in poor condition:</u>			
8	Door frames	m2	12
9	Windows with burglar bars	m2	8
10	Extra over for paintwork in the "Deep" colour group	m2	4
Carried Forward to Summary of Section No. 4			R
Section No. 4			
Renovations 5 Seats (Water-borne)			
Bill No. 8			
PAINTWORK			
Diatho Consulting (PTY) LTD			

Bill No	<u>SECTION SUMMARY - Renovations 5 Seats (Water-borne)</u>	Page No	Amount
1	Alterations	97	
2	CONCRETE, FORMWORK AND REINFORCEMENT	101	
3	CARPENTRY AND JOINERY	104	
4	IRONMONGERY	107	
5	METALWORK	110	
6	PLUMBING AND DRAINAGE	119	
7	GLAZING	121	
8	PAINTWORK	124	
	Carried to Final Summary		R
	Section No. 4 Renovations 5 Seats (Water-borne) Diatho Consulting (PTY) LTD		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be included in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p>The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "hard rock" or "soft rock".</p> <p>The nature of the ground is assumed to be gravel, therefore "earth", but possibly interspersed with "soft rock".</p> <p>The nature of the ground is assumed to be silty clay with loose river boulders varying in size up to approximately 450mm diameter, therefore "earth", but possibly interspersed with "hard rock".</p>			
Carried Forward		R	
<p>Section No. 5 F7 Female Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>			

Brought Forward		R
<p>Trial holes indicate that the nature of the ground is silty clay to a depth of approximately 500mm with fine to medium loose sandy material below, therefore "earth". The trial holes also indicate that the water table is at a maximum depth of approximately 1000mm.</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p><u>Subterranean water:</u></p> <p>No subterranean water is expected</p> <p>Should the Contractor however, encounter any subterranean water on the site, he shall immediately notify the Principal Agent thereof and submit recommendations for keeping the works free from subterranean water together with all costs involved therewith</p> <p><u>Excavation for working space in rock:</u></p> <p>Notwithstanding clause 10 measurement rule 27 of the Standard System of Measuring Building Work, excavation for working space in material of a more different character (e.g. soft or hard rock) will be measured in cubic metres to the extent executed and given as "extra over" bulk excavation or trench and hole excavation as the case may be</p> <p><u>Carting away of excavated material</u></p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p>		
<p style="text-align: center;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>		R

Brought Forward				R
<u>Filling</u>				
Notwithstanding the reference to prescribed multiple handling in clause 1 page 10 of the Standard System (7th Edition, 2015) of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material				
<u>Testing:</u>				
<i>Prices for backfilling to trenches and holes only are to include for all necessary density tests in accordance with SANS 1200D</i>				

<u>EXCAVATIONS, FILLING, ETC</u>				
<u>EXCAVATIONS, ETC</u>				
<u>Excavation in earth not exceeding 2m deep:</u>				
1	Reduced levels under floors	m3	2	
2	Trenches and holes for thickening under surface beds, etc	m3	3	
3	Trenches	m3	9	
4	Pit	m3	30	
<u>Extra over trench and hole excavations in earth for excavation in:</u>				
5	Soft rock	m3	1	
6	Hard rock	m3	0.4	
<u>Extra over all excavations for carting away:</u>				
7	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	10	
Carried Forward				R
Section No. 5 F7 Female Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>Risk of collapse of excavations:</u>			
8	Sides of trench and hole excavations not exceeding 1,5m deep	m2	25
<u>Keeping excavations free of water:</u>			
9	Keeping excavations free of all water other than subterranean water		Item
<u>FILLING ETC</u>			
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 93% Mod AASHTO density:</u>			
10	Backfilling to trenches, holes, etc	m3	3
<u>G5 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>			
11	Under floors, steps, pavings, etc	m3	2
<u>Compaction of surfaces:</u>			
12	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	21
<u>Prescribed density tests on filling:</u>			
13	"Modified AASHTO Density" test	No	6
<u>SOIL POISONING</u>			
<u>Soil insecticide in accordance with SANS 5859:</u>			
14	Soil insecticide (protection against termites) applied as specified under floors, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	21
Carried Forward			R
Section No. 5 F7 Female Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD			

	Brought Forward				R
15	To bottoms and sides of trenches, etc	m2	40		
	Carried Forward to Summary of Section No. 5				R
	Section No. 5				
	F7 Female Ablutions				
	Bill No. 1				
	EARTHWORKS				
	Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Cost of tests:</u></p> <p><u>Breeze concrete:</u></p> <p>Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>			R

<p style="text-align: center;">Brought Forward</p> <p><u>Lightweight concrete:</u></p> <p>Lightweight concrete shall have a density of 600kg/m³ for the top 50mm and 400kg/m³ for the remaining thickness. The minimum thickness at outlets, channels, etc shall be 50mm</p> <p><u>Waterproof concrete:</u></p> <p>"Waterproof concrete" shall have the same properties as normal concrete, but the following shall be modified to make the the concrete more water-tight:</p> <ol style="list-style-type: none"> 1. a cement/water ratio of minimum 1.9 and maximum 2.1 2. minimum OPC content of 300kg/m³ 3. Polypropolene micro fibres added to concrete at rate of 182 million per m³ <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself</p> <p>Formwork to soffits of solid slabs, etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described</p> <p>Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described</p> <p style="text-align: center;">-----</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>	R	

Brought Forward				R
<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>15MPa/19mm concrete:</u>				
1	Surface blinding under footings and bases	m3	1	
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>30MPa/19mm concrete:</u>				
	Strip footings	m3	3	
	Surface beds on waterproofing	m3	4	
2	Surface beds in tank bottoms			
		m3	3	
3	Aprons cast in panels to falls	m3	2	
<u>TEST BLOCKS</u>				
4	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	2	
<u>CONCRETE SUNDRIES</u>				
<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>				
5	Surface beds, slabs, etc	m2	12	
<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>				
<u>Rough formwork to sides:</u>				
6	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	42	
Carried Forward				R
Section No. 5 F7 Female Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>MOVEMENT JOINTS, ETC</u>			
<u>Expansion joints with 10mm softboard between vertical concrete and brick surfaces:</u>			
7	Not exceeding 300mm high to edges of surface beds	m	21
<u>Saw-cut joints:</u>			
8	6 x 10mm Saw-cut joints in top of concrete	m	31
<u>REINFORCEMENT (PROVISIONAL)</u>			
<u>Mild steel reinforcement to structural concrete work:</u>			
9	Mild steel bar reinforcement (8 to 40mm diameter bars)	t	0.08
<u>High tensile steel reinforcement to structural concrete work:</u>			
10	High tensile steel bar reinforcement (8 to 40mm diameter bars)	t	0.19
<u>Fabric reinforcement:</u>			
11	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	12
Carried Forward to Summary of Section No. 5			R
Section No. 5			
F7 Female Ablutions			
Bill No. 2			
CONCRETE, FORMWORK AND REINFORCEMENT			
Diatho Consulting (PTY) LTD			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>General:</u></p> <p>Non-load bearing brickwork is to be built to full height less 20mm gap next to the ceiling and is to be left for 14 days before grouting up in 1:3 cement mortar.</p> <p><u>Sizes in descriptions:</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p>			
<p>Carried Forward</p>		R	
<p>Section No. 5 F7 Female Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>Hollow walls:</u></p> <p>Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole</p> <p><u>Bagged and sealed walls:</u></p> <p>Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats bitumen emulsion waterproofing coating</p> <p><u>Face bricks :</u></p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>All face brickwork shall be regularly cleaned down as the work proceeds and shall be protected as necessary by an approved method</p> <p><u>Pointing:</u></p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include smooth floated square recessed, hollow recessed, weathered pointing, etc</p> <p style="text-align: center;">-----</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in class 1 mortar:</u></p> <p>1 One brick walls m2 10</p> <p>2 One brick walls in pit m2 20</p>			
	Carried Forward			R
	<p>Section No. 5 F7 Female Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
3	Half brick wall corbelling in pit	m	12
	<u>2,5mm Brickwork reinforcement:</u>		
4	150mm Wide reinforcement built in horizontally	m	61
	<u>FACE BRICKWORK</u>		
	<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>		
5	Extra over brickwork for face brickwork	m2	4
	<u>SUPERSTRUCTURE</u>		
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar in loadbearing walls etc:</u>		
6	One brick walls	m2	66
	<u>BRICKWORK SUNDRIES</u>		
	<u>Joint forming material in movement joints:</u>		
7	12mm Fibre board built in vertically through brick walls	m	52
	<u>2,5mm Brickwork reinforcement:</u>		
8	75mm Wide reinforcement built in horizontally	m	77
9	150mm Wide reinforcement built in horizontally	m	217
	<u>Prestressed fabricated concrete lintels, including necessary temporary supports:</u>		
10	110 x 75mm Lintels in lengths not exceeding 3m long	m	41
	<u>FACE BRICKWORK</u>		
Carried Forward			R
Section No. 5 F7 Female Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD			

Brought Forward			R
<p><u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u></p>			
11	Half brick wall faced on both sides	m2	26
12	Extra over brickwork for face brickwork	m2	151
13	Extra over brickwork for brick-on-edge header course lintel pointed on face and 120mm soffit	m	8
14	Fair raking cutting	m	10
<p><u>Brick-on-edge header course coping, sills, etc. of face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with recessed joints on all exposed faces</u></p>			
15	150mm Wide sills set sloping and slightly projecting	m	7
<p>Carried Forward to Summary of Section No. 5</p>			R
<p>Section No. 5 F7 Female Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.4</u></p> <p><u>WATERPROOFING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Waterproofing:</u></p> <p>Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets, etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs</p> <p style="text-align: center;">-----</p>			
<p>Carried Forward</p>		R	
<p>Section No. 5 F7 Female Ablutions Bill No. 4 WATERPROOFING Diatho Consulting (PTY) LTD</p>			

Brought Forward							
<u>DAMPPROOFING OF WALLS AND FLOORS</u>							
<u>One layer 375 micron embossed polyethylene dampproof course (SANS 952-1985 type B):</u>							
1	In walls	m2	60				
2	In walls vertically at reveals	m2	3				
<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape:</u>							
3	Under surface beds	m2	15				
<u>JOINT SEALANTS ETC</u>							
<u>Two- part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>							
4	6 x 10mm In saw cut joints in floors	m	31				
<u>White silicone sealing compound including backing cord, bond breaker, primer, etc</u>							
5	6 x 10mm In expansion joints in floors, including raking out expansion joint filler as necessary [LI]	m	21				
Carried Forward to Summary of Section No. 5							
Section No. 5							
F7 Female Ablutions							
Bill No. 4							
WATERPROOFING							
Diatho Consulting (PTY) LTD							
							R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.5</u></p> <p><u>ROOF COVERINGS</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Profiled metal roof sheeting and accessories shall be supplied with a 10 year guarantee and be installed by an approved installer</p> <p>All fixing holes shall be drilled and not punched</p> <p>Roof covering accessories shall be manufactured from the same material as used for roof covering</p> <p style="text-align: center;">-----</p> <p><u>PROFILED METAL SHEETING AND ACCESSORIES</u></p>			
<p>Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>		<p>R</p>	

	Brought Forward			R
	<p><u>0,6 mm "Klip-Lok 406" or similar approved light industrial Z275 spelter galvanised steel sheeting, with "Classicoat" finish one side and half coat "Classicoat Grey" other side, and accessories fixed to timber purlins or rails at approximately 1500mm centres:</u></p>			
1	Roof coverings with pitch not exceeding 25 degrees	m2	31	
	<p><u>Accessories:</u></p>			
2	Apex flashings 462mm girth	m	16	
	<p><u>ROOF AND WALL INSULATION</u></p> <p><u>"Sisalation 405" or similar approved residential grade aluminium foil based insulation:</u></p>			
3	Insulation sheeting laid taut over purlins at approximately 1000mm centres and fixed concurrent with roof covering with minimum 150mm stapled laps, including galvanised steel straining wires at not exceeding 400mm centres and double-sided tape at edges where required	m2	31	
	Carried Forward to Summary of Section No. 5			R
	<p>Section No. 5 F7 Female Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing:</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given separately elsewhere</p> <p><u>Joinery:</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			R

Brought Forward				R
Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts				
<u>Particle board</u>				
All particle board shall comply with SANS 50312 having the required marking as per SANS 50312/EN 312				
<u>Decorative thermosetting plastic laminate covering:</u>				
Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish				
<u>Sizes:</u>				
Sizes are nominal and the Contractor shall make allowance in his prices for minor variances in stated finished sizes of timber doors, door members, door frames, architraves, etc				
<u>Prices</u>				
Prices for all joinery work are to include for general framing, housing and notching, arris rounded angles, glueing, blocking, planting on, screwing, adhesives, dowels, pellets, cross tongues, screws and nails and setting up complete and also for all square cutting and waste. Tops shall be secured with metal or hardwood buttons.				

<u>ROOFS, ETC</u>				
<u>Sawn softwood grade 5:</u>				
1 38 x 114mm Wall plates bolted	m		18	
2 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m		58	
Carried Forward				R
Section No. 5 F7 Female Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD				

Brought Forward				R
3	50 x 76mm Purlins	m	60	
<u>EAVES, VERGES, ETC</u>				
<u>Medium density plain fibre-cement fascias and barge boards:</u>				
4	19 x 235mm Fascias and barge boards, including aluminium H-profile jointing strips	m	26	
<u>DOORS, ETC</u>				
<u>Wrought meranti doors hung to steel frames:</u>				
5	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding including 150mm undercut (D2)	No	7	
6	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1)	No	3	
Carried Forward to Summary of Section No. 5				R
Section No. 5				
F7 Female Ablutions				
Bill No. 6				
CARPENTRY AND JOINERY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.7</u></p> <p><u>IRONMONGERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p>			
<p>Carried Forward</p>		R	
<p>Section No. 5 F7 Female Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>Locks:</u></p> <p>Notwithstanding Clause 2, Item 3 of the "Ironmongery" trade of the Standard System (7th Edition, 2015) of Measuring Building Work, descriptions of locks shall be deemed to include two keys per lock</p> <p><u>Finishes to ironmongery:</u></p> <p>Where applicable, finishes to ironmongery are indicated by suffixes in accordance with the following list:</p> <p>BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AN Anodised natural AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded BBS Brushed stainless steel</p> <p style="text-align: center;">-----</p> <p><u>CATCHES, CABIN HOOKS, ETC</u></p> <p>1 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged</p> <p><u>LOCKS</u></p> <p><u>"Union Assa Abloy" or similar approved:</u></p> <p>2 50mm Brass padlock</p> <p>3 Four lever lockset</p>	No	8	
	Carried Forward			R
	<p>Section No. 5 F7 Female Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

		Brought Forward		R
4	"Ref. CZ80941SC" Indicator bolt	No	7	
		<u>HANDLES</u>		
		<u>"Union Assa Abloy" or similar approved:</u>		
5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres	Pairs	3.0	
		<u>PUSH PLATES AND KICK PLATES</u>		
		<u>"Union Assa Abloy" or similar approved:</u>		
		<u>1.2mm Thick satin finished "Union" stainless steel plates countersunk screwed along edges at not exceeding 200mm centres</u>		
6	200 x 800mm Type "SS5089-200W" kicking plate	No	14	
		<u>DOOR CLOSERS</u>		
		<u>"Dorma" or similar approved:</u>		
7	"Dorma" TS73N/EN3-4 parallel arm door closer delayed closing-push side fitting	No	1	
		<u>LETTERS, NAMEPLATES, ETC</u>		
		<u>"Dorma" or similar approved:</u>		
8	DSS-131 Engraved "Female" information sign, plugged	No	2	
9	DSS-131 Engraved "Emergency Exit" information sign, plugged	No	1	
		<u>SUNDRIES</u>		
10	25mm Diameter wall mounted door stop plugged	No	9	
		Carried Forward		R
Section No. 5 F7 Female Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD				

		Brought Forward		R
<u>BATHROOM FITTINGS</u>				
<u>"Kimberley-Clark" or similar approved:</u>				
11	"Ref. SQ2 code 405607B" white lockable toilet roll holder	No	7	
12	Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc	No	7	
Carried Forward to Summary of Section No. 5				R
Section No. 5				
F7 Female Ablutions				
Bill No. 7				
IRONMONGERY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.8</u></p> <p><u>METALWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions of bolts, anchors, etc:</u></p> <p>Descriptions of bolts shall be deemed to include nuts and washers</p> <p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete</p> <p>Items described as "holed for bolt(s)" shall be deemed to exclude the bolts, unless otherwise described</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres</p>			
Carried Forward		R	
<p>Section No. 5 F7 Female Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>			

Brought Forward			R	
<p><u>Fixing:</u></p> <p>Unless otherwise described, descriptions of items shall be deemed to include for fixing to brickwork or concrete</p> <p>Where items are described as "bolted", the bolts are measured elsewhere as stated in clause N.7 of the Model Preambles</p> <p><u>References:</u></p> <p>References in descriptions of windows, doors, gates, etc refer to the respective types of windows, doors, etc detailed in the Architect's window schedules numbered</p> <ul style="list-style-type: none"> • 21111/FSPS/S005 • T-2003 • T-2004 • T-2005 <p>and bound into the back of these bills of quantities</p> <p>Tenderers are to price the following items in conjunction with the above Architect's drawings, etc and no claim arising from brevity of descriptions in these bills of quantities, of items shown on the Architect's drawings, etc shall be entertained</p> <p style="text-align: center;">-----</p>				
Carried Forward			R	
<p>Section No. 5 F7 Female Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>				

Brought Forward							
<u>STEEL GATES, SCREENS, ETC</u>							
<u>Welded screens and gates, to brickwalls:</u>							
1	Single gate and frame size to fit standard door, size 813 x 2032mm high	No	3				R
<u>PRESSED STEEL DOOR FRAMES</u>							
<u>1,6mm Double rebated frames suitable for half brick walls:</u>							
2	Frame for door size 813 x 2032mm high	No	7				
<u>1,6mm Double rebated frames suitable for one brick walls:</u>							
3	Frame for door size 813 x 2032mm high	No	3				
<u>STEEL WINDOWS, DOORS, ETC</u>							
<u>Standard windows:</u>							
4	Window type NE1, 533 x 654mm high (N1)	No	7				
5	Window type NE7, 1022 x 654mm high (N2)	No	4				
 Carried Forward to Summary of Section No. 5							
Section No. 5							
F7 Female Ablutions							
Bill No. 8							
METALWORK							
Diatho Consulting (PTY) LTD							
							R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.9</u></p> <p><u>PLASTERING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Moisture tests:</u></p> <p>Before any finishes, coverings, etc are applied to screeds, plastering, etc or any other in-situ finish, moisture tests are to be carried out to the complete satisfaction of the Project Manager to ensure that these surfaces have the correct moisture content for the finish to be applied</p> <p><u>Labours, etc</u></p> <p>Labours such as fair, rounded and chamfered edges, trowel cuts, throats, V-joints, angles, etc shall be deemed to be included in the descriptions</p>			
Carried Forward		R	
<p>Section No. 5 F7 Female Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Sample Panels</u></p> <p>A sample panel size 1m x1m, of each of the various plaster type wall and floor finishes in this contract, shall be prepared for the approval of the Project Manager and the cost of the sample panel(s) shall be deemed to be included in the overall costs of the <u>relevant</u> wall and floor finishes</p> <p><u>GRANOLITHIC</u></p> <p><u>Method:</u></p> <p>The method to be used shall be either the monolithic method or the bonded method</p> <p><u>Preparation:</u></p> <p>For granolithic applied monolithically, the concrete floor shall be swept clean after bleeding of the concrete has ceased and the slab has begun to stiffen; any remaining bleed water shall be removed and the granolithic applied immediately thereafter. For granolithic to be bonded to the floor slab after it has hardened, the slab surface shall be hacked (preferably by mechanical means) until all laitance, dirt, oil, etc is dislodged and swept clean of all loose matter. The slab shall then be wetted and kept damp for at least six hours before applying the granolithic</p> <p><u>Mix:</u></p> <p>Unless otherwise described, granolithic shall attain a compressive strength of at least 41MPa. The coarse aggregate shall comply with SANS 1083 and shall generally be capable of passing a 10mm mesh sieve. Where the thickness of the granolithic exceeds 25mm, the size of the coarse aggregate shall be increased to the maximum size compatible with the thickness of the granolithic</p>				R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>				R

<p style="text-align: center;">Brought Forward</p> <p><u>Panels:</u></p> <p>Granolithic shall be laid in panels not exceeding 14m² for monolithic finishes, not exceeding 9,5m² for bonded finishes and not exceeding 6m² for all external granolithic. Wherever possible, panels shall be square but at no time should the length of the panel exceed 1,5 times its width</p> <p>Where possible joints between panels shall be positioned over joints in the floor slab and shall be at least 3mm wide through the full thickness of the finish, separated by strips of wood or fibreboard and finished with V-joints</p> <p><u>Laying:</u></p> <p>Monolithic granolithic shall be applied to the partially set slab and thoroughly compacted and lightly wood floated to the required levels</p> <p>Bonded granolithic shall be applied to the slab after applying a 1:1 sand-and-cement slurry brushed over the surface and allowed to partially set before applying the granolithic. The granolithic shall be thoroughly compacted and lightly wood floated to the required levels</p> <p>After wood floating, the monolithic and bonded granolithic shall remain undisturbed until bleeding has ceased and the surface has stiffened. Any remaining bleed water and laitance shall then be removed and the surface steel trowelled or power floated</p> <p><u>Curing, seasoning and protection:</u></p> <p>Granolithic shall be covered with clean hessian with waterproof building foil over and kept wet for at least seven days after laying</p> <p><u>Colour:</u></p> <p>Coloured granolithic shall be tinted with an approved colouring pigment mixed into a true and even colour</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>	R	

	Brought Forward			R
	<p><u>TINTED WHITE CEMENT SCREEDS</u></p> <p>Tinted screed shall be composed of one bag White Portland Cement and two wheelbarrows "Malmesbury" sand. Surfaces shall be finished with a steel trowel to leave a smooth finish and coated with two coats "Earthcote S.I. Floorcote" two-pack polyurethane floor sealer applied as per the manufacturer's recommendations</p> <p>NOTE: Tinted screeds are to be strengthened with "Primal Eccos" acrylic polymer (15% of the water volume is to be substituted with the acrylic polymer during the mixing process)</p> <p>Coarse sand is to be used for these screeds</p> <p>All tinting, finishing, strengthening, etc are to be mixed, applied, etc strictly in accordance with the manufacturer's instructions</p> <p><u>CEMENT PLASTER</u></p> <p>Unless otherwise described, cement plaster shall be taken to mean Class 1 cement plaster i.e. 1:4 cement:sand plaster (common cement)</p> <p style="text-align: center;">-----</p> <p><u>CEMENT SCREEDS TO CONCRETE</u></p> <p><u>Cement screeds steel trowelled, on concrete:</u></p>			
1	30mm Thick to floors	m2	12	
	<p><u>FLOOR AND WALL SEALERS</u></p> <p><u>Minimum two coats approved epoxy coat, on concrete:</u></p>			
2	On screed	m2	12	
	<p>Carried Forward to Summary of Section No. 5</p> <p>Section No. 5 F7 Female Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.10</u></p> <p><u>PLUMBING AND DRAINAGE</u> <u>(PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Wire gratings:</u></p> <p>Descriptions of gutter outlets, etc shall be deemed to include wire balloon gratings</p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p>			
<p>Carried Forward</p>		R	
<p>Section No. 5 F7 Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>Stainless steel basins, sinks, wash troughs, urinals, etc:</u></p> <p>Stainless steel for economy basins, domestic sinks and worktops shall be Type 430 (17/0)</p> <p>Stainless steel for urinals, basins, quality sinks, wash troughs, institutional equipment, etc shall be Type 304 (18/8)</p> <p>Stainless steel for laboratory sinks, photographic equipment, etc shall be Type 316 (18/8)</p> <p>Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable</p> <p><u>Sealing of edges:</u></p> <p>Outer edges of sinks, basins, baths, urinals, etc are to be sealed against adjacent surfaces with approved mildew resistant silicone sealant and prices must include therefor</p>				R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>				R

<p style="text-align: center;">Brought Forward</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPE) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claims for extra bushes, reducers, etc will be entertained</p> <p><u>Fixing of pipes:</u></p> <p>Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls, etc casting in, building in or suspending not exceeding 1m below suspension level</p> <p><u>Paper wrapping to pipes:</u></p> <p>Pipes chased into brickwork must be wrapped with two layers of stout brown paper tied with wire. Rates are to include for wrapping around joints and fittings</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SANS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SANS 1200L : Medium-pressure pipelines SANS 1200LD : Sewers SANS 1200LE : Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SANS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SANS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

	Brought Forward		R
<p><u>General:</u></p> <p>Descriptions of cast iron roof outlets shall be deemed to include joints to pipes and casting into concrete (adaptors for joints to PVC pipes, etc are given separately)</p> <p>Descriptions of overflow pipes where measured in number, shall be deemed to include joints to cisterns and splay cut ends</p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site</p> <p>Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)</p> <p>Descriptions of WC pans, slop hoppers, etc shall be deemed to include for joints to soil pipes (pan connectors are separately measured) and shall have straight or side outlets and "P" or "S" traps as necessary</p> <p>Description of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.</p> <p><u>As-built drawings:</u></p> <p>Where required, the Contractor shall prepare an updated set of as-built drawings. At completion of the contract the Contractor shall hand these drawings to the Project Manager for reproducing onto the originals for handing over to the Employer (provision for allowance of as-built drawings elsewhere)</p>			
<p style="text-align: right;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			R

Brought Forward			R
<u>Proprietary items:</u>			
Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items			
Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.			
Prices are to be based on the specific products/articles specified.			
On request, returnable samples are to be provided to the Project Manager for consideration			

<u>RAINWATER DISPOSAL</u>			
<u>0,6mm Galvanised sheet steel gutters and rainwater pipes with powder coated finish on outside to match roof sheeting colour:</u>			
1	150 x150mm Box gutters	m	8
2	100 x 75mm Rainwater pipes	m	5
3	Extra over gutter for stopped end	No	2
4	Extra over gutter for outlet for 100 x 75mm pipe	No	2
5	Extra over rainwater pipe for bend	No	2
6	Extra over rainwater pipe for shoe	No	2
7	Extra over rainwater pipe for eaves or plinth offset	No	4
Carried Forward			R
Section No. 5 F7 Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Brought Forward									
<u>ENVIRO-LOO TOILET SYSTEMS</u>									
<u>Supply and install "Enviroloo systems" or similar approved:</u>									
8	"Enviro Loo System FG-1040 STDCA/A Standard" strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvered inlets (PL.1), drying plate (PL.2), two x air inlets (PL.3), toilet pan, seat and lid (PL.4), 3500mm long outlet vent pipe (PL.5), ventilation extraction unit (PL.6) fixed to wall with vent wall bracket (PL.7), 1 bag mounting screws and organic starter, enzyme and toilet cleaner (PL.8) including all necessary interconnector piping between multiple tanks, emergency outlet piping, etc	No		7					
<u>INSPECTION BY ENVIRO-LOO/SUPPLIER</u>									
9	Two site visits to be made by the "Enviro loo" suppliers to assist/support the contractor in the installation of the "enviro loo" and a final inspection to be ascertain the enviro loo has been installed correctly at which time a Certificate of Compliance should be issued between the Department of Education Limpopo and Enviro Loo Options Limpopo				Item				
<u>SANITARY FITTINGS</u>									
<u>"Vaal" or similar approved:</u>									
10	455 x 290mm "Hibiscus" 7050 wash hand basin bolted to wall	No		5					
<u>Precast concrete wash trough:</u>									
11	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, including all necessary pipework including soak away approximately 10 meters away from the wash trough, sized at 1000 x 1000 x 1000mm covered with "bidim" complete etc	No		1					
<u>TRAPS, ETC</u>									
Carried Forward									
Section No. 5 F7 Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD									

Brought Forward			R
<u>uPVC:</u>			
12	40 x 40mm Double bowl wash trough or sink reseal "P" or "S" trap combination	No	6
<u>"Cobra Watertech" or similar approved:</u>			
13	50mm Code 365 CP bottle trap	No	7
<u>TAPS, VALVES, ETC</u>			
<u>"Cobra Watertech" or similar approved:</u>			
14	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No	20
15	15mm Code FPT2A1RO-OGP01 "Roma" basin tap with waste union	No	10
16	15mm Code 503-21CP elbow action pillar tap	No	6
<u>SANITARY PLUMBING</u>			
<u>uPVC pipes:</u>			
17	50mm Pipes	m	85
18	110mm Pipes	m	75
19	50mm Diameter pipe laid in and including trenches not exceeding 1m deep	m	86
20	Ditto, but 110mm diameter	m	98
<u>Extra over uPVC pipes for fittings:</u>			
21	50mm Bend	No	23
22	50mm Junction	No	23
Carried Forward			R
Section No. 5 F7 Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

	Brought Forward				R
23	50mm Junction with cleaning eye and lid	No	23		
24	110mm Straight pan connector	No	15		
25	110mm Bend	No	30		
26	110mm Junction	No	30		
27	110mm Reducing junction	No	45		
28	110mm Access bend	No	15		
29	110mm Double junction	No	45		
30	110mm "GI Two-way" vent valve	No	15		
	<u>Testing:</u>				
31	Testing waste pipe system			Item	
	<u>WATER SUPPLIES</u>				
	<u>Class 1 copper pipes with capillary couplings:</u>				
32	15mm Pipe fixed to walls, in chases, etc	m	70		
33	Ditto, but 22mm diameter	m	100		
	<u>Extra over Class 1 copper pipes for capillary fittings:</u>				
34	15mm Fittings	No	100		
35	22mm Fittings	No	100		
	<u>Testing:</u>				
36	Testing water pipe system			Item	
	Carried Forward to Summary of Section No. 5				R
	Section No. 5				
	F7 Female Ablutions				
	Bill No. 10				
	PLUMBING AND DRAINAGE				
	Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.11</u></p> <p><u>GLAZING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Float glass:</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass:</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p style="text-align: center;">-----</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p>			
<p>Carried Forward</p>		R	
<p>Section No. 5 F7 Female Ablutions Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>			

	Brought Forward				
	<u>6,38mm Obscure safety glass:</u>				R
1	Panes not exceeding 0,1m ²	m2	4		
	<u>TOPS, SHELVES, DOORS, MIRRORS, ETC</u>				
	<u>Silvered float glass copper backed mirrors with polished edges holed for and fixed with chromium plated dome capped mirror screws with foam backing strip all round to plugs in walls</u>				
2	6mm "GG" quality polished glass mirror 450 x 800mm high with polished edges fixed to wall with four 35mm round nose chromium plated mirror screws	No	7		
	Carried Forward to Summary of Section No. 5				R
	Section No. 5				
	F7 Female Ablutions				
	Bill No. 11				
	GLAZING				
	Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 5</u></p> <p><u>BILL NO.12</u></p> <p><u>PAINTWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and minor cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces:</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p style="text-align: right;">Carried Forward</p> <p>Section No. 5 F7 Female Ablutions Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward		R	
<p><u>Previously painted wood surfaces:</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with "Plascon", etc specifications, unless otherwise described</p> <p><u>COLOURS</u></p> <p>When staining timber, the resultant colour or shade must be to the complete satisfaction of the Project Manager before any overcoating or preservative is applied</p> <p>Paintwork is classified in the following different colour groups: "White", "Pastel", "Deep" and "Transparent" in accordance with the "Natural Colour System" (NCS) adopted by the SA National Standards Unless otherwise described, all paintwork shall be deemed to be classified in the "White" colour group</p> <p style="text-align: center;">-----</p> <p><u>PAINTWORK, ETC TO NEW WORK</u></p> <p><u>ON FIBRE-CEMENT BOARD SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use, on:</u></p>				
<p>1 Fascias and barge boards, including priming metal jointing strips</p>	m2	6		
<p><u>METAL SURFACES WITH</u></p>				
	Carried Forward		R	
<p>Section No. 5 F7 Female Ablutions Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>				

	Brought Forward			R
	<u>One coat alkyd based zinc phosphate primer and two coats premium quality polyurethane enamel paint, on steel:</u>			
2	Door frames	m2	17	
3	Windows	m2	9	
4	Gates, grilles, burglar screens, balustrades, etc (both sides measured over the full flat area)	m2	7	
5	Extra over for paintwork in the "Deep" colour group	m2	33	
	<u>ON WOOD SURFACES</u>			
	<u>One coat primer, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on:</u>			
6	Doors	m2	32	
7	Roof timbers at eaves and verges	m2	38	
8	Extra over for paintwork in the "Deep" colour group	m2	70	
	Carried Forward to Summary of Section No. 5			R
	Section No. 5			
	F7 Female Ablutions			
	Bill No. 12			
	PAINTWORK			
	Diatho Consulting (PTY) LTD			

Bill No	<u>SECTION SUMMARY - F7 Female Ablutions</u>	Page No	Amount
1	EARTHWORKS	130	
2	CONCRETE, FORMWORK AND REINFORCEMENT	134	
3	MASONRY	138	
4	WATERPROOFING	140	
5	ROOF COVERINGS	142	
6	CARPENTRY AND JOINERY	145	
7	IRONMONGERY	149	
8	METALWORK	152	
9	PLASTERING	156	
10	PLUMBING AND DRAINAGE	166	
11	GLAZING	168	
12	PAINTWORK	171	
	Carried to Final Summary		R
	Section No. 5 F7 Female Ablutions Diatho Consulting (PTY) LTD		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be included in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p>The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "hard rock" or "soft rock".</p> <p>The nature of the ground is assumed to be gravel, therefore "earth", but possibly interspersed with "soft rock".</p> <p>The nature of the ground is assumed to be silty clay with loose river boulders varying in size up to approximately 450mm diameter, therefore "earth", but possibly interspersed with "hard rock".</p>			
Carried Forward		R	
<p>Section No. 6 FD7 - Female Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>			

Brought Forward	R
<p>Trial holes indicate that the nature of the ground is silty clay to a depth of approximately 500mm with fine to medium loose sandy material below, therefore "earth". The trial holes also indicate that the water table is at a maximum depth of approximately 1000mm.</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p><u>Subterranean water:</u></p> <p>No subterranean water is expected</p> <p>Should the Contractor however, encounter any subterranean water on the site, he shall immediately notify the Principal Agent thereof and submit recommendations for keeping the works free from subterranean water together with all costs involved therewith</p> <p><u>Excavation for working space in rock:</u></p> <p>Notwithstanding clause 10 measurement rule 27 of the Standard System of Measuring Building Work, excavation for working space in material of a more different character (e.g. soft or hard rock) will be measured in cubic metres to the extent executed and given as "extra over" bulk excavation or trench and hole excavation as the case may be</p> <p><u>Carting away of excavated material</u></p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p>	R
Carried Forward	R
<p>Section No. 6 FD7 - Female Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>	

Brought Forward				R
<u>Filling</u>				
Notwithstanding the reference to prescribed multiple handling in clause 1 page 10 of the Standard System (7th Edition, 2015) of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material				
<u>Testing:</u>				
<i>Prices for backfilling to trenches and holes only are to include for all necessary density tests in accordance with SANS 1200D</i>				

<u>EXCAVATIONS, FILLING, ETC</u>				
<u>EXCAVATIONS, ETC</u>				
<u>Excavation in earth not exceeding 2m deep:</u>				
1	Reduced levels under floors	m3	4	
2	Trenches	m3	11	
3	Trenches and holes for thickening under surface beds, etc	m3	3	
4	Pit	m3	30	
<u>Extra over trench and hole excavations in earth for excavation in:</u>				
5	Soft rock	m3	11	
6	Hard rock	m3	1	
<u>Extra over all excavations for carting away:</u>				
7	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	14	
Carried Forward				R
Section No. 6 FD7 - Female Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>Risk of collapse of excavations:</u>			
8	Sides of trench and hole excavations not exceeding 1,5m deep	m2	31
<u>Keeping excavations free of water:</u>			
9	Keeping excavations free of all water other than subterranean water		Item
<u>FILLING ETC</u>			
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 93% Mod AASHTO density:</u>			
10	Backfilling to trenches, holes, etc	m3	0.2
<u>G5 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>			
11	Under floors, steps, pavings, etc	m3	4
<u>Compaction of surfaces:</u>			
12	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	33
<u>Prescribed density tests on filling:</u>			
13	"Modified AASHTO Density" test	No	12
<u>SOIL POISONING</u>			
<u>Soil insecticide in accordance with SANS 5859:</u>			
14	Soil insecticide (protection against termites) applied as specified under floors, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	83
Carried Forward			R
Section No. 6 FD7 - Female Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD			

15	<p style="text-align: right;">Brought Forward</p> <p>To bottoms and sides of trenches, etc</p>	m2	17	R	
<p style="text-align: center;">Carried Forward to Summary of Section No. 6</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Cost of tests:</u></p> <p><u>Breeze concrete:</u></p> <p>Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated</p>			
<p>Carried Forward</p>		R	
<p>Section No. 6 FD7 - Female Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Lightweight concrete:</u></p> <p>Lightweight concrete shall have a density of 600kg/m³ for the top 50mm and 400kg/m³ for the remaining thickness. The minimum thickness at outlets, channels, etc shall be 50mm</p> <p><u>Waterproof concrete:</u></p> <p>"Waterproof concrete" shall have the same properties as normal concrete, but the following shall be modified to make the the concrete more water-tight:</p> <ol style="list-style-type: none"> 1. a cement/water ratio of minimum 1.9 and maximum 2.1 2. minimum OPC content of 300kg/m³ 3. Polypropolene micro fibres added to concrete at rate of 182 million per m³ <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself</p> <p>Formwork to soffits of solid slabs, etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described</p> <p>Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described</p> <p style="text-align: center;">-----</p>		<p>R</p>
<p style="text-align: center;">Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>		<p>R</p>

Brought Forward			R
<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
<u>15MPa/19mm concrete:</u>			
1	Surface blinding under footings and bases	m3	1
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
<u>30MPa/19mm concrete:</u>			
	Strip footings	m3	4
	Surface beds on waterproofing	m3	5
2	Surface beds in tank bottoms		
		m3	3
3	Aprons cast in panels to falls	m3	2
<u>TEST BLOCKS</u>			
4	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	3
<u>CONCRETE SUNDRIES</u>			
<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>			
5	Surface beds, slabs, etc	m2	25
<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>			
<u>Rough formwork to sides:</u>			
6	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	52
Carried Forward			R
Section No. 6 FD7 - Female Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD			

Brought Forward			R
<u>MOVEMENT JOINTS, ETC</u>			
<u>Expansion joints with 10mm softboard between vertical concrete and brick surfaces:</u>			
7	Not exceeding 300mm high to edges of surface beds	m	42
<u>Saw-cut joints:</u>			
8	6 x 10mm Saw-cut joints in top of concrete	m	63
<u>REINFORCEMENT (PROVISIONAL)</u>			
<u>Mild steel reinforcement to structural concrete work:</u>			
9	Mild steel bar reinforcement (8 to 40mm diameter bars)	t	0.10
<u>High tensile steel reinforcement to structural concrete work:</u>			
10	High tensile steel bar reinforcement (8 to 40mm diameter bars)	t	0.24
<u>Fabric reinforcement:</u>			
11	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	25
Carried Forward to Summary of Section No. 6			R
Section No. 6			
FD7 - Female Ablutions			
Bill No. 2			
CONCRETE, FORMWORK AND REINFORCEMENT			
Diatho Consulting (PTY) LTD			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>General:</u></p> <p>Non-load bearing brickwork is to be built to full height less 20mm gap next to the ceiling and is to be left for 14 days before grouting up in 1:3 cement mortar.</p> <p><u>Sizes in descriptions:</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p>			
<p>Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>		<p>R</p>	

	Brought Forward			R
	<p><u>Hollow walls:</u></p> <p>Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole</p> <p><u>Bagged and sealed walls:</u></p> <p>Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats bitumen emulsion waterproofing coating</p> <p><u>Face bricks :</u></p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>All face brickwork shall be regularly cleaned down as the work proceeds and shall be protected as necessary by an approved method</p> <p><u>Pointing:</u></p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include smooth floated square recessed, hollow recessed, weathered pointing, etc</p> <p style="text-align: center;">-----</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in class 1 mortar:</u></p>			
1	One brick walls	m2	13	
2	One brick walls in pit	m2	22	
	Carried Forward			R
	<p>Section No. 6 FD7 - Female Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
3	Half brick wall corbelling in pit	m	55
	<u>2,5mm Brickwork reinforcement:</u>		
4	150mm Wide reinforcement built in horizontally	m	38
	<u>FACE BRICKWORK</u>		
	<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>		
5	Extra over brickwork for face brickwork	m2	4
	<u>SUPERSTRUCTURE</u>		
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar in loadbearing walls etc:</u>		
6	One brick walls	m2	83
	<u>BRICKWORK SUNDRIES</u>		
	<u>Joint forming material in movement joints:</u>		
7	12mm Fibre board built in vertically through brick walls	m	66
	<u>2,5mm Brickwork reinforcement:</u>		
8	75mm Wide reinforcement built in horizontally	m	77
9	150mm Wide reinforcement built in horizontally	m	269
	<u>Prestressed fabricated concrete lintels, including necessary temporary supports:</u>		
10	110 x 75mm Lintels in lengths not exceeding 3m long	m	32
	<u>FACE BRICKWORK</u>		
	Carried Forward		
	Section No. 6 FD7 - Female Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD		
			R

Brought Forward			R
<p><u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u></p>			
11	Half brick wall faced on both sides	m2	26
12	Extra over brickwork for face brickwork	m2	167
13	Extra over brickwork for brick-on-edge header course lintel pointed on face and 120mm soffit	m	9
14	Fair raking cutting	m	7
<p><u>Brick-on-edge header course coping, sills, etc. of face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with recessed joints on all exposed faces</u></p>			
15	150mm Wide sills set sloping and slightly projecting	m	7
<p>Carried Forward to Summary of Section No. 6</p>			R
<p>Section No. 6 FD7 - Female Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.4</u></p> <p><u>WATERPROOFING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Waterproofing:</u></p> <p>Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets, etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs</p> <p style="text-align: center;">-----</p>			
<p>Carried Forward</p>		R	
<p>Section No. 6 FD7 - Female Ablutions Bill No. 4 WATERPROOFING Diatho Consulting (PTY) LTD</p>			

Brought Forward							
<u>DAMPPROOFING OF WALLS AND FLOORS</u>							
<u>One layer 375 micron embossed polyethylene dampproof course (SANS 952-1985 type B):</u>							
1	In walls	m2	310				R
2	In walls vertically at reveals	m2	4				
<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape:</u>							
3	Under surface beds	m2	25				
<u>JOINT SEALANTS ETC</u>							
<u>Two- part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>							
4	6 x 10mm In saw cut joints in floors	m	63				
<u>White silicone sealing compound including backing cord, bond breaker, primer, etc</u>							
5	6 x 10mm In expansion joints in floors, including raking out expansion joint filler as necessary [LI]	m	42				
Carried Forward to Summary of Section No. 6							
Section No. 6							
FD7 - Female Ablutions							
Bill No. 4							
WATERPROOFING							
Diatho Consulting (PTY) LTD							
							R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.5</u></p> <p><u>ROOF COVERINGS</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Profiled metal roof sheeting and accessories shall be supplied with a 10 year guarantee and be installed by an approved installer</p> <p>All fixing holes shall be drilled and not punched</p> <p>Roof covering accessories shall be manufactured from the same material as used for roof covering</p> <p style="text-align: center;">-----</p> <p><u>PROFILED METAL SHEETING AND ACCESSORIES</u></p>			
<p>Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>		<p>R</p>	

	Brought Forward			R
	<p><u>0,6 mm "Klip-Lok 406" or similar approved light industrial Z275 spelter galvanised steel sheeting, with "Classicoat" finish one side and half coat "Classicoat Grey" other side, and accessories fixed to timber purlins or rails at approximately 1500mm centres:</u></p>			
1	Roof coverings with pitch not exceeding 25 degrees	m2	43	
	<p><u>Accessories:</u></p>			
2	Apex flashings 462mm girth	m	20	
	<p><u>ROOF AND WALL INSULATION</u></p> <p><u>"Sisalation 405" or similar approved residential grade aluminium foil based insulation:</u></p>			
3	Insulation sheeting laid taut over purlins at approximately 1000mm centres and fixed concurrent with roof covering with minimum 150mm stapled laps, including galvanised steel straining wires at not exceeding 400mm centres and double-sided tape at edges where required	m2	43	
<p>Carried Forward to Summary of Section No. 6</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>				R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing:</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given separately elsewhere</p> <p><u>Joinery:</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			R

Brought Forward				R
Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts				
<u>Particle board</u>				
All particle board shall comply with SANS 50312 having the required marking as per SANS 50312/EN 312				
<u>Decorative thermosetting plastic laminate covering:</u>				
Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish				
<u>Sizes:</u>				
Sizes are nominal and the Contractor shall make allowance in his prices for minor variances in stated finished sizes of timber doors, door members, door frames, architraves, etc				
<u>Prices</u>				
Prices for all joinery work are to include for general framing, housing and notching, arris rounded angles, glueing, blocking, planting on, screwing, adhesives, dowels, pellets, cross tongues, screws and nails and setting up complete and also for all square cutting and waste. Tops shall be secured with metal or hardwood buttons.				

<u>ROOFS, ETC</u>				
<u>Sawn softwood grade 5:</u>				
1 38 x 114mm Wall plates bolted	m		18	
2 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m		58	
Carried Forward				R
Section No. 6 FD7 - Female Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD				

Brought Forward				R
3	50 x 76mm Purlins	m	60	
<u>EAVES, VERGES, ETC</u>				
<u>Medium density plain fibre-cement fascias and barge boards:</u>				
4	19 x 235mm Fascias and barge boards, including aluminium H-profile jointing strips	m	30	
<u>DOORS, ETC</u>				
<u>Wrought meranti doors hung to steel frames:</u>				
5	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding including 150mm undercut (D2)	No	3	
6	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1)	No	7	
Carried Forward to Summary of Section No. 6				R
Section No. 6				
FD7 - Female Ablutions				
Bill No. 6				
CARPENTRY AND JOINERY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.7</u></p> <p><u>IRONMONGERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
	<p><u>Locks:</u></p> <p>Notwithstanding Clause 2, Item 3 of the "Ironmongery" trade of the Standard System (7th Edition, 2015) of Measuring Building Work, descriptions of locks shall be deemed to include two keys per lock</p> <p><u>Finishes to ironmongery:</u></p> <p>Where applicable, finishes to ironmongery are indicated by suffixes in accordance with the following list:</p> <p>BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AN Anodised natural AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded BBS Brushed stainless steel</p> <p style="text-align: center;">-----</p> <p><u>CATCHES, CABIN HOOKS, ETC</u></p> <p>1 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged</p> <p><u>LOCKS</u></p> <p><u>"Union Assa Abloy" or similar approved:</u></p> <p>2 50mm Brass padlock</p> <p>3 Four lever lockset</p>	No	8	
	Carried Forward			R
	<p>Section No. 6 FD7 - Female Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

Brought Forward				R
4	"Ref. CZ80941SC" Indicator bolt	No	7	
	<u>HANDLES</u>			
	<u>"Union Assa Abloy" or similar approved:</u>			
5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres	Pairs	3.0	
	<u>PUSH PLATES AND KICK PLATES</u>			
	<u>"Union Assa Abloy" or similar approved:</u>			
	<u>1.2mm Thick satin finished "Union" stainless steel plates countersunk screwed along edges at not exceeding 200mm centres</u>			
6	200 x 800mm Type "SS5089-200W" kicking plate	No	7	
	<u>DOOR CLOSERS</u>			
	<u>"Dorma" or similar approved:</u>			
7	"Dorma" TS73N/EN3-4 parallel arm door closer delayed closing-push side fitting	No		
	<u>LETTERS, NAMEPLATES, ETC</u>			
	<u>"Dorma" or similar approved:</u>			
8	DSS-131 Engraved "Female" information sign, plugged	No	2	
9	DSS-131 Engraved "Emergency Exit" information sign, plugged	No	1	
	<u>SUNDRIES</u>			
10	25mm Diameter wall mounted door stop plugged	No	9	
	Carried Forward			R
	Section No. 6 FD7 - Female Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD			

	Brought Forward				
	<u>BATHROOM FITTINGS</u>				R
	<u>"Vaal Paragon" or similar approved</u>				
11	32mm Type 9 back grab rail 800mm long plugged	No	1		
12	32mm Type 8 side grab rail 900mm girth plugged	No	1		
	<u>"Kimberley-Clark" or similar approved:</u>				
13	"Ref. SQ2 code 405607B" white lockable toilet roll holder	No	8		
14	Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc	No	7		
Carried Forward to Summary of Section No. 6					
Section No. 6					
FD7 - Female Ablutions					
Bill No. 7					
IRONMONGERY					
Diatho Consulting (PTY) LTD					
					R

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.8</u></p> <p><u>METALWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions of bolts, anchors, etc:</u></p> <p>Descriptions of bolts shall be deemed to include nuts and washers</p> <p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete</p> <p>Items described as "holed for bolt(s)" shall be deemed to exclude the bolts, unless otherwise described</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres</p>			
	Carried Forward		R	
	<p>Section No. 6 FD7 - Female Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>			

Brought Forward			R	
<p><u>Fixing:</u></p> <p>Unless otherwise described, descriptions of items shall be deemed to include for fixing to brickwork or concrete</p> <p>Where items are described as "bolted", the bolts are measured elsewhere as stated in clause N.7 of the Model Preambles</p> <p><u>References:</u></p> <p>References in descriptions of windows, doors, gates, etc refer to the respective types of windows, doors, etc detailed in the Architect's window schedules numbered</p> <ul style="list-style-type: none"> • 21111/FSPS/S005 • T-2003 • T-2004 • T-2005 <p>and bound into the back of these bills of quantities</p> <p>Tenderers are to price the following items in conjunction with the above Architect's drawings, etc and no claim arising from brevity of descriptions in these bills of quantities, of items shown on the Architect's drawings, etc shall be entertained</p> <p style="text-align: center;">-----</p>				
Carried Forward			R	
<p>Section No. 6 FD7 - Female Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>				

Brought Forward									
<u>STEEL GATES, SCREENS, ETC</u>									
<u>Welded screens and gates, to brickwalls:</u>									
1	Single gate and frame size to fit standard door, size 813 x 2032mm high	No	3						
<u>PRESSED STEEL DOOR FRAMES</u>									
<u>1,6mm Double rebated frames suitable for half brick walls:</u>									
2	Frame for door size 813 x 2032mm high	No	8						
<u>1,6mm Double rebated frames suitable for one brick walls:</u>									
3	Frame for door size 813 x 2032mm high	No	3						
<u>STEEL WINDOWS, DOORS, ETC</u>									
<u>Standard windows:</u>									
4	Window type NE1, 533 x 654mm high (N1)	No	8						
5	Window type NE7, 1022 x 654mm high (N2)	No	4						
Carried Forward to Summary of Section No. 6									
Section No. 6									
FD7 - Female Ablutions									
Bill No. 8									
METALWORK									
Diatho Consulting (PTY) LTD									

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.9</u></p> <p><u>PLASTERING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Moisture tests:</u></p> <p>Before any finishes, coverings, etc are applied to screeds, plastering, etc or any other in-situ finish, moisture tests are to be carried out to the complete satisfaction of the Project Manager to ensure that these surfaces have the correct moisture content for the finish to be applied</p> <p><u>Labours, etc</u></p> <p>Labours such as fair, rounded and chamfered edges, trowel cuts, throats, V-joints, angles, etc shall be deemed to be included in the descriptions</p>			
Carried Forward		R	
<p>Section No. 6 FD7 - Female Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Sample Panels</u></p> <p>A sample panel size 1m x1m, of each of the various plaster type wall and floor finishes in this contract, shall be prepared for the approval of the Project Manager and the cost of the sample panel(s) shall be deemed to be included in the overall costs of the <u>relevant</u> wall and floor finishes</p> <p><u>GRANOLITHIC</u></p> <p><u>Method:</u></p> <p>The method to be used shall be either the monolithic method or the bonded method</p> <p><u>Preparation:</u></p> <p>For granolithic applied monolithically, the concrete floor shall be swept clean after bleeding of the concrete has ceased and the slab has begun to stiffen; any remaining bleed water shall be removed and the granolithic applied immediately thereafter. For granolithic to be bonded to the floor slab after it has hardened, the slab surface shall be hacked (preferably by mechanical means) until all laitance, dirt, oil, etc is dislodged and swept clean of all loose matter. The slab shall then be wetted and kept damp for at least six hours before applying the granolithic</p> <p><u>Mix:</u></p> <p>Unless otherwise described, granolithic shall attain a compressive strength of at least 41MPa. The coarse aggregate shall comply with SANS 1083 and shall generally be capable of passing a 10mm mesh sieve. Where the thickness of the granolithic exceeds 25mm, the size of the coarse aggregate shall be increased to the maximum size compatible with the thickness of the granolithic</p>				R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>				R

<p style="text-align: center;">Brought Forward</p> <p><u>Panels:</u></p> <p>Granolithic shall be laid in panels not exceeding 14m² for monolithic finishes, not exceeding 9,5m² for bonded finishes and not exceeding 6m² for all external granolithic. Wherever possible, panels shall be square but at no time should the length of the panel exceed 1,5 times its width</p> <p>Where possible joints between panels shall be positioned over joints in the floor slab and shall be at least 3mm wide through the full thickness of the finish, separated by strips of wood or fibreboard and finished with V-joints</p> <p><u>Laying:</u></p> <p>Monolithic granolithic shall be applied to the partially set slab and thoroughly compacted and lightly wood floated to the required levels</p> <p>Bonded granolithic shall be applied to the slab after applying a 1:1 sand-and-cement slurry brushed over the surface and allowed to partially set before applying the granolithic. The granolithic shall be thoroughly compacted and lightly wood floated to the required levels</p> <p>After wood floating, the monolithic and bonded granolithic shall remain undisturbed until bleeding has ceased and the surface has stiffened. Any remaining bleed water and laitance shall then be removed and the surface steel trowelled or power floated</p> <p><u>Curing, seasoning and protection:</u></p> <p>Granolithic shall be covered with clean hessian with waterproof building foil over and kept wet for at least seven days after laying</p> <p><u>Colour:</u></p> <p>Coloured granolithic shall be tinted with an approved colouring pigment mixed into a true and even colour</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>	R	

	Brought Forward			R
	<p><u>TINTED WHITE CEMENT SCREEDS</u></p> <p>Tinted screed shall be composed of one bag White Portland Cement and two wheelbarrows "Malmesbury" sand. Surfaces shall be finished with a steel trowel to leave a smooth finish and coated with two coats "Earthcote S.I. Floorcote" two-pack polyurethane floor sealer applied as per the manufacturer's recommendations</p> <p>NOTE: Tinted screeds are to be strengthened with "Primal Eccos" acrylic polymer (15% of the water volume is to be substituted with the acrylic polymer during the mixing process)</p> <p>Coarse sand is to be used for these screeds</p> <p>All tinting, finishing, strengthening, etc are to be mixed, applied, etc strictly in accordance with the manufacturer's instructions</p> <p><u>CEMENT PLASTER</u></p> <p>Unless otherwise described, cement plaster shall be taken to mean Class 1 cement plaster i.e. 1:4 cement:sand plaster (common cement)</p> <p style="text-align: center;">-----</p> <p><u>CEMENT SCREEDS TO CONCRETE</u></p> <p><u>Cement screeds steel trowelled, on concrete:</u></p>			
1	30mm Thick to floors	m2	25	
	<p><u>FLOOR AND WALL SEALERS</u></p> <p><u>Minimum two coats approved epoxy coat, on concrete:</u></p>			
2	On screed	m2	25	
	<p>Carried Forward to Summary of Section No. 6</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			R

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.10</u></p> <p><u>PLUMBING AND DRAINAGE</u> <u>(PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Wire gratings:</u></p> <p>Descriptions of gutter outlets, etc shall be deemed to include wire balloon gratings</p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p>			
	Carried Forward		R	
	<p>Section No. 6 FD7 - Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>Stainless steel basins, sinks, wash troughs, urinals, etc:</u></p> <p>Stainless steel for economy basins, domestic sinks and worktops shall be Type 430 (17/0)</p> <p>Stainless steel for urinals, basins, quality sinks, wash troughs, institutional equipment, etc shall be Type 304 (18/8)</p> <p>Stainless steel for laboratory sinks, photographic equipment, etc shall be Type 316 (18/8)</p> <p>Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable</p> <p><u>Sealing of edges:</u></p> <p>Outer edges of sinks, basins, baths, urinals, etc are to be sealed against adjacent surfaces with approved mildew resistant silicone sealant and prices must include therefor</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

<p style="text-align: center;">Brought Forward</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPE) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claims for extra bushes, reducers, etc will be entertained</p> <p><u>Fixing of pipes:</u></p> <p>Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls, etc casting in, building in or suspending not exceeding 1m below suspension level</p> <p><u>Paper wrapping to pipes:</u></p> <p>Pipes chased into brickwork must be wrapped with two layers of stout brown paper tied with wire. Rates are to include for wrapping around joints and fittings</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SANS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SANS 1200L : Medium-pressure pipelines SANS 1200LD : Sewers SANS 1200LE : Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SANS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SANS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

Brought Forward		R
<p><u>General:</u></p> <p>Descriptions of cast iron roof outlets shall be deemed to include joints to pipes and casting into concrete (adaptors for joints to PVC pipes, etc are given separately)</p> <p>Descriptions of overflow pipes where measured in number, shall be deemed to include joints to cisterns and splay cut ends</p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site</p> <p>Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)</p> <p>Descriptions of WC pans, slop hoppers, etc shall be deemed to include for joints to soil pipes (pan connectors are separately measured) and shall have straight or side outlets and "P" or "S" traps as necessary</p> <p>Description of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.</p> <p><u>As-built drawings:</u></p> <p>Where required, the Contractor shall prepare an updated set of as-built drawings. At completion of the contract the Contractor shall hand these drawings to the Project Manager for reproducing onto the originals for handing over to the Employer (provision for allowance of as-built drawings elsewhere)</p>		
Carried Forward		R
<p>Section No. 6 FD7 - Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		

Brought Forward			R
<u>Proprietary items:</u>			
Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items			
Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.			
Prices are to be based on the specific products/articles specified.			
On request, returnable samples are to be provided to the Project Manager for consideration			

<u>RAINWATER DISPOSAL</u>			
<u>0,6mm Galvanised sheet steel gutters and rainwater pipes with powder coated finish on outside to match roof sheeting colour:</u>			
1	150 x150mm Box gutters	m	10
2	100 x 75mm Rainwater pipes	m	5
3	Extra over gutter for stopped end	No	2
4	Extra over gutter for outlet for 100 x 75mm pipe	No	2
5	Extra over rainwater pipe for bend	No	2
6	Extra over rainwater pipe for shoe	No	2
7	Extra over rainwater pipe for eaves or plinth offset	No	2
Carried Forward			R
Section No. 6 FD7 - Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Brought Forward				R
<u>ENVIRO-LOO TOILET SYSTEMS</u>				
<u>Supply and install "Enviroloo systems" or similar approved:</u>				
8	"Enviro Loo System FG-1040 STDCA/A Standard" strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvered inlets (PL.1), drying plate (PL.2), two x air inlets (PL.3), toilet pan, seat and lid (PL.4), 3500mm long outlet vent pipe (PL.5), ventilation extraction unit (PL.6) fixed to wall with vent wall bracket (PL.7), 1 bag mounting screws and organic starter, enzyme and toilet cleaner (PL.8) including all necessary interconnector piping between multiple tanks, emergency outlet piping, etc	No	7	
<u>SANITARY FITTINGS</u>				
<u>"Vaal" or similar approved:</u>				
9	455 x 290mm "Hibiscus" 7050 wash hand basin bolted to wall	No	6	
10	"Pearl Paraplegic" 7300SC paraplegic WC suite with lid, fittings, purpose made CP side flush lever and purpose made double flap white epoxy painted wooden seat	No	1	
<u>Precast concrete wash trough:</u>				
<u>TRAPS, ETC</u>				
<u>uPVC:</u>				
<u>"Cobra Watertech" or similar approved:</u>				
11	50mm Code 365 CP bottle trap	No	6	
<u>TAPS, VALVES, ETC</u>				
<u>"Cobra Watertech" or similar approved:</u>				
12	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No	14	
Carried Forward				R
Section No. 6 FD7 - Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

Brought Forward			R
13	15mm Code FPT2A1RO-OGP01 "Roma" basin tap with waste union	No	6
14	15mm Code 503-21CP elbow action pillar tap	No	1
<u>SANITARY PLUMBING</u>			
<u>uPVC pipes:</u>			
15	50mm Pipes	m	30
16	110mm Pipes	m	40
17	50mm Diameter pipe laid in and including trenches not exceeding 1m deep	m	39
18	Ditto, but 110mm diameter	m	52
<u>Extra over uPVC pipes for fittings:</u>			
19	50mm Bend	No	12
20	50mm Junction	No	12
21	50mm Junction with cleaning eye and lid	No	12
22	110mm Straight pan connector	No	8
23	110mm Bend	No	16
24	110mm Junction	No	16
25	110mm Reducing junction	No	24
26	110mm Access bend	No	8
27	110mm Double junction	No	24
28	110mm "GI Two-way" vent valve	No	8
Carried Forward			R
Section No. 6 FD7 - Female Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

	Brought Forward			R
	<u>Testing:</u>			
29	Testing waste pipe system		Item	
	<u>WATER SUPPLIES</u>			
	<u>Class 1 copper pipes with capillary couplings:</u>			
30	15mm Pipe fixed to walls, in chases, etc	m	42	
31	Ditto, but 22mm diameter	m	70	
	<u>Extra over Class 1 copper pipes for capillary fittings:</u>			
32	15mm Fittings	No	70	
33	22mm Fittings	No	70	
	<u>Testing:</u>			
34	Testing water pipe system		Item	
Carried Forward to Summary of Section No. 6				R
Section No. 6				
FD7 - Female Ablutions				
Bill No. 10				
PLUMBING AND DRAINAGE				
Diatho Consulting (PTY) LTD				

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.11</u></p> <p><u>GLAZING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Float glass:</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass:</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p style="text-align: center;">-----</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p>			
	Carried Forward		R	
	<p>Section No. 6 FD7 - Female Ablutions Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>			

		Brought Forward		R
	<u>6,38mm Obscure safety glass:</u>			
1	Panes not exceeding 0,1m ²	m2	5	
	<u>TOPS, SHELVES, DOORS, MIRRORS, ETC</u>			
	<u>Silvered float glass copper backed mirrors with polished edges holed for and fixed with chromium plated dome capped mirror screws with foam backing strip all round to plugs in walls</u>			
2	6mm "GG" quality polished glass mirror 450 x 800mm high with polished edges fixed to wall with four 35mm round nose chromium plated mirror screws	No	6	
Carried Forward to Summary of Section No. 6				R
Section No. 6				
FD7 - Female Ablutions				
Bill No. 11				
GLAZING				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 6</u></p> <p><u>BILL NO.12</u></p> <p><u>PAINTWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and minor cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces:</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p style="text-align: right;">Carried Forward</p> <p>Section No. 6 FD7 - Female Ablutions Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
	<p><u>Previously painted wood surfaces:</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with "Plascon", etc specifications, unless otherwise described</p> <p><u>COLOURS</u></p> <p>When staining timber, the resultant colour or shade must be to the complete satisfaction of the Project Manager before any overcoating or preservative is applied</p> <p>Paintwork is classified in the following different colour groups: "White", "Pastel", "Deep" and "Transparent" in accordance with the "Natural Colour System" (NCS) adopted by the SA National Standards Unless otherwise described, all paintwork shall be deemed to be classified in the "White" colour group</p> <p style="text-align: center;">-----</p> <p><u>PAINTWORK, ETC TO NEW WORK</u></p> <p><u>ON FIBRE-CEMENT BOARD SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use, on:</u></p>			
1	Fascias and barge boards, including priming metal jointing strips	m2	8	
	<p><u>METAL SURFACES WITH</u></p>			
	Carried Forward			R
	<p>Section No. 6 FD7 - Female Ablutions Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<u>One coat alkyd based zinc phosphate primer and two coats premium quality polyurethane enamel paint, on steel:</u>			
2	Door frames	m2	17	
3	Windows	m2	9	
4	Gates, grilles, burglar screens, balustrades, etc (both sides measured over the full flat area)	m2	7	
5	Extra over for paintwork in the "Deep" colour group	m2	33	
	<u>ON WOOD SURFACES</u>			
	<u>One coat primer, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on:</u>			
6	Doors	m2	89	
7	Roof timbers at eaves and verges	m2	38	
8	Extra over for paintwork in the "Deep" colour group	m2	70	
	Carried Forward to Summary of Section No. 6			R
	Section No. 6			
	FD7 - Female Ablutions			
	Bill No. 12			
	PAINTWORK			
	Diatho Consulting (PTY) LTD			

Bill No	<u>SECTION SUMMARY - FD7 - Female Ablutions</u>	Page No	Amount
1	EARTHWORKS	177	
2	CONCRETE, FORMWORK AND REINFORCEMENT	181	
3	MASONRY	185	
4	WATERPROOFING	187	
5	ROOF COVERINGS	189	
6	CARPENTRY AND JOINERY	192	
7	IRONMONGERY	196	
8	METALWORK	199	
9	PLASTERING	203	
10	PLUMBING AND DRAINAGE	213	
11	GLAZING	215	
12	PAINTWORK	218	
	Carried to Final Summary		R
	Section No. 6 FD7 - Female Ablutions Diatho Consulting (PTY) LTD		

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be included in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p>The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "hard rock" or "soft rock".</p> <p>The nature of the ground is assumed to be gravel, therefore "earth", but possibly interspersed with "soft rock".</p> <p>The nature of the ground is assumed to be silty clay with loose river boulders varying in size up to approximately 450mm diameter, therefore "earth", but possibly interspersed with "hard rock".</p>			
	Carried Forward		R	
	<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>			

Brought Forward	R
<p>Trial holes indicate that the nature of the ground is silty clay to a depth of approximately 500mm with fine to medium loose sandy material below, therefore "earth". The trial holes also indicate that the water table is at a maximum depth of approximately 1000mm.</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p><u>Subterranean water:</u></p> <p>No subterranean water is expected</p> <p>Should the Contractor however, encounter any subterranean water on the site, he shall immediately notify the Principal Agent thereof and submit recommendations for keeping the works free from subterranean water together with all costs involved therewith</p> <p><u>Excavation for working space in rock:</u></p> <p>Notwithstanding clause 10 measurement rule 27 of the Standard System of Measuring Building Work, excavation for working space in material of a more different character (e.g. soft or hard rock) will be measured in cubic metres to the extent executed and given as "extra over" bulk excavation or trench and hole excavation as the case may be</p> <p><u>Carting away of excavated material</u></p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p>	R
Carried Forward	R
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>	

Brought Forward				R
<u>Filling</u>				
Notwithstanding the reference to prescribed multiple handling in clause 1 page 10 of the Standard System (7th Edition, 2015) of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material				
<u>Testing:</u>				
<i>Prices for backfilling to trenches and holes only are to include for all necessary density tests in accordance with SANS 1200D</i>				

<u>EXCAVATIONS, FILLING, ETC</u>				
<u>EXCAVATIONS, ETC</u>				
<u>Excavation in earth not exceeding 2m deep:</u>				
1	Reduced levels under floors	m3	7	
2	Trenches	m3	12	
3	Trenches and holes for thickening under surface beds, etc	m3	3	
<u>Extra over trench and hole excavations in earth for excavation in:</u>				
4	Soft rock	m3	1	
5	Hard rock	m3	1	
<u>Extra over all excavations for carting away:</u>				
6	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	17	
Carried Forward				R
Section No. 7 SFD8 - Female Educator Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>Risk of collapse of excavations:</u>			
7	Sides of trench and hole excavations not exceeding 1,5m deep	m2	34
<u>Keeping excavations free of water:</u>			
8	Keeping excavations free of all water other than subterranean water		Item
<u>FILLING ETC</u>			
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 93% Mod AASHTO density:</u>			
9	Backfilling to trenches, holes, etc	m3	4
<u>G5 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>			
10	Under floors, steps, pavings, etc	m3	7
<u>Compaction of surfaces:</u>			
11	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	44
<u>Prescribed density tests on filling:</u>			
12	"Modified AASHTO Density" test	No	15
<u>SOIL POISONING</u>			
<u>Soil insecticide in accordance with SANS 5859:</u>			
13	Soil insecticide (protection against termites) applied as specified under floors, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	44
Carried Forward			R
Section No. 7 SFD8 - Female Educator Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD			

Brought Forward

R

14 To bottoms and sides of trenches, etc

m2

53

Carried Forward to Summary of Section No. 7

Section No. 7
 SFD8 - Female Educator Ablutions
 Bill No. 1
 EARTHWORKS
Diatho Consulting (PTY) LTD

R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Cost of tests:</u></p> <p><u>Breeze concrete:</u></p> <p>Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>			R

<p style="text-align: center;">Brought Forward</p> <p><u>Lightweight concrete:</u></p> <p>Lightweight concrete shall have a density of 600kg/m³ for the top 50mm and 400kg/m³ for the remaining thickness. The minimum thickness at outlets, channels, etc shall be 50mm</p> <p><u>Waterproof concrete:</u></p> <p>"Waterproof concrete" shall have the same properties as normal concrete, but the following shall be modified to make the the concrete more water-tight:</p> <ol style="list-style-type: none"> 1. a cement/water ratio of minimum 1.9 and maximum 2.1 2. minimum OPC content of 300kg/m³ 3. Polypropolene micro fibres added to concrete at rate of 182 million per m³ <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself</p> <p>Formwork to soffits of solid slabs, etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described</p> <p>Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described</p> <p style="text-align: center;">-----</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>	R	

Brought Forward				R
<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>15MPa/19mm concrete:</u>				
1	Surface blinding under footings and bases	m3	2	
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>30MPa/19mm concrete:</u>				
	Strip footings	m3	5	
	Surface beds on waterproofing	m3	8	
<u>TEST BLOCKS</u>				
2	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	5	
<u>CONCRETE SUNDRIES</u>				
<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>				
3	Surface beds, slabs, etc	m2	44	
<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>				
<u>Rough formwork to sides:</u>				
4	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	56	
<u>MOVEMENT JOINTS, ETC</u>				
<u>Expansion joints with 10mm softboard between vertical concrete and brick surfaces:</u>				
5	Not exceeding 300mm high to edges of surface beds	m	57	
Carried Forward				R
Section No. 7 SFD8 - Female Educator Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD				

Brought Forward							
	<u>Saw-cut joints:</u>						R
6	6 x 10mm Saw-cut joints in top of concrete	m	68				
	<u>REINFORCEMENT (PROVISIONAL)</u>						
	<u>Mild steel reinforcement to structural concrete work:</u>						
7	Mild steel bar reinforcement (8 to 40mm diameter bars)	t	0.11				
	<u>High tensile steel reinforcement to structural concrete work:</u>						
8	High tensile steel bar reinforcement (8 to 40mm diameter bars)	t	0.25				
	<u>Fabric reinforcement:</u>						
9	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	44				
Carried Forward to Summary of Section No. 7							R
Section No. 7							
SFD8 - Female Educator Ablutions							
Bill No. 2							
CONCRETE, FORMWORK AND REINFORCEMENT							
Diatho Consulting (PTY) LTD							

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>General:</u></p> <p>Non-load bearing brickwork is to be built to full height less 20mm gap next to the ceiling and is to be left for 14 days before grouting up in 1:3 cement mortar.</p> <p><u>Sizes in descriptions:</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p>			
<p>Carried Forward</p>		R	
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>Hollow walls:</u></p> <p>Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole</p> <p><u>Bagged and sealed walls:</u></p> <p>Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats bitumen emulsion waterproofing coating</p> <p><u>Face bricks :</u></p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>All face brickwork shall be regularly cleaned down as the work proceeds and shall be protected as necessary by an approved method</p> <p><u>Pointing:</u></p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include smooth floated square recessed, hollow recessed, weathered pointing, etc</p> <p style="text-align: center;">-----</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in class 1 mortar:</u></p>			
1	One brick walls	m2	14	
	<p><u>2,5mm Brickwork reinforcement:</u></p>			
2	150mm Wide reinforcement built in horizontally	m	41	
	Carried Forward			R
	<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
<u>FACE BRICKWORK</u>			
<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
3	Extra over brickwork for face brickwork	m2	5
<u>SUPERSTRUCTURE</u>			
<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar in loadbearing walls etc:</u>			
4	One brick walls	m2	83
<u>BRICKWORK SUNDRIES</u>			
<u>Joint forming material in movement joints:</u>			
5	12mm Fibre board built in vertically through brick walls	m	68
<u>2,5mm Brickwork reinforcement:</u>			
6	75mm Wide reinforcement built in horizontally	m	97
7	150mm Wide reinforcement built in horizontally	m	279
<u>Prestressed fabricated concrete lintels, including necessary temporary supports:</u>			
8	110 x 75mm Lintels in lengths not exceeding 3m long	m	56
<u>FACE BRICKWORK</u>			
<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
9	Half brick wall faced on both sides	m2	33
10	Extra over brickwork for face brickwork	m2	148
Carried Forward			R
Section No. 7 SFD8 - Female Educator Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD			

	Brought Forward				R
11	Extra over brickwork for brick-on-edge header course lintel pointed on face and 120mm soffit	m	14		
12	Fair raking cutting	m	10		
	<u>Brick-on-edge header course coping, sills, etc. of face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with recessed joints on all exposed faces</u>				
13	150mm Wide sills set sloping and slightly projecting	m	13		
Carried Forward to Summary of Section No. 7					R
Section No. 7 SFD8 - Female Educator Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.4</u></p> <p><u>WATERPROOFING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Waterproofing:</u></p> <p>Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets, etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs</p> <p style="text-align: center;">-----</p>			
<p>Carried Forward</p>		R	
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 4 WATERPROOFING Diatho Consulting (PTY) LTD</p>			

Brought Forward							
<u>DAMPPROOFING OF WALLS AND FLOORS</u>							
<u>One layer 375 micron embossed polyethylene dampproof course (SANS 952-1985 type B):</u>							
1	In walls	m2	338				
2	In walls vertically at reveals	m2	4				
<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape:</u>							
3	Under surface beds	m2	53				
<u>JOINT SEALANTS ETC</u>							
<u>Two- part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>							
4	6 x 10mm In saw cut joints in floors	m	68				
<u>White silicone sealing compound including backing cord, bond breaker, primer, etc</u>							
5	6 x 10mm In expansion joints in floors, including raking out expansion joint filler as necessary [LI]	m	57				
Carried Forward to Summary of Section No. 7							
Section No. 7							
SFD8 - Female Educator Ablutions							
Bill No. 4							
WATERPROOFING							
Diatho Consulting (PTY) LTD							
							R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.5</u></p> <p><u>ROOF COVERINGS</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Profiled metal roof sheeting and accessories shall be supplied with a 10 year guarantee and be installed by an approved installer</p> <p>All fixing holes shall be drilled and not punched</p> <p>Roof covering accessories shall be manufactured from the same material as used for roof covering</p> <p style="text-align: center;">-----</p> <p><u>PROFILED METAL SHEETING AND ACCESSORIES</u></p>			
Carried Forward		R	
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
<p><u>0,6 mm "Klip-Lok 406" or similar approved light industrial Z275 spelter galvanised steel sheeting, with "Classicoat" finish one side and half coat "Classicoat Grey" other side, and accessories fixed to timber purlins or rails at approximately 1500mm centres:</u></p>			
1	Roof coverings with pitch not exceeding 25 degrees	m2	41
<p><u>Accessories:</u></p>			
2	Apex flashings 462mm girth	m	22
<p><u>ROOF AND WALL INSULATION</u></p>			
<p><u>"Sisalation 405" or similar approved residential grade aluminium foil based insulation:</u></p>			
3	Insulation sheeting laid taut over purlins at approximately 1000mm centres and fixed concurrent with roof covering with minimum 150mm stapled laps, including galvanised steel straining wires at not exceeding 400mm centres and double-sided tape at edges where required	m2	41
<p>Carried Forward to Summary of Section No. 7</p>			R
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing:</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given separately elsewhere</p> <p><u>Joinery:</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p>			
Carried Forward		R	
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			

Brought Forward				R
Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts				
<u>Particle board</u>				
All particle board shall comply with SANS 50312 having the required marking as per SANS 50312/EN 312				
<u>Decorative thermosetting plastic laminate covering:</u>				
Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish				
<u>Sizes:</u>				
Sizes are nominal and the Contractor shall make allowance in his prices for minor variances in stated finished sizes of timber doors, door members, door frames, architraves, etc				
<u>Prices</u>				
Prices for all joinery work are to include for general framing, housing and notching, arris rounded angles, glueing, blocking, planting on, screwing, adhesives, dowels, pellets, cross tongues, screws and nails and setting up complete and also for all square cutting and waste. Tops shall be secured with metal or hardwood buttons.				

<u>ROOFS, ETC</u>				
<u>Sawn softwood grade 5:</u>				
1 38 x 114mm Wall plates bolted	m	18		
2 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m	58		
Carried Forward				R
Section No. 7 SFD8 - Female Educator Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD				

Brought Forward				R
3	50 x 76mm Purlins	m	60	
<u>EAVES, VERGES, ETC</u>				
<u>Medium density plain fibre-cement fascias and barge boards:</u>				
4	19 x 235mm Fascias and barge boards, including aluminium H-profile jointing strips	m	32	
<u>DOORS, ETC</u>				
<u>Wrought meranti doors hung to steel frames:</u>				
5	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding including 150mm undercut (D2)	No	8	
6	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1)	No	3	
Carried Forward to Summary of Section No. 7				R
Section No. 7				
SFD8 - Female Educator Ablutions				
Bill No. 6				
CARPENTRY AND JOINERY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.7</u></p> <p><u>IRONMONGERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p>			
<p>Carried Forward</p>		R	
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

Brought Forward				R
<u>Locks:</u>				
Notwithstanding Clause 2, Item 3 of the "Ironmongery" trade of the Standard System (7th Edition, 2015) of Measuring Building Work, descriptions of locks shall be deemed to include two keys per lock				
<u>Finishes to ironmongery:</u>				
Where applicable, finishes to ironmongery are indicated by suffixes in accordance with the following list:				
BS Satin bronze lacquered				
CH Chromium plated				
SC Satin chromium plated				
SE Silver enamelled				
GE Grey enamelled				
AN Anodised natural				
AS Anodised silver				
AB Anodised bronze				
AG Anodised gold				
ABL Anodised black				
PB Polished brass				
PL Polished and lacquered				
PT Epoxy coated				
SD Sanded				
BBS Brushed stainless steel				

<u>CATCHES, CABIN HOOKS, ETC</u>				
1	150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	9	
<u>LOCKS</u>				
<u>"Union Assa Abloy" or similar approved:</u>				
2	50mm Brass padlock	No	3	
3	Four lever lockset	No	3	
Carried Forward				R
Section No. 7 SFD8 - Female Educator Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD				

Brought Forward				R
4	"Ref. CZ80941SC" Indicator bolt	No	8	
	<u>HANDLES</u>			
	<u>"Union Assa Abloy" or similar approved:</u>			
5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres	Pairs	3.0	
	<u>PUSH PLATES AND KICK PLATES</u>			
	<u>"Union Assa Abloy" or similar approved:</u>			
	<u>1.2mm Thick satin finished "Union" stainless steel plates countersunk screwed along edges at not exceeding 200mm centres</u>			
6	200 x 800mm Type "SS5089-200W" kicking plate	No	20	
	<u>LETTERS, NAMEPLATES, ETC</u>			
	<u>"Dorma" or similar approved:</u>			
7	DSS-131 Engraved "Female" information sign, plugged	No	2	
8	DSS-131 Engraved "Emergency Exit" information sign, plugged	No	1	
	<u>SUNDRIES</u>			
9	25mm Diameter wall mounted door stop plugged	No	10	
	<u>BATHROOM FITTINGS</u>			
	<u>"Vaal Paragon" or similar approved</u>			
10	32mm Type 9 back grab rail 800mm long plugged	No	1	
	Carried Forward			R
	Section No. 7 SFD8 - Female Educator Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD			

	Brought Forward				
11	32mm Type 8 side grab rail 900mm girth plugged	No	1		R
	<u>"Kimberley-Clark" or similar approved:</u>				
12	"Ref. SQ2 code 405607B" white lockable toilet roll holder	No	9		
13	Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc	No	6		
Carried Forward to Summary of Section No. 7					
Section No. 7					
SFD8 - Female Educator Ablutions					
Bill No. 7					
IRONMONGERY					
Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.8</u></p> <p><u>METALWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions of bolts, anchors, etc:</u></p> <p>Descriptions of bolts shall be deemed to include nuts and washers</p> <p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete</p> <p>Items described as "holed for bolt(s)" shall be deemed to exclude the bolts, unless otherwise described</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres</p>			
Carried Forward		R	
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>			

	Brought Forward		R
<p><u>Fixing:</u></p> <p>Unless otherwise described, descriptions of items shall be deemed to include for fixing to brickwork or concrete</p> <p>Where items are described as "bolted", the bolts are measured elsewhere as stated in clause N.7 of the Model Preambles</p> <p><u>References:</u></p> <p>References in descriptions of windows, doors, gates, etc refer to the respective types of windows, doors, etc detailed in the Architect's window schedules numbered</p> <ul style="list-style-type: none"> • 21111/FSPS/S005 • T-2003 • T-2004 • T-2005 <p>and bound into the back of these bills of quantities</p> <p>Tenderers are to price the following items in conjunction with the above Architect's drawings, etc and no claim arising from brevity of descriptions in these bills of quantities, of items shown on the Architect's drawings, etc shall be entertained</p> <p style="text-align: center;">-----</p>			
<p style="text-align: right;">Carried Forward</p> <p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward					
	<u>STEEL GATES, SCREENS, ETC</u>					R
	<u>Welded screens and gates, to brickwalls:</u>					
1	Single gate and frame size to fit standard door, size 813 x 2032mm high	No	3			
	<u>PRESSED STEEL DOOR FRAMES</u>					
	<u>1,6mm Double rebated frames suitable for half brick walls:</u>					
2	Frame for door size 813 x 2032mm high	No	9			
	<u>1,6mm Double rebated frames suitable for one brick walls:</u>					
3	Frame for door size 813 x 2032mm high	No	3			
	<u>STEEL WINDOWS, DOORS, ETC</u>					
	<u>Standard windows:</u>					
4	Window type NE1, 533 x 654mm high (N1)	No	1			
5	Window type NE7, 1022 x 654mm high (N2)	No	13			
	Carried Forward to Summary of Section No. 7					R
	Section No. 7					
	SFD8 - Female Educator Ablutions					
	Bill No. 8					
	METALWORK					
	Diatho Consulting (PTY) LTD					

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.9</u></p> <p><u>PLUMBING AND DRAINAGE (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Wire gratings:</u></p> <p>Descriptions of gutter outlets, etc shall be deemed to include wire balloon gratings</p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p>			
	Carried Forward		R	
	<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 9 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>Stainless steel basins, sinks, wash troughs, urinals, etc:</u></p> <p>Stainless steel for economy basins, domestic sinks and worktops shall be Type 430 (17/0)</p> <p>Stainless steel for urinals, basins, quality sinks, wash troughs, institutional equipment, etc shall be Type 304 (18/8)</p> <p>Stainless steel for laboratory sinks, photographic equipment, etc shall be Type 316 (18/8)</p> <p>Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable</p> <p><u>Sealing of edges:</u></p> <p>Outer edges of sinks, basins, baths, urinals, etc are to be sealed against adjacent surfaces with approved mildew resistant silicone sealant and prices must include therefor</p>				R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 9 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>				R

<p style="text-align: center;">Brought Forward</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPE) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 9 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

<p style="text-align: center;">Brought Forward</p> <p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claims for extra bushes, reducers, etc will be entertained</p> <p><u>Fixing of pipes:</u></p> <p>Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls, etc casting in, building in or suspending not exceeding 1m below suspension level</p> <p><u>Paper wrapping to pipes:</u></p> <p>Pipes chased into brickwork must be wrapped with two layers of stout brown paper tied with wire. Rates are to include for wrapping around joints and fittings</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 9 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SANS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SANS 1200L : Medium-pressure pipelines SANS 1200LD : Sewers SANS 1200LE : Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SANS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SANS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 9 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

Brought Forward			R
<p><u>General:</u></p> <p>Descriptions of cast iron roof outlets shall be deemed to include joints to pipes and casting into concrete (adaptors for joints to PVC pipes, etc are given separately)</p> <p>Descriptions of overflow pipes where measured in number, shall be deemed to include joints to cisterns and splay cut ends</p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site</p> <p>Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)</p> <p>Descriptions of WC pans, slop hoppers, etc shall be deemed to include for joints to soil pipes (pan connectors are separately measured) and shall have straight or side outlets and "P" or "S" traps as necessary</p> <p>Description of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.</p> <p><u>As-built drawings:</u></p> <p>Where required, the Contractor shall prepare an updated set of as-built drawings. At completion of the contract the Contractor shall hand these drawings to the Project Manager for reproducing onto the originals for handing over to the Employer (provision for allowance of as-built drawings elsewhere)</p>			
Carried Forward			R
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 9 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

Brought Forward			R																												
<p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p> <p style="text-align: center;">-----</p> <p><u>RAINWATER DISPOSAL</u></p> <p><u>0,6mm Galvanised sheet steel gutters and rainwater pipes with powder coated finish on outside to match roof sheeting colour:</u></p> <table style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 5%; text-align: center;">1</td> <td style="width: 60%;">150 x150mm Box gutters</td> <td style="width: 15%; text-align: center;">m</td> <td style="width: 20%; text-align: center;">22</td> </tr> <tr> <td style="text-align: center;">2</td> <td>100 x 75mm Rainwater pipes</td> <td style="text-align: center;">m</td> <td style="text-align: center;">5</td> </tr> <tr> <td style="text-align: center;">3</td> <td>Extra over gutter for stopped end</td> <td style="text-align: center;">No</td> <td style="text-align: center;">2</td> </tr> <tr> <td style="text-align: center;">4</td> <td>Extra over gutter for outlet for 100 x 75mm pipe</td> <td style="text-align: center;">No</td> <td style="text-align: center;">2</td> </tr> <tr> <td style="text-align: center;">5</td> <td>Extra over rainwater pipe for bend</td> <td style="text-align: center;">No</td> <td style="text-align: center;">2</td> </tr> <tr> <td style="text-align: center;">6</td> <td>Extra over rainwater pipe for shoe</td> <td style="text-align: center;">No</td> <td style="text-align: center;">2</td> </tr> <tr> <td style="text-align: center;">7</td> <td>Extra over rainwater pipe for eaves or plinth offset</td> <td style="text-align: center;">No</td> <td style="text-align: center;">2</td> </tr> </table>				1	150 x150mm Box gutters	m	22	2	100 x 75mm Rainwater pipes	m	5	3	Extra over gutter for stopped end	No	2	4	Extra over gutter for outlet for 100 x 75mm pipe	No	2	5	Extra over rainwater pipe for bend	No	2	6	Extra over rainwater pipe for shoe	No	2	7	Extra over rainwater pipe for eaves or plinth offset	No	2
1	150 x150mm Box gutters	m	22																												
2	100 x 75mm Rainwater pipes	m	5																												
3	Extra over gutter for stopped end	No	2																												
4	Extra over gutter for outlet for 100 x 75mm pipe	No	2																												
5	Extra over rainwater pipe for bend	No	2																												
6	Extra over rainwater pipe for shoe	No	2																												
7	Extra over rainwater pipe for eaves or plinth offset	No	2																												
Carried Forward			R																												
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 9 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>																															

	Brought Forward				R
	<u>SANITARY FITTINGS</u>				
	<u>"Vaal" or similar approved:</u>				
8	455 x 290mm "Hibiscus" 7050 wash hand basin bolted to wall	No	6		
9	"Daisy Elite" 772403 close-coupled WC suite comprising pan with double flap heavy duty thermoset seat (Code: 8531Z0) and matching 9 litre cistern	No	8		
10	"Pearl Paraplegic" 7300SC paraplegic WC suite with lid, fittings, purpose made CP side flush lever and purpose made double flap white epoxy painted wooden seat	No	1		
	<u>TRAPS, ETC</u>				
	<u>uPVC:</u>				
11	40 x 40mm Double bowl wash trough or sink reseal "P" or "S" trap combination	No	6		
	<u>TAPS, VALVES, ETC</u>				
	<u>"Cobra Watertech" or similar approved:</u>				
12	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No	1		
13	15mm Code 503-21CP elbow action pillar tap	No	1		
14	19mm chrome plated push button taps to wash troughs	No	12		
15	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No	12		
	<u>SANITARY PLUMBING</u>				
	Carried Forward				R
	Section No. 7 SFD8 - Female Educator Ablutions Bill No. 9 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

	Brought Forward				R
	<u>uPVC pipes:</u>				
16	50mm Pipes	m	12		
17	110mm Pipes	m	5		
18	50mm Diameter pipe laid in and including trenches not exceeding 1m deep	m	12		
19	Ditto, but 110mm diameter	m	7		
	<u>Extra over uPVC pipes for fittings:</u>				
20	50mm Bend	No	6		
21	50mm Junction	No	6		
22	50mm Junction with cleaning eye and lid	No	3		
23	110mm Straight pan connector	No	1		
24	110mm Bend	No	8		
25	110mm Junction	No	8		
26	110mm Reducing junction	No	3		
27	110mm Access bend	No	1		
28	110mm Double junction	No	3		
29	110mm "GI Two-way" vent valve	No	1		
	<u>Testing:</u>				
30	Testing waste pipe system		Item		
	<u>WATER SUPPLIES</u>				
	Carried Forward				R
	Section No. 7 SFD8 - Female Educator Ablutions Bill No. 9 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>Class 1 copper pipes with capillary couplings:</u>			
31	15mm Pipe fixed to walls, in chases, etc	m	35
32	Ditto, but 22mm diameter	m	65
<u>Extra over Class 1 copper pipes for capillary fittings:</u>			
33	15mm Fittings	No	17
34	22mm Fittings	No	17
<u>Testing:</u>			
35	Testing water pipe system		Item
Carried Forward to Summary of Section No. 7			R
Section No. 7			
SFD8 - Female Educator Ablutions			
Bill No. 9			
PLUMBING AND DRAINAGE			
Diatho Consulting (PTY) LTD			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.10</u></p> <p><u>GLAZING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Float glass:</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass:</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p style="text-align: center;">-----</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p>			
<p>Carried Forward</p>		R	
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 10 GLAZING Diatho Consulting (PTY) LTD</p>			

Brought Forward					
	<u>6,38mm Obscure safety glass:</u>				R
1	Panes not exceeding 0,1m ²	m2	17		
	<u>TOPS, SHELVES, DOORS, MIRRORS, ETC</u>				
	<u>Silvered float glass copper backed mirrors with polished edges holed for and fixed with chromium plated dome capped mirror screws with foam backing strip all round to plugs in walls</u>				
2	6mm "GG" quality polished glass mirror 450 x 800mm high with polished edges fixed to wall with four 35mm round nose chromium plated mirror screws	No	8		
Carried Forward to Summary of Section No. 7					R
Section No. 7					
SFD8 - Female Educator Ablutions					
Bill No. 10					
GLAZING					
Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 7</u></p> <p><u>BILL NO.11</u></p> <p><u>PAINTWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and minor cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces:</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p style="text-align: right;">Carried Forward</p> <p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 11 PAINTWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward		R	
<p><u>Previously painted wood surfaces:</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with "Plascon", etc specifications, unless otherwise described</p> <p><u>COLOURS</u></p> <p>When staining timber, the resultant colour or shade must be to the complete satisfaction of the Project Manager before any overcoating or preservative is applied</p> <p>Paintwork is classified in the following different colour groups: "White", "Pastel", "Deep" and "Transparent" in accordance with the "Natural Colour System" (NCS) adopted by the SA National Standards Unless otherwise described, all paintwork shall be deemed to be classified in the "White" colour group</p> <p style="text-align: center;">-----</p> <p><u>PAINTWORK, ETC TO NEW WORK</u></p> <p><u>ON FIBRE-CEMENT BOARD SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use, on:</u></p>				
<p>1 Fascias and barge boards, including priming metal jointing strips</p>	m2	8		
<p><u>METAL SURFACES WITH</u></p>				
	Carried Forward		R	
<p>Section No. 7 SFD8 - Female Educator Ablutions Bill No. 11 PAINTWORK Diatho Consulting (PTY) LTD</p>				

	Brought Forward			R
	<u>One coat alkyd based zinc phosphate primer and two coats premium quality polyurethane enamel paint, on steel:</u>			
2	Door frames	m2	19	
3	Windows	m2	17	
4	Gates, grilles, burglar screens, balustrades, etc (both sides measured over the full flat area)	m2	7	
5	Extra over for paintwork in the "Deep" colour group	m2	42	
	<u>ON WOOD SURFACES</u>			
	<u>One coat primer, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on:</u>			
6	Doors	m2	36	
7	Roof timbers at eaves and verges	m2	38	
8	Extra over for paintwork in the "Deep" colour group	m2	74	
	Carried Forward to Summary of Section No. 7			R
	Section No. 7			
	SFD8 - Female Educator Ablutions			
	Bill No. 11			
	PAINTWORK			
	Diatho Consulting (PTY) LTD			

Bill No	<u>SECTION SUMMARY - SFD8 - Female Educator Ablutions</u>	Page No	Amount
1	EARTHWORKS	224	
2	CONCRETE, FORMWORK AND REINFORCEMENT	228	
3	MASONRY	232	
4	WATERPROOFING	234	
5	ROOF COVERINGS	236	
6	CARPENTRY AND JOINERY	239	
7	IRONMONGERY	243	
8	METALWORK	246	
9	PLUMBING AND DRAINAGE	256	
10	GLAZING	258	
11	PAINTWORK	261	
	Carried to Final Summary		R
	Section No. 7 SFD8 - Female Educator Ablutions Diatho Consulting (PTY) LTD		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be included in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p>The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "hard rock" or "soft rock".</p> <p>The nature of the ground is assumed to be gravel, therefore "earth", but possibly interspersed with "soft rock".</p> <p>The nature of the ground is assumed to be silty clay with loose river boulders varying in size up to approximately 450mm diameter, therefore "earth", but possibly interspersed with "hard rock".</p> <p style="text-align: right;">Carried Forward</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>			R

<p style="text-align: center;">Brought Forward</p> <p>Trial holes indicate that the nature of the ground is silty clay to a depth of approximately 500mm with fine to medium loose sandy material below, therefore "earth". The trial holes also indicate that the water table is at a maximum depth of approximately 1000mm.</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p><u>Subterranean water:</u></p> <p>No subterranean water is expected</p> <p>Should the Contractor however, encounter any subterranean water on the site, he shall immediately notify the Principal Agent thereof and submit recommendations for keeping the works free from subterranean water together with all costs involved therewith</p> <p><u>Excavation for working space in rock:</u></p> <p>Notwithstanding clause 10 measurement rule 27 of the Standard System of Measuring Building Work, excavation for working space in material of a more different character (e.g. soft or hard rock) will be measured in cubic metres to the extent executed and given as "extra over" bulk excavation or trench and hole excavation as the case may be</p> <p><u>Carting away of excavated material</u></p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>	R	

Brought Forward				R
<u>Filling</u>				
Notwithstanding the reference to prescribed multiple handling in clause 1 page 10 of the Standard System (7th Edition, 2015) of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material				
<u>Testing:</u>				
<i>Prices for backfilling to trenches and holes only are to include for all necessary density tests in accordance with SANS 1200D</i>				

<u>EXCAVATIONS, FILLING, ETC</u>				
<u>EXCAVATIONS, ETC</u>				
<u>Excavation in earth not exceeding 2m deep:</u>				
1	Reduced levels under floors	m3	2	
2	Trenches	m3	7	
3	Trenches and holes for thickening under surface beds, etc	m3	1	
<u>Extra over trench and hole excavations in earth for excavation in:</u>				
4	Soft rock	m3	1	
5	Hard rock	m3	0.4	
<u>Extra over all excavations for carting away:</u>				
6	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	8	
Carried Forward				R
Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>Risk of collapse of excavations:</u>			
7	Sides of trench and hole excavations not exceeding 1,5m deep	m2	20
<u>Keeping excavations free of water:</u>			
8	Keeping excavations free of all water other than subterranean water		Item
<u>FILLING ETC</u>			
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 93% Mod AASHTO density:</u>			
9	Backfilling to trenches, holes, etc	m3	2
<u>G5 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>			
10	Under floors, steps, pavings, etc	m3	2
<u>Compaction of surfaces:</u>			
11	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	18
<u>Prescribed density tests on filling:</u>			
12	"Modified AASHTO Density" test	No	8
<u>SOIL POISONING</u>			
<u>Soil insecticide in accordance with SANS 5859:</u>			
13	Soil insecticide (protection against termites) applied as specified under floors, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	16
Carried Forward			R
Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD			

		Brought Forward			
14	To bottoms and sides of trenches, etc	m2	32		R
Carried Forward to Summary of Section No. 8					
Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Cost of tests:</u></p> <p><u>Breeze concrete:</u></p> <p>Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated</p>			
<p>Carried Forward</p>		R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Lightweight concrete:</u></p> <p>Lightweight concrete shall have a density of 600kg/m³ for the top 50mm and 400kg/m³ for the remaining thickness. The minimum thickness at outlets, channels, etc shall be 50mm</p> <p><u>Waterproof concrete:</u></p> <p>"Waterproof concrete" shall have the same properties as normal concrete, but the following shall be modified to make the the concrete more water-tight:</p> <ol style="list-style-type: none"> 1. a cement/water ratio of minimum 1.9 and maximum 2.1 2. minimum OPC content of 300kg/m³ 3. Polypropolene micro fibres added to concrete at rate of 182 million per m³ <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself</p> <p>Formwork to soffits of solid slabs, etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described</p> <p>Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described</p> <p style="text-align: center;">-----</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>		R	

		Brought Forward		R
<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>15MPa/19mm concrete:</u>				
1	Surface blinding under footings and bases	m3	1	
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>30MPa/19mm concrete:</u>				
	Strip footings	m3	3	
	Surface beds on waterproofing	m3	2	
<u>TEST BLOCKS</u>				
2	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	2	
<u>CONCRETE SUNDRIES</u>				
<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>				
3	Surface beds, slabs, etc	m2	16	
<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>				
<u>Rough formwork to sides:</u>				
4	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	33	
<u>MOVEMENT JOINTS, ETC</u>				
<u>Expansion joints with 10mm softboard between vertical concrete and brick surfaces:</u>				
5	Not exceeding 300mm high to edges of surface beds	m	21	
		Carried Forward		R
Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD				

Brought Forward							
	<u>Saw-cut joints:</u>						R
6	6 x 10mm Saw-cut joints in top of concrete	m	25				
	<u>REINFORCEMENT (PROVISIONAL)</u>						
	<u>Mild steel reinforcement to structural concrete work:</u>						
7	Mild steel bar reinforcement (8 to 40mm diameter bars)	t	0.06				
	<u>High tensile steel reinforcement to structural concrete work:</u>						
8	High tensile steel bar reinforcement (8 to 40mm diameter bars)	t	0.15				
	<u>Fabric reinforcement:</u>						
9	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	16				
Carried Forward to Summary of Section No. 8							R
Section No. 8							
M2 + 2UR Male Educators Ablutions							
Bill No. 2							
CONCRETE, FORMWORK AND REINFORCEMENT							
Diatho Consulting (PTY) LTD							

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>General:</u></p> <p>Non-load bearing brickwork is to be built to full height less 20mm gap next to the ceiling and is to be left for 14 days before grouting up in 1:3 cement mortar.</p> <p><u>Sizes in descriptions:</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p>			
<p>Carried Forward</p>		R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>Hollow walls:</u></p> <p>Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole</p> <p><u>Bagged and sealed walls:</u></p> <p>Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats bitumen emulsion waterproofing coating</p> <p><u>Face bricks :</u></p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>All face brickwork shall be regularly cleaned down as the work proceeds and shall be protected as necessary by an approved method</p> <p><u>Pointing:</u></p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include smooth floated square recessed, hollow recessed, weathered pointing, etc</p> <p style="text-align: center;">-----</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in class 1 mortar:</u></p>			
1	One brick walls	m2	8	
	<p><u>2,5mm Brickwork reinforcement:</u></p>			
2	150mm Wide reinforcement built in horizontally	m	49	
	Carried Forward			R
	<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
<u>FACE BRICKWORK</u>			
<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
3	Extra over brickwork for face brickwork	m2	3
<u>SUPERSTRUCTURE</u>			
<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar in loadbearing walls etc:</u>			
4	One brick walls	m2	47
<u>BRICKWORK SUNDRIES</u>			
<u>Joint forming material in movement joints:</u>			
5	12mm Fibre board built in vertically through brick walls	m	41
<u>2,5mm Brickwork reinforcement:</u>			
6	75mm Wide reinforcement built in horizontally	m	26
7	150mm Wide reinforcement built in horizontally	m	151
<u>Prestressed fabricated concrete lintels, including necessary temporary supports:</u>			
8	110 x 75mm Lintels in lengths not exceeding 3m long	m	18
<u>FACE BRICKWORK</u>			
<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
9	Half brick wall faced on both sides	m2	9
10	Extra over brickwork for face brickwork	m2	93
Carried Forward			R
Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD			

	Brought Forward			R
11	Extra over brickwork for brick-on-edge header course lintel pointed on face and 120mm soffit	m	6	
12	Fair raking cutting	m	10	
	<u>Brick-on-edge header course coping, sills, etc. of face</u>			
	<u>bricks (Allow a Prime Cost Amount of R5</u>			
	<u>500.00/1000 bricks delivered to site excluding VAT)</u>			
	<u>pointed with recessed joints on all exposed faces</u>			
13	150mm Wide sills set sloping and slightly projecting	m	5	
Carried Forward to Summary of Section No. 8				R
Section No. 8				
M2 + 2UR Male Educators Ablutions				
Bill No. 3				
MASONRY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.4</u></p> <p><u>WATERPROOFING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Waterproofing:</u></p> <p>Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets, etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs</p> <p style="text-align: center;">-----</p>			
<p>Carried Forward</p>		R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 4 WATERPROOFING Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
<u>DAMPPROOFING OF WALLS AND FLOORS</u>			
<u>One layer 375 micron embossed polyethylene dampproof course (SANS 952-1985 type B):</u>			
1	In walls	m2	47
2	In walls vertically at reveals	m2	3
<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape:</u>			
3	Under surface beds	m2	19
<u>JOINT SEALANTS ETC</u>			
<u>Two- part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>			
4	6 x 10mm In saw cut joints in floors	m	25
<u>White silicone sealing compound including backing cord, bond breaker, primer, etc</u>			
5	6 x 10mm In expansion joints in floors, including raking out expansion joint filler as necessary [LI]	m	21
Carried Forward to Summary of Section No. 8			R
Section No. 8			
M2 + 2UR Male Educators Ablutions			
Bill No. 4			
WATERPROOFING			
Diatho Consulting (PTY) LTD			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.5</u></p> <p><u>ROOF COVERINGS</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Profiled metal roof sheeting and accessories shall be supplied with a 10 year guarantee and be installed by an approved installer</p> <p>All fixing holes shall be drilled and not punched</p> <p>Roof covering accessories shall be manufactured from the same material as used for roof covering</p> <p style="text-align: center;">-----</p> <p><u>PROFILED METAL SHEETING AND ACCESSORIES</u></p>			
Carried Forward		R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
<p><u>0,6 mm "Klip-Lok 406" or similar approved light industrial Z275 spelter galvanised steel sheeting, with "Classicoat" finish one side and half coat "Classicoat Grey" other side, and accessories fixed to timber purlins or rails at approximately 1500mm centres:</u></p>			
1	Roof coverings with pitch not exceeding 25 degrees	m2	22
<p><u>Accessories:</u></p>			
2	Apex flashings 462mm girth	m	10
<p><u>ROOF AND WALL INSULATION</u></p>			
<p><u>"Sisalation 405" or similar approved residential grade aluminium foil based insulation:</u></p>			
3	Insulation sheeting laid taut over purlins at approximately 1000mm centres and fixed concurrent with roof covering with minimum 150mm stapled laps, including galvanised steel straining wires at not exceeding 400mm centres and double-sided tape at edges where required	m2	22
<p>Carried Forward to Summary of Section No. 8</p>			R
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing:</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given separately elsewhere</p> <p><u>Joinery:</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p>			
Carried Forward		R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			

Brought Forward				R
Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts				
<u>Particle board</u>				
All particle board shall comply with SANS 50312 having the required marking as per SANS 50312/EN 312				
<u>Decorative thermosetting plastic laminate covering:</u>				
Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish				
<u>Sizes:</u>				
Sizes are nominal and the Contractor shall make allowance in his prices for minor variances in stated finished sizes of timber doors, door members, door frames, architraves, etc				
<u>Prices</u>				
Prices for all joinery work are to include for general framing, housing and notching, arris rounded angles, glueing, blocking, planting on, screwing, adhesives, dowels, pellets, cross tongues, screws and nails and setting up complete and also for all square cutting and waste. Tops shall be secured with metal or hardwood buttons.				

<u>ROOFS, ETC</u>				
<u>Sawn softwood grade 5:</u>				
1 38 x 114mm Wall plates bolted	m		14	
2 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m		45	
Carried Forward				R
Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD				

Brought Forward				R
3	50 x 76mm Purlins	m	46	
	<u>EAVES, VERGES, ETC</u>			
	<u>Medium density plain fibre-cement fascias and barge boards:</u>			
4	19 x 235mm Fascias and barge boards, including aluminium H-profile jointing strips	m	20	
	<u>DOORS, ETC</u>			
	<u>Wrought meranti doors hung to steel frames:</u>			
5	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding including 150mm undercut (D2)	No	2	
6	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1)	No	2	
Carried Forward to Summary of Section No. 8				R
Section No. 8				
M2 + 2UR Male Educators Ablutions				
Bill No. 6				
CARPENTRY AND JOINERY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.7</u></p> <p><u>IRONMONGERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p>			
Carried Forward		R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>Locks:</u></p> <p>Notwithstanding Clause 2, Item 3 of the "Ironmongery" trade of the Standard System (7th Edition, 2015) of Measuring Building Work, descriptions of locks shall be deemed to include two keys per lock</p> <p><u>Finishes to ironmongery:</u></p> <p>Where applicable, finishes to ironmongery are indicated by suffixes in accordance with the following list:</p> <p>BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AN Anodised natural AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded BBS Brushed stainless steel</p> <p style="text-align: center;">-----</p> <p><u>CATCHES, CABIN HOOKS, ETC</u></p> <p>1 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged</p> <p style="text-align: right; margin-right: 20px;">No 3</p> <p><u>LOCKS</u></p> <p><u>"Union Assa Abloy" or similar approved:</u></p> <p>2 50mm Brass padlock</p> <p style="text-align: right; margin-right: 20px;">No 2</p> <p>3 Four lever lockset</p> <p style="text-align: right; margin-right: 20px;">No 2</p>			
	Carried Forward			R
	<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

Brought Forward				R
4	"Ref. CZ80941SC" Indicator bolt	No	2	
	<u>HANDLES</u>			
	<u>"Union Assa Abloy" or similar approved:</u>			
5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres	Pairs	2.0	
	<u>PUSH PLATES AND KICK PLATES</u>			
	<u>"Union Assa Abloy" or similar approved:</u>			
	<u>1.2mm Thick satin finished "Union" stainless steel plates countersunk screwed along edges at not exceeding 200mm centres</u>			
6	200 x 800mm Type "SS5089-200W" kicking plate	No	4	
	<u>LETTERS, NAMEPLATES, ETC</u>			
	<u>"Dorma" or similar approved:</u>			
7	DSS-130 Engraved "Male" information sign	No	1	
8	DSS-130 Engraved "Emergency Exit" information sign	No	1	
	<u>SUNDRIES</u>			
9	25mm Diameter wall mounted door stop plugged	No	3	
	<u>BATHROOM FITTINGS</u>			
	<u>"Kimberley-Clark" or similar approved:</u>			
10	"Ref. SQ2 code 405607B" white lockable toilet roll holder	No	2	
Carried Forward to Summary of Section No. 8				R
Section No. 8				
M2 + 2UR Male Educators Ablutions				
Bill No. 7				
IRONMONGERY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.8</u></p> <p><u>METALWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions of bolts, anchors, etc:</u></p> <p>Descriptions of bolts shall be deemed to include nuts and washers</p> <p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete</p> <p>Items described as "holed for bolt(s)" shall be deemed to exclude the bolts, unless otherwise described</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres</p>			
Carried Forward		R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>			

Brought Forward			R	
<p><u>Fixing:</u></p> <p>Unless otherwise described, descriptions of items shall be deemed to include for fixing to brickwork or concrete</p> <p>Where items are described as "bolted", the bolts are measured elsewhere as stated in clause N.7 of the Model Preambles</p> <p><u>References:</u></p> <p>References in descriptions of windows, doors, gates, etc refer to the respective types of windows, doors, etc detailed in the Architect's window schedules numbered</p> <ul style="list-style-type: none"> • 21111/FSPS/S005 • T-2003 • T-2004 • T-2005 <p>and bound into the back of these bills of quantities</p> <p>Tenderers are to price the following items in conjunction with the above Architect's drawings, etc and no claim arising from brevity of descriptions in these bills of quantities, of items shown on the Architect's drawings, etc shall be entertained</p> <p style="text-align: center;">-----</p>				
Carried Forward			R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>				

Brought Forward		R
<u>STEEL GATES, SCREENS, ETC</u>		
<u>Welded screens and gates, to brickwalls:</u>		
1	Single gate and frame size to fit standard door, size 813 x 2032mm high	No 1
<u>PRESSED STEEL DOOR FRAMES</u>		
<u>1,6mm Double rebated frames suitable for half brick walls:</u>		
2	Frame for door size 813 x 2032mm high	No 2
<u>1,6mm Double rebated frames suitable for one brick walls:</u>		
3	Frame for door size 813 x 2032mm high	No 2
<u>STEEL WINDOWS, DOORS, ETC</u>		
<u>Standard windows:</u>		
4	Window type NE1, 533 x 654mm high (N1)	No 5
5	Window type NE7, 1022 x 654mm high (N2)	No 3
Carried Forward to Summary of Section No. 8		R
Section No. 8		
M2 + 2UR Male Educators Ablutions		
Bill No. 8		
METALWORK		
Diatho Consulting (PTY) LTD		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.9</u></p> <p><u>PLASTERING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Moisture tests:</u></p> <p>Before any finishes, coverings, etc are applied to screeds, plastering, etc or any other in-situ finish, moisture tests are to be carried out to the complete satisfaction of the Project Manager to ensure that these surfaces have the correct moisture content for the finish to be applied</p> <p><u>Labours, etc</u></p> <p>Labours such as fair, rounded and chamfered edges, trowel cuts, throats, V-joints, angles, etc shall be deemed to be included in the descriptions</p>			
Carried Forward		R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Sample Panels</u></p> <p>A sample panel size 1m x1m, of each of the various plaster type wall and floor finishes in this contract, shall be prepared for the approval of the Project Manager and the cost of the sample panel(s) shall be deemed to be included in the overall costs of the <u>relevant</u> wall and floor finishes</p> <p><u>GRANOLITHIC</u></p> <p><u>Method:</u></p> <p>The method to be used shall be either the monolithic method or the bonded method</p> <p><u>Preparation:</u></p> <p>For granolithic applied monolithically, the concrete floor shall be swept clean after bleeding of the concrete has ceased and the slab has begun to stiffen; any remaining bleed water shall be removed and the granolithic applied immediately thereafter. For granolithic to be bonded to the floor slab after it has hardened, the slab surface shall be hacked (preferably by mechanical means) until all laitance, dirt, oil, etc is dislodged and swept clean of all loose matter. The slab shall then be wetted and kept damp for at least six hours before applying the granolithic</p> <p><u>Mix:</u></p> <p>Unless otherwise described, granolithic shall attain a compressive strength of at least 41MPa. The coarse aggregate shall comply with SANS 1083 and shall generally be capable of passing a 10mm mesh sieve. Where the thickness of the granolithic exceeds 25mm, the size of the coarse aggregate shall be increased to the maximum size compatible with the thickness of the granolithic</p>				R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>				R

<p style="text-align: center;">Brought Forward</p> <p><u>Panels:</u></p> <p>Granolithic shall be laid in panels not exceeding 14m² for monolithic finishes, not exceeding 9,5m² for bonded finishes and not exceeding 6m² for all external granolithic. Wherever possible, panels shall be square but at no time should the length of the panel exceed 1,5 times its width</p> <p>Where possible joints between panels shall be positioned over joints in the floor slab and shall be at least 3mm wide through the full thickness of the finish, separated by strips of wood or fibreboard and finished with V-joints</p> <p><u>Laying:</u></p> <p>Monolithic granolithic shall be applied to the partially set slab and thoroughly compacted and lightly wood floated to the required levels</p> <p>Bonded granolithic shall be applied to the slab after applying a 1:1 sand-and-cement slurry brushed over the surface and allowed to partially set before applying the granolithic. The granolithic shall be thoroughly compacted and lightly wood floated to the required levels</p> <p>After wood floating, the monolithic and bonded granolithic shall remain undisturbed until bleeding has ceased and the surface has stiffened. Any remaining bleed water and laitance shall then be removed and the surface steel trowelled or power floated</p> <p><u>Curing, seasoning and protection:</u></p> <p>Granolithic shall be covered with clean hessian with waterproof building foil over and kept wet for at least seven days after laying</p> <p><u>Colour:</u></p> <p>Coloured granolithic shall be tinted with an approved colouring pigment mixed into a true and even colour</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>	R	

	Brought Forward			R
	<p><u>TINTED WHITE CEMENT SCREEDS</u></p> <p>Tinted screed shall be composed of one bag White Portland Cement and two wheelbarrows "Malmesbury" sand. Surfaces shall be finished with a steel trowel to leave a smooth finish and coated with two coats "Earthcote S.I. Floorcote" two-pack polyurethane floor sealer applied as per the manufacturer's recommendations</p> <p>NOTE: Tinted screeds are to be strengthened with "Primal Eccos" acrylic polymer (15% of the water volume is to be substituted with the acrylic polymer during the mixing process)</p> <p>Coarse sand is to be used for these screeds</p> <p>All tinting, finishing, strengthening, etc are to be mixed, applied, etc strictly in accordance with the manufacturer's instructions</p> <p><u>CEMENT PLASTER</u></p> <p>Unless otherwise described, cement plaster shall be taken to mean Class 1 cement plaster i.e. 1:4 cement:sand plaster (common cement)</p> <p style="text-align: center;">-----</p> <p><u>CEMENT SCREEDS TO CONCRETE</u></p> <p><u>Cement screeds steel trowelled, on concrete:</u></p>			
1	30mm Thick to floors	m2	16	
	<p><u>FLOOR AND WALL SEALERS</u></p> <p><u>Minimum two coats approved epoxy coat, on concrete:</u></p>			
2	On screed	m2	16	
	<p>Carried Forward to Summary of Section No. 8</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.10</u></p> <p><u>PLUMBING AND DRAINAGE</u> <u>(PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Wire gratings:</u></p> <p>Descriptions of gutter outlets, etc shall be deemed to include wire balloon gratings</p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p>			
Carried Forward		R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>Stainless steel basins, sinks, wash troughs, urinals, etc:</u></p> <p>Stainless steel for economy basins, domestic sinks and worktops shall be Type 430 (17/0)</p> <p>Stainless steel for urinals, basins, quality sinks, wash troughs, institutional equipment, etc shall be Type 304 (18/8)</p> <p>Stainless steel for laboratory sinks, photographic equipment, etc shall be Type 316 (18/8)</p> <p>Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable</p> <p><u>Sealing of edges:</u></p> <p>Outer edges of sinks, basins, baths, urinals, etc are to be sealed against adjacent surfaces with approved mildew resistant silicone sealant and prices must include therefor</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

<p style="text-align: center;">Brought Forward</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPE) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claims for extra bushes, reducers, etc will be entertained</p> <p><u>Fixing of pipes:</u></p> <p>Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls, etc casting in, building in or suspending not exceeding 1m below suspension level</p> <p><u>Paper wrapping to pipes:</u></p> <p>Pipes chased into brickwork must be wrapped with two layers of stout brown paper tied with wire. Rates are to include for wrapping around joints and fittings</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SANS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SANS 1200L : Medium-pressure pipelines SANS 1200LD : Sewers SANS 1200LE : Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SANS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SANS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

Brought Forward			R
<p><u>General:</u></p> <p>Descriptions of cast iron roof outlets shall be deemed to include joints to pipes and casting into concrete (adaptors for joints to PVC pipes, etc are given separately)</p> <p>Descriptions of overflow pipes where measured in number, shall be deemed to include joints to cisterns and splay cut ends</p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site</p> <p>Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)</p> <p>Descriptions of WC pans, slop hoppers, etc shall be deemed to include for joints to soil pipes (pan connectors are separately measured) and shall have straight or side outlets and "P" or "S" traps as necessary</p> <p>Description of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.</p> <p><u>As-built drawings:</u></p> <p>Where required, the Contractor shall prepare an updated set of as-built drawings. At completion of the contract the Contractor shall hand these drawings to the Project Manager for reproducing onto the originals for handing over to the Employer (provision for allowance of as-built drawings elsewhere)</p>			
Carried Forward			R
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
<u>Proprietary items:</u>			
Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items			
Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.			
Prices are to be based on the specific products/articles specified.			
On request, returnable samples are to be provided to the Project Manager for consideration			

<u>RAINWATER DISPOSAL</u>			
<u>0,6mm Galvanised sheet steel gutters and rainwater pipes with powder coated finish on outside to match roof sheeting colour:</u>			
1	150 x150mm Box gutters	m	10
2	100 x 75mm Rainwater pipes	m	3
3	Extra over gutter for stopped end	No	2
4	Extra over gutter for outlet for 100 x 75mm pipe	No	2
5	Extra over rainwater pipe for bend	No	2
6	Extra over rainwater pipe for shoe	No	2
7	Extra over rainwater pipe for eaves or plinth offset	No	2
Carried Forward			R
Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Brought Forward			R
<u>SANITARY FITTINGS</u>			
<u>"Vaal" or similar approved:</u>			
8	455 x 290mm "Hibiscus" 7050 wash hand basin bolted to wall	No	3
9	"Daisy Elite" 772403 close-coupled WC suite comprising pan with double flap heavy duty thermoset seat (Code: 8531Z0) and matching 9 litre cistern	No	2
10	Flat back urinal overall size 295 x 315 x 415mm high with 40mm chromium plated domical grating (Code 878720) and top inlet spreader (Code 8543) with two hanger brackets with flushmaster junior (Code 812720) hung to wall	No	2
<u>TRAPS, ETC</u>			
<u>"Cobra Watertech" or similar approved:</u>			
11	50mm Code 365 CP bottle trap	No	3
<u>TAPS, VALVES, ETC</u>			
<u>"Cobra Watertech" or similar approved:</u>			
12	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No	5
13	15mm Code FPT2A1RO-OGP01 "Roma" basin tap with waste union	No	3
<u>SANITARY PLUMBING</u>			
<u>uPVC pipes:</u>			
14	50mm Pipes	m	25
15	110mm Pipes	m	10
Carried Forward			R
Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Brought Forward			R
16	50mm Diameter pipe laid in and including trenches not exceeding 1m deep	m	75
17	Ditto, but 110mm diameter	m	30
<u>Extra over uPVC pipes for fittings:</u>			
18	50mm Bend	No	10
19	50mm Junction	No	10
20	50mm Junction with cleaning eye and lid	No	10
21	110mm Straight pan connector	No	2
22	110mm Bend	No	4
23	110mm Junction	No	4
24	110mm Reducing junction	No	6
25	110mm Access bend	No	2
26	110mm Double junction	No	6
27	110mm "GI Two-way" vent valve	No	2
<u>Testing:</u>			
28	Testing waste pipe system		Item
<u>WATER SUPPLIES</u>			
<u>Class 1 copper pipes with capillary couplings:</u>			
29	15mm Pipe fixed to walls, in chases, etc	m	21
30	Ditto, but 22mm diameter	m	35
Carried Forward			R
Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

	Brought Forward			R
	<u>Extra over Class 1 copper pipes for capillary fittings:</u>			
31	15mm Fittings	No	35	
32	22mm Fittings	No	35	
	<u>Testing:</u>			
33	Testing water pipe system		Item	
Carried Forward to Summary of Section No. 8				R
Section No. 8				
M2 + 2UR Male Educators Ablutions				
Bill No. 10				
PLUMBING AND DRAINAGE				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.11</u></p> <p><u>GLAZING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Float glass:</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass:</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p style="text-align: center;">-----</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p>			
<p>Carried Forward</p>		R	
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>			

		Brought Forward			R
1	<p><u>6,38mm Obscure safety glass:</u></p> <p>Panes not exceeding 0,1m²</p>	m2	3		R
<p>Carried Forward to Summary of Section No. 8</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 8</u></p> <p><u>BILL NO.12</u></p> <p><u>PAINTWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and minor cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces:</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
<p><u>Previously painted wood surfaces:</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with "Plascon", etc specifications, unless otherwise described</p> <p><u>COLOURS</u></p> <p>When staining timber, the resultant colour or shade must be to the complete satisfaction of the Project Manager before any overcoating or preservative is applied</p> <p>Paintwork is classified in the following different colour groups: "White", "Pastel", "Deep" and "Transparent" in accordance with the "Natural Colour System" (NCS) adopted by the SA National Standards Unless otherwise described, all paintwork shall be deemed to be classified in the "White" colour group</p> <p style="text-align: center;">-----</p> <p><u>PAINTWORK, ETC TO NEW WORK</u></p> <p><u>ON FIBRE-CEMENT BOARD SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use, on:</u></p>				
<p>1 Fascias and barge boards, including priming metal jointing strips</p>	m2	5		
<p><u>METAL SURFACES WITH</u></p>				
	Carried Forward			R
<p>Section No. 8 M2 + 2UR Male Educators Ablutions Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>				

	Brought Forward			R
	<u>One coat alkyd based zinc phosphate primer and two coats premium quality polyurethane enamel paint, on steel:</u>			
2	Door frames	m2	6	
3	Windows	m2	6	
4	Gates, grilles, burglar screens, balustrades, etc (both sides measured over the full flat area)	m2	3	
5	Extra over for paintwork in the "Deep" colour group	m2	15	
	<u>ON WOOD SURFACES</u>			
	<u>One coat primer, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on:</u>			
6	Doors	m2	11	
7	Roof timbers at eaves and verges	m2	29	
8	Extra over for paintwork in the "Deep" colour group	m2	40	
	Carried Forward to Summary of Section No. 8			R
	Section No. 8			
	M2 + 2UR Male Educators Ablutions			
	Bill No. 12			
	PAINTWORK			
	Diatho Consulting (PTY) LTD			

Bill No	<u>SECTION SUMMARY - M2 + 2UR Male Educators Ablutions</u>	Page No	Amount
1	EARTHWORKS	267	
2	CONCRETE, FORMWORK AND REINFORCEMENT	271	
3	MASONRY	275	
4	WATERPROOFING	277	
5	ROOF COVERINGS	279	
6	CARPENTRY AND JOINERY	282	
7	IRONMONGERY	285	
8	METALWORK	288	
9	PLASTERING	292	
10	PLUMBING AND DRAINAGE	302	
11	GLAZING	304	
12	PAINTWORK	307	
	Carried to Final Summary		R
	Section No. 8 M2 + 2UR Male Educators Ablutions Diatho Consulting (PTY) LTD		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be included in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p>The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "hard rock" or "soft rock".</p> <p>The nature of the ground is assumed to be gravel, therefore "earth", but possibly interspersed with "soft rock".</p> <p>The nature of the ground is assumed to be silty clay with loose river boulders varying in size up to approximately 450mm diameter, therefore "earth", but possibly interspersed with "hard rock".</p>			
Carried Forward		R	
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>			

Brought Forward	R
<p>Trial holes indicate that the nature of the ground is silty clay to a depth of approximately 500mm with fine to medium loose sandy material below, therefore "earth". The trial holes also indicate that the water table is at a maximum depth of approximately 1000mm.</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p><u>Subterranean water:</u></p> <p>No subterranean water is expected</p> <p>Should the Contractor however, encounter any subterranean water on the site, he shall immediately notify the Principal Agent thereof and submit recommendations for keeping the works free from subterranean water together with all costs involved therewith</p> <p><u>Excavation for working space in rock:</u></p> <p>Notwithstanding clause 10 measurement rule 27 of the Standard System of Measuring Building Work, excavation for working space in material of a more different character (e.g. soft or hard rock) will be measured in cubic metres to the extent executed and given as "extra over" bulk excavation or trench and hole excavation as the case may be</p> <p><u>Carting away of excavated material</u></p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p>	R
Carried Forward	R
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>	

Brought Forward				R
<u>Filling</u>				
Notwithstanding the reference to prescribed multiple handling in clause 1 page 10 of the Standard System (7th Edition, 2015) of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material				
<u>Testing:</u>				
<i>Prices for backfilling to trenches and holes only are to include for all necessary density tests in accordance with SANS 1200D</i>				

<u>EXCAVATIONS, FILLING, ETC</u>				
<u>EXCAVATIONS, ETC</u>				
<u>Excavation in earth not exceeding 2m deep:</u>				
1 Reduced levels under floors	m3	3		
2 Trenches	m3	10		
3 Holes	m3	21		
4 Trenches and holes for thickening under surface beds, etc	m3	3		
<u>Extra over trench and hole excavations in earth for excavation in:</u>				
5 Soft rock	m3	1		
6 Hard rock	m3	1		
<u>Extra over all excavations for carting away:</u>				
7 Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	12		
Carried Forward				R
Section No. 9 M6 + 3UR Male Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>Risk of collapse of excavations:</u>			
8	Sides of trench and hole excavations not exceeding 1,5m deep	m2	29
<u>Keeping excavations free of water:</u>			
9	Keeping excavations free of all water other than subterranean water		Item
<u>FILLING ETC</u>			
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 93% Mod AASHTO density:</u>			
10	Backfilling to trenches, holes, etc	m3	3
<u>G5 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>			
11	Under floors, steps, pavings, etc	m3	3
<u>Compaction of surfaces:</u>			
12	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	17
<u>Prescribed density tests on filling:</u>			
13	"Modified AASHTO Density" test	No	6
<u>SOIL POISONING</u>			
<u>Soil insecticide in accordance with SANS 5859:</u>			
14	Soil insecticide (protection against termites) applied as specified under floors, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	17
Carried Forward			R
Section No. 9 M6 + 3UR Male Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD			

	Brought Forward				R
15	To bottoms and sides of trenches, etc	m2	46		
Carried Forward to Summary of Section No. 9 Section No. 9 M6 + 3UR Male Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Cost of tests:</u></p> <p><u>Breeze concrete:</u></p> <p>Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated</p>			
Carried Forward			R
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Lightweight concrete:</u></p> <p>Lightweight concrete shall have a density of 600kg/m³ for the top 50mm and 400kg/m³ for the remaining thickness. The minimum thickness at outlets, channels, etc shall be 50mm</p> <p><u>Waterproof concrete:</u></p> <p>"Waterproof concrete" shall have the same properties as normal concrete, but the following shall be modified to make the the concrete more water-tight:</p> <ol style="list-style-type: none"> 1. a cement/water ratio of minimum 1.9 and maximum 2.1 2. minimum OPC content of 300kg/m³ 3. Polypropolene micro fibres added to concrete at rate of 182 million per m³ <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself</p> <p>Formwork to soffits of solid slabs, etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described</p> <p>Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described</p> <p style="text-align: center;">-----</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>	R	

Brought Forward			R
<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
<u>15MPa/19mm concrete:</u>			
1	Surface blinding under footings and bases	m3	1
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
<u>30MPa/19mm concrete:</u>			
	Strip footings	m3	4
	Surface beds on waterproofing	m3	5
2	Surface beds in tank bottoms		
		m3	3
3	Aprons cast in panels to falls	m3	7
<u>TEST BLOCKS</u>			
4	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	11
<u>CONCRETE SUNDRIES</u>			
<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>			
5	Surface beds, slabs, etc	m2	17
<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>			
<u>Rough formwork to sides:</u>			
6	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	48
Carried Forward			R
Section No. 9 M6 + 3UR Male Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD			

Brought Forward			R
<u>MOVEMENT JOINTS, ETC</u>			
<u>Expansion joints with 10mm softboard between vertical concrete and brick surfaces:</u>			
7	Not exceeding 300mm high to edges of surface beds	m	21
<u>Saw-cut joints:</u>			
8	6 x 10mm Saw-cut joints in top of concrete	m	25
<u>REINFORCEMENT (PROVISIONAL)</u>			
<u>Mild steel reinforcement to structural concrete work:</u>			
9	Mild steel bar reinforcement (8 to 40mm diameter bars)	t	0.09
<u>High tensile steel reinforcement to structural concrete work:</u>			
10	High tensile steel bar reinforcement (8 to 40mm diameter bars)	t	0.22
<u>Fabric reinforcement:</u>			
11	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	17
Carried Forward to Summary of Section No. 9			R
Section No. 9			
M6 + 3UR Male Ablutions			
Bill No. 2			
CONCRETE, FORMWORK AND REINFORCEMENT			
Diatho Consulting (PTY) LTD			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>General:</u></p> <p>Non-load bearing brickwork is to be built to full height less 20mm gap next to the ceiling and is to be left for 14 days before grouting up in 1:3 cement mortar.</p> <p><u>Sizes in descriptions:</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p>			
Carried Forward		R	
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>Hollow walls:</u></p> <p>Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole</p> <p><u>Bagged and sealed walls:</u></p> <p>Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats bitumen emulsion waterproofing coating</p> <p><u>Face bricks :</u></p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>All face brickwork shall be regularly cleaned down as the work proceeds and shall be protected as necessary by an approved method</p> <p><u>Pointing:</u></p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include smooth floated square recessed, hollow recessed, weathered pointing, etc</p> <p style="text-align: center;">-----</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in class 1 mortar:</u></p>			
1	One brick walls	m2	12	
2	One brick walls in pit	m2	20	
	Carried Forward			R
	<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
3	Half brick wall corbelling in pit	m	12
	<u>2,5mm Brickwork reinforcement:</u>		
4	150mm Wide reinforcement built in horizontally	m	142
	<u>FACE BRICKWORK</u>		
	<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>		
5	Extra over brickwork for face brickwork	m2	4
	<u>SUPERSTRUCTURE</u>		
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar in loadbearing walls etc:</u>		
6	One brick walls	m2	67
	<u>BRICKWORK SUNDRIES</u>		
	<u>Joint forming material in movement joints:</u>		
7	12mm Fibre board built in vertically through brick walls	m	15
	<u>2,5mm Brickwork reinforcement:</u>		
8	75mm Wide reinforcement built in horizontally	m	122
9	150mm Wide reinforcement built in horizontally	m	223
	<u>Prestressed fabricated concrete lintels, including necessary temporary supports:</u>		
10	110 x 75mm Lintels in lengths not exceeding 3m long	m	31
	<u>FACE BRICKWORK</u>		
	Carried Forward		R
	Section No. 9 M6 + 3UR Male Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD		

	Brought Forward			R
	<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
11	Half brick wall faced on both sides	m2	41	
12	Extra over brickwork for face brickwork	m2	134	
13	Extra over brickwork for brick-on-edge header course lintel pointed on face and 120mm soffit	m	9	
14	Fair raking cutting	m	23	
	<u>Brick-on-edge header course coping, sills, etc. of face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with recessed joints on all exposed faces</u>			
15	150mm Wide sills set sloping and slightly projecting	m	8	
Carried Forward to Summary of Section No. 9				R
Section No. 9				
M6 + 3UR Male Ablutions				
Bill No. 3				
MASONRY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.4</u></p> <p><u>WATERPROOFING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Waterproofing:</u></p> <p>Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets, etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs</p> <p style="text-align: center;">-----</p>			
<p>Carried Forward</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 4 WATERPROOFING Diatho Consulting (PTY) LTD</p>		<p>R</p>	

Brought Forward							
<u>DAMPPROOFING OF WALLS AND FLOORS</u>							
<u>One layer 375 micron embossed polyethylene dampproof course (SANS 952-1985 type B):</u>							
1	In walls	m2	69				
2	In walls vertically at reveals	m2	5				
<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape:</u>							
3	Under surface beds	m2	20				
<u>JOINT SEALANTS ETC</u>							
<u>Two- part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>							
4	6 x 10mm In saw cut joints in floors	m	25				
<u>White silicone sealing compound including backing cord, bond breaker, primer, etc</u>							
5	6 x 10mm In expansion joints in floors, including raking out expansion joint filler as necessary [LI]	m	21				
 Carried Forward to Summary of Section No. 9							
Section No. 9							
M6 + 3UR Male Ablutions							
Bill No. 4							
WATERPROOFING							
Diatho Consulting (PTY) LTD							
							R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.5</u></p> <p><u>ROOF COVERINGS</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Profiled metal roof sheeting and accessories shall be supplied with a 10 year guarantee and be installed by an approved installer</p> <p>All fixing holes shall be drilled and not punched</p> <p>Roof covering accessories shall be manufactured from the same material as used for roof covering</p> <p style="text-align: center;">-----</p> <p><u>PROFILED METAL SHEETING AND ACCESSORIES</u></p>			
Carried Forward		R	
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>0,6 mm "Klip-Lok 406" or similar approved light industrial Z275 spelter galvanised steel sheeting, with "Classicoat" finish one side and half coat "Classicoat Grey" other side, and accessories fixed to timber purlins or rails at approximately 1500mm centres:</u></p>			
1	Roof coverings with pitch not exceeding 25 degrees	m2	58	
	<p><u>Accessories:</u></p>			
2	Apex flashings 462mm girth	m	23	
	<p><u>ROOF AND WALL INSULATION</u></p> <p><u>"Sisalation 405" or similar approved residential grade aluminium foil based insulation:</u></p>			
3	Insulation sheeting laid taut over purlins at approximately 1000mm centres and fixed concurrent with roof covering with minimum 150mm stapled laps, including galvanised steel straining wires at not exceeding 400mm centres and double-sided tape at edges where required	m2	58	
<p>Carried Forward to Summary of Section No. 9</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>				R

Item No		Quantity	Rate		Amount
	<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing:</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given separately elsewhere</p> <p><u>Joinery:</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p>				
	Carried Forward				
	<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			R	

Brought Forward				R
Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts				
<u>Particle board</u>				
All particle board shall comply with SANS 50312 having the required marking as per SANS 50312/EN 312				
<u>Decorative thermosetting plastic laminate covering:</u>				
Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish				
<u>Sizes:</u>				
Sizes are nominal and the Contractor shall make allowance in his prices for minor variances in stated finished sizes of timber doors, door members, door frames, architraves, etc				
<u>Prices</u>				
Prices for all joinery work are to include for general framing, housing and notching, arris rounded angles, glueing, blocking, planting on, screwing, adhesives, dowels, pellets, cross tongues, screws and nails and setting up complete and also for all square cutting and waste. Tops shall be secured with metal or hardwood buttons.				

<u>ROOFS, ETC</u>				
<u>Sawn softwood grade 5:</u>				
1 38 x 114mm Wall plates bolted	m		18	
2 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m		58	
Carried Forward				R
Section No. 9 M6 + 3UR Male Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD				

Brought Forward				R
3	50 x 76mm Purlins	m	60	
<u>EAVES, VERGES, ETC</u>				
<u>Medium density plain fibre-cement fascias and barge boards:</u>				
4	19 x 235mm Fascias and barge boards, including aluminium H-profile jointing strips	m	43	
<u>DOORS, ETC</u>				
<u>Wrought meranti doors hung to steel frames:</u>				
5	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding including 150mm undercut (D2)	No	6	
6	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1)	No	3	
Carried Forward to Summary of Section No. 9				R
Section No. 9				
M6 + 3UR Male Ablutions				
Bill No. 6				
CARPENTRY AND JOINERY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.7</u></p> <p><u>IRONMONGERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p>			
<p>Carried Forward</p>		R	
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>Locks:</u></p> <p>Notwithstanding Clause 2, Item 3 of the "Ironmongery" trade of the Standard System (7th Edition, 2015) of Measuring Building Work, descriptions of locks shall be deemed to include two keys per lock</p> <p><u>Finishes to ironmongery:</u></p> <p>Where applicable, finishes to ironmongery are indicated by suffixes in accordance with the following list:</p> <p>BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AN Anodised natural AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded BBS Brushed stainless steel</p> <p style="text-align: center;">-----</p> <p><u>CATCHES, CABIN HOOKS, ETC</u></p> <p>1 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged</p> <p><u>LOCKS</u></p> <p><u>"Union Assa Abloy" or similar approved:</u></p> <p>2 50mm Brass padlock</p> <p>3 Four lever lockset</p>	No	7	
	Carried Forward			R
	<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

Brought Forward				R
4	"Ref. CZ80941SC" Indicator bolt	No	6	
	<u>HANDLES</u>			
	<u>"Union Assa Abloy" or similar approved:</u>			
5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres	Pairs	3.0	
	<u>PUSH PLATES AND KICK PLATES</u>			
	<u>"Union Assa Abloy" or similar approved:</u>			
	<u>1.2mm Thick satin finished "Union" stainless steel plates countersunk screwed along edges at not exceeding 200mm centres</u>			
6	200 x 800mm Type "SS5089-200W" kicking plate	No	12	
	<u>LETTERS, NAMEPLATES, ETC</u>			
	<u>"Dorma" or similar approved:</u>			
7	DSS-130 Engraved "Male" information sign	No	2	
8	DSS-130 Emergency Exit "Male" information sign	No	1	
	<u>SUNDRIES</u>			
9	25mm Diameter wall mounted door stop plugged	No	8	
	<u>BATHROOM FITTINGS</u>			
	<u>"Kimberley-Clark" or similar approved:</u>			
10	"Ref. SQ2 code 405607B" white lockable toilet roll holder	No	6	
Carried Forward to Summary of Section No. 9				R
Section No. 9				
M6 + 3UR Male Ablutions				
Bill No. 7				
IRONMONGERY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.8</u></p> <p><u>METALWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions of bolts, anchors, etc:</u></p> <p>Descriptions of bolts shall be deemed to include nuts and washers</p> <p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete</p> <p>Items described as "holed for bolt(s)" shall be deemed to exclude the bolts, unless otherwise described</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres</p>			
Carried Forward		R	
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>			

Brought Forward			R	
<p><u>Fixing:</u></p> <p>Unless otherwise described, descriptions of items shall be deemed to include for fixing to brickwork or concrete</p> <p>Where items are described as "bolted", the bolts are measured elsewhere as stated in clause N.7 of the Model Preambles</p> <p><u>References:</u></p> <p>References in descriptions of windows, doors, gates, etc refer to the respective types of windows, doors, etc detailed in the Architect's window schedules numbered</p> <ul style="list-style-type: none"> • 21111/FSPS/S005 • T-2003 • T-2004 • T-2005 <p>and bound into the back of these bills of quantities</p> <p>Tenderers are to price the following items in conjunction with the above Architect's drawings, etc and no claim arising from brevity of descriptions in these bills of quantities, of items shown on the Architect's drawings, etc shall be entertained</p> <p style="text-align: center;">-----</p>				
Carried Forward			R	
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>				

Brought Forward		R
<u>STEEL GATES, SCREENS, ETC</u>		
<u>Welded screens and gates, to brickwalls:</u>		
1	Single gate and frame size to fit standard door, size 813 x 2032mm high	No 3
<u>PRESSED STEEL DOOR FRAMES</u>		
<u>1,6mm Double rebated frames suitable for half brick walls:</u>		
2	Frame for door size 813 x 2032mm high	No 6
<u>1,6mm Double rebated frames suitable for one brick walls:</u>		
3	Frame for door size 813 x 2032mm high	No 3
<u>STEEL WINDOWS, DOORS, ETC</u>		
<u>Standard windows:</u>		
4	Window type NE1, 533 x 654mm high (N1)	No 7
5	Window type NE7, 1022 x 654mm high (N2)	No 5
Carried Forward to Summary of Section No. 9		R
Section No. 9		
M6 + 3UR Male Ablutions		
Bill No. 8		
METALWORK		
Diatho Consulting (PTY) LTD		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.9</u></p> <p><u>PLASTERING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Moisture tests:</u></p> <p>Before any finishes, coverings, etc are applied to screeds, plastering, etc or any other in-situ finish, moisture tests are to be carried out to the complete satisfaction of the Project Manager to ensure that these surfaces have the correct moisture content for the finish to be applied</p> <p><u>Labours, etc</u></p> <p>Labours such as fair, rounded and chamfered edges, trowel cuts, throats, V-joints, angles, etc shall be deemed to be included in the descriptions</p>			
Carried Forward		R	
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Sample Panels</u></p> <p>A sample panel size 1m x1m, of each of the various plaster type wall and floor finishes in this contract, shall be prepared for the approval of the Project Manager and the cost of the sample panel(s) shall be deemed to be included in the overall costs of the <u>relevant</u> wall and floor finishes</p> <p><u>GRANOLITHIC</u></p> <p><u>Method:</u></p> <p>The method to be used shall be either the monolithic method or the bonded method</p> <p><u>Preparation:</u></p> <p>For granolithic applied monolithically, the concrete floor shall be swept clean after bleeding of the concrete has ceased and the slab has begun to stiffen; any remaining bleed water shall be removed and the granolithic applied immediately thereafter. For granolithic to be bonded to the floor slab after it has hardened, the slab surface shall be hacked (preferably by mechanical means) until all laitance, dirt, oil, etc is dislodged and swept clean of all loose matter. The slab shall then be wetted and kept damp for at least six hours before applying the granolithic</p> <p><u>Mix:</u></p> <p>Unless otherwise described, granolithic shall attain a compressive strength of at least 41MPa. The coarse aggregate shall comply with SANS 1083 and shall generally be capable of passing a 10mm mesh sieve. Where the thickness of the granolithic exceeds 25mm, the size of the coarse aggregate shall be increased to the maximum size compatible with the thickness of the granolithic</p>				R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>				R

<p style="text-align: center;">Brought Forward</p> <p><u>Panels:</u></p> <p>Granolithic shall be laid in panels not exceeding 14m² for monolithic finishes, not exceeding 9,5m² for bonded finishes and not exceeding 6m² for all external granolithic. Wherever possible, panels shall be square but at no time should the length of the panel exceed 1,5 times its width</p> <p>Where possible joints between panels shall be positioned over joints in the floor slab and shall be at least 3mm wide through the full thickness of the finish, separated by strips of wood or fibreboard and finished with V-joints</p> <p><u>Laying:</u></p> <p>Monolithic granolithic shall be applied to the partially set slab and thoroughly compacted and lightly wood floated to the required levels</p> <p>Bonded granolithic shall be applied to the slab after applying a 1:1 sand-and-cement slurry brushed over the surface and allowed to partially set before applying the granolithic. The granolithic shall be thoroughly compacted and lightly wood floated to the required levels</p> <p>After wood floating, the monolithic and bonded granolithic shall remain undisturbed until bleeding has ceased and the surface has stiffened. Any remaining bleed water and laitance shall then be removed and the surface steel trowelled or power floated</p> <p><u>Curing, seasoning and protection:</u></p> <p>Granolithic shall be covered with clean hessian with waterproof building foil over and kept wet for at least seven days after laying</p> <p><u>Colour:</u></p> <p>Coloured granolithic shall be tinted with an approved colouring pigment mixed into a true and even colour</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>	R	

Brought Forward				R
<u>TINTED WHITE CEMENT SCREEDS</u>				
Tinted screed shall be composed of one bag White Portland Cement and two wheelbarrows "Malmesbury" sand. Surfaces shall be finished with a steel trowel to leave a smooth finish and coated with two coats "Earthcote S.I. Floorcote" two-pack polyurethane floor sealer applied as per the manufacturer's recommendations				
NOTE: Tinted screeds are to be strengthened with "Primal Eccos" acrylic polymer (15% of the water volume is to be substituted with the acrylic polymer during the mixing process)				
Coarse sand is to be used for these screeds				
All tinting, finishing, strengthening, etc are to be mixed, applied, etc strictly in accordance with the manufacturer's instructions				
<u>CEMENT PLASTER</u>				
Unless otherwise described, cement plaster shall be taken to mean Class 1 cement plaster i.e. 1:4 cement:sand plaster (common cement)				

<u>CEMENT SCREEDS TO CONCRETE</u>				
<u>Cement screeds steel trowelled, on concrete:</u>				
1	30mm Thick to floors	m2	17	
<u>SPECIAL FLOOR COATING</u>				
<u>Minimum two coats approved epoxy coat, on concrete:</u>				
2	On screed	m2	17	
Carried Forward				R
Section No. 9 M6 + 3UR Male Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD				

Brought Forward			R
	<p><u>Prepare all surfaces as necessary, prime with "Flowprime" primer and apply 6mm thick anti-slip "Flowcrete Flowfresh HF" or similar approved heavy duty chemical resistant antimicrobial treated polyurethane resin floor screed of approved colour and applied by an approved specialist, on:</u></p>		
3	On internal plastered pit walls and floors	m2	
	<p><u>INTERNAL PLASTER</u></p> <p><u>Cement plaster steel trowelled, on brickwork:</u></p>		
4	On walls	m2	
<p>Carried Forward to Summary of Section No. 9</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.10</u></p> <p><u>PLUMBING AND DRAINAGE</u> <u>(PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Wire gratings:</u></p> <p>Descriptions of gutter outlets, etc shall be deemed to include wire balloon gratings</p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p>			
Carried Forward		R	
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>Stainless steel basins, sinks, wash troughs, urinals, etc:</u></p> <p>Stainless steel for economy basins, domestic sinks and worktops shall be Type 430 (17/0)</p> <p>Stainless steel for urinals, basins, quality sinks, wash troughs, institutional equipment, etc shall be Type 304 (18/8)</p> <p>Stainless steel for laboratory sinks, photographic equipment, etc shall be Type 316 (18/8)</p> <p>Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable</p> <p><u>Sealing of edges:</u></p> <p>Outer edges of sinks, basins, baths, urinals, etc are to be sealed against adjacent surfaces with approved mildew resistant silicone sealant and prices must include therefor</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

<p style="text-align: center;">Brought Forward</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPE) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claims for extra bushes, reducers, etc will be entertained</p> <p><u>Fixing of pipes:</u></p> <p>Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls, etc casting in, building in or suspending not exceeding 1m below suspension level</p> <p><u>Paper wrapping to pipes:</u></p> <p>Pipes chased into brickwork must be wrapped with two layers of stout brown paper tied with wire. Rates are to include for wrapping around joints and fittings</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SANS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SANS 1200L : Medium-pressure pipelines SANS 1200LD : Sewers SANS 1200LE : Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SANS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SANS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

	Brought Forward		R
<p><u>General:</u></p> <p>Descriptions of cast iron roof outlets shall be deemed to include joints to pipes and casting into concrete (adaptors for joints to PVC pipes, etc are given separately)</p> <p>Descriptions of overflow pipes where measured in number, shall be deemed to include joints to cisterns and splay cut ends</p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site</p> <p>Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)</p> <p>Descriptions of WC pans, slop hoppers, etc shall be deemed to include for joints to soil pipes (pan connectors are separately measured) and shall have straight or side outlets and "P" or "S" traps as necessary</p> <p>Description of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.</p> <p><u>As-built drawings:</u></p> <p>Where required, the Contractor shall prepare an updated set of as-built drawings. At completion of the contract the Contractor shall hand these drawings to the Project Manager for reproducing onto the originals for handing over to the Employer (provision for allowance of as-built drawings elsewhere)</p>			
<p style="text-align: right;">Carried Forward</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			R

Brought Forward			R
<u>Proprietary items:</u>			
Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items			
Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.			
Prices are to be based on the specific products/articles specified.			
On request, returnable samples are to be provided to the Project Manager for consideration			

<u>RAINWATER DISPOSAL</u>			
<u>0,6mm Galvanised sheet steel gutters and rainwater pipes with powder coated finish on outside to match roof sheeting colour:</u>			
1	150 x150mm Box gutters	m	16
2	100 x 75mm Rainwater pipes	m	5
3	Extra over gutter for stopped end	No	4
4	Extra over gutter for outlet for 100 x 75mm pipe	No	4
5	Extra over rainwater pipe for bend	No	4
6	Extra over rainwater pipe for shoe	No	4
7	Extra over rainwater pipe for eaves or plinth offset	No	4
Carried Forward			R
Section No. 9 M6 + 3UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Brought Forward				R
<u>SANITARY FITTINGS</u>				
<u>"Vaal" or similar approved:</u>				
8	455 x 290mm "Hibiscus" 7050 wash hand basin bolted to wall	No		
9	"Daisy Elite" 772403 close-coupled WC suite comprising pan with double flap heavy duty thermoset seat (Code: 8531Z0) and matching 9 litre cistern	No		
10	Flat back urinal overall size 295 x 315 x 415mm high with 40mm chromium plated domical grating (Code 878720) and top inlet spreader (Code 8543) with two hanger brackets with flushmaster junior (Code 812720) hung to wall	No	3	
<u>Supply and install "Enviroloo systems" or similar approved:</u>				
11	"Enviro Loo System FG-1040 STDCA/A Standard" strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvered inlets (PL.1), drying plate (PL.2), two x air inlets (PL.3), toilet pan, seat and lid (PL.4), 3500mm long outlet vent pipe (PL.5), ventilation extraction unit (PL.6) fixed to wall with vent wall bracket (PL.7), 1 bag mounting screws and organic starter, enzyme and toilet cleaner (PL.8) including all necessary interconnector piping between multiple tanks, emergency outlet piping, etc	No		
12	"Enviro Loo 2 Pan Urinal Evaporative Tank System code FG-862B " strictly in accordance with manufacturers instructions, unit comprising of urinal evaporative tank (PL.1), urinal bowl (PL.5), 3500mm long outlet vent pipe (PL.3), ventilation extraction unit (PL.3) fixed to wall with vent wall bracket (PL.4), 1 bag mounting screws and organic starter, enzyme and toilet cleaner (PL.8) including all necessary piping, traps, etc	No	1	
Carried Forward				R
Section No. 9 M6 + 3UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

	Brought Forward				R
13	"Enviro Loo 3 Pan Urinal Evaporative Tank System code FG-862B " strictly in accordance with manufacturers instructions, unit comprising of urinal evaporative tank (PL.1), urinal bowl (PL.5), 3500mm long outlet vent pipe (PL.3), ventilation extraction unit (PL.3) fixed to wall with vent wall bracket (PL.4), 1 bag mounting screws and organic starter, enzyme and toilet cleaner (PL.8) including all necessary piping, traps, etc	No	1		
14	"Enviro Loo 4 Pan Urinal Evaporative Tank System code FG-862B " strictly in accordance with manufacturers instructions, unit comprising of urinal evaporative tank (PL.1), urinal bowl (PL.5), 3500mm long outlet vent pipe (PL.3), ventilation extraction unit (PL.3) fixed to wall with vent wall bracket (PL.4), 1 bag mounting screws and organic starter, enzyme and toilet cleaner (PL.8) including all necessary piping, traps, etc	No	1		
	<u>Precast concrete wash trough:</u>				
15	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, including all necessary pipework including soak away approximately 10 meters away from the wash trough, sized at 1000 x 1000 x 1000mm covered with "bidim" complete etc	No			
	<u>BUDGETARY ALLOWANCES</u>				
	<u>SUPERVISION OF INSTALLATION OF "ENVIRO LOO":</u>				
16	Two site visits to be made by the "enviroo loo" suppliers to assist/support the contractor in the installation of the "enviro loo" and a final inspection to be ascertain the enviro loo has been installed correctly at which time a Certificate of Compliance should be issued between Mvula Trust and Enviro Loo Options Limpopo.			Item	
	Carried Forward				R
	Section No. 9 M6 + 3UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

	Brought Forward				R
17	Profit and attendance for the above		Item		
	<u>TRAPS, ETC</u>				
	<u>"Cobra Watertech" or similar approved:</u>				
18	50mm Code 365 CP bottle trap	No			
	<u>uPVC:</u>				
19	40 x 40mm Double bowl wash trough or sink reseal "P" or "S" trap combination	No			
	<u>TAPS, VALVES, ETC</u>				
	<u>"Cobra Watertech" or similar approved:</u>				
20	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No			
21	15mm Code FPT2A1RO-OGP01 "Roma" basin tap with waste union	No			
22	15mm Code 503-21CP elbow action pillar tap	No			
23	19mm chrome plated push button taps to wash troughs	No			
24	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No			
	<u>SANITARY PLUMBING</u>				
	<u>uPVC pipes:</u>				
25	50mm Pipes	m	15		
26	110mm Pipes	m			
	Carried Forward				R
	Section No. 9 M6 + 3UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

Brought Forward				R
27	50mm Diameter pipe laid in and including trenches not exceeding 1m deep	m	45	
28	Ditto, but 110mm diameter	m		
<u>Extra over uPVC pipes for fittings:</u>				
29	50mm Bend	No	6	
30	50mm Junction	No	6	
31	50mm Junction with cleaning eye and lid	No	6	
32	110mm Straight pan connector	No		
33	110mm Bend	No		
34	110mm Junction	No		
35	110mm Reducing junction	No		
36	110mm Access bend	No		
37	110mm Double junction	No		
38	110mm "GI Two-way" vent valve	No		
<u>WATER SUPPLIES</u>				
<u>Class 1 copper pipes with capillary couplings:</u>				
39	15mm Pipe fixed to walls, in chases, etc	m	9	
40	Ditto, but 22mm diameter	m	15	
<u>Extra over Class 1 copper pipes for capillary fittings:</u>				
41	15mm Fittings	No	15	
42	22mm Fittings	No	3	
Carried Forward to Summary of Section No. 9				R
Section No. 9				
M6 + 3UR Male Ablutions				
Bill No. 10				
PLUMBING AND DRAINAGE				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.11</u></p> <p><u>GLAZING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Float glass:</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass:</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p style="text-align: center;">-----</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p>			
<p>Carried Forward</p>		R	
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>			

		Brought Forward			R
1	<p><u>6,38mm Obscure safety glass:</u></p> <p>Panes not exceeding 0,1m²</p>	m2	5		R
<p>Carried Forward to Summary of Section No. 9</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 9</u></p> <p><u>BILL NO.12</u></p> <p><u>PAINTWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and minor cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces:</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
<p><u>Previously painted wood surfaces:</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with "Plascon", etc specifications, unless otherwise described</p> <p><u>COLOURS</u></p> <p>When staining timber, the resultant colour or shade must be to the complete satisfaction of the Project Manager before any overcoating or preservative is applied</p> <p>Paintwork is classified in the following different colour groups: "White", "Pastel", "Deep" and "Transparent" in accordance with the "Natural Colour System" (NCS) adopted by the SA National Standards Unless otherwise described, all paintwork shall be deemed to be classified in the "White" colour group</p> <p style="text-align: center;">-----</p> <p><u>PAINTWORK, ETC TO NEW WORK</u></p> <p><u>ON FIBRE-CEMENT BOARD SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use, on:</u></p>				
<p>1 Fascias and barge boards, including priming metal jointing strips</p>	m2	11		
<p><u>METAL SURFACES WITH</u></p>				
	Carried Forward			R
<p>Section No. 9 M6 + 3UR Male Ablutions Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>				

	Brought Forward			R
	<u>One coat alkyd based zinc phosphate primer and two coats premium quality polyurethane enamel paint, on steel:</u>			
2	Door frames	m2	15	
3	Windows	m2	10	
4	Gates, grilles, burglar screens, balustrades, etc (both sides measured over the full flat area)	m2	7	
5	Extra over for paintwork in the "Deep" colour group	m2	32	
	<u>ON WOOD SURFACES</u>			
	<u>One coat primer, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on:</u>			
6	Doors	m2	29	
7	Roof timbers at eaves and verges	m2	38	
8	Extra over for paintwork in the "Deep" colour group	m2	67	
	Carried Forward to Summary of Section No. 9			R
	Section No. 9			
	M6 + 3UR Male Ablutions			
	Bill No. 12			
	PAINTWORK			
	Diatho Consulting (PTY) LTD			

Bill No	<u>SECTION SUMMARY - M6 + 3UR Male Ablutions</u>	Page No	Amount
1	EARTHWORKS	313	
2	CONCRETE, FORMWORK AND REINFORCEMENT	317	
3	MASONRY	321	
4	WATERPROOFING	323	
5	ROOF COVERINGS	325	
6	CARPENTRY AND JOINERY	328	
7	IRONMONGERY	331	
8	METALWORK	334	
9	PLASTERING	339	
10	PLUMBING AND DRAINAGE	350	
11	GLAZING	352	
12	PAINTWORK	355	
	Carried to Final Summary		R
	Section No. 9 M6 + 3UR Male Ablutions Diatho Consulting (PTY) LTD		

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be included in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p>The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "hard rock" or "soft rock".</p> <p>The nature of the ground is assumed to be gravel, therefore "earth", but possibly interspersed with "soft rock".</p> <p>The nature of the ground is assumed to be silty clay with loose river boulders varying in size up to approximately 450mm diameter, therefore "earth", but possibly interspersed with "hard rock".</p>			
	Carried Forward		R	
	<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p>Trial holes indicate that the nature of the ground is silty clay to a depth of approximately 500mm with fine to medium loose sandy material below, therefore "earth". The trial holes also indicate that the water table is at a maximum depth of approximately 1000mm.</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p><u>Subterranean water:</u></p> <p>No subterranean water is expected</p> <p>Should the Contractor however, encounter any subterranean water on the site, he shall immediately notify the Principal Agent thereof and submit recommendations for keeping the works free from subterranean water together with all costs involved therewith</p> <p><u>Excavation for working space in rock:</u></p> <p>Notwithstanding clause 10 measurement rule 27 of the Standard System of Measuring Building Work, excavation for working space in material of a more different character (e.g. soft or hard rock) will be measured in cubic metres to the extent executed and given as "extra over" bulk excavation or trench and hole excavation as the case may be</p> <p><u>Carting away of excavated material</u></p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>	R	

Brought Forward				R
<u>Filling</u>				
Notwithstanding the reference to prescribed multiple handling in clause 1 page 10 of the Standard System (7th Edition, 2015) of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material				
<u>Testing:</u>				
<i>Prices for backfilling to trenches and holes only are to include for all necessary density tests in accordance with SANS 1200D</i>				

<u>EXCAVATIONS, FILLING, ETC</u>				
<u>EXCAVATIONS, ETC</u>				
<u>Excavation in earth not exceeding 2m deep:</u>				
1	Reduced levels under floors	m3	2	
2	Trenches	m3	8	
3	Trenches and holes for thickening under surface beds, etc	m3	2	
4	Pit	m3	21	
<u>Extra over trench and hole excavations in earth for excavation in:</u>				
5	Soft rock	m3	1	
6	Hard rock	m3	6	
<u>Extra over all excavations for carting away:</u>				
7	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	10	
Carried Forward				R
Section No. 10 M4 +2UR Male Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>Risk of collapse of excavations:</u>			
8	Sides of trench and hole excavations not exceeding 1,5m deep	m2	24
<u>Keeping excavations free of water:</u>			
9	Keeping excavations free of all water other than subterranean water		Item
<u>FILLING ETC</u>			
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 93% Mod AASHTO density:</u>			
10	Backfilling to trenches, holes, etc	m3	3
<u>G5 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>			
11	Under floors, steps, pavings, etc	m3	2
<u>Compaction of surfaces:</u>			
12	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	15
<u>Prescribed density tests on filling:</u>			
13	"Modified AASHTO Density" test	No	3
<u>SOIL POISONING</u>			
<u>Soil insecticide in accordance with SANS 5859:</u>			
14	Soil insecticide (protection against termites) applied as specified under floors, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	15
Carried Forward			R
Section No. 10 M4 +2UR Male Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD			

	Brought Forward				R
15	To bottoms and sides of trenches, etc	m2	38		
Carried Forward to Summary of Section No. 10					
Section No. 10 M4 +2UR Male Ablutions Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD					
					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Cost of tests:</u></p> <p><u>Breeze concrete:</u></p> <p>Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>			R

<p style="text-align: center;">Brought Forward</p> <p><u>Lightweight concrete:</u></p> <p>Lightweight concrete shall have a density of 600kg/m³ for the top 50mm and 400kg/m³ for the remaining thickness. The minimum thickness at outlets, channels, etc shall be 50mm</p> <p><u>Waterproof concrete:</u></p> <p>"Waterproof concrete" shall have the same properties as normal concrete, but the following shall be modified to make the the concrete more water-tight:</p> <ol style="list-style-type: none"> 1. a cement/water ratio of minimum 1.9 and maximum 2.1 2. minimum OPC content of 300kg/m³ 3. Polypropolene micro fibres added to concrete at rate of 182 million per m³ <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself</p> <p>Formwork to soffits of solid slabs, etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described</p> <p>Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described</p> <p style="text-align: center;">-----</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>	R	

Brought Forward				R
<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>15MPa/19mm concrete:</u>				
1	Surface blinding under footings and bases	m3	1	
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>30MPa/19mm concrete:</u>				
	Strip footings	m3	3	
	Surface beds on waterproofing	m3	4	
	Surface beds in tank bottoms	m3	2	
<u>TEST BLOCKS</u>				
2	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	8	
<u>CONCRETE SUNDRIES</u>				
<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>				
3	Surface beds, slabs, etc	m2	15	
<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>				
<u>Rough formwork to sides:</u>				
4	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	40	
<u>MOVEMENT JOINTS, ETC</u>				
Carried Forward				R
Section No. 10 M4 +2UR Male Ablutions Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>Expansion joints with 10mm softboard between vertical concrete and brick surfaces:</u>			
5	Not exceeding 300mm high to edges of surface beds	m	21
<u>Saw-cut joints:</u>			
6	6 x 10mm Saw-cut joints in top of concrete	m	32
<u>REINFORCEMENT (PROVISIONAL)</u>			
<u>Mild steel reinforcement to structural concrete work:</u>			
7	Mild steel bar reinforcement (8 to 40mm diameter bars)	t	0.08
<u>High tensile steel reinforcement to structural concrete work:</u>			
8	High tensile steel bar reinforcement (8 to 40mm diameter bars)	t	0.18
<u>Fabric reinforcement:</u>			
9	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	15
Carried Forward to Summary of Section No. 10			R
Section No. 10			
M4 +2UR Male Ablutions			
Bill No. 2			
CONCRETE, FORMWORK AND REINFORCEMENT			
Diatho Consulting (PTY) LTD			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>General:</u></p> <p>Non-load bearing brickwork is to be built to full height less 20mm gap next to the ceiling and is to be left for 14 days before grouting up in 1:3 cement mortar.</p> <p><u>Sizes in descriptions:</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p>			
<p>Carried Forward</p>		R	
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>Hollow walls:</u></p> <p>Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole</p> <p><u>Bagged and sealed walls:</u></p> <p>Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats bitumen emulsion waterproofing coating</p> <p><u>Face bricks :</u></p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>All face brickwork shall be regularly cleaned down as the work proceeds and shall be protected as necessary by an approved method</p> <p><u>Pointing:</u></p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include smooth floated square recessed, hollow recessed, weathered pointing, etc</p> <p style="text-align: center;">-----</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in class 1 mortar:</u></p>			
1	One brick walls	m2	8	
	<p><u>2,5mm Brickwork reinforcement:</u></p>			
2	150mm Wide reinforcement built in horizontally	m	117	
	Carried Forward			R
	<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
<u>FACE BRICKWORK</u>			
<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
3	Extra over brickwork for face brickwork	m2	3
<u>SUPERSTRUCTURE</u>			
<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar in loadbearing walls etc:</u>			
4	One brick walls	m2	50
<u>BRICKWORK SUNDRIES</u>			
<u>Joint forming material in movement joints:</u>			
5	12mm Fibre board built in vertically through brick walls	m	12
<u>2,5mm Brickwork reinforcement:</u>			
6	75mm Wide reinforcement built in horizontally	m	82
7	150mm Wide reinforcement built in horizontally	m	183
<u>Prestressed fabricated concrete lintels, including necessary temporary supports:</u>			
8	110 x 75mm Lintels in lengths not exceeding 3m long	m	15
<u>FACE BRICKWORK</u>			
<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
9	Half brick wall faced on both sides	m2	28
10	Extra over brickwork for face brickwork	m2	96
Carried Forward			R
Section No. 10 M4 +2UR Male Ablutions Bill No. 3 MASONRY Diatho Consulting (PTY) LTD			

	Brought Forward				R
11	Extra over brickwork for brick-on-edge header course lintel pointed on face and 120mm soffit	m	11		
12	Fair raking cutting	m			
	<u>Brick-on-edge header course coping, sills, etc. of face</u> <u>bricks (Allow a Prime Cost Amount of R5</u> <u>500.00/1000 bricks delivered to site excluding VAT)</u> <u>pointed with recessed joints on all exposed faces</u>				
13	150mm Wide sills set sloping and slightly projecting	m	11		
Carried Forward to Summary of Section No. 10					R
Section No. 10					
M4 +2UR Male Ablutions					
Bill No. 3					
MASONRY					
Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.4</u></p> <p><u>WATERPROOFING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Waterproofing:</u></p> <p>Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets, etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs</p> <p style="text-align: center;">-----</p>			
<p>Carried Forward</p>		R	
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 4 WATERPROOFING Diatho Consulting (PTY) LTD</p>			

Brought Forward						
<u>DAMPPROOFING OF WALLS AND FLOORS</u>						
<u>One layer 375 micron embossed polyethylene dampproof course (SANS 952-1985 type B):</u>						
1	In walls	m2	57			
2	In walls vertically at reveals	m2	9			
<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape:</u>						
3	Under surface beds	m2	18			
<u>JOINT SEALANTS ETC</u>						
<u>Two- part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>						
4	6 x 10mm In saw cut joints in floors	m	32			
<u>White silicone sealing compound including backing cord, bond breaker, primer, etc</u>						
5	6 x 10mm In expansion joints in floors, including raking out expansion joint filler as necessary [LI]	m	21			
Carried Forward to Summary of Section No. 10						
Section No. 10						
M4 +2UR Male Ablutions						
Bill No. 4						
WATERPROOFING						
Diatho Consulting (PTY) LTD						

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.5</u></p> <p><u>ROOF COVERINGS</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Profiled metal roof sheeting and accessories shall be supplied with a 10 year guarantee and be installed by an approved installer</p> <p>All fixing holes shall be drilled and not punched</p> <p>Roof covering accessories shall be manufactured from the same material as used for roof covering</p> <p style="text-align: center;">-----</p> <p><u>PROFILED METAL SHEETING AND ACCESSORIES</u></p>			
Carried Forward		R	
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>			

	Brought Forward		R
	<p><u>0,6 mm "Klip-Lok 406" or similar approved light industrial Z275 spelter galvanised steel sheeting, with "Classicoat" finish one side and half coat "Classicoat Grey" other side, and accessories fixed to timber purlins or rails at approximately 1500mm centres:</u></p>		
1	Roof coverings with pitch not exceeding 25 degrees	m2	
	<p><u>Accessories:</u></p>		
2	Apex flashings 462mm girth	m	
	<p><u>ROOF AND WALL INSULATION</u></p>		
	<p><u>"Sisalation 405" or similar approved residential grade aluminium foil based insulation:</u></p>		
3	Insulation sheeting laid taut over purlins at approximately 1000mm centres and fixed concurrent with roof covering with minimum 150mm stapled laps, including galvanised steel straining wires at not exceeding 400mm centres and double-sided tape at edges where required	m2	
	<p>Carried Forward to Summary of Section No. 10</p>		R
	<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing:</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given separately elsewhere</p> <p><u>Joinery:</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p>			
Carried Forward		R	
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			

Brought Forward			R								
<p>Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts</p> <p><u>Particle board</u></p> <p>All particle board shall comply with SANS 50312 having the required marking as per SANS 50312/EN 312</p> <p><u>Decorative thermosetting plastic laminate covering:</u></p> <p>Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish</p> <p><u>Sizes:</u></p> <p>Sizes are nominal and the Contractor shall make allowance in his prices for minor variances in stated finished sizes of timber doors, door members, door frames, architraves, etc</p> <p><u>Prices</u></p> <p>Prices for all joinery work are to include for general framing, housing and notching, arris rounded angles, glueing, blocking, planting on, screwing, adhesives, dowels, pellets, cross tongues, screws and nails and setting up complete and also for all square cutting and waste. Tops shall be secured with metal or hardwood buttons.</p> <p style="text-align: center;">-----</p> <p><u>ROOFS, ETC</u></p> <p><u>Sawn softwood grade 5:</u></p> <table><tbody><tr><td style="width: 5%;">1</td><td style="width: 85%;">38 x 114mm Wall plates bolted</td><td style="width: 10%;">m</td><td></td></tr><tr><td>2</td><td>38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m</td><td>m</td><td></td></tr></tbody></table>				1	38 x 114mm Wall plates bolted	m		2	38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m	
1	38 x 114mm Wall plates bolted	m									
2	38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m									
Carried Forward			R								
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>											

Brought Forward					
3	50 x 76mm Purlins	m			R
	<u>EAVES, VERGES, ETC</u>				
	<u>Medium density plain fibre-cement fascias and barge boards:</u>				
4	19 x 235mm Fascias and barge boards, including aluminium H-profile jointing strips	m			
	<u>DOORS, ETC</u>				
	<u>Wrought meranti doors hung to steel frames:</u>				
5	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding including 150mm undercut (D2)	No			
6	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1)	No	1		
Carried Forward to Summary of Section No. 10					R
Section No. 10					
M4 +2UR Male Ablutions					
Bill No. 6					
CARPENTRY AND JOINERY					
Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.7</u></p> <p><u>IRONMONGERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			R

Brought Forward			R
<p><u>Locks:</u></p> <p>Notwithstanding Clause 2, Item 3 of the "Ironmongery" trade of the Standard System (7th Edition, 2015) of Measuring Building Work, descriptions of locks shall be deemed to include two keys per lock</p> <p><u>Finishes to ironmongery:</u></p> <p>Where applicable, finishes to ironmongery are indicated by suffixes in accordance with the following list:</p> <p>BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AN Anodised natural AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded BBS Brushed stainless steel</p> <p style="text-align: center;">-----</p> <p><u>CATCHES, CABIN HOOKS, ETC</u></p> <p>1 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged</p> <p style="text-align: right;">No 1</p> <p><u>LOCKS</u></p> <p><u>"Union Assa Abloy" or similar approved:</u></p> <p>2 50mm Brass padlock</p> <p style="text-align: right;">No 7</p> <p>3 Four lever lockset</p> <p style="text-align: right;">No 7</p>			
Carried Forward			R
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

	Brought Forward				
4	"Ref. CZ80941SC" Indicator bolt	No			R
	<u>HANDLES</u>				
	<u>"Union Assa Abloy" or similar approved:</u>				
5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres	Pairs	7.0		
	<u>PUSH PLATES AND KICK PLATES</u>				
	<u>"Union Assa Abloy" or similar approved:</u>				
	<u>1.2mm Thick satin finished "Union" stainless steel plates countersunk screwed along edges at not exceeding 200mm centres</u>				
6	200 x 800mm Type "SS5089-200W" kicking plate	No			
	<u>LETTERS, NAMEPLATES, ETC</u>				
	<u>"Dorma" or similar approved:</u>				
7	DSS-130 Engraved "Male" information sign	No	6		
8	DSS-130 Engraved "Emergency Exit" information sign	No	1		
	<u>SUNDRIES</u>				
9	25mm Diameter wall mounted door stop plugged	No	6		
	<u>BATHROOM FITTINGS</u>				
	<u>"Kimberley-Clark" or similar approved:</u>				
10	"Ref. SQ2 code 405607B" white lockable toilet roll holder	No	4		
Carried Forward to Summary of Section No. 10					R
Section No. 10					
M4 +2UR Male Ablutions					
Bill No. 7					
IRONMONGERY					
Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.8</u></p> <p><u>METALWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions of bolts, anchors, etc:</u></p> <p>Descriptions of bolts shall be deemed to include nuts and washers</p> <p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete</p> <p>Items described as "holed for bolt(s)" shall be deemed to exclude the bolts, unless otherwise described</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres</p>			
Carried Forward		R	
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>			

Brought Forward			R	
<p><u>Fixing:</u></p> <p>Unless otherwise described, descriptions of items shall be deemed to include for fixing to brickwork or concrete</p> <p>Where items are described as "bolted", the bolts are measured elsewhere as stated in clause N.7 of the Model Preambles</p> <p><u>References:</u></p> <p>References in descriptions of windows, doors, gates, etc refer to the respective types of windows, doors, etc detailed in the Architect's window schedules numbered</p> <ul style="list-style-type: none"> • 21111/FSPS/S005 • T-2003 • T-2004 • T-2005 <p>and bound into the back of these bills of quantities</p> <p>Tenderers are to price the following items in conjunction with the above Architect's drawings, etc and no claim arising from brevity of descriptions in these bills of quantities, of items shown on the Architect's drawings, etc shall be entertained</p> <p style="text-align: center;">-----</p>				
Carried Forward			R	
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>				

Brought Forward									
<u>STEEL GATES, SCREENS, ETC</u>									
<u>Welded screens and gates, to brickwalls:</u>									
1	Single gate and frame size to fit standard door, size 813 x 2032mm high	No	6						
<u>PRESSED STEEL DOOR FRAMES</u>									
<u>1,6mm Double rebated frames suitable for half brick walls:</u>									
2	Frame for door size 813 x 2032mm high	No							
<u>1,6mm Double rebated frames suitable for one brick walls:</u>									
3	Frame for door size 813 x 2032mm high	No	6						
<u>STEEL WINDOWS, DOORS, ETC</u>									
<u>Standard windows:</u>									
4	Window type NE1, 533 x 654mm high (N1)	No	5						
5	Window type NE7, 1022 x 654mm high (N2)	No	3						
Carried Forward to Summary of Section No. 10									
Section No. 10									
M4 +2UR Male Ablutions									
Bill No. 8									
METALWORK									
Diatho Consulting (PTY) LTD									

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.9</u></p> <p><u>PLASTERING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Moisture tests:</u></p> <p>Before any finishes, coverings, etc are applied to screeds, plastering, etc or any other in-situ finish, moisture tests are to be carried out to the complete satisfaction of the Project Manager to ensure that these surfaces have the correct moisture content for the finish to be applied</p> <p><u>Labours, etc</u></p> <p>Labours such as fair, rounded and chamfered edges, trowel cuts, throats, V-joints, angles, etc shall be deemed to be included in the descriptions</p>			
Carried Forward		R	
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Sample Panels</u></p> <p>A sample panel size 1m x1m, of each of the various plaster type wall and floor finishes in this contract, shall be prepared for the approval of the Project Manager and the cost of the sample panel(s) shall be deemed to be included in the overall costs of the <u>relevant</u> wall and floor finishes</p> <p><u>GRANOLITHIC</u></p> <p><u>Method:</u></p> <p>The method to be used shall be either the monolithic method or the bonded method</p> <p><u>Preparation:</u></p> <p>For granolithic applied monolithically, the concrete floor shall be swept clean after bleeding of the concrete has ceased and the slab has begun to stiffen; any remaining bleed water shall be removed and the granolithic applied immediately thereafter. For granolithic to be bonded to the floor slab after it has hardened, the slab surface shall be hacked (preferably by mechanical means) until all laitance, dirt, oil, etc is dislodged and swept clean of all loose matter. The slab shall then be wetted and kept damp for at least six hours before applying the granolithic</p> <p><u>Mix:</u></p> <p>Unless otherwise described, granolithic shall attain a compressive strength of at least 41MPa. The coarse aggregate shall comply with SANS 1083 and shall generally be capable of passing a 10mm mesh sieve. Where the thickness of the granolithic exceeds 25mm, the size of the coarse aggregate shall be increased to the maximum size compatible with the thickness of the granolithic</p>				R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>				R

<p style="text-align: center;">Brought Forward</p> <p><u>Panels:</u></p> <p>Granolithic shall be laid in panels not exceeding 14m² for monolithic finishes, not exceeding 9,5m² for bonded finishes and not exceeding 6m² for all external granolithic. Wherever possible, panels shall be square but at no time should the length of the panel exceed 1,5 times its width</p> <p>Where possible joints between panels shall be positioned over joints in the floor slab and shall be at least 3mm wide through the full thickness of the finish, separated by strips of wood or fibreboard and finished with V-joints</p> <p><u>Laying:</u></p> <p>Monolithic granolithic shall be applied to the partially set slab and thoroughly compacted and lightly wood floated to the required levels</p> <p>Bonded granolithic shall be applied to the slab after applying a 1:1 sand-and-cement slurry brushed over the surface and allowed to partially set before applying the granolithic. The granolithic shall be thoroughly compacted and lightly wood floated to the required levels</p> <p>After wood floating, the monolithic and bonded granolithic shall remain undisturbed until bleeding has ceased and the surface has stiffened. Any remaining bleed water and laitance shall then be removed and the surface steel trowelled or power floated</p> <p><u>Curing, seasoning and protection:</u></p> <p>Granolithic shall be covered with clean hessian with waterproof building foil over and kept wet for at least seven days after laying</p> <p><u>Colour:</u></p> <p>Coloured granolithic shall be tinted with an approved colouring pigment mixed into a true and even colour</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>	R	

Brought Forward			R
<u>TINTED WHITE CEMENT SCREEDS</u>			
Tinted screed shall be composed of one bag White Portland Cement and two wheelbarrows "Malmesbury" sand. Surfaces shall be finished with a steel trowel to leave a smooth finish and coated with two coats "Earthcote S.I. Floorcote" two-pack polyurethane floor sealer applied as per the manufacturer's recommendations			
NOTE: Tinted screeds are to be strengthened with "Primal Eccos" acrylic polymer (15% of the water volume is to be substituted with the acrylic polymer during the mixing process)			
Coarse sand is to be used for these screeds			
All tinting, finishing, strengthening, etc are to be mixed, applied, etc strictly in accordance with the manufacturer's instructions			
<u>CEMENT PLASTER</u>			
Unless otherwise described, cement plaster shall be taken to mean Class 1 cement plaster i.e. 1:4 cement:sand plaster (common cement)			

<u>CEMENT SCREEDS TO CONCRETE</u>			
<u>Cement screeds steel trowelled, on concrete:</u>			
1	30mm Thick to floors	m2	15
<u>SPECIAL FLOOR COATING</u>			
<u>Minimum two coats approved epoxy coat, on concrete:</u>			
2	On screed	m2	15
Carried Forward			R
Section No. 10 M4 +2UR Male Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD			

		Brought Forward			R
3	<p><u>Prepare all surfaces as necessary, prime with "Flowprime" primer and apply 6mm thick anti-slip "Flowcrete Flowfresh HF" or similar approved heavy duty chemical resistant antimicrobial treated polyurethane resin floor screed of approved colour and applied by an approved specialist, on:</u></p> <p>On internal plastered pit walls and floors</p>	m2	50		R
<p>Carried Forward to Summary of Section No. 10</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.10</u></p> <p><u>PLUMBING AND DRAINAGE</u> <u>(PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Wire gratings:</u></p> <p>Descriptions of gutter outlets, etc shall be deemed to include wire balloon gratings</p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p>			
<p>Carried Forward</p>		R	
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

	Brought Forward		R
<p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>Stainless steel basins, sinks, wash troughs, urinals, etc:</u></p> <p>Stainless steel for economy basins, domestic sinks and worktops shall be Type 430 (17/0)</p> <p>Stainless steel for urinals, basins, quality sinks, wash troughs, institutional equipment, etc shall be Type 304 (18/8)</p> <p>Stainless steel for laboratory sinks, photographic equipment, etc shall be Type 316 (18/8)</p> <p>Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable</p> <p><u>Sealing of edges:</u></p> <p>Outer edges of sinks, basins, baths, urinals, etc are to be sealed against adjacent surfaces with approved mildew resistant silicone sealant and prices must include therefor</p>			
<p style="text-align: right;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			R

<p style="text-align: center;">Brought Forward</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPE) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claims for extra bushes, reducers, etc will be entertained</p> <p><u>Fixing of pipes:</u></p> <p>Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls, etc casting in, building in or suspending not exceeding 1m below suspension level</p> <p><u>Paper wrapping to pipes:</u></p> <p>Pipes chased into brickwork must be wrapped with two layers of stout brown paper tied with wire. Rates are to include for wrapping around joints and fittings</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SANS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SANS 1200L : Medium-pressure pipelines SANS 1200LD : Sewers SANS 1200LE : Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SANS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SANS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

Brought Forward		R
<p><u>General:</u></p> <p>Descriptions of cast iron roof outlets shall be deemed to include joints to pipes and casting into concrete (adaptors for joints to PVC pipes, etc are given separately)</p> <p>Descriptions of overflow pipes where measured in number, shall be deemed to include joints to cisterns and splay cut ends</p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site</p> <p>Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)</p> <p>Descriptions of WC pans, slop hoppers, etc shall be deemed to include for joints to soil pipes (pan connectors are separately measured) and shall have straight or side outlets and "P" or "S" traps as necessary</p> <p>Description of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.</p> <p><u>As-built drawings:</u></p> <p>Where required, the Contractor shall prepare an updated set of as-built drawings. At completion of the contract the Contractor shall hand these drawings to the Project Manager for reproducing onto the originals for handing over to the Employer (provision for allowance of as-built drawings elsewhere)</p>		
<p>Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R

Brought Forward			R
<u>Proprietary items:</u>			
Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items			
Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.			
Prices are to be based on the specific products/articles specified.			
On request, returnable samples are to be provided to the Project Manager for consideration			

<u>RAINWATER DISPOSAL</u>			
<u>0,6mm Galvanised sheet steel gutters and rainwater pipes with powder coated finish on outside to match roof sheeting colour:</u>			
1	150 x150mm Box gutters	m	12
2	100 x 75mm Rainwater pipes	m	12
3	Extra over gutter for stopped end	No	4
4	Extra over gutter for outlet for 100 x 75mm pipe	No	4
5	Extra over rainwater pipe for bend	No	4
6	Extra over rainwater pipe for shoe	No	4
7	Extra over rainwater pipe for eaves or plinth offset	No	4
Carried Forward			R
Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Brought Forward				R
<u>SANITARY FITTINGS</u>				
<u>"Vaal" or similar approved:</u>				
8	455 x 290mm "Hibiscus" 7050 wash hand basin bolted to wall	No	3	
<u>Supply and install "Enviroloo systems" or similar approved:</u>				
9	"Enviro Loo System FG-1040 STDCA/A Standard" strictly in accordance with manufacturers instructions, unit comprising of top unit and two x louvered inlets (PL.1), drying plate (PL.2), two x air inlets (PL.3), toilet pan, seat and lid (PL.4), 3500mm long outlet vent pipe (PL.5), ventilation extraction unit (PL.6) fixed to wall with vent wall bracket (PL.7), 1 bag mounting screws and organic starter, enzyme and toilet cleaner (PL.8) including all necessary interconnector piping between multiple tanks, emergency outlet piping, etc	No	4	
10	"Enviro Loo 3 Pan Urinal Evaporative Tank System code FG-862B " strictly in accordance with manufacturers instructions, unit comprising of urinal evaporative tank (PL.1), urinal bowl (PL.5), 3500mm long outlet vent pipe (PL.3), ventilation extraction unit (PL.3) fixed to wall with vent wall bracket (PL.4), 1 bag mounting screws and organic starter, enzyme and toilet cleaner (PL.8) including all necessary piping, traps, etc	No	2	
<u>Precast concrete wash trough:</u>				
11	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, including all necessary pipework including soak away approximately 10 meters away from the wash trough, sized at 1000 x 1000 x 1000mm covered with "bidim" complete etc	No	1	
<u>BUDGETARY ALLOWANCES</u>				
Carried Forward				R
Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

Brought Forward									
									R
		<u>SUPERVISION OF INSTALLATION OF "ENVIRO LOO":</u>							
12	Two site visits to be made by the "enviroo loo" suppliers to assist/support the contractor in the installation of the "enviro loo" and a final inspection to be ascertain the enviro loo has been installed correctly at which time a Certificate of Compliance should be issued between Mvula Trust and Enviro Loo Options Limpopo.							Item	
13	Profit and attendance for the above							Item	
		<u>TRAPS, ETC</u>							
		<u>"Cobra Watertech" or similar approved:</u>							
14	50mm Code 365 CP bottle trap	No		3					
		<u>uPVC:</u>							
15	40 x 40mm Double bowl wash trough or sink reseal "P" or "S" trap combination	No		2					
		<u>TAPS, VALVES, ETC</u>							
		<u>"Cobra Watertech" or similar approved:</u>							
16	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No		7					
17	15mm Code FPT2A1RO-OGP01 "Roma" basin tap with waste union	No		4					
18	15mm Code 503-21CP elbow action pillar tap	No		3					
19	19mm chrome plated push button taps to wash troughs	No		2					
20	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No		2					
		Carried Forward							
									R
		Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD							

	Brought Forward				R
	<u>SANITARY PLUMBING</u>				
	<u>uPVC pipes:</u>				
21	50mm Pipes	m	25		
22	110mm Pipes	m	4		
23	50mm Diameter pipe laid in and including trenches not exceeding 1m deep	m	50		
24	Ditto, but 110mm diameter	m	4		
	<u>Extra over uPVC pipes for fittings:</u>				
25	50mm Bend	No	10		
26	50mm Junction	No	10		
27	50mm Junction with cleaning eye and lid	No	10		
28	110mm Straight pan connector	No	4		
29	110mm Bend	No	8		
30	110mm Junction	No	8		
31	110mm Reducing junction	No	12		
32	110mm Access bend	No	4		
33	110mm Double junction	No	4		
34	110mm "GI Two-way" vent valve	No	4		
	<u>WATER SUPPLIES</u>				
	Carried Forward				R
	Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

	Brought Forward			R
	<u>Class 1 copper pipes with capillary couplings:</u>			
35	15mm Pipe fixed to walls, in chases, etc	m	35	
36	Ditto, but 22mm diameter	m	45	
	<u>Extra over Class 1 copper pipes for capillary fittings:</u>			
37	15mm Fittings	No	45	
38	22mm Fittings	No	37	
Carried Forward to Summary of Section No. 10				R
Section No. 10 M4 +2UR Male Ablutions Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.11</u></p> <p><u>GLAZING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Float glass:</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass:</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p style="text-align: center;">-----</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p>			
<p>Carried Forward</p>		R	
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>			

		Brought Forward			R
1	<p><u>6,38mm Obscure safety glass:</u></p> <p>Panes not exceeding 0,1m²</p>	m2	4		R
<p>Carried Forward to Summary of Section No. 10</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 10</u></p> <p><u>BILL NO.12</u></p> <p><u>PAINTWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and minor cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces:</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 10 M4 +2UR Male Ablutions Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>			R

Brought Forward		R
<p><u>Previously painted wood surfaces:</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with "Plascon", etc specifications, unless otherwise described</p> <p><u>COLOURS</u></p> <p>When staining timber, the resultant colour or shade must be to the complete satisfaction of the Project Manager before any overcoating or preservative is applied</p> <p>Paintwork is classified in the following different colour groups: "White", "Pastel", "Deep" and "Transparent" in accordance with the "Natural Colour System" (NCS) adopted by the SA National Standards Unless otherwise described, all paintwork shall be deemed to be classified in the "White" colour group</p> <p style="text-align: center;">-----</p> <p><u>PAINTWORK, ETC TO NEW WORK</u></p> <p><u>ON FIBRE-CEMENT BOARD SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use, on:</u></p>		
1	Fascias and barge boards, including priming metal jointing strips	m2
<p><u>METAL SURFACES WITH</u></p>		
Carried Forward		R
<p>Section No. 10 M4 +2UR Male Ablutions Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>		

	Brought Forward			R
	<u>One coat alkyd based zinc phosphate primer and two coats premium quality polyurethane enamel paint, on steel:</u>			
2	Door frames	m2	11	
3	Windows	m2	7	
4	Gates, grilles, burglar screens, balustrades, etc (both sides measured over the full flat area)	m2	20	
5	Extra over for paintwork in the "Deep" colour group	m2	38	
	<u>ON WOOD SURFACES</u>			
	<u>One coat primer, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on:</u>			
6	Doors	m2	21	
7	Roof timbers at eaves and verges	m2		
8	Extra over for paintwork in the "Deep" colour group	m2	21	
Carried Forward to Summary of Section No. 10				R
Section No. 10				
M4 +2UR Male Ablutions				
Bill No. 12				
PAINTWORK				
Diatho Consulting (PTY) LTD				

Bill No	<u>SECTION SUMMARY - M4 +2UR Male Ablutions</u>	Page No	Amount
1	EARTHWORKS	361	
2	CONCRETE, FORMWORK AND REINFORCEMENT	365	
3	MASONRY	369	
4	WATERPROOFING	371	
5	ROOF COVERINGS	373	
6	CARPENTRY AND JOINERY	376	
7	IRONMONGERY	379	
8	METALWORK	382	
9	PLASTERING	387	
10	PLUMBING AND DRAINAGE	398	
11	GLAZING	400	
12	PAINTWORK	403	
	Carried to Final Summary		R
	Section No. 10 M4 +2UR Male Ablutions Diatho Consulting (PTY) LTD		

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be included in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p>The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "hard rock" or "soft rock".</p> <p>The nature of the ground is assumed to be gravel, therefore "earth", but possibly interspersed with "soft rock".</p> <p>The nature of the ground is assumed to be silty clay with loose river boulders varying in size up to approximately 450mm diameter, therefore "earth", but possibly interspersed with "hard rock".</p>			
	Carried Forward		R	
	<p>Section No. 11 GRD5 Grade R Unisex Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>			

Brought Forward		R
<p>Trial holes indicate that the nature of the ground is silty clay to a depth of approximately 500mm with fine to medium loose sandy material below, therefore "earth". The trial holes also indicate that the water table is at a maximum depth of approximately 1000mm.</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p><u>Subterranean water:</u></p> <p>No subterranean water is expected</p> <p>Should the Contractor however, encounter any subterranean water on the site, he shall immediately notify the Principal Agent thereof and submit recommendations for keeping the works free from subterranean water together with all costs involved therewith</p> <p><u>Excavation for working space in rock:</u></p> <p>Notwithstanding clause 10 measurement rule 27 of the Standard System of Measuring Building Work, excavation for working space in material of a more different character (e.g. soft or hard rock) will be measured in cubic metres to the extent executed and given as "extra over" bulk excavation or trench and hole excavation as the case may be</p> <p><u>Carting away of excavated material</u></p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p>		
<p style="text-align: center;">Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>		R

Brought Forward				R
<u>Filling</u>				
Notwithstanding the reference to prescribed multiple handling in clause 1 page 10 of the Standard System (7th Edition, 2015) of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material				
<u>Testing:</u>				
<i>Prices for backfilling to trenches and holes only are to include for all necessary density tests in accordance with SANS 1200D</i>				

<u>EXCAVATIONS, FILLING, ETC</u>				
<u>EXCAVATIONS, ETC</u>				
<u>Excavation in earth not exceeding 2m deep:</u>				
1	Reduced levels under floors	m3	3	
2	Trenches	m3	9	
3	Trenches and holes for thickening under surface beds, etc	m3	1	
<u>Extra over trench and hole excavations in earth for excavation in:</u>				
4	Soft rock	m3	1	
5	Hard rock	m3	0.4	
<u>Extra over all excavations for carting away:</u>				
6	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	10	
Carried Forward				R
Section No. 11 GRD5 Grade R Unisex Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>Risk of collapse of excavations:</u>			
7	Sides of trench and hole excavations not exceeding 1,5m deep	m2	25
<u>Keeping excavations free of water:</u>			
8	Keeping excavations free of all water other than subterranean water		Item
<u>FILLING ETC</u>			
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 93% Mod AASHTO density:</u>			
9	Backfilling to trenches, holes, etc	m3	3
<u>G5 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>			
10	Under floors, steps, pavings, etc	m3	3
<u>Compaction of surfaces:</u>			
11	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	24
<u>Prescribed density tests on filling:</u>			
12	"Modified AASHTO Density" test	No	10
<u>SOIL POISONING</u>			
<u>Soil insecticide in accordance with SANS 5859:</u>			
13	Soil insecticide (protection against termites) applied as specified under floors, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	24
Carried Forward			R
Section No. 11 GRD5 Grade R Unisex Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD			

		Brought Forward			
14	To bottoms and sides of trenches, etc		m2	40	R
Carried Forward to Summary of Section No. 11					
Section No. 11 GRD5 Grade R Unisex Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Cost of tests:</u></p> <p><u>Breeze concrete:</u></p> <p>Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated</p>			
<p>Carried Forward</p>		R	
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Lightweight concrete:</u></p> <p>Lightweight concrete shall have a density of 600kg/m³ for the top 50mm and 400kg/m³ for the remaining thickness. The minimum thickness at outlets, channels, etc shall be 50mm</p> <p><u>Waterproof concrete:</u></p> <p>"Waterproof concrete" shall have the same properties as normal concrete, but the following shall be modified to make the the concrete more water-tight:</p> <ol style="list-style-type: none"> 1. a cement/water ratio of minimum 1.9 and maximum 2.1 2. minimum OPC content of 300kg/m³ 3. Polypropolene micro fibres added to concrete at rate of 182 million per m³ <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself</p> <p>Formwork to soffits of solid slabs, etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described</p> <p>Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described</p> <p style="text-align: center;">-----</p>		<p>R</p>
<p style="text-align: center;">Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>		<p>R</p>

	Brought Forward			R
	<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
	<u>15MPa/19mm concrete:</u>			
1	Surface blinding under footings and bases	m3	1	
	<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
	<u>30MPa/19mm concrete:</u>			
	Strip footings	m3	3	
	Surface beds on waterproofing	m3	3	
	<u>TEST BLOCKS</u>			
2	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	2	
	<u>CONCRETE SUNDRIES</u>			
	<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>			
3	Surface beds, slabs, etc	m2	20	
	<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>			
	<u>Rough formwork to sides:</u>			
4	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	42	
	<u>MOVEMENT JOINTS, ETC</u>			
	<u>Expansion joints with 10mm softboard between vertical concrete and brick surfaces:</u>			
5	Not exceeding 300mm high to edges of surface beds	m	32	
	Carried Forward			R
	Section No. 11 GRD5 Grade R Unisex Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD			

Brought Forward							
	<u>Saw-cut joints:</u>						R
6	6 x 10mm Saw-cut joints in top of concrete	m	38				
	<u>REINFORCEMENT (PROVISIONAL)</u>						
	<u>Mild steel reinforcement to structural concrete work:</u>						
7	Mild steel bar reinforcement (8 to 40mm diameter bars)	t	0.08				
	<u>High tensile steel reinforcement to structural concrete work:</u>						
8	High tensile steel bar reinforcement (8 to 40mm diameter bars)	t	0.19				
	<u>Fabric reinforcement:</u>						
9	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	20				
Carried Forward to Summary of Section No. 11							R
Section No. 11 GRD5 Grade R Unisex Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD							

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>General:</u></p> <p>Non-load bearing brickwork is to be built to full height less 20mm gap next to the ceiling and is to be left for 14 days before grouting up in 1:3 cement mortar.</p> <p><u>Sizes in descriptions:</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p>			
<p>Carried Forward</p>		R	
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>Hollow walls:</u></p> <p>Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole</p> <p><u>Bagged and sealed walls:</u></p> <p>Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats bitumen emulsion waterproofing coating</p> <p><u>Face bricks :</u></p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>All face brickwork shall be regularly cleaned down as the work proceeds and shall be protected as necessary by an approved method</p> <p><u>Pointing:</u></p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include smooth floated square recessed, hollow recessed, weathered pointing, etc</p> <p style="text-align: center;">-----</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in class 1 mortar:</u></p>			
1	One brick walls	m2	11	
	<p><u>2,5mm Brickwork reinforcement:</u></p>			
2	150mm Wide reinforcement built in horizontally	m	124	
	Carried Forward			R
	<p>Section No. 11 GRD5 Grade R Unisex Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
<u>FACE BRICKWORK</u>			
<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
3	Extra over brickwork for face brickwork	m2	4
<u>SUPERSTRUCTURE</u>			
<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar in loadbearing walls etc:</u>			
4	One brick walls	m2	114
<u>BRICKWORK SUNDRIES</u>			
<u>Joint forming material in movement joints:</u>			
5	12mm Fibre board built in vertically through brick walls	m	97
<u>2,5mm Brickwork reinforcement:</u>			
6	75mm Wide reinforcement built in horizontally	m	52
7	150mm Wide reinforcement built in horizontally	m	357
<u>Prestressed fabricated concrete lintels, including necessary temporary supports:</u>			
8	110 x 75mm Lintels in lengths not exceeding 3m long	m	28
<u>FACE BRICKWORK</u>			
<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
9	Half brick wall faced on both sides	m2	18
10	Extra over brickwork for face brickwork	m2	228
Carried Forward			R
Section No. 11 GRD5 Grade R Unisex Bill No. 3 MASONRY Diatho Consulting (PTY) LTD			

	Brought Forward				R
11	Extra over brickwork for brick-on-edge header course lintel pointed on face and 120mm soffit	m	8		
12	Fair raking cutting	m	10		
	<u>Brick-on-edge header course coping, sills, etc. of face</u> <u>bricks (Allow a Prime Cost Amount of R5</u> <u>500.00/1000 bricks delivered to site excluding VAT)</u> <u>pointed with recessed joints on all exposed faces</u>				
13	150mm Wide sills set sloping and slightly projecting	m	6		
Carried Forward to Summary of Section No. 11					R
Section No. 11					
GRD5 Grade R Unisex					
Bill No. 3					
MASONRY					
Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.4</u></p> <p><u>WATERPROOFING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Waterproofing:</u></p> <p>Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets, etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs</p> <p style="text-align: center;">-----</p>			
<p>Carried Forward</p>		R	
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 4 WATERPROOFING Diatho Consulting (PTY) LTD</p>			

Brought Forward					
<u>DAMPPROOFING OF WALLS AND FLOORS</u>					
<u>One layer 375 micron embossed polyethylene dampproof course (SANS 952-1985 type B):</u>					
1	In walls	m2	60		
2	In walls vertically at reveals	m2	5		
<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape:</u>					
3	Under surface beds	m2	24		
<u>JOINT SEALANTS ETC</u>					
<u>Two- part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>					
4	6 x 10mm In saw cut joints in floors	m	38		
<u>White silicone sealing compound including backing cord, bond breaker, primer, etc</u>					
5	6 x 10mm In expansion joints in floors, including raking out expansion joint filler as necessary [LI]	m	32		
Carried Forward to Summary of Section No. 11					
Section No. 11					
GRD5 Grade R Unisex					
Bill No. 4					
WATERPROOFING					
Diatho Consulting (PTY) LTD					
				R	

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.5</u></p> <p><u>ROOF COVERINGS</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Profiled metal roof sheeting and accessories shall be supplied with a 10 year guarantee and be installed by an approved installer</p> <p>All fixing holes shall be drilled and not punched</p> <p>Roof covering accessories shall be manufactured from the same material as used for roof covering</p> <p style="text-align: center;">-----</p> <p><u>PROFILED METAL SHEETING AND ACCESSORIES</u></p>			
Carried Forward		R	
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>			

Brought Forward		R
<p><u>0,6 mm "Klip-Lok 406" or similar approved light industrial Z275 spelter galvanised steel sheeting, with "Classicoat" finish one side and half coat "Classicoat Grey" other side, and accessories fixed to timber purlins or rails at approximately 1500mm centres:</u></p>		
1	Roof coverings with pitch not exceeding 25 degrees	m2 29
<p><u>Accessories:</u></p>		
2	Apex flashings 462mm girth	m 16
<p><u>ROOF AND WALL INSULATION</u></p>		
<p><u>"Sisalation 405" or similar approved residential grade aluminium foil based insulation:</u></p>		
3	Insulation sheeting laid taut over purlins at approximately 1000mm centres and fixed concurrent with roof covering with minimum 150mm stapled laps, including galvanised steel straining wires at not exceeding 400mm centres and double-sided tape at edges where required	m2 29
<p>Carried Forward to Summary of Section No. 11</p>		R
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing:</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given separately elsewhere</p> <p><u>Joinery:</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p>			
Carried Forward		R	
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			

Brought Forward				R
Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts				
<u>Particle board</u>				
All particle board shall comply with SANS 50312 having the required marking as per SANS 50312/EN 312				
<u>Decorative thermosetting plastic laminate covering:</u>				
Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish				
<u>Sizes:</u>				
Sizes are nominal and the Contractor shall make allowance in his prices for minor variances in stated finished sizes of timber doors, door members, door frames, architraves, etc				
<u>Prices</u>				
Prices for all joinery work are to include for general framing, housing and notching, arris rounded angles, glueing, blocking, planting on, screwing, adhesives, dowels, pellets, cross tongues, screws and nails and setting up complete and also for all square cutting and waste. Tops shall be secured with metal or hardwood buttons.				

<u>ROOFS, ETC</u>				
<u>Sawn softwood grade 5:</u>				
1 38 x 114mm Wall plates bolted	m		27	
2 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m		85	
Carried Forward				R
Section No. 11 GRD5 Grade R Unisex Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD				

Brought Forward				R
3	50 x 76mm Purlins	m	88	
<u>EAVES, VERGES, ETC</u>				
<u>Medium density plain fibre-cement fascias and barge boards:</u>				
4	19 x 235mm Fascias and barge boards, including aluminium H-profile jointing strips	m	26	
<u>DOORS, ETC</u>				
<u>Wrought meranti doors hung to steel frames:</u>				
5	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding including 150mm undercut (D2)	No	5	
6	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1)	No	2	
Carried Forward to Summary of Section No. 11				R
Section No. 11				
GRD5 Grade R Unisex				
Bill No. 6				
CARPENTRY AND JOINERY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.7</u></p> <p><u>IRONMONGERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
	<p><u>Locks:</u></p> <p>Notwithstanding Clause 2, Item 3 of the "Ironmongery" trade of the Standard System (7th Edition, 2015) of Measuring Building Work, descriptions of locks shall be deemed to include two keys per lock</p> <p><u>Finishes to ironmongery:</u></p> <p>Where applicable, finishes to ironmongery are indicated by suffixes in accordance with the following list:</p> <p>BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AN Anodised natural AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded BBS Brushed stainless steel</p> <p style="text-align: center;">-----</p> <p><u>CATCHES, CABIN HOOKS, ETC</u></p> <p>1 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged</p> <p><u>LOCKS</u></p> <p><u>"Union Assa Abloy" or similar approved:</u></p> <p>2 50mm Brass padlock</p> <p>3 Four lever lockset</p>	No	5	
	Carried Forward			R
	<p>Section No. 11 GRD5 Grade R Unisex Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

Brought Forward					
4	"Ref. CZ80941SC" Indicator bolt	No	5		R
	<u>HANDLES</u>				
	<u>"Union Assa Abloy" or similar approved:</u>				
5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres	Pairs	2.0		
	<u>PUSH PLATES AND KICK PLATES</u>				
	<u>"Union Assa Abloy" or similar approved:</u>				
	<u>1.2mm Thick satin finished "Union" stainless steel plates countersunk screwed along edges at not exceeding 200mm centres</u>				
6	200 x 800mm Type "SS5089-200W" kicking plate	No	14		
	<u>DOOR CLOSERS</u>				
	<u>"Dorma" or similar approved:</u>				
7	"Dorma" TS73N/EN3-4 parallel arm door closer delayed closing-push side fitting.	No	1		
	<u>LETTERS, NAMEPLATES, ETC</u>				
	<u>"Dorma" or similar approved:</u>				
8	DSS-131 Engraved "Grade R" information sign, plugged	No	2		
	<u>SUNDRIES</u>				
9	25mm Diameter wall mounted door stop plugged	No	7		
	<u>BATHROOM FITTINGS</u>				
Carried Forward					R
Section No. 11 GRD5 Grade R Unisex Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD					

	Brought Forward				
	<u>"Vaal Paragon" or similar approved</u>				R
10	32mm Type 9 back grab rail 800mm long plugged	No	1		
11	32mm Type 8 side grab rail 900mm girth plugged	No	1		
	<u>"Kimberley-Clark" or similar approved:</u>				
12	"Ref. SQ2 code 405607B" white lockable toilet roll holder	No	6		
13	Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc	No	3		
Carried Forward to Summary of Section No. 11					R
Section No. 11 GRD5 Grade R Unisex Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.8</u></p> <p><u>METALWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions of bolts, anchors, etc:</u></p> <p>Descriptions of bolts shall be deemed to include nuts and washers</p> <p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete</p> <p>Items described as "holed for bolt(s)" shall be deemed to exclude the bolts, unless otherwise described</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres</p>			
Carried Forward		R	
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>			

Brought Forward			R	
<p><u>Fixing:</u></p> <p>Unless otherwise described, descriptions of items shall be deemed to include for fixing to brickwork or concrete</p> <p>Where items are described as "bolted", the bolts are measured elsewhere as stated in clause N.7 of the Model Preambles</p> <p><u>References:</u></p> <p>References in descriptions of windows, doors, gates, etc refer to the respective types of windows, doors, etc detailed in the Architect's window schedules numbered</p> <ul style="list-style-type: none"> • 21111/FSPS/S005 • T-2003 • T-2004 • T-2005 <p>and bound into the back of these bills of quantities</p> <p>Tenderers are to price the following items in conjunction with the above Architect's drawings, etc and no claim arising from brevity of descriptions in these bills of quantities, of items shown on the Architect's drawings, etc shall be entertained</p> <p style="text-align: center;">-----</p>				
Carried Forward			R	
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>				

Brought Forward		R
<u>STEEL GATES, SCREENS, ETC</u>		
<u>Welded screens and gates, to brickwalls:</u>		
1	Single gate and frame size to fit standard door, size 813 x 2032mm high	No 2
<u>PRESSED STEEL DOOR FRAMES</u>		
<u>1,6mm Double rebated frames suitable for half brick walls:</u>		
2	Frame for door size 813 x 2032mm high	No 5
<u>1,6mm Double rebated frames suitable for one brick walls:</u>		
3	Frame for door size 813 x 2032mm high	No 2
<u>STEEL WINDOWS, DOORS, ETC</u>		
<u>Standard windows:</u>		
4	Window type NE1, 533 x 654mm high (N1)	No 6
5	Window type NE7, 1022 x 654mm high (N2)	No 3
Carried Forward to Summary of Section No. 11		R
Section No. 11		
GRD5 Grade R Unisex		
Bill No. 8		
METALWORK		
Diatho Consulting (PTY) LTD		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.9</u></p> <p><u>PLASTERING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Moisture tests:</u></p> <p>Before any finishes, coverings, etc are applied to screeds, plastering, etc or any other in-situ finish, moisture tests are to be carried out to the complete satisfaction of the Project Manager to ensure that these surfaces have the correct moisture content for the finish to be applied</p> <p><u>Labours, etc</u></p> <p>Labours such as fair, rounded and chamfered edges, trowel cuts, throats, V-joints, angles, etc shall be deemed to be included in the descriptions</p>			
Carried Forward		R	
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Sample Panels</u></p> <p>A sample panel size 1m x1m, of each of the various plaster type wall and floor finishes in this contract, shall be prepared for the approval of the Project Manager and the cost of the sample panel(s) shall be deemed to be included in the overall costs of the <u>relevant</u> wall and floor finishes</p> <p><u>GRANOLITHIC</u></p> <p><u>Method:</u></p> <p>The method to be used shall be either the monolithic method or the bonded method</p> <p><u>Preparation:</u></p> <p>For granolithic applied monolithically, the concrete floor shall be swept clean after bleeding of the concrete has ceased and the slab has begun to stiffen; any remaining bleed water shall be removed and the granolithic applied immediately thereafter. For granolithic to be bonded to the floor slab after it has hardened, the slab surface shall be hacked (preferably by mechanical means) until all laitance, dirt, oil, etc is dislodged and swept clean of all loose matter. The slab shall then be wetted and kept damp for at least six hours before applying the granolithic</p> <p><u>Mix:</u></p> <p>Unless otherwise described, granolithic shall attain a compressive strength of at least 41MPa. The coarse aggregate shall comply with SANS 1083 and shall generally be capable of passing a 10mm mesh sieve. Where the thickness of the granolithic exceeds 25mm, the size of the coarse aggregate shall be increased to the maximum size compatible with the thickness of the granolithic</p>				R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>				R

<p style="text-align: center;">Brought Forward</p> <p><u>Panels:</u></p> <p>Granolithic shall be laid in panels not exceeding 14m² for monolithic finishes, not exceeding 9,5m² for bonded finishes and not exceeding 6m² for all external granolithic. Wherever possible, panels shall be square but at no time should the length of the panel exceed 1,5 times its width</p> <p>Where possible joints between panels shall be positioned over joints in the floor slab and shall be at least 3mm wide through the full thickness of the finish, separated by strips of wood or fibreboard and finished with V-joints</p> <p><u>Laying:</u></p> <p>Monolithic granolithic shall be applied to the partially set slab and thoroughly compacted and lightly wood floated to the required levels</p> <p>Bonded granolithic shall be applied to the slab after applying a 1:1 sand-and-cement slurry brushed over the surface and allowed to partially set before applying the granolithic. The granolithic shall be thoroughly compacted and lightly wood floated to the required levels</p> <p>After wood floating, the monolithic and bonded granolithic shall remain undisturbed until bleeding has ceased and the surface has stiffened. Any remaining bleed water and laitance shall then be removed and the surface steel trowelled or power floated</p> <p><u>Curing, seasoning and protection:</u></p> <p>Granolithic shall be covered with clean hessian with waterproof building foil over and kept wet for at least seven days after laying</p> <p><u>Colour:</u></p> <p>Coloured granolithic shall be tinted with an approved colouring pigment mixed into a true and even colour</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>	R	

	Brought Forward			R
	<p><u>TINTED WHITE CEMENT SCREEDS</u></p> <p>Tinted screed shall be composed of one bag White Portland Cement and two wheelbarrows "Malmesbury" sand. Surfaces shall be finished with a steel trowel to leave a smooth finish and coated with two coats "Earthcote S.I. Floorcote" two-pack polyurethane floor sealer applied as per the manufacturer's recommendations</p> <p>NOTE: Tinted screeds are to be strengthened with "Primal Eccos" acrylic polymer (15% of the water volume is to be substituted with the acrylic polymer during the mixing process)</p> <p>Coarse sand is to be used for these screeds</p> <p>All tinting, finishing, strengthening, etc are to be mixed, applied, etc strictly in accordance with the manufacturer's instructions</p> <p><u>CEMENT PLASTER</u></p> <p>Unless otherwise described, cement plaster shall be taken to mean Class 1 cement plaster i.e. 1:4 cement:sand plaster (common cement)</p> <p style="text-align: center;">-----</p> <p><u>CEMENT SCREEDS TO CONCRETE</u></p> <p><u>Cement screeds steel trowelled, on concrete:</u></p> <p>1 30mm Thick to floors m2 20</p> <p><u>FLOOR AND WALL SEALERS</u></p> <p><u>Minimum two coats approved epoxy coat, on concrete:</u></p> <p>2 On screed m2 20</p>			R
	<p>Carried Forward to Summary of Section No. 11</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.10</u></p> <p><u>PLUMBING AND DRAINAGE</u> <u>(PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Wire gratings:</u></p> <p>Descriptions of gutter outlets, etc shall be deemed to include wire balloon gratings</p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p>			
<p>Carried Forward</p>		R	
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>Stainless steel basins, sinks, wash troughs, urinals, etc:</u></p> <p>Stainless steel for economy basins, domestic sinks and worktops shall be Type 430 (17/0)</p> <p>Stainless steel for urinals, basins, quality sinks, wash troughs, institutional equipment, etc shall be Type 304 (18/8)</p> <p>Stainless steel for laboratory sinks, photographic equipment, etc shall be Type 316 (18/8)</p> <p>Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable</p> <p><u>Sealing of edges:</u></p> <p>Outer edges of sinks, basins, baths, urinals, etc are to be sealed against adjacent surfaces with approved mildew resistant silicone sealant and prices must include therefor</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

<p style="text-align: center;">Brought Forward</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPE) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claims for extra bushes, reducers, etc will be entertained</p> <p><u>Fixing of pipes:</u></p> <p>Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls, etc casting in, building in or suspending not exceeding 1m below suspension level</p> <p><u>Paper wrapping to pipes:</u></p> <p>Pipes chased into brickwork must be wrapped with two layers of stout brown paper tied with wire. Rates are to include for wrapping around joints and fittings</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SANS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SANS 1200L : Medium-pressure pipelines SANS 1200LD : Sewers SANS 1200LE : Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SANS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SANS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

Brought Forward		R
<p><u>General:</u></p> <p>Descriptions of cast iron roof outlets shall be deemed to include joints to pipes and casting into concrete (adaptors for joints to PVC pipes, etc are given separately)</p> <p>Descriptions of overflow pipes where measured in number, shall be deemed to include joints to cisterns and splay cut ends</p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site</p> <p>Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)</p> <p>Descriptions of WC pans, slop hoppers, etc shall be deemed to include for joints to soil pipes (pan connectors are separately measured) and shall have straight or side outlets and "P" or "S" traps as necessary</p> <p>Description of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.</p> <p><u>As-built drawings:</u></p> <p>Where required, the Contractor shall prepare an updated set of as-built drawings. At completion of the contract the Contractor shall hand these drawings to the Project Manager for reproducing onto the originals for handing over to the Employer (provision for allowance of as-built drawings elsewhere)</p>		
<p>Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R

Brought Forward			R
<u>Proprietary items:</u>			
Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items			
Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.			
Prices are to be based on the specific products/articles specified.			
On request, returnable samples are to be provided to the Project Manager for consideration			

<u>RAINWATER DISPOSAL</u>			
<u>0,6mm Galvanised sheet steel gutters and rainwater pipes with powder coated finish on outside to match roof sheeting colour:</u>			
1	150 x150mm Box gutters	m	8
2	100 x 75mm Rainwater pipes	m	3
3	Extra over gutter for stopped end	No	2
4	Extra over gutter for outlet for 100 x 75mm pipe	No	3
5	Extra over rainwater pipe for bend	No	3
6	Extra over rainwater pipe for shoe	No	3
7	Extra over rainwater pipe for eaves or plinth offset	No	3
Carried Forward			R
Section No. 11 GRD5 Grade R Unisex Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Brought Forward		R
<u>SANITARY FITTINGS</u>		
<u>"Vaal" or similar approved:</u>		
8	455 x 290mm "Hibiscus" 7050 wash hand basin bolted to wall	No 1
9	"Daisy Elite" 772403 close-coupled WC suite comprising pan with double flap heavy duty thermoset seat (Code: 8531Z0) and matching 9 litre cistern	No 5
10	"Pearl Paraplegic" 7300SC paraplegic WC suite with lid, fittings, purpose made CP side flush lever and purpose made double flap white epoxy painted wooden seat	No 1
<u>Precast concrete wash trough:</u>		
11	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, including all necessary pipework including soak away approximately 10 meters away from the wash trough, sized at 1000 x 1000 x 1000mm covered with "bidim" complete etc	No 1
<u>TRAPS, ETC</u>		
<u>uPVC:</u>		
12	40 x 40mm Double bowl wash trough or sink reseal "P" or "S" trap combination	No 1
<u>"Cobra Watertech" or similar approved:</u>		
13	50mm Code 365 CP bottle trap	No 1
<u>TAPS, VALVES, ETC</u>		
<u>"Cobra Watertech" or similar approved:</u>		
14	19mm chrome plated push button taps to wash troughs	No 1
Carried Forward		R
Section No. 11 GRD5 Grade R Unisex Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD		

Brought Forward			R
15	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No	7
16	15mm Code 503-21CP elbow action pillar tap	No	1
<u>SANITARY PLUMBING</u>			
<u>uPVC pipes:</u>			
17	50mm Pipes	m	5
18	110mm Pipes	m	6
19	50mm Diameter pipe laid in and including trenches not exceeding 1m deep	m	7
20	Ditto, but 110mm diameter	m	6
<u>Extra over uPVC pipes for fittings:</u>			
21	50mm Bend	No	2
22	50mm Junction	No	2
23	50mm Junction with cleaning eye and lid	No	2
24	110mm Straight pan connector	No	6
25	110mm Bend	No	12
26	110mm Junction	No	12
27	110mm Reducing junction	No	18
28	110mm Access bend	No	6
29	110mm Double junction	No	6
30	110mm "GI Two-way" vent valve	No	6
Carried Forward			R
Section No. 11 GRD5 Grade R Unisex Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

	Brought Forward			R
	<u>Testing:</u>			
31	Testing waste pipe system		Item	
	<u>WATER SUPPLIES</u>			
	<u>Class 1 copper pipes with capillary couplings:</u>			
32	15mm Pipe fixed to walls, in chases, etc	m	21	
33	Ditto, but 22mm diameter	m	35	
	<u>Extra over Class 1 copper pipes for capillary fittings:</u>			
34	15mm Fittings	No	35	
35	22mm Fittings	No	35	
	<u>Testing:</u>			
36	Testing water pipe system		Item	
Carried Forward to Summary of Section No. 11				R
Section No. 11 GRD5 Grade R Unisex Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.11</u></p> <p><u>GLAZING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Float glass:</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass:</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p style="text-align: center;">-----</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p>			
<p>Carried Forward</p>		R	
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>			

		Brought Forward			R
	<u>6,38mm Obscure safety glass:</u>				
1	Panes not exceeding 0,1m ²	m2	4		
Carried Forward to Summary of Section No. 11					R
Section No. 11					
GRD5 Grade R Unisex					
Bill No. 11					
GLAZING					
Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 11</u></p> <p><u>BILL NO.12</u></p> <p><u>PAINTWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and minor cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces:</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p style="text-align: right;">Carried Forward</p> <p>Section No. 11 GRD5 Grade R Unisex Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward		R
<p><u>Previously painted wood surfaces:</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with "Plascon", etc specifications, unless otherwise described</p> <p><u>COLOURS</u></p> <p>When staining timber, the resultant colour or shade must be to the complete satisfaction of the Project Manager before any overcoating or preservative is applied</p> <p>Paintwork is classified in the following different colour groups: "White", "Pastel", "Deep" and "Transparent" in accordance with the "Natural Colour System" (NCS) adopted by the SA National Standards Unless otherwise described, all paintwork shall be deemed to be classified in the "White" colour group</p> <p style="text-align: center;">-----</p> <p><u>PAINTWORK, ETC TO NEW WORK</u></p> <p><u>ON FIBRE-CEMENT BOARD SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use, on:</u></p>			
1	Fascias and barge boards, including priming metal jointing strips	m2	7
<p><u>METAL SURFACES WITH</u></p>			
Carried Forward			R
<p>Section No. 11 GRD5 Grade R Unisex Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<u>One coat alkyd based zinc phosphate primer and two coats premium quality polyurethane enamel paint, on steel:</u>			
2	Door frames	m2	13	
3	Windows	m2	8	
4	Gates, grilles, burglar screens, balustrades, etc (both sides measured over the full flat area)	m2	7	
5	Extra over for paintwork in the "Deep" colour group	m2	28	
	<u>ON WOOD SURFACES</u>			
	<u>One coat primer, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on:</u>			
6	Doors	m2	25	
7	Roof timbers at eaves and verges	m2	56	
8	Extra over for paintwork in the "Deep" colour group	m2	225	
	Carried Forward to Summary of Section No. 11			R
	Section No. 11			
	GRD5 Grade R Unisex			
	Bill No. 12			
	PAINTWORK			
	Diatho Consulting (PTY) LTD			

Bill No	<u>SECTION SUMMARY - GRD5 Grade R Unisex</u>	Page No	Amount
1	EARTHWORKS	409	
2	CONCRETE, FORMWORK AND REINFORCEMENT	413	
3	MASONRY	417	
4	WATERPROOFING	419	
5	ROOF COVERINGS	421	
6	CARPENTRY AND JOINERY	424	
7	IRONMONGERY	428	
8	METALWORK	431	
9	PLASTERING	435	
10	PLUMBING AND DRAINAGE	445	
11	GLAZING	447	
12	PAINTWORK	450	
	Carried to Final Summary		R
	Section No. 11 GRD5 Grade R Unisex Diatho Consulting (PTY) LTD		

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be included in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground</u></p> <p>The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "hard rock" or "soft rock".</p> <p>The nature of the ground is assumed to be gravel, therefore "earth", but possibly interspersed with "soft rock".</p> <p>The nature of the ground is assumed to be silty clay with loose river boulders varying in size up to approximately 450mm diameter, therefore "earth", but possibly interspersed with "hard rock".</p>			
Carried Forward		R	
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>			

Brought Forward	R
<p>Trial holes indicate that the nature of the ground is silty clay to a depth of approximately 500mm with fine to medium loose sandy material below, therefore "earth". The trial holes also indicate that the water table is at a maximum depth of approximately 1000mm.</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p><u>Subterranean water:</u></p> <p>No subterranean water is expected</p> <p>Should the Contractor however, encounter any subterranean water on the site, he shall immediately notify the Principal Agent thereof and submit recommendations for keeping the works free from subterranean water together with all costs involved therewith</p> <p><u>Excavation for working space in rock:</u></p> <p>Notwithstanding clause 10 measurement rule 27 of the Standard System of Measuring Building Work, excavation for working space in material of a more different character (e.g. soft or hard rock) will be measured in cubic metres to the extent executed and given as "extra over" bulk excavation or trench and hole excavation as the case may be</p> <p><u>Carting away of excavated material</u></p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p>	R
Carried Forward	R
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>	

Brought Forward				R
<u>Filling</u>				
Notwithstanding the reference to prescribed multiple handling in clause 1 page 10 of the Standard System (7th Edition, 2015) of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material				
<u>Testing:</u>				
<i>Prices for backfilling to trenches and holes only are to include for all necessary density tests in accordance with SANS 1200D</i>				

<u>EXCAVATIONS, FILLING, ETC</u>				
<u>EXCAVATIONS, ETC</u>				
<u>Excavation in earth not exceeding 2m deep:</u>				
1	Reduced levels under floors	m3	2	
2	Trenches	m3	7	
3	Trenches and holes for thickening under surface beds, etc	m3	1	
<u>Extra over trench and hole excavations in earth for excavation in:</u>				
4	Soft rock	m3	1	
5	Hard rock	m3	0.4	
<u>Extra over all excavations for carting away:</u>				
6	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	8	
Carried Forward				R
Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>Risk of collapse of excavations:</u>			
7	Sides of trench and hole excavations not exceeding 1,5m deep	m2	21
<u>Keeping excavations free of water:</u>			
8	Keeping excavations free of all water other than subterranean water		Item
<u>FILLING ETC</u>			
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 93% Mod AASHTO density:</u>			
9	Backfilling to trenches, holes, etc	m3	3
<u>G5 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>			
10	Under floors, steps, pavings, etc	m3	2
<u>Compaction of surfaces:</u>			
11	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	16
<u>Prescribed density tests on filling:</u>			
12	"Modified AASHTO Density" test	No	6
<u>SOIL POISONING</u>			
<u>Soil insecticide in accordance with SANS 5859:</u>			
13	Soil insecticide (protection against termites) applied as specified under floors, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	16
Carried Forward			R
Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD			

14	<p style="text-align: right;">Brought Forward</p> <p>To bottoms and sides of trenches, etc</p> <p style="text-align: right;">Carried Forward to Summary of Section No. 12</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 1 EARTHWORKS Diatho Consulting (PTY) LTD</p>	m2	34	R	
----	---	----	----	---	--

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.2</u></p> <p><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Cost of tests:</u></p> <p><u>Breeze concrete:</u></p> <p>Breeze concrete shall consist of twelve parts clean dry furnace ash, free from coal or other foreign matter, to one part cement (1:12); the ash graded up to particles which will pass a 16,5mm ring from a minimum which fails to pass a 4,75mm mesh. The finer materials from the screening are to be first mixed with the cement into a mortar and the ash added afterwards and thoroughly incorporated</p>			
Carried Forward		R	
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Lightweight concrete:</u></p> <p>Lightweight concrete shall have a density of 600kg/m³ for the top 50mm and 400kg/m³ for the remaining thickness. The minimum thickness at outlets, channels, etc shall be 50mm</p> <p><u>Waterproof concrete:</u></p> <p>"Waterproof concrete" shall have the same properties as normal concrete, but the following shall be modified to make the the concrete more water-tight:</p> <ol style="list-style-type: none"> 1. a cement/water ratio of minimum 1.9 and maximum 2.1 2. minimum OPC content of 300kg/m³ 3. Polypropolene micro fibres added to concrete at rate of 182 million per m³ <p><u>Formwork:</u></p> <p>Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use</p> <p>The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself</p> <p>Formwork to soffits of solid slabs, etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described</p> <p>Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described</p> <p style="text-align: center;">-----</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD</p>	R	

Brought Forward				R
<u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>15MPa/19mm concrete:</u>				
1	Surface blinding under footings and bases	m3	1	
<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>				
<u>30MPa/19mm concrete:</u>				
	Strip footings	m3	3	
	Surface beds on waterproofing	m3	2	
<u>TEST BLOCKS</u>				
2	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	2	
<u>CONCRETE SUNDRIES</u>				
<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>				
3	Surface beds, slabs, etc	m2	12	
<u>ROUGH FORMWORK (DEGREE OF ACCURACY III)</u>				
<u>Rough formwork to sides:</u>				
4	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	35	
<u>MOVEMENT JOINTS, ETC</u>				
<u>Expansion joints with 10mm softboard between vertical concrete and brick surfaces:</u>				
5	Not exceeding 300mm high to edges of surface beds	m	23	
Carried Forward				R
Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD				

Brought Forward							
	<u>Saw-cut joints:</u>						R
6	6 x 10mm Saw-cut joints in top of concrete	m	27				
	<u>REINFORCEMENT (PROVISIONAL)</u>						
	<u>Mild steel reinforcement to structural concrete work:</u>						
7	Mild steel bar reinforcement (8 to 40mm diameter bars)	t	0.07				
	<u>High tensile steel reinforcement to structural concrete work:</u>						
8	High tensile steel bar reinforcement (8 to 40mm diameter bars)	t	0.16				
	<u>Fabric reinforcement:</u>						
9	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	12				
Carried Forward to Summary of Section No. 12 Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT Diatho Consulting (PTY) LTD							R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.3</u></p> <p><u>MASONRY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>BRICKWORK</u></p> <p><u>General:</u></p> <p>Non-load bearing brickwork is to be built to full height less 20mm gap next to the ceiling and is to be left for 14 days before grouting up in 1:3 cement mortar.</p> <p><u>Sizes in descriptions:</u></p> <p>Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick</p>			
<p>Carried Forward</p>		R	
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>Hollow walls:</u></p> <p>Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole</p> <p><u>Bagged and sealed walls:</u></p> <p>Walls in two skins described as "bagged and sealed" shall be deemed to include having the outer face of the inner skin bagged with 1:6 cement and sand mixture and sealed with two coats bitumen emulsion waterproofing coating</p> <p><u>Face bricks :</u></p> <p>Bricks shall be ordered timeously to obtain uniformity in size and colour</p> <p>All face brickwork shall be regularly cleaned down as the work proceeds and shall be protected as necessary by an approved method</p> <p><u>Pointing:</u></p> <p>Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include smooth floated square recessed, hollow recessed, weathered pointing, etc</p> <p style="text-align: center;">-----</p> <p><u>FOUNDATIONS (PROVISIONAL)</u></p> <p><u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in class 1 mortar:</u></p>			
1	One brick walls	m2	9	
	<p><u>2,5mm Brickwork reinforcement:</u></p>			
2	150mm Wide reinforcement built in horizontally	m	104	
	Carried Forward			R
	<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 3 MASONRY Diatho Consulting (PTY) LTD</p>			

Brought Forward			R
<u>FACE BRICKWORK</u>			
<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
3	Extra over brickwork for face brickwork	m2	3
<u>SUPERSTRUCTURE</u>			
<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar in loadbearing walls etc:</u>			
4	One brick walls	m2	115
<u>BRICKWORK SUNDRIES</u>			
<u>Joint forming material in movement joints:</u>			
5	12mm Fibre board built in vertically through brick walls	m	94
<u>2,5mm Brickwork reinforcement:</u>			
6	75mm Wide reinforcement built in horizontally	m	52
7	150mm Wide reinforcement built in horizontally	m	356
<u>Prestressed fabricated concrete lintels, including necessary temporary supports:</u>			
8	110 x 75mm Lintels in lengths not exceeding 3m long	m	31
<u>FACE BRICKWORK</u>			
<u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u>			
9	Half brick wall faced on both sides	m2	18
10	Extra over brickwork for face brickwork	m2	230
Carried Forward			R
Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 3 MASONRY Diatho Consulting (PTY) LTD			

	Brought Forward			R
11	Extra over brickwork for brick-on-edge header course lintel pointed on face and 120mm soffit	m	6	
12	Fair raking cutting	m	10	
	<u>Brick-on-edge header course coping, sills, etc. of face</u> <u>bricks (Allow a Prime Cost Amount of R5</u> <u>500.00/1000 bricks delivered to site excluding VAT)</u> <u>pointed with recessed joints on all exposed faces</u>			
13	150mm Wide sills set sloping and slightly projecting	m	5	
Carried Forward to Summary of Section No. 12				R
Section No. 12				
GR 5 Grade R Unisex Ablution				
Bill No. 3				
MASONRY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.4</u></p> <p><u>WATERPROOFING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Waterproofing:</u></p> <p>Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets, etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs</p> <p style="text-align: center;">-----</p>			
<p>Carried Forward</p>		R	
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 4 WATERPROOFING Diatho Consulting (PTY) LTD</p>			

Brought Forward							
<u>DAMPPROOFING OF WALLS AND FLOORS</u>							
<u>One layer 375 micron embossed polyethylene dampproof course (SANS 952-1985 type B):</u>							
1	In walls	m2	50				R
2	In walls vertically at reveals	m2	3				
<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape:</u>							
3	Under surface beds	m2	12				
<u>JOINT SEALANTS ETC</u>							
<u>Two- part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>							
4	6 x 10mm In saw cut joints in floors	m	27				
<u>White silicone sealing compound including backing cord, bond breaker, primer, etc</u>							
5	6 x 10mm In expansion joints in floors, including raking out expansion joint filler as necessary [LI]	m	23				
Carried Forward to Summary of Section No. 12							
Section No. 12							
GR 5 Grade R Unisex Ablution							
Bill No. 4							
WATERPROOFING							
Diatho Consulting (PTY) LTD							
							R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.5</u></p> <p><u>ROOF COVERINGS</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Profiled metal roof sheeting and accessories shall be supplied with a 10 year guarantee and be installed by an approved installer</p> <p>All fixing holes shall be drilled and not punched</p> <p>Roof covering accessories shall be manufactured from the same material as used for roof covering</p> <p style="text-align: center;">-----</p> <p><u>PROFILED METAL SHEETING AND ACCESSORIES</u></p>			
Carried Forward		R	
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>			

	Brought Forward			R
	<p><u>0,6 mm "Klip-Lok 406" or similar approved light industrial Z275 spelter galvanised steel sheeting, with "Classicoat" finish one side and half coat "Classicoat Grey" other side, and accessories fixed to timber purlins or rails at approximately 1500mm centres:</u></p>			
1	Roof coverings with pitch not exceeding 25 degrees	m2	21	
	<p><u>Accessories:</u></p>			
2	Apex flashings 462mm girth	m	12	
	<p><u>ROOF AND WALL INSULATION</u></p> <p><u>"Sisalation 405" or similar approved residential grade aluminium foil based insulation:</u></p>			
3	Insulation sheeting laid taut over purlins at approximately 1000mm centres and fixed concurrent with roof covering with minimum 150mm stapled laps, including galvanised steel straining wires at not exceeding 400mm centres and double-sided tape at edges where required	m2	21	
<p>Carried Forward to Summary of Section No. 12</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 5 ROOF COVERINGS Diatho Consulting (PTY) LTD</p>				<p>R</p>

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.6</u></p> <p><u>CARPENTRY AND JOINERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Fixing:</u></p> <p>Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins, or to be shot-pinned, to brickwork or concrete</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 500mm centres, and where described as "bolted", the bolts have been given separately elsewhere</p> <p><u>Joinery:</u></p> <p>Descriptions of frames shall be deemed to include frames, transomes, rails, etc</p>			
Carried Forward		R	
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD</p>			

Brought Forward				R
Descriptions of hardwood joinery shall be deemed to include sinking and pelleting heads and nuts of bolts				
<u>Particle board</u>				
All particle board shall comply with SANS 50312 having the required marking as per SANS 50312/EN 312				
<u>Decorative thermosetting plastic laminate covering:</u>				
Laminate covering shall be glued under pressure and edge strips of same shall be butt jointed at junctions with adjacent similar finish				
<u>Sizes:</u>				
Sizes are nominal and the Contractor shall make allowance in his prices for minor variances in stated finished sizes of timber doors, door members, door frames, architraves, etc				
<u>Prices</u>				
Prices for all joinery work are to include for general framing, housing and notching, arris rounded angles, glueing, blocking, planting on, screwing, adhesives, dowels, pellets, cross tongues, screws and nails and setting up complete and also for all square cutting and waste. Tops shall be secured with metal or hardwood buttons.				

<u>ROOFS, ETC</u>				
<u>Sawn softwood grade 5:</u>				
1 38 x 114mm Wall plates bolted	m	27		
2 38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m	85		
Carried Forward				R
Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 6 CARPENTRY AND JOINERY Diatho Consulting (PTY) LTD				

Brought Forward				R
3	50 x 76mm Purlins	m	88	
<u>EAVES, VERGES, ETC</u>				
<u>Medium density plain fibre-cement fascias and barge boards:</u>				
4	19 x 235mm Fascias and barge boards, including aluminium H-profile jointing strips	m	22	
<u>DOORS, ETC</u>				
<u>Wrought meranti doors hung to steel frames:</u>				
5	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding including 150mm undercut (D2)	No	1	
6	44mm Framed batten door 813 x 2032mm high of 44 x 150mm top rail and stiles, 22 x 150mm middle ledge and braces and 22 x 220mm bottom rail filled in with 22mm V-jointed one side boarding and including weatherboard (D1)	No	5	
Carried Forward to Summary of Section No. 12				R
Section No. 12				
GR 5 Grade R Unisex Ablution				
Bill No. 6				
CARPENTRY AND JOINERY				
Diatho Consulting (PTY) LTD				

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.7</u></p> <p><u>IRONMONGERY</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Proprietary items:</u></p> <p>Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items</p> <p>Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.</p> <p>Prices are to be based on the specific products/articles specified.</p> <p>On request, returnable samples are to be provided to the Project Manager for consideration</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
	<p><u>Locks:</u></p> <p>Notwithstanding Clause 2, Item 3 of the "Ironmongery" trade of the Standard System (7th Edition, 2015) of Measuring Building Work, descriptions of locks shall be deemed to include two keys per lock</p> <p><u>Finishes to ironmongery:</u></p> <p>Where applicable, finishes to ironmongery are indicated by suffixes in accordance with the following list:</p> <p>BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AN Anodised natural AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded BBS Brushed stainless steel</p> <p style="text-align: center;">-----</p> <p><u>CATCHES, CABIN HOOKS, ETC</u></p> <p>1 150mm Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged</p> <p style="text-align: right; margin-right: 20px;">No 5</p> <p><u>LOCKS</u></p> <p><u>"Union Assa Abloy" or similar approved:</u></p> <p>2 50mm Brass padlock</p> <p style="text-align: right; margin-right: 20px;">No 1</p> <p>3 Four lever lockset</p> <p style="text-align: right; margin-right: 20px;">No 1</p>			
	Carried Forward			R
	<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD</p>			

Brought Forward				R
4	"Ref. CZ80941SC" Indicator bolt	No	5	
	<u>HANDLES</u>			
	<u>"Union Assa Abloy" or similar approved:</u>			
5	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres	Pairs	1.0	
	<u>PUSH PLATES AND KICK PLATES</u>			
	<u>"Union Assa Abloy" or similar approved:</u>			
	<u>1.2mm Thick satin finished "Union" stainless steel plates countersunk screwed along edges at not exceeding 200mm centres</u>			
6	200 x 800mm Type "SS5089-200W" kicking plate	No	6	
	<u>DOOR CLOSERS</u>			
	<u>"Dorma" or similar approved:</u>			
7	"Dorma" TS73N/EN3-4 parallel arm door closer delayed closing-push side fitting.	No	1	
	<u>LETTERS, NAMEPLATES, ETC</u>			
	<u>"Dorma" or similar approved:</u>			
8	DSS-131 Engraved "Grade R" information sign, plugged	No	1	
	<u>SUNDRIES</u>			
9	25mm Diameter wall mounted door stop plugged	No	6	
	<u>BATHROOM FITTINGS</u>			
Carried Forward				R
Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 7 IRONMONGERY Diatho Consulting (PTY) LTD				

	Brought Forward			R
	<u>"Kimberley-Clark" or similar approved:</u>			
10	"Ref. SQ2 code 405607B" white lockable toilet roll holder	No	5	
11	Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc	No	2	
Carried Forward to Summary of Section No. 12				
Section No. 12				
GR 5 Grade R Unisex Ablution				
Bill No. 7				
IRONMONGERY				
Diatho Consulting (PTY) LTD				
				R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.8</u></p> <p><u>METALWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Descriptions of bolts, anchors, etc:</u></p> <p>Descriptions of bolts shall be deemed to include nuts and washers</p> <p>Descriptions of expansion anchors and bolts and chemical anchors and bolts shall be deemed to include nuts, washers and mortices in brickwork or concrete</p> <p>Items described as "holed for bolt(s)" shall be deemed to exclude the bolts, unless otherwise described</p> <p>Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres</p>			
<p>Carried Forward</p>		R	
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>			

	Brought Forward		R
<p><u>Fixing:</u></p> <p>Unless otherwise described, descriptions of items shall be deemed to include for fixing to brickwork or concrete</p> <p>Where items are described as "bolted", the bolts are measured elsewhere as stated in clause N.7 of the Model Preambles</p> <p><u>References:</u></p> <p>References in descriptions of windows, doors, gates, etc refer to the respective types of windows, doors, etc detailed in the Architect's window schedules numbered</p> <ul style="list-style-type: none"> • 21111/FSPS/S005 • T-2003 • T-2004 • T-2005 <p>and bound into the back of these bills of quantities</p> <p>Tenderers are to price the following items in conjunction with the above Architect's drawings, etc and no claim arising from brevity of descriptions in these bills of quantities, of items shown on the Architect's drawings, etc shall be entertained</p> <p style="text-align: center;">-----</p>			
<p style="text-align: right;">Carried Forward</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 8 METALWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward					
	<u>STEEL GATES, SCREENS, ETC</u>					R
	<u>Welded screens and gates, to brickwalls:</u>					
1	Single gate and frame size to fit standard door, size 813 x 2032mm high	No	1			
	<u>PRESSED STEEL DOOR FRAMES</u>					
	<u>1,6mm Double rebated frames suitable for half brick walls:</u>					
2	Frame for door size 813 x 2032mm high	No	5			
	<u>1,6mm Double rebated frames suitable for one brick walls:</u>					
3	Frame for door size 813 x 2032mm high	No	1			
	<u>STEEL WINDOWS, DOORS, ETC</u>					
	<u>Standard windows:</u>					
4	Window type NE1, 533 x 654mm high (N1)	No	5			
5	Window type NE7, 1022 x 654mm high (N2)	No	2			
	Carried Forward to Summary of Section No. 12					R
	Section No. 12					
	GR 5 Grade R Unisex Ablution					
	Bill No. 8					
	METALWORK					
	Diatho Consulting (PTY) LTD					

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.9</u></p> <p><u>PLASTERING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Moisture tests:</u></p> <p>Before any finishes, coverings, etc are applied to screeds, plastering, etc or any other in-situ finish, moisture tests are to be carried out to the complete satisfaction of the Project Manager to ensure that these surfaces have the correct moisture content for the finish to be applied</p> <p><u>Labours, etc</u></p> <p>Labours such as fair, rounded and chamfered edges, trowel cuts, throats, V-joints, angles, etc shall be deemed to be included in the descriptions</p>			
Carried Forward		R	
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>Sample Panels</u></p> <p>A sample panel size 1m x1m, of each of the various plaster type wall and floor finishes in this contract, shall be prepared for the approval of the Project Manager and the cost of the sample panel(s) shall be deemed to be included in the overall costs of the <u>relevant</u> wall and floor finishes</p> <p><u>GRANOLITHIC</u></p> <p><u>Method:</u></p> <p>The method to be used shall be either the monolithic method or the bonded method</p> <p><u>Preparation:</u></p> <p>For granolithic applied monolithically, the concrete floor shall be swept clean after bleeding of the concrete has ceased and the slab has begun to stiffen; any remaining bleed water shall be removed and the granolithic applied immediately thereafter. For granolithic to be bonded to the floor slab after it has hardened, the slab surface shall be hacked (preferably by mechanical means) until all laitance, dirt, oil, etc is dislodged and swept clean of all loose matter. The slab shall then be wetted and kept damp for at least six hours before applying the granolithic</p> <p><u>Mix:</u></p> <p>Unless otherwise described, granolithic shall attain a compressive strength of at least 41MPa. The coarse aggregate shall comply with SANS 1083 and shall generally be capable of passing a 10mm mesh sieve. Where the thickness of the granolithic exceeds 25mm, the size of the coarse aggregate shall be increased to the maximum size compatible with the thickness of the granolithic</p>				R
<p style="text-align: center;">Carried Forward</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>				R

<p style="text-align: center;">Brought Forward</p> <p><u>Panels:</u></p> <p>Granolithic shall be laid in panels not exceeding 14m² for monolithic finishes, not exceeding 9,5m² for bonded finishes and not exceeding 6m² for all external granolithic. Wherever possible, panels shall be square but at no time should the length of the panel exceed 1,5 times its width</p> <p>Where possible joints between panels shall be positioned over joints in the floor slab and shall be at least 3mm wide through the full thickness of the finish, separated by strips of wood or fibreboard and finished with V-joints</p> <p><u>Laying:</u></p> <p>Monolithic granolithic shall be applied to the partially set slab and thoroughly compacted and lightly wood floated to the required levels</p> <p>Bonded granolithic shall be applied to the slab after applying a 1:1 sand-and-cement slurry brushed over the surface and allowed to partially set before applying the granolithic. The granolithic shall be thoroughly compacted and lightly wood floated to the required levels</p> <p>After wood floating, the monolithic and bonded granolithic shall remain undisturbed until bleeding has ceased and the surface has stiffened. Any remaining bleed water and laitance shall then be removed and the surface steel trowelled or power floated</p> <p><u>Curing, seasoning and protection:</u></p> <p>Granolithic shall be covered with clean hessian with waterproof building foil over and kept wet for at least seven days after laying</p> <p><u>Colour:</u></p> <p>Coloured granolithic shall be tinted with an approved colouring pigment mixed into a true and even colour</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>	R	

	Brought Forward			R
	<p><u>TINTED WHITE CEMENT SCREEDS</u></p> <p>Tinted screed shall be composed of one bag White Portland Cement and two wheelbarrows "Malmesbury" sand. Surfaces shall be finished with a steel trowel to leave a smooth finish and coated with two coats "Earthcote S.I. Floorcote" two-pack polyurethane floor sealer applied as per the manufacturer's recommendations</p> <p>NOTE: Tinted screeds are to be strengthened with "Primal Eccos" acrylic polymer (15% of the water volume is to be substituted with the acrylic polymer during the mixing process)</p> <p>Coarse sand is to be used for these screeds</p> <p>All tinting, finishing, strengthening, etc are to be mixed, applied, etc strictly in accordance with the manufacturer's instructions</p> <p><u>CEMENT PLASTER</u></p> <p>Unless otherwise described, cement plaster shall be taken to mean Class 1 cement plaster i.e. 1:4 cement:sand plaster (common cement)</p> <p style="text-align: center;">-----</p> <p><u>CEMENT SCREEDS TO CONCRETE</u></p> <p><u>Cement screeds steel trowelled, on concrete:</u></p>			
1	30mm Thick to floors	m2	12	
	<p><u>FLOOR AND WALL SEALERS</u></p> <p><u>Minimum two coats approved epoxy coat, on concrete:</u></p>			
2	On screed	m2	12	
	<p>Carried Forward to Summary of Section No. 12</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 9 PLASTERING Diatho Consulting (PTY) LTD</p>			R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.10</u></p> <p><u>PLUMBING AND DRAINAGE</u> <u>(PROVISIONAL)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Wire gratings:</u></p> <p>Descriptions of gutter outlets, etc shall be deemed to include wire balloon gratings</p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p>			
<p>Carried Forward</p>		R	
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			

<p style="text-align: center;">Brought Forward</p> <p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>Stainless steel basins, sinks, wash troughs, urinals, etc:</u></p> <p>Stainless steel for economy basins, domestic sinks and worktops shall be Type 430 (17/0)</p> <p>Stainless steel for urinals, basins, quality sinks, wash troughs, institutional equipment, etc shall be Type 304 (18/8)</p> <p>Stainless steel for laboratory sinks, photographic equipment, etc shall be Type 316 (18/8)</p> <p>Units shall have standard aprons on all exposed edges and tiling keys against walls where applicable</p> <p><u>Sealing of edges:</u></p> <p>Outer edges of sinks, basins, baths, urinals, etc are to be sealed against adjacent surfaces with approved mildew resistant silicone sealant and prices must include therefor</p>		R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		R	

<p style="text-align: center;">Brought Forward</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPe) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

Brought Forward		R
<p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016. Only compression fittings shall be used in walls or in ground</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claims for extra bushes, reducers, etc will be entertained</p> <p><u>Fixing of pipes:</u></p> <p>Unless specifically otherwise stated, descriptions of pipes shall be deemed to include fixing to walls, etc casting in, building in or suspending not exceeding 1m below suspension level</p> <p><u>Paper wrapping to pipes:</u></p> <p>Pipes chased into brickwork must be wrapped with two layers of stout brown paper tied with wire. Rates are to include for wrapping around joints and fittings</p>		
Carried Forward		R
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>		

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SANS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SANS 1200L : Medium-pressure pipelines SANS 1200LD : Sewers SANS 1200LE : Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SANS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SANS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>	R	

	Brought Forward		R
<p><u>General:</u></p> <p>Descriptions of cast iron roof outlets shall be deemed to include joints to pipes and casting into concrete (adaptors for joints to PVC pipes, etc are given separately)</p> <p>Descriptions of overflow pipes where measured in number, shall be deemed to include joints to cisterns and splay cut ends</p> <p>Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site</p> <p>Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)</p> <p>Descriptions of WC pans, slop hoppers, etc shall be deemed to include for joints to soil pipes (pan connectors are separately measured) and shall have straight or side outlets and "P" or "S" traps as necessary</p> <p>Description of waste unions shall be deemed to include rubber or vulcanite plugs and chains fixed to fittings.</p> <p><u>As-built drawings:</u></p> <p>Where required, the Contractor shall prepare an updated set of as-built drawings. At completion of the contract the Contractor shall hand these drawings to the Project Manager for reproducing onto the originals for handing over to the Employer (provision for allowance of as-built drawings elsewhere)</p>			
<p style="text-align: right;">Carried Forward</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD</p>			R

Brought Forward			R
<u>Proprietary items:</u>			
Where applicable, the manufacturers' names or product catalogue titles are given in sub-headings preceding the items			
Note that the manufacturers names specified in this trade are for the purposes of competitive pricing.			
Prices are to be based on the specific products/articles specified.			
On request, returnable samples are to be provided to the Project Manager for consideration			

<u>RAINWATER DISPOSAL</u>			
<u>0,6mm Galvanised sheet steel gutters and rainwater pipes with powder coated finish on outside to match roof sheeting colour:</u>			
1	150 x150mm Box gutters	m	6
2	100 x 75mm Rainwater pipes	m	3
3	Extra over gutter for stopped end	No	4
4	Extra over gutter for outlet for 100 x 75mm pipe	No	3
5	Extra over rainwater pipe for bend	No	3
6	Extra over rainwater pipe for shoe	No	3
7	Extra over rainwater pipe for eaves or plinth offset	No	3
Carried Forward			R
Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Brought Forward				R
<u>SANITARY FITTINGS</u>				
<u>"Vaal" or similar approved:</u>				
8	455 x 290mm "Hibiscus" 7050 wash hand basin bolted to wall	No	3	
9	"Daisy Elite" 772403 close-coupled WC suite comprising pan with double flap heavy duty thermoset seat (Code: 8531Z0) and matching 9 litre cistern	No	5	
<u>Precast concrete wash trough:</u>				
10	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, including all necessary pipework including soak away approximately 10 meters away from the wash trough, sized at 1000 x 1000 x 1000mm covered with "bidim" complete etc	No	3	
<u>TRAPS, ETC</u>				
<u>uPVC:</u>				
11	40 x 40mm Double bowl wash trough or sink reseal "P" or "S" trap combination	No	3	
<u>"Cobra Watertech" or similar approved:</u>				
12	50mm Code 365 CP bottle trap	No	3	
<u>TAPS, VALVES, ETC</u>				
<u>"Cobra Watertech" or similar approved:</u>				
13	19mm chrome plated push button taps to wash troughs	No	6	
14	15mm Code 232/350 FCP angle regulating valve and flexible connection pipe	No	14	
15	15mm Code 503-21CP elbow action pillar tap	No	3	
Carried Forward				R
Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

		Brought Forward		R
<u>SANITARY PLUMBING</u>				
<u>uPVC pipes:</u>				
16	50mm Pipes	m	30	
17	110mm Pipes	m	5	
18	50mm Diameter pipe laid in and including trenches not exceeding 1m deep	m	39	
19	Ditto, but 110mm diameter	m	5	
<u>Extra over uPVC pipes for fittings:</u>				
20	50mm Bend	No	12	
21	50mm Junction	No	12	
22	50mm Junction with cleaning eye and lid	No	12	
23	110mm Straight pan connector	No	5	
24	110mm Bend	No	10	
25	110mm Junction	No	10	
26	110mm Reducing junction	No	15	
27	110mm Access bend	No	5	
28	110mm Double junction	No	5	
29	110mm "GI Two-way" vent valve	No	5	
<u>Testing:</u>				
30	Testing waste pipe system		Item	
		Carried Forward		R
Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>WATER SUPPLIES</u>			
<u>Class 1 copper pipes with capillary couplings:</u>			
31	15mm Pipe fixed to walls, in chases, etc	m	33
32	Ditto, but 22mm diameter	m	55
<u>Extra over Class 1 copper pipes for capillary fittings:</u>			
33	15mm Fittings	No	55
34	22mm Fittings	No	55
<u>Testing:</u>			
35	Testing water pipe system		Item
Carried Forward to Summary of Section No. 12			R
Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 10 PLUMBING AND DRAINAGE Diatho Consulting (PTY) LTD			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.11</u></p> <p><u>GLAZING</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Float glass:</u></p> <p>The term "float glass" is used for monolithic annealed glass</p> <p><u>Laminated glass:</u></p> <p>Laminated glass to have polyvinyl butyral (PVB) interlayer(s)</p> <p style="text-align: center;">-----</p> <p><u>GLAZING TO STEEL WITH PUTTY</u></p>			
<p>Carried Forward</p>		R	
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>			

		Brought Forward			R
1	<p><u>6,38mm Obscure safety glass:</u></p> <p>Panes not exceeding 0,1m²</p>	m2	3		R
<p>Carried Forward to Summary of Section No. 12</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 11 GLAZING Diatho Consulting (PTY) LTD</p>					R

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 12</u></p> <p><u>BILL NO.12</u></p> <p><u>PAINTWORK</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>PREPARATORY WORK TO EXISTING WORK</u></p> <p><u>Previously painted plastered surfaces:</u></p> <p>Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and minor cracks shall be opened, filled with a suitable filler and finished smooth</p> <p><u>Previously painted metal surfaces:</u></p> <p>Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal</p> <p style="text-align: right;">Carried Forward</p> <p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>			R

	Brought Forward			R
<p><u>Previously painted wood surfaces:</u></p> <p>Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth</p> <p><u>PAINT SPECIFICATIONS</u></p> <p>All painting shall be done in accordance with "Plascon", etc specifications, unless otherwise described</p> <p><u>COLOURS</u></p> <p>When staining timber, the resultant colour or shade must be to the complete satisfaction of the Project Manager before any overcoating or preservative is applied</p> <p>Paintwork is classified in the following different colour groups: "White", "Pastel", "Deep" and "Transparent" in accordance with the "Natural Colour System" (NCS) adopted by the SA National Standards Unless otherwise described, all paintwork shall be deemed to be classified in the "White" colour group</p> <p style="text-align: center;">-----</p> <p><u>PAINTWORK, ETC TO NEW WORK</u></p> <p><u>ON FIBRE-CEMENT BOARD SURFACES</u></p> <p><u>One coat alkali resistant primer and two coats superior quality acrylic emulsion paint for interior and exterior use, on:</u></p>				
<p>1 Fascias and barge boards, including priming metal jointing strips</p>	m2	5		
<p><u>METAL SURFACES WITH</u></p>				
	Carried Forward			R
<p>Section No. 12 GR 5 Grade R Unisex Ablution Bill No. 12 PAINTWORK Diatho Consulting (PTY) LTD</p>				

	Brought Forward			R
	<u>One coat alkyd based zinc phosphate primer and two coats premium quality polyurethane enamel paint, on steel:</u>			
2	Door frames	m2	11	
3	Windows	m2	6	
4	Gates, grilles, burglar screens, balustrades, etc (both sides measured over the full flat area)	m2	3	
5	Extra over for paintwork in the "Deep" colour group	m2	11	
	<u>ON WOOD SURFACES</u>			
	<u>One coat primer, one coat alkyd based universal undercoat and two coats superior quality universal enamel paint, on:</u>			
6	Doors	m2	21	
7	Roof timbers at eaves and verges	m2	56	
8	Extra over for paintwork in the "Deep" colour group	m2	221	
	Carried Forward to Summary of Section No. 12			R
	Section No. 12			
	GR 5 Grade R Unisex Ablution			
	Bill No. 12			
	PAINTWORK			
	Diatho Consulting (PTY) LTD			

Bill No	<u>SECTION SUMMARY - GR 5 Grade R Unisex Ablution</u>	Page No	Amount
1	EARTHWORKS	456	
2	CONCRETE, FORMWORK AND REINFORCEMENT	460	
3	MASONRY	464	
4	WATERPROOFING	466	
5	ROOF COVERINGS	468	
6	CARPENTRY AND JOINERY	471	
7	IRONMONGERY	475	
8	METALWORK	478	
9	PLASTERING	482	
10	PLUMBING AND DRAINAGE	492	
11	GLAZING	494	
12	PAINTWORK	497	
Carried to Final Summary			R
Section No. 12 GR 5 Grade R Unisex Ablution Diatho Consulting (PTY) LTD			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 13</u></p> <p><u>BILL NO.1</u></p> <p><u>EXTERNAL WORK (PROVISIONAL)</u></p> <p><u>(ALL TRADES)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The Model Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p>Labour Intensive Methods:</p> <p>The contractor will be required to use labour intensive for items which have been marked with the letters [LI] in the Scope of Work.</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Nature of ground:</u></p> <p>The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "soft rock" or "hard rock"</p>			
Carried Forward			R
<p>Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD</p>			

Brought Forward	R
<p>The nature of the ground is assumed to be gravel, therefore "earth", but possibly interspersed with "soft rock" or "hard rock"</p> <p>The nature of the ground is assumed to be silty clay with loose river boulders varying in size up to approximately 450mm diameter, all of which will be deemed as "earth", but possibly interspersed with "hard rock"</p> <p>Trial holes indicate that the nature of the ground is silty clay to a depth of approximately 500mm with fine to medium loose sandy material below, therefore "earth"</p> <p>A soils investigation has been carried out on the site by the Engineer and the report is annexed to these bills of quantities. The soils report indicates that the ground varies between transported soils at surface comprising gravel layers of varying thickness and interspersed with clay, and weathered shales varying from very soft rock to medium hard rock consistency, all of which will be deemed as "earth". All very hard unweathered shale, ironstone, etc the removal of which necessitates the use of explosives or heavy duty hydraulic percussion hammers (peckers), will be classified as "hard rock"</p> <p>Should the Contractor encounter any "soft" or "hard" rock in the excavations, he shall immediately notify the Engineer who shall be the sole arbiter as to what constitutes "soft" or "hard" rock for final account purposes</p> <p><u>Subterranean water:</u></p> <p>No subterranean water is expected</p> <p><u>Excavation for working space in rock:</u></p> <p>Notwithstanding clause 11 of the Standard System of Measuring Building Work, excavation for working space in rock will be measured in cubic metres to the extent executed and given as "extra over" bulk excavation or trench and hole excavation as the case may be</p>	R
Carried Forward	R
<p>Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD</p>	

Brought Forward				R
<u>Carting away of excavated material:</u>				
Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site				
<u>Filling:</u>				
Notwithstanding the reference to prescribed multiple handling in Clause 1 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any necessary multiple handling of material				
<u>Testing:</u>				
<i>Prices for backfilling to trenches and holes only are to include for all necessary density tests in accordance with SANS 1200D</i>				
<u>Maintenance period:</u>				
The maintenance period to civil works such as roads, parking and related earthworks shall be twelve calendar months				

<u>SITE CLEARANCE, ETC</u>				
<u>Site clearance:</u>				
1 Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush, etc and trees not exceeding 200mm girth	m2	696		
2 Stripping average 150mm thick layer of top soil and depositing material in prescribed stock piles on site	m2	696		
Carried Forward				R
Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD				

Brought Forward				R
<u>REMOVAL OF TREES, ETC</u>				
3	Tree stump exceeding 200mm and not exceeding 500mm girth	No	5	
<u>PAVINGS, ETC</u>				
<u>SUPPLEMENTARY PREAMBLES</u>				
<u>Testing of material and filling:</u>				
Descriptions of earth filling, compaction, etc shall be deemed to include for all necessary testing required in accordance with the SABS 1200 series				
<u>EARTHWORKS</u>				
<u>Excavation in earth not exceeding 2m deep:</u>				
4	Over site under paving etc to reduce levels and dispose in prescribed stock piles on site	m3	119	
<u>Extra over all excavations for carting away:</u>				
5	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	119	
<u>Compaction of surfaces:</u>				
6	Rip and re-compact in-situ materials to a depth of 150mm, breaking down over size material and reconsolidate to 93% modified AASHTO density	m2	266	
<u>Keeping excavations free of water:</u>				
7	Keeping excavations free of all water other than subterranean water		Item	
Carried Forward				R
Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>C4 filling supplied and carted on by the Contractor, stabilised with 2.5% OPC cement compacted in layers not exceeding 150mm to 97% Mod. AASHTO density</u>			
8	Sub-base under roads	m3	40
<u>Earth filling from commercial sources supplied by the Contractor under parking areas, roadways, etc:</u>			
9	Sub-base course of G7 material compacted to 93% Mod AASHTO density	m3	40
10	Base course stabilised G7 material with CEM II 32.5 BV compacted to 97% Mod AASHTO density	m3	40
<u>Weedkiller (active ingredients metalaclor 102,8 g/l, terbitilasién 248,6 g/l and atrasién 248,6 g/l) mixed in the proportion of 100 ml weedkiller to 100 l water and applied at a rate of 10 l/m2:</u>			
11	Under paving, etc	m2	266
<u>PRECAST CONCRETE</u>			
<u>Paving of 200 x 100 x 60mm "Type S-A" precast concrete paving bricks with butt joints, on 20mm thick river sand bed with sand-and-cement mixture swept into joints and hosed down, including preparation of ground or filling:</u>			
12	Paving in herringbone bond pattern to falls	m2	266
<u>Precast concrete finished smooth on exposed surfaces, including bedding, jointing and pointing:</u>			
13	150 x 300mm High kerbs (SANS 927 fig 8) with 150 x 150 x 300mm unreinforced concrete haunching at back of each joint, including excavation, backfilling, etc	m	177

<u>RAMPS</u>			
Carried Forward			R
Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD			

Brought Forward			R
<u>EARTHWORKS</u>			
<u>Excavation in earth not exceeding 2m deep:</u>			
14	Reduced levels under floors	m3	1
<u>Extra over all excavations for carting away:</u>			
15	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	1
<u>G7 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>			
16	Under floors, steps, pavings, etc	m3	1
<u>Compaction of surfaces:</u>			
17	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	4
<u>Prescribed density tests on filling:</u>			
18	"Modified AASHTO Density" test	No	1
<u>Soil insecticide in accordance with SANS 5859:</u>			
19	Soil insecticide (protection against termites) applied as specified to bottoms and sides of trenches, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	4
<u>CONCRETE WORK</u>			
<u>25MPa/19mm reinforced concrete:</u>			
	Ramps	m3	1
Carried Forward			R
Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD			

Brought Forward					
<u>Test cubes</u>					
20	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	0.4		
<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>					
21	Surface beds, slabs, etc to falls	m2	4		
<u>FORMWORK</u>					
<u>Smooth formwork to sides:</u>					
22	Sloping outer edges of ramps approximately 450mm high extreme	m	8		
<u>REINFORCEMENT</u>					
<u>Fabric reinforcement:</u>					
23	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	4		

<u>APRONS</u>					
<u>EARTHWORKS</u>					
<u>Excavation in earth not exceeding 2m deep:</u>					
24	Reduced levels under floors	m3	32		
<u>Extra over all excavations for carting away:</u>					
25	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	32		
Carried Forward				R	
Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD					

Brought Forward			R
<u>G7 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>			
26	Under floors, steps, pavings, etc	m3	32
<u>Compaction of surfaces:</u>			
27	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	212
<u>Prescribed density tests on filling:</u>			
28	"Modified AASHTO Density" test	No	71
<u>Soil insecticide in accordance with SANS 5859:</u>			
29	Soil insecticide (protection against termites) applied as specified to bottoms and sides of trenches, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	212
<u>CONCRETE WORK</u>			
<u>25MPa/19mm reinforced concrete:</u>			
	Aprons	m3	32
<u>Test cubes</u>			
30	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	11
<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>			
31	Surface beds, slabs, etc to falls	m2	212
<u>REINFORCEMENT</u>			
Carried Forward			R
Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD			

	Brought Forward				R
	<u>Fabric reinforcement:</u>				
32	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	212		

	<u>THE FOLLOWING IN RAINWATER STORAGE TANK STRUCTURES:</u>				
	<u>EXCAVATIONS, ETC</u>				
	<u>Excavation in earth not exceeding 2m deep:</u>				
33	Trenches	m3	5		
	<u>Extra over trench and hole excavations in earth for excavation in:</u>				
34	Soft rock	m3	1		
35	Hard rock	m3	0.3		
	<u>Extra over all excavations for carting away:</u>				
36	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	3		
	<u>Risk of collapse of excavations:</u>				
37	Sides of trench and hole excavations not exceeding 1,5m deep	m2	2		
	<u>Keeping excavations free of water:</u>				
38	Keeping excavations free of all water other than subterranean water		Item		
	Carried Forward				R
	Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD				

Brought Forward			R
<p><u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 93% Mod AASHTO density:</u></p>			
39	Backfilling to trenches, holes, etc	m3	2
<p><u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u></p>			
<p><u>25MPa/19mm concrete:</u></p>			
	Strip footings	m3	2
	Surface beds	m3	1
<p><u>TEST BLOCKS</u></p>			
40	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	1
<p><u>MASONRY</u></p>			
<p><u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar in loadbearing walls etc:</u></p>			
41	One brick walls	m2	21
<p><u>2,5mm Brickwork reinforcement:</u></p>			
42	150mm Wide reinforcement built in horizontally	m	53
<p><u>FACE BRICKWORK</u></p>			
<p><u>Face bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with flush horizontal and vertical joints</u></p>			
43	Extra over brickwork for face brickwork	m2	12
Carried Forward			R
<p>Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD</p>			

	Brought Forward				R
	<u>Brick-on-edge header course coping, sills, etc. of face</u> <u>bricks (Allow a Prime Cost Amount of R5 500.00/1000 bricks delivered to site excluding VAT) pointed with recessed joints on all exposed faces</u>				
44	220mm Copings on top of one brick walls	m	18		

	<u>EXISTING FENCING</u>				
	<u>Upgrading of existing</u>				
45	Upgrading of existing security fencing and gates including replacement of poles, wiring, gates, etc as directed including painting and straightening and leave in a perfect working order, all to the satisfaction of the Principal Agent	m	580		
	<u>PAINTING</u>				
	<u>Paintwork etc, to existing work</u>				
	<u>Clean surface and allow to dry completely, prime and apply one coat Gloss Enamel (Traffic Green as specified by the LDOE) N0 BRUSH PAINTING</u>				
46	On palisade fencing (Measured over the full area of both sides)	m2	2 188		
	<u>NEW FENCING</u>				
	Carried Forward				R
	Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD				

	Brought Forward			R
	<p><u>Steel palisade fencing, gates, etc including one priming coat and two coats high gloss enamel Traffic Green paint on using compressor spray gun metal stays, gates, framing and etc:</u></p>			
47	<p>1800mm High palisade fencing comprising of 40 x 40 x 2mm angle iron welded flash with the back of the post 300mm from top of paling and 300mm from bottom of paling (350mm from ground level), 21 palings per panel consist of 30 x 30 x 2mm x 1 800mm High steel angle iron inserted and firmly welded to the bearers at 133mm centre to centre with "Devil Fork" on top and dove tail at the bottom welded to 76 x 76 x 2mm steel tubing posts 2 400mm long/ high with closing pyramid caps on top and M12 anti vandal nuts and bolts and posts set and cast into and including 300 x 300 x 600mm deep concrete base at 3 000mm centres.</p>	m	1 000	
48	<p>4000 x 1800mm High Sliding gate comprising of 40 x40 x 2mm angle iron palings welded to a 76 x 38 x 2mm rectangular tubing bearer frame, palings are to be placed 133mm apart each other centre to centre with 2 x 80mm roller coaster wheels fitted with ball bearing at 500mm from edge of the gate with 12mm steel track rod welded to 40 x 40 x 5mm angle iron fixed into a 300mm Wide x 400mm thick x 5m length of the gate and 2 No x 75mm x 75mm x 2mm steel square tubing posts at each side of the gate opening with closing pyramid caps on top and planted into concrete footing 450 x 450 x 600mm deep including excavations, backfilling and locking mechanism.</p>	No	1	
49	<p>1500mm Wide x 1800mm High Swing gate comprising of 40 x40 x 2mm angle iron palings welded to a 50 x 25 x 1.6mm rectangular tubing bearer frame, palings are to be placed 133mm apart each other centre to centre and 2 No x 75mm x 75mm x 2mm steel square tubing posts at each side of the gate opening with closing pyramid caps on top and planted into concrete footing 450 x 450 x 600mm deep including excavations, backfilling and locking mechanism.</p>	No	2	
	<p>Carried Forward to Summary of Section No. 13</p>			R
	<p>Section No. 13 SITE WORKS Bill No. 1 EXTERNAL WORKS Diatho Consulting (PTY) LTD</p>			

Item No	Quantity	Rate	Amount
<p><u>SECTION NO. 13</u></p> <p><u>BILL NO.2</u></p> <p><u>SITE SERVICES (PROVISIONAL)</u></p> <p><u>(ALL TRADES)</u></p> <p style="text-align: center;">-----</p> <p><u>PREAMBLES</u></p> <p>The General Preambles for Trades (2017 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained</p> <p>The following "Supplementary Preambles" are incorporated in this bill to satisfy the requirements of the project and shall take precedence over the provisions of the said General Preambles</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>Stormwater channels:</u></p> <p>Descriptions of channels shall be deemed to include necessary excavation, surface preparation, compaction, etc and disposal of surplus material on site</p> <p><u>French drains:</u></p> <p>Descriptions of french drains shall be deemed to include excavation, stone filling graded from 300mm diameter at bottom to 75mm diameter at top, approved geofabric filter blanket over stone, 300mm earthfilling over and disposal of surplus material on site</p> <p style="text-align: right; margin-right: 50px;">Carried Forward</p> <p>Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD</p>			R

<p style="text-align: center;">Brought Forward</p> <p><u>Septic tanks:</u></p> <p>Descriptions of proprietary type septic tanks shall be deemed to include excavation, bedding and jointing, concrete base slabs, jointing to drains and backfilling, compaction, etc all in accordance with the manufacturer's instructions and disposal of surplus material on site</p> <p><u>uPVC pipes and fittings:</u></p> <p>Sewer and drainage pipes and fittings shall be jointed and sealed with butyl rubber rings</p> <p>Soil, waste and vent pipes and fittings shall be solvent weld jointed or sealed with butyl rubber rings</p> <p><u>uPVC pressure pipes and fittings:</u></p> <p>Pipes of 50mm diameter and smaller shall be plain ended with solvent welded uPVC loose sockets and fittings</p> <p>Pipes of 63mm diameter and greater shall have sockets and spigots with push-in type integral rubber ring joints. Bends shall be uPVC and all other fittings shall be cast iron, all with similar push-in type joints</p> <p><u>High density polyethylene (HDPE) pipes and fittings:</u></p> <p>Pipes shall be type IV and of the class specified with "Plasson" or "Alprene" compression fittings</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>"Polycop" polypropylene pipes:</u></p> <p>Polypropylene pipes 54mm diameter and smaller shall be seamless copper coloured Class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or where so described "Polylock" compression fittings</p> <p>Pipes shall be firmly fixed to walls, etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions</p> <p><u>Copper pipes:</u></p> <p>Pipes shall be hard drawn and half-hard "Maksal" pipes of the class described. Class 0 (thin walled hard drawn) pipes shall not be bent. Class 1 (thin walled half-hard), Class 2 (half-hard) and Class 3 (heavy walled half-hard) pipes shall only be bent with benders with inner and outer formers. Fittings to copper waste, vent and anti-syphon pipes, capillary solder fittings and compression fittings shall be "Cobra Watertech" type. Capillary solder fittings shall comply with ISO 2016</p> <p>Copper pipes are to be installed in accordance with the latest revision of the Code of Practice for Copper Plumbing soldering techniques. Flux, solder, etc to be strictly in accordance with the manufacturer's requirements with special attention to copper flux composition</p> <p><u>Reducing fittings:</u></p> <p>Where fittings have reducing ends or branches they are described as "reducing". In the case of pipes with diameters not exceeding 60mm, only the largest end or branch size is given. Should the Contractor wish to use other fittings and bushes or reducers he may do so on the understanding that no claim in this regard will be entertained. In the case of pipes with diameters exceeding 60mm, all sizes are given and no claim for extra bushes, reducers, etc will be entertained</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD</p>	R	

<p style="text-align: center;">Brought Forward</p> <p><u>Disinfection of water pipework:</u></p> <p>Water pipework is to be disinfected at completion in accordance with SABS 1200L (provision for disinfection elsewhere)</p> <p><u>"Densyl" petrolatum anti-corrosion tape as manufactured by Denso SA (Pty) Ltd.:</u></p> <p>Pipes to be taped shall be coated with the appropriate primer and the tape shall be applied in the appropriate widths and with suitable overlaps</p> <p>Couplings and fittings to pipes shall be taped in strict accordance with the manufacturer's instructions including mastic, tape, "Layflat" sheeting, securing of same, etc</p> <p>Prices for wrapping of pipes shall include for all work as described to couplings in the length</p> <p><u>Laying, backfilling, bedding, etc of pipes:</u></p> <p>Pipes shall be laid and bedded in accordance with manufacturers' instructions and trenches shall be carefully backfilled</p> <p>Where no manufacturers' instructions exist, pipes shall be laid in accordance with Clauses 5.1 and 5.2 of each of the following: SABS 1200L : Medium-pressure pipelines SABS 1200LD : Sewers SABS 1200LE: Stormwater drainage</p> <p>Pipe trenches, etc shall be backfilled in accordance with Clauses 3, 5.5, 5.6, 5.7 and 7 of SABS 1200DB : Earthworks (Pipe trenches)</p> <p>Pipes shall be bedded in accordance with Clauses 3.1 to 3.4.1, 5.1 to 5.3 and 7 of SABS 1200LB : Bedding (Pipes)</p> <p>Unless otherwise described, bedding of rigid pipes shall be Class B bedding</p>	R	
<p style="text-align: center;">Carried Forward</p> <p>Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD</p>	R	

Brought Forward				R
<u>General:</u>				
Descriptions of pipes laid in and including trenches and of inspection chambers, catchpits, etc shall be deemed to include excavation, bedding, backfilling, compaction to a minimum of 98% Mod AASHTO density and disposal of surplus material on site				
Descriptions of service pipes and flexible connecting pipes shall be deemed to include connections to taps, cisterns, etc and to steel pipes (adaptors for connections to copper pipes, etc are given separately)				

<u>STORMWATER MANAGEMENT:</u>				
<u>STORMWATER CHANNELS:</u>				
<u>EARTHWORKS</u>				
<u>Excavation in earth not exceeding 2m deep:</u>				
1	Reduced levels stormwater channels	m3	80	
<u>Extra over all excavations for carting away:</u>				
2	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	80	
<u>G7 filling material supplied by the contractor, compacted to 95% Mod AASHTO density:</u>				
3	Under stormwater channels, etc	m3	80	
<u>Compaction of surfaces:</u>				
4	Compaction of ground surface under stormwater channels etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	531	
Carried Forward				R
Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD				

Brought Forward				R
<u>Prescribed density tests on filling:</u>				
5	"Modified AASHTO Density" test	No	5	
<u>Soil insecticide in accordance with SANS 5859:</u>				
6	Soil insecticide (protection against termites) applied as specified to bottoms and sides of trenches, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	531	
<u>CONCRETE WORK</u>				
7	25Mpa/19mm Mass concrete in V-shaped channel 700mm wide x 75mm thick cast in 2 000mm intervals with rounded salient edges and finished on exposed surfaces with 2:1 cement mortar, with and including one layer of ref.193 mesh reinforcement, laid to falls in panels not exceeding 2,0m long with 12mm bitumen impregnated soft board movement joints with exposed edges raked out for a depth of 10mm and filled with bituminous compound including all necessary excavations, form work, backfilling, clearing, levelling and etc.	m	354	
8	Extra for fair open end	No	118	
9	Extra for fair stopped end	No	118	
10	Extra for angle intersection	No	118	
<u>Test cubes</u>				
11	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	13	
<u>Finishing top surfaces of concrete smooth with a steel trowel:</u>				
12	Stormwater channels to falls	m2	531	
<u>THE FOLLOWING IN SEPTIC TANK:</u>				
Carried Forward				R
Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD				

Brought Forward			R
<u>EARTHWORKS</u>			
<u>Excavation in earth exceeding 2m and not exceeding 4m deep:</u>			
13	Septic tank pit	m3	140
<u>Extra over trench and hole excavations in earth for excavation in:</u>			
14	Soft rock	m3	14
15	Hard rock	m3	7
<u>Extra over all excavations for carting away:</u>			
16	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	125
<u>Risk of collapse of excavations:</u>			
17	Sides of trench and hole excavations not exceeding 1,5m deep	m2	80
<u>Keeping excavations free of water:</u>			
18	Keeping excavations free of all water other than subterranean water		Item
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 93% Mod AASHTO density:</u>			
19	Backfilling to trenches, holes, etc	m3	15
<u>Compaction of surfaces:</u>			
20	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 91% Mod AASHTO density	m2	80
Carried Forward			R
Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD			

Brought Forward			R
<u>Prescribed density tests on filling:</u>			
21	"Modified AASHTO Density" test	No	5
<u>Soil insecticide in accordance with SANS 5859:</u>			
22	Soil insecticide (protection against termites) applied as specified to bottoms and sides of trenches, etc including forming and poisoning shallow furrows against foundation walls, etc filling in furrows and ramming	m2	80
<u>CONCRETE WORK</u>			
<u>15MPa/19mm unreinforced concrete:</u>			
23	Surface blinding under footings and bases	m3	15
<u>25MPa/19mm reinforced concrete:</u>			
	Mass concrete to bottoms	m3	20
	Slabs	m3	15
<u>Test cubes</u>			
24	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	4
<u>FORMWORK</u>			
<u>Smooth formwork to sides:</u>			
25	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	25
<u>REINFORCEMENT</u>			
<u>Fabric reinforcement:</u>			
26	Type 395 fabric reinforcement in concrete surface beds, slabs, etc	m2	80
Carried Forward			R
Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD			

Brought Forward			R
<u>High tensile steel reinforcement to structural concrete work:</u>			
27	110mm Diameter drain pipes, fixed raking or vertically in ramps to cleaning eyes, etc (no excavations)	m	20
28	All Diameter bars	t	3.00
29	110mm Pipes laid in and including trenches not exceeding 1m deep	m	20
30	110mm Pipes laid in and including trenches exceeding 1m and not exceeding 2m deep	m	5
31	Extra over uPVC piping for 110mm bend	No	5
<u>BRICKWORK</u>			
<u>Brickwork of NFP bricks in class II mortar</u>			
32	Half brick walls	m2	17
33	Extra over uPVC piping for 110mm junction	No	20
34	One brick walls	m2	70
35	Extra over uPVC piping for 110mm stop end	No	10
Carried Forward			R
Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD			

Brought Forward							
36	110mm uPVC cleaning eye fixed to 110mm uPVC drain pipe, including 350 x 350 x 75mm thick in-situ 15 MPa/19mm mass concrete surround, the whole finished smooth on all exposed faces with exposed angles rounded, including all necessary excavations, formwork, backfilling, etc.						
		No	2				
	<u>BRICKWORK SUNDRIES:</u>						
	<u>Bagging of 1:3 cement and sand mixture</u>						
37	Outer face of external brick wall	m2	350				
	<u>2,5mm Brickwork reinforcement:</u>						
38	75mm Wide reinforcement built in horizontally	m	44				
39	150mm Wide reinforcement built in horizontally	m	206				
	<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952-1985 type C) sealed at laps with PVC self-adhesive tape:</u>						
40	Under surface beds	m2	50				
	<u>SPECIAL FLOOR COATING</u>						
	<u>Prepare all surfaces as necessary, prime with "Flowprime" primer and apply 6mm thick anti-slip "Flowcrete Flowfresh HF" or similar approved heavy duty chemical resistant antimicrobial treated polyurethane resin floor screed of approved colour and applied by an approved specialist, on:</u>						
41	On internal plastered walls	m2	88				
	<u>INTERNAL PLASTER</u>						
	Carried Forward						R
	Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD						

		Brought Forward		R
	<u>Cement plaster steel trowelled, on brickwork:</u>			
42	On walls	m2	88	

	<u>THE FOLLOWING IN PREFABRICATED STEEL TANK:</u>			
	<u>EARTHWORKS</u>			
	<u>SITE PREPARATION</u>			
43	Remove topsoil to nominal depth 150mm, stockpile and maintain	m2	25	
	<u>BULK EXCAVATION - TANK BASE</u>			
	<u>b) Extra-over for:</u>			
44	Intermediate excavation	m3	3	
45	Hard rock excavation	m3	5	
	<u>RESTRICTED EXCAVATIONS</u>			
46	Excavate for restricted foundations, footings and trenches in all materials and use for backfill or embankment or dispose.	m3	25	
	<u>EARTHWORKS (ROADS, SUBGRADE)</u>			
47	Rip and re-compact insitu to 90% MOD AASHTO	m3	1	
48	Geotechnical grid (Traix TX170)	m2	1	
	Carried Forward			R
	Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD			

Brought Forward				R
49	Backfill 500mm with course insitu material in 150mm layers.	m3	5	
<u>PREFABRICATED TANK</u>				
50	Supply, handle, install, erect hot dipped 70kl galvanised Prefabricated steel tank. 4,88m length x 4.88m width x 2.44m deep. Including lockable access manhole with built-in screened vent. Internal and external ladder, a level indicator, as well as all fittings required for installation. And the supply, handling, installation, and erection of hot dipped galvanised steel support structures 6m high, including an access ladder with safety cage. As well as all standard fittings required for installation and walkway around tank base with rails	No	1	
<u>CONCRETE</u>				
51	Binding layer in 15MPa concrete (50mm thick)	m2	1	
52	Shutter rough	m2	25	
<u>SCHEDULED REINFORCEMENT</u>				
53	Steel bars	t	3.00	
54	Strength of concrete grade 30/19	m3	23	
<u>UNFORMED SURFACE FINISHES</u>				
55	Steel float	m2	25	
56	M20 Bolts cast in complete with washer plate and nuts, all galvanised.	No	16	
<u>PIPES</u>				
Carried Forward				R
Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD				

Brought Forward				R
<u>Supply, lay, bed, test, disinfect flanged pipes complete with couplings for Class 16 mild steel pipes of the following diameter: (All material including fittings to be SABS approved)</u>				
57	1. 65 mm diameter	m	18	
58	3. 80 mm diameter	m	12	
<u>Supply, handle, lay, disinfect, bed in flexible pipe bedding and test uPVC class 16 pipes complete with spigot and socket joints.(All material including fittings to be SABS approved)</u>				
59	1. 75 mm diamete	m	12	
60	2. 90 mm diameter	m	12	
<u>SPECIALS AND FITTINGS</u>				
Extra-over 8.2.1 for supplying, laying, bedding, jointing and testing of the following fittings for use on Steel pipes				
<u>90 degree bends</u>				
61	1. 75mm	No	4	
62	2. 90mm	No	8	
<u>Equal Tee</u>				
63	1. 100mm x 100mm	No	2	
Extra-over 8.2.1 for supplying, laying, bedding, jointing and testing of the following fittings for use on uPVC pipes				
<u>90 degree bends</u>				
64	1. 75mm	No	1	
Carried Forward				R
Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD				

		Brought Forward		R
65	2. 90mm	No	1	
	<u>11.25 degree Bends</u>			
66	1. 75mm	No	1	
67	2. 90mm	No	1	
	<u>22.5 degree Bends</u>			
68	1. 75mm	No	1	
69	2. 90mm	No	1	
	<u>45 degree Bends</u>			
70	1. 75mm	No	1	
71	2. 90mm	No	1	
	<u>Flange adaptors</u>			
72	1. 110mm	No	4	
	<u>Extra over Item 8.2.1 for supplying, fixing and bedding of valves; Class 16:</u>			
	<u>Viking Johnson/Klamflex flanged adaptors PN 16</u>			
73	1. 100mm	No	2	
74	ND100 AVK Dismantling joint PN16 or similar approved	No	4	
75	ND100 flanged cosmos Meinecke WPD bulk meter with digital output or similar approved; Class 16	No	1	
76	ND100 flanged Bermad 70F Y-Pattern strainer or similar approved; Class 16	No	2	
77	ND100 flanged ball valve; Class 16	No	1	
		Carried Forward		R
	Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD			

		Brought Forward		R
78	Steel Plinths	No	4	
79	DN25 automatic air release valve, Vent O Mat or similar approved brand as per inlet chamber detail; Class 25	No	2	
80	ND25 brass fullway gate valve to sabs 776 Class 10	No	2	
81	ND25 galvanised barrel nipple PN16	No	2	
82	ND100 In line tee with outlet diameter as specified in the nodal descriptions and reduced to 25bsp female end connection PN16	No	2	
83	ND100 mm, 150mm long double flanged pipe, PN 16 to SANS standard	No	2	
84	ND100 mm, 600mm long double flanged pipe, PN 16 to SANS standard	No	2	
85	ND100 flanged Vosa Series 7354 Equilibrium float valve or similar approved; Class 16	No	1	
86	DN100 flanged mild steel flanged sweep tee; flanges drilled according to SANS 1123 table 16	No	1	
87	DN100 Blank flange with 20 mm hole drilled onto it and 25 mm nipple welded onto it; nipple to be male threaded on one end.	No	1	
88	DN25 Female threaded ball valve, PN16	No	1	
89	DN25 Nipple, one end male and one end female threaded	No	1	
		Carried Forward		R
Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD				

Brought Forward			R
90	DN25 automatic air release valve, Vent O Mat or similar approved brand as per tank inlet detail; Class 25	No	1
91	ND100 mm, 240mm long double flanged pipe, PN 16 to SANS standard	No	1
92	ND150 mild steel pipe, PN 16,6m long,one end flanged as per detail drawing 14491-D-C-WAT-D05, actual length of pipe to be confirmed on site confirmed on site	No	1
<u>Isolating valves</u>			
Extra-over item 6.13 for the supplying, installing cutting in and testing flanged Class 16 anti-clockwise closing non rising spindle resilient seal gate valves for steel pipes as shown on detailed drawings for pipe diameters			
93	1. 100 mm diameter	No	5
94	2. 150 mm	No	1
<u>CHAMBERS</u>			
95	Construct concrete inlet and outlet chamber Type 1 complete with step irons, and frames as per detailed drawings, up to 2.0m depth.	No	1
96	Construct scour valve chamber Type 4, complete with stepirons, frames and and scour wing wall structure as per detailed drawings up to 2.5m depth.	No	1
<u>SUNDRIES</u>			
97	Thrust blocks and pedestals class 25/19 concrete	m3	5
Carried Forward			R
Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD			

	Brought Forward		R
	<u>THE FOLLOWING IN UPGRADING OF EXISTING BOREHOLE:</u>		
98	Allow the Amount of R 150 000.00(One Hundred and fifty Thousand Rand) NET for upgrading of existing Borehole to be executed by Specialist	Item	150 000.00
99	Profit and attendance for the above	Item	
	<u>NEW BOREHOLE</u>		
100	Allow the Amount of R 250 000.00 (Two Hundred Fifty Thousand Rand) NET for Borehole to be executed by Specialist	Item	250 000.00
101	Profit and attendance for the above	Item	
	<u>WATER TREATMENT PLANT</u>		
102	Allow the Amount of R 250 000.00(Two Hundred and Fifty Thousand Rand) NET for Water treatment to be executed by Specialist	Item	250 000.00
103	Profit and attendance for the above	Item	
	<u>SUNDRY SANITARY FITTINGS</u>		
104	Drinking fountain @ 1000mm high - 1000mm diameter precast pipe on 1400 x 1400 x 200mm thick 20MPa/19mm mass concrete footings including any necessary excavation, filling, reinforcement, top finished with 100mm thick 20MPa/19mm mass concrete slab graded to falls to 100mm dia upvc outlet (water outlet elsewhere), with wood float finish and fitted with and including 20mm diameter galvanised mild steel pipe 2,3m long including three bends, three tees, three reducers, four 22mm chromium plated Walcro 109 foundation demand tap for hold open application and one 20mm dia hose-bib-tap RB with lockshield and loose key and hose union complete with and including all plumbing work as per detail 923-S2-101-wd-106	No	3
	Carried Forward to Summary of Section No. 13		R
	Section No. 13 SITE WORKS Bill No. 2 SITE SERVICES Diatho Consulting (PTY) LTD		

SECTION SUMMARY - SITE WORKS

Bill No		Page No	Amount
1	EXTERNAL WORKS	510	
2	SITE SERVICES	527	
Carried to Final Summary			R
Section No. 13 SITE WORKS Diatho Consulting (PTY) LTD			

Section No	<u>FINAL SUMMARY</u>	Page No	Amount
1	Preliminaries	47	
2	Demolitions	51	
3	Renovations - 4 seats (Enviroloo)	92	
4	Renovations 5 Seats (Water-borne)	125	
5	F7 Female Ablutions	172	
6	FD7 - Female Ablutions	219	
7	SFD8 - Female Educator Ablutions	262	
8	M2 + 2UR Male Educators Ablutions	308	
9	M6 + 3UR Male Ablutions	356	
10	M4 +2UR Male Ablutions	404	
11	GRD5 Grade R Unisex	451	
12	GR 5 Grade R Unisex Ablution	498	
13	SITE WORKS	528	
	SUB TOTAL		R
	<u>CONTRACT CONTINGENCIES</u>		
	Allow the sum of 10% (ten percent) of the above sub total for Contingencies to be spent as the Principal Agent may direct and to be deducted in whole or in part if not required		R
	SUB TOTAL		R
	<u>VALUE ADDED TAX</u>		
	Value Added Tax [15%]		R
	Carried to Form of Tender		R
	Diatho Consulting (PTY) LTD		