

ESKOM TRANSMISSION REAL ESTATE

REPLACEMENT OF SKYLIGHTS,MINOR INTERIOR WORKS AND PARKING BAYS AT VICTORIA LAKE INN ACCOMC
REPLACEMENT OF SKYLIGHTS,MINOR INTERIOR WORKS AND PARKING BAYS AT VICTORIA LAKE INN ACCOMC

ITEM NO.	DESCRIPTION	UNIT
	<u>SECTION 02</u>	
	<u>BILL 01:SHE SCHEDULE</u>	
	TIME RELATED	
1	Supply of all items of Personal Protective Clothing/Equipment & ensure use thereof for full compliance	
1.1	Steel toe capped safety boots .	Sum
1.2	Overall - 2 piece suit with luminous strap.	Sum
1.3	Gloves.	Sum
1.4	Hard hats with adjustable 3 point webbing chin strap as per SANS 1397.	Sum
1.6	Ear protection (earplugs, ear muffs etc.)	Item
1.7	Eye protection appropriate to task performed	Item
1.8	Dust Mask.	Item
1.9	COVID-19 related supplies	item
1.9	Induction tags/cards	Item
1.10	Luminous high visibility safety vests	Item
1.11	SHE training incl first aider level 2, fire warden,HIRA, RCAT,Fall protection developer, Scaffold erector,dismantle and inspection, Working at heights etc	Item
2	Supply and provision of Equipment for working at Heights & ensure use thereof for full compliance to OHS ACT and Eskom's SHE spec	

2.1	FALL ARREST SYSTEM (An approved Fall Arrest System, together with training is to be supplied and installed by the <i>Contractor</i> . The <i>Contractor</i> is to supply sufficient climbing attachment units for his workforce and ensure training by the Supplier before use. It is mandatory for the <i>Contractor</i> to use the system once installed). The <i>Contractor</i> will take ownership of the fall arrest system and it must be removed after use.	Item
2.2	Fall Protection Equipment and fall protection plan incl risk assessment.	Item
2.3	Fall Arrest System (FAS) - Double lanyard harness	Item
2.4	Evaluation of physical and psychological fitness of personnel working at heights	Item
2.5	Portable Ladders	Item
2.6	Scaffold access ladders	Item
2.7	Rescue personel	Item
3	Barricading	
3.1	Supply, erection and maintenance of all shark nets and barricading which would be required during construction to make the site safe in accordance with the OHS Act	Item
4	Transport	
4.1	Transportation of employees in compliance with the Transportation of employees procedure and any other legislative or regulated requirements. Other - (<i>Contractor</i> to Specify)	Item
5	Compliance	
5.1	Provision of all signage in terms of latest legislation/SANS 1186 code Other - (<i>Contractor</i> to Specify)	Item
5.2	Preparation and Submission of safety file	Item
6	Human Resources	
6.1	Appointment of SHEQ OFFICER FULL TIME ON SITE WITH MINIMUM NATIONAL DIPLOMA (SACPCMP registration) Costs associated with the appointment of Safety personel and actual time spent on implementation, managing, documenting, monitoring, reviewing, internal and external audits, incident investigations and mitigating safety related impacts.	Item
7	OHS Risk Assessment	

7.1	Baseline risk assessment for the scope of works	Item
8	Occupational Health	
8.1	Pre-employment medical screening	Item
8.2	Exit Medical Screening	Item
9	Environmental Measurement and Payment as per the Site Information	
9.1	Environmental management plan	Item
9.2	Fire management and control measures	Item
10	Waste Management (Costs associated with the management of general, hazardous waste, etc.)	
10.1	Waste Bins, skips & lids and covers	Item
10.2	General waste collection and disposal at a registered dumping site	Item
10.3	Hazardous waste transportation and disposal at a registered facility	Item
10.4	Waste Management plan	Item
11	Oil Management	
11.1	Oil spill kits	Item
11.2	Drip trays	Item
SUB-TOTAL CARRIED TO SUMMARY		

ODATION, SIMMERPAN.
ODATION, SIMMERPAN.

QUANTITY	RATE	AMOUNT
1		R0.00
1		R0.00
1		R0.00
1		R0.00
1		R0.00
1		R0.00
1		R0.00
1		R0.00
1		R0.00
1		R0.00
1		R0.00

