Item No.	Description	Unit of Measure	Quantity	No.	Rate /day	Total per 1 month	Months	Total per year	Duration (Years)
1.	**Preliminaries and General**								
1.1	D/C LDV 4x4 (max 2.4 L) Vehicle (Wet rate)	Day	22	1			4		4
1.2	Mobile Chemical Toilets (Service Only)	Weekly	4	2			4		4
1.3	Mobile Tearoom (Gazibo 3x3 m)	Day	22	2			4		4
	Total Preliminaries and General								
2.	**SHE**								
2.1	Mine Health and Safety File	Annum	1						4
2.2	PPE (2 sets of overalls. Safety Boots. Jacket. Brush Cutter Helmet with Shield. Gloves. Shin Shield. Aprin. Safety Goggles. Sun Hat. Sun Screen. Ear Plugs. Reflector Vest) Medical Surveyance Entry and Exit.	Annum	27						4
	Total SHE								
3	**Equipment**								
3.1	45 cc Chain saw with chain. Supplied and serviced with fuel and Two stroke oil.	Month	1	1			4		4
3.2	45 cc straight shaft brush cutters with steel blades. Supplied and serviced with fuel and Two stroke oil.	Month	1	10			4		4
3.3	Shovel	Item	10				1		4
3.4	Garden Rake	Item	10				1		4
3.5	Garden Hoe	Item	10				1		4
3.6	Garden Fork	Item	10				1		4
3.7	Picks with Plastic Handles	Item	10				1		4
3.8	Consumables	Item	1				4		4
3.9	500 Litre Diesel Bowser	Day	22				4		4
	Total Equipment								

4	**Machines**								
4.1	75 kw Tractor (Wet rate) with a 1.2 m Rotary Shlasher a Three Wheel Finger Rake and a 1.2 m Roll Baler as per the MHSA Requirements	Day	22	1			1		4
4.2	4X4 55kW TLB (Wet rate). Rear Bucket Size 800mm. Front Bucket Size 2300 mm as per the MHSA Requirements	Day	22	1			6		4
4.3	100 kW Grader (Wet rate) as per the MHSA Requirements	Day	22	1			1		4
4.4	10 cub meter double Axle Tipper truck (Wet rate) as per the MHSA Requirements	Day	22	1			6		4
4.5	Double Axle Horse with Tripple Axle Lowbed Semi Trailer (Wet rate) as per the MHSA Requirements	Trip	8				1		4
	Total Machines								
5	**Operating Labour**								
5.1	Supervisor	Hours	176	1			6		4
5.2	Team Leader	Hours	176	2			4		4
5.3	Utility Workers	Hours	176	20			4		4
5.4	Mobile Plant Operators (TLB,Grader,Tracktor,Tipper,Horse&Trailer)	Hours	176	4			4		4
	Total Operating Labour								