

Subject	RFQ
Project Name	Removal of a Roof Mounted Maintenance Crane
Reference	



Name of Supplier

SCOPE OF WORK AND SPECIFIC INSTRUCTIONS.

1. LEGISLATIVE REQUIREMENT

The service provider will be responsible for the provision of required service as described in specification below. All services including materials and workmanship to be in accordance with these specification guideline and client requirements, applicable to local and national regulations and industry standards for respective trades.

2. CODES AND STANDARDS

The following codes and ordinances were used in the design of the project and shall be complied with during execution of the project.

Government notices.

The Electricity Act 1984 (Act 41 of 1984) as amended,

The South African National Standard SANS 10142: Code of Practice for Electrical Installations as amended.

The Occupational Health and Safety Act, 1993 Lift Escalator and Passenger conveyor Regulations, 2009.

SANS1545, EN81 for Electric Lifts and Service Lifts as amended.

The Local Municipal Bye-Laws and regulations as well as the regulations of the Local Supply Authority.

National Building Regulations and Building Standards.

The Local Fire Regulations and Codes relevant to lifts. The South African Regulations of the Post & Telecommunications as applicable.

The Standard Regulations of any Government Department or Public Service company where applicable.

Building & Facilities Regulations, providing accessibility and usability for the Physically Handicapped.

3. SAFETY

The Contractors' Staff and Labourers to be used on site must:

Have and use all safety and personal protective equipment (PPE) necessary for the task to be performed on site and in the site.

Conform to the acceptable standards of behaviour and dress appropriately.

Protective Clothing: The contractor shall provide all forms of safety and protective clothing for their personnel. The clothing shall also clearly indicate the name of the Company on it in large and clear letters so that the public can clearly identify the Company if need be. Full Personal Protective Equipment (PPE) shall be worn whenever vegetation management work is performed and this shall include, but not be limited to, the following

- A. Safety shoes/boots;
- B. Hard hat
- C. Overalls
- D. Full length leather gloves/gauntlets
- E. Protective eyewear (face shields)
- F. Protective leg wear (leggings)
- G. Safety belts (harness)
- H. Safety Shoes
- I. Ear muffs.

4. SPECIAL CONDITIONS

- A. Compulsory site inspections will be conducted at the applicable SAPO building.
- B. Bidder are to make himself fully aware of the current conditioned of the building where the crane is located.

- C. Bidders will be required to gather all relevant data pertaining to the equipment for correct.
- D. Bidders will be required to submit a method statement for execution of the dismantling project with they are priced documents
- E. Bidders will be required to submit a safety plan for execution of the project

5. SCOPE OF WORK

The successful bidder will do the following.

- Dismantle the fixed maintenance crane on the roof
- Disconnect all power supply and properly insulate all cables
- Remove all rubble and clean up

6. DURATION

Fourteen working days.

7. PRICING SCHEDULE

				Site Name	Gqeberha Regional Office
	Roof Mounted Crane Dismantle				
Item	Description	UNIT	QTY	RATE	AMOUNT
1	CRANE				
1.1	Dismantling of Rusted mounted 12 ton straight arm maintenance crane Length 6-10m, lifting height 73m. counterweights, main boom, Hook, Hoist, Trolley, Bridge	Sum	1		
2	ELECTRICAL				
2.1	Safely disconnect, isolate and Insulate electric cable for the cranes power supply	Sum	1		
3	RIGGING/MOVING				
3.1	Rigging /Move all dismantled parts from the roof to approved scape metal site.	Sum	1		
Notes: Crane is located on the roof of a 15th story high building +-70 m high					
Notes: Access to the roof is via the stapes, none of the lifts are operational					

8. COST SUMMARY

Cost Summary	
Site Name	Gqeberha Regional Office
Site Size	
Site Location :	PE
City	Gqeberha
Municipality	Nelson Mandela Bay
Street Address	259 Govan Mbeki Street
GPS Coordinates	
Expected Period	14 days

CRANE	
ELECTRICAL	
RIGGING/MOVING	
<i>Total</i>	

TOTAL COST BEFORE VAT	
15% VALUE ADDED TAX	
TOTAL COST	

AMOUNT TO BE CARRIED OVER TO RFQ DOCUMENT	