

Item No	Quantity	Rate	Amount
<p><b><u>SECTION No. 1 - PRELIMINARIES</u></b></p>			
<p><b><u>BILL NO. 1</u></b></p>			
<p><b><u>PRELIMINARIES</u></b></p>			
<p><b><u>MEANING OF TERMS "TENDER / TENDERER"</u></b></p>			
<p>Any reference to the words "Tender" or "Tenderer" herein and/or in any other documentation shall be construed to have the same meaning as the words "Bid" or "Bidder"</p>			
<p><b><u>PRELIMINARIES</u></b></p>			
<p>The JBCC Preliminaries Code 2103, May 2005 edition for use with the JBCC Principal Building Agreement Edition 4.1 Code 2101, March 2005 is taken to be incorporated herein. The tenderer is deemed to have referred to these documents for the full intent and meaning of each clause. These clauses are referred to by number and heading only. Where standard clauses or options are not applicable to the contract such modifications or corrections as are necessary are given under each relevant clause. Where an item is not relevant to this specific contract such item is marked "N/A" signifying "Not Applicable"</p>			
<p><b><u>PRICING OF PRELIMINARIES</u></b></p>			
<p>Should Option A, as set out in clause B10.3.1 hereinafter be used for the adjustment of preliminaries then each item priced is to be allocated to one or more of the three categories Fixed, Value Related or Time Related and the respective amounts entered in the spaces provided under each item</p>			
<p>Items not priced in these Preliminaries shall be deemed to be included elsewhere in these Bills of Quantities</p>			
<p><b>Carried to Collection</b></p>			
<p>Section No. 1            Bill No. 1            PRELIMINARIES AND GENERAL  <b>TMT-DBE-2324-SAFEOS-ECCL94</b>  <b>PROVISIONAL BILLS OF QUANTITIES</b></p>		R	

**SECTION A: JBCC PRINCIPAL BUILDING AGREEMENT**

**DEFINITIONS**

1 **A1.0 DEFINITIONS AND INTERPRETATION**

Clause 1.0

Clause 1.1 Definition of "**Commencement Date**" is added:

**"COMMENCEMENT DATE"** means the date that is 5 working days after site hand over.

Clause 1.1 Definition of "**Construction Guarantee**" is amended by replacing it with the following:

**"CONSTRUCTION GUARANTEE"** means a guarantee at call obtained by the **contractor** from an institution approved by the **employer** in terms of the **employer's** construction guarantee form as selected in the **schedule**

Clause 1.1 Definition of "**Construction Period**" is amended by replacing it with the following:

**"CONSTRUCTION PERIOD"** means the period commencing on the **commencement date** and ending on the date of **practical completion**

Clause 1.1 Definition of "**Corrupt Practice**" is added:

**"CORRUPT PRACTICE"** means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution

Clause 1.1 Definition of "**Fraudulent Practice**" is added:

**Carried to Collection**

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

R

**"FRAUDULENT PRACTICE"** means a misrepresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of any tenderer and includes collusive practice among tenderers (prior to or after the tender submission) designed to establish tender prices at artificial non-competitive levels and to deprive the tenderer of the benefits of free and open competition

Clause 1.1 Definition of **"Interest"** is amended by replacing it with the following:

**"INTEREST"** means the interest rates applicable on this contract, whether specifically indicated in the relevant clauses or not, will be in terms of the legislation of the Republic of South Africa, and in particular:

(a) in respect of interest owed by the employer, the interest rate as determined by the Minister of Justice and Constitutional Development from time to time, in terms of section 1(2) of the Prescribed Rate of Interest Act, 1975 (Act No. 55 of 1975), will apply;

and

(b) in respect of interest owed to the employer, the interest rate as determined by the Minister of Finance, from time to time, in terms of section 80(1)(b) of the Public Finance Management Act, 1999 (Act No. 1 of 1999), will apply

Clause 1.1 Definition of **"Principal Agent"** is amended by replacing it with the following:

**"PRINCIPAL AGENT"** means the person or entity appointed by the **employer** and named in the **schedule**. In the event of a **principal agent** not being appointed, then all the duties and obligations of a **principal agent** as detailed in the **agreement** shall be fulfilled by a representative of the **employer** as named in the **schedule**

Clause 1.1 Definition of **"Security"** is amended by replacing it with the following:

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

"**SECURITY**" means the form of security provided by the **employer** or **contractor**, as stated in the **schedule**, from which the **contractor** or **employer** may recover expense or loss

Clause 1.6 is amended by replacing the words "prepaid registered post, telefax or e-mail" with "prepaid registered post or telefax"

Clause 1.6.4 is amended by replacing it with the following:

No clause

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**OBJECTIVE AND PREPARATION**

1 **A2.0 OFFER, ACCEPTANCE AND PERFORMANCE**

Clause 2.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **A3.0 DOCUMENTS**

Clause 3.0

Clause 3.2.1 is amended by replacing "14.1" with "14.0"

Clause 3.7 is amended by the addition of the following:

The **contractor** shall supply and keep a copy of the **JBCC** Series 2000 Principal Building Agreement and Preliminaries applicable to this contract on the **site**, to which the **employer, principal agent** and **agents** shall have access at all times

Clause 3.10 is amended by replacing the second reference to "**principal agent**" with the word "**employer**"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1 **A4.0 DESIGN RESPONSIBILITY**  
 Clause 4.0  
 Clause 4.3 is amended by replacing it with the following:  
 No clause  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **A5.0 EMPLOYER'S AGENTS**  
 Clause 5.0  
 Clause 5.1.2 is amended to include clauses 32.6.3, 34.3 and 34.4 in terms of which the employer has retained its authority and has not given a mandate to the principal agent and in terms of which the employer shall sign all documents.  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3 **A6.0 SITE REPRESENTATIVE**  
 Clause 6.0  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4 **A7.0 COMPLIANCE WITH REGULATIONS**  
 Clause 7.0  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

5 **A8.0 WORKS RISK**  
 Clause 8.0  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1 **A9.0 INDEMNITIES**

Clause 9.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **A10.0 WORKS INSURANCES**

Clause 10.0

Clause 10.0 is amended by the addition of the following clauses:

**10.5 Damage to the Works**

- (a) Without in any way limiting the **contractor's** obligations in terms of the contract, the **contractor** shall bear the full risk of damage to and/or destruction of the **works** by whatever cause during construction of the **works** and hereby indemnifies and holds harmless the **employer** against any such damage. The **contractor** shall take such precautions and security measures and other steps for the protection and security of the **works** as the **contractor** may deem necessary
- (b) The **contractor** shall at all times proceed immediately to remove or dispose of any debris arising from damage to or destruction of the **works** and to rebuild, restore, replace and/or repair the **works**
- (c) The **employer** shall carry the risk of damage to or destruction of the **works** and materials paid for by the **employer** that is the result of the excepted risks as set out in 10.6
- (d) Where the **employer** bears the risk in terms of this contract, the **contractor** shall, if requested to do so, reinstate any damage or destroyed portions of the **works** and the costs of such reinstatement shall be measured and valued in terms of 32.0 hereof

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

**10.6 Injury to Persons or loss of or damage to Properties**

- (a) The **contractor** shall be liable for and hereby indemnifies the **employer** against any liability, loss, claim or proceeding whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever arising out of or in the course of or caused by the execution of the **works** unless due to any act or negligence of any person for whose actions the **employer** is legally liable
- (b) The **contractor** shall be liable for and hereby indemnifies the **employer** against any liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the **site**, whether belonging to or under the control of the **employer** or any other body or person, arising out of or in the course of or by reason of the execution of the **works** unless due to any act or negligence of any person for whose actions the **employer** is legally liable
- (c) The **contractor** shall, upon receiving a **contract instruction** from the **principal agent**, cause the same to be made good in a perfect and workmanlike manner at his own cost and in default thereof the **employer** shall be entitled to cause it to be made good and to recover the cost thereof from the **contractor** or to deduct the same from amounts due to the **contractor**
- (d) The **contractor** shall be responsible for the protection and safety of such portions of the premises placed under his control by the **employer** for the purpose of executing the **works** until the issue of the **certificate of practical completion**

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

- (e) Where the execution of the **works** involves the risk of removal of or interference with support to adjoining properties including land or structures or any structures to be altered or added to, the **contractor** shall obtain adequate insurance and will remain adequately insured or insured to the specific limit stated in the contract against the death of or injury to persons or damage to such property consequent on such removal or interference with the support until such portion of the **works** has been completed
- (f) The **contractor** shall at all times proceed immediately at his own cost to remove or dispose of any debris and to rebuild, restore, replace and/or repair such property and to execute the **works**

**10.7 High risk insurance**

In the event of the project being executed in a geological area classified as a "High Risk Area", that is an area which is subject to highly unstable subsurface conditions that might result in catastrophic ground movement evident by sinkhole or doline formation the following will apply:

**10.7.1 Damage to the works**

The **contractor** shall, from the **commencement date** of the **works** until the date of the **certificate of practical completion** bear the full risk of and hereby indemnifies and holds harmless the **employer** against any damage to and/or destruction of the **works** consequent upon a catastrophic ground movement as mentioned above. The **contractor** shall take such precautions and security measures and other steps for the protection of the **works** as he may deem necessary

When so instructed to do so by the **principal agent**, the **contractor** shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the **works** and to rebuild, restore, replace and/or repair the **works**, at the **contractor's** own costs

**Carried to Collection**

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

R



**10.7.2 Injury to persons or loss of or damage to property**

The **contractor** shall be liable for and hereby indemnifies and holds harmless the **employer** against any liability, loss, claim or proceeding arising at any time during the period of the contract whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever resulting from, arising out of, or caused by a catastrophic ground movement as mentioned above

The **contractor** shall be liable for and hereby indemnifies the **employer** against any and all liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the **site**, whether belonging to or under the control of the **employer** or any other body or person whomsoever arising out of or caused by a catastrophic ground movement, as mentioned above, which occurred during the period of the contract

**10.7.3** It is the responsibility of the **contractor** to ensure that he has adequate insurance to cover his risk and liability as mentioned in 10.7.1 and 10.7.2. Without limiting the **contractor's** obligations in terms of the contract, the **contractor** shall, within twenty-one (21) **calendar days** of the **commencement date** but before commencement of the **works**, submit to the **employer** proof of such insurance policy, if requested to do so

**10.7.4** The **employer** shall be entitled to recover any and all losses and/or damages of whatever nature suffered or incurred consequent upon the **contractor's** default of his obligations as set out in 10.7.1; 10.7.2 and 10.7.3. Such losses or damages may be recovered from the **contractor** or by deducting the same from any amounts still due under this contract or under any other contract presently or hereafter existing between the **employer** and the **contractor** and for this purpose all these contracts shall be considered one indivisible whole

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1	<p><b>A11.0 LIABILITY INSURANCES</b></p> <p>Clause 11.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>	Item		
2	<p><b>A12.0 EFFECTING INSURANCES</b></p> <p>Clause 12.0</p> <p>Fixed: _____ Value related: _____ Time related: _____</p>	Item		
3	<p><b>A13.0 No clause</b></p>	N/A		
4	<p><b>A14.0 SECURITY</b></p> <p>Clause 14.0</p> <p>Clauses 14.1 - 14.8 are amended by replacing them with the following:</p> <p>14.1 The security to be submitted by the contractor to the employer will be as a payment reduction of up to ten per cent (10%) of the value certified in the payment certificate (excluding VAT)</p> <p>14.1.1 The payment reduction of the value certified in a <b>payment certificate</b> shall be <i>mutatis mutandi</i> in terms of 31.8(A)</p> <p>14.1.2 The <b>employer</b> shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the <b>employer</b> complies with the provisions of 33.4 in which event the <b>employer's</b> entitlement shall take precedence over his obligations to refund the payment reduction <b>security</b> or portions thereof to the <b>contractor</b></p> <p>14.2 Where security as a payment reduction of ten per cent (10%) of the value certified in the payment certificate (excluding VAT) has been selected:</p> <p>14.2.1 The payment reduction of the value certified in a <b>payment certificate</b> shall be <i>mutatis mutandi</i> in terms of 31.8(B)</p> <p style="text-align: right;"><b>Carried to Collection</b></p> <p>Section No. 1 Bill No. 1 PRELIMINARIES AND GENERAL <b>TMT-DBE-2324-SAFEOS-ECCL94</b> <b>PROVISIONAL BILLS OF QUANTITIES</b></p>			

R

14.2.2 The **employer** shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the **employer** complies with the provisions of 33.4 in which event the **employer's** entitlement shall take precedence over his obligations to refund the payment reduction **security** or portions thereof to the **contractor**

14.9 Should the **contractor** fail to furnish the **security** in terms of 14.2, the **employer**, in his sole discretion and without notification to the **contractor**, is entitled to change the **contractor's** selected form of **security** to that of a ten per cent (10%) payment reduction of the value certified in the **payment certificate** (excluding VAT), whereafter 14.7 shall be applicable

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**EXECUTION**

1 **A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS**

Clause 15.0

Clause 15.1.1 is amended by replacing it with:

No clause

Clause 15.1.2 is amended by replacing it with:

The **security** selected in terms of 14.0

Clause 15.1 is amended by the addition of the following clause:

15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within fourteen (14) **calendar days of commencement date**

Clause 15.2.1 is amended by replacing it with the following clause:

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

Give the **contractor** possession of the **site** within ten (10) **working days** of the **contractor** complying with the terms of 15.1.4

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

1 **A16.0 ACCESS TO THE WORKS**

Clause 16.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **A17.0 CONTRACT INSTRUCTIONS**

Clause 17.0

Clause 17.1.11 is amended by deleting the words "and the appointment of **nominated** and **selected subcontractors**"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3 **A18.0 SETTING OUT OF THE WORKS**

Clause 18.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4 **A19.0 ASSIGNMENT**

Clause 19.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1 **A20.0 NOMINATED SUBCONTRACTORS**

Clause 20.0

Clause 20.1.3 is amended by replacing it with the following:

No clause

Note: See item B9.1 hereinafter for adjustment of attendance on **nominated subcontractors** executing work allowed for under provisional sums

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **A21.0 SELECTED SUBCONTRACTORS**

Clause 21.0

Clause 21 is amended by replacing it with:

No clause

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3 **A22.0 EMPLOYER'S DIRECT CONTRACTORS**

Clause 22.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4 **A23.0 CONTRACTOR'S DOMESTIC SUBCONTRACTORS**

Clause 23.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

**COMPLETION**

1 **A24.0 PRACTICAL COMPLETION**

Clause 24.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **A25.0 WORKS COMPLETION**

Clause 25.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3 **A26.0 FINAL COMPLETION**

Clause 26.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4 **A27.0 LATENT DEFECTS LIABILITY PERIOD**

Clause 27.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

5 **A28.0 SECTIONAL COMPLETION**

Clause 28.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

6 **A29.0 REVISION OF DATE FOR PRACTICAL COMPLETION**

Clause 29.0

Clause 29.2.5 is amended by replacing it with:

No clause

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1 **A30.0 PENALTY FOR NON-COMPLETION**  
 Clause 30.0  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

**PAYMENT**

2 **A31.0 INTERIM PAYMENT TO THE CONTRACTOR**

Clause 31.0  
 Clause 31.5.2 is amended by replacing "14.7.1" with "14.0 and 31.8"  
 Clause 31.8 is amended by replacing it with the following two alternative clauses:

**Alternative A**

31.8(A) Where a **security** is selected in terms of 14.1; the value of the **works** in terms of 31.4.1 and **materials and goods** in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments:

31.8(A).1 Ninety-five percent (95%) of such value in interim **payment certificates** issued up to the date of **practical completion**

31.8(A).2 Ninety-seven and half percent (97.5%) of such value in interim **payment certificates** issued on the date of **practical completion** and up to but excluding the date of **final completion**

31.8(A).3 Ninety-nine percent (99%) of such value in interim **payment certificates** issued on the date of **final completion** and up to but excluding the final **payment certificate** in terms of 34.6

31.8(A).4 One hundred percent (100%) of such value in the final **payment certificate** in terms of 34.6 except where the amount certified is in favour of the **employer**. In such an event the payment reduction shall remain at the adjustment level applicable to the final **payment certificate**

**Carried to Collection**

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

Item

R

Clause 31.12 is amended by deleting the following:

Payment shall be subject to the **employer** giving the **contractor** a tax invoice for the amount due

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**1 A32.0 ADJUSTMENT TO THE CONTRACT VALUE**

Clause 32.0

Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence:

"due to no fault of the **contractor**"

Add the following clauses: 33.2.9 to 33.2.13:

33.2.9 the **contractor's** failure or neglect to commence with the works on the dates prescribed in the contract

33.2.10 the **contractor's** failure or neglect to proceed with the works in terms of the contract

33.2.11 the **contractor's** failure or neglect for any reason to complete the works in accordance with the contract

33.2.12 the **contractor's** refusal or neglect to comply strictly with any of the conditions of contract or any contract instructions and/or orders in writing given in terms of the contract

33.2.13 the **contractor's** estate being sequestrated; liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa.

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**2 A33.0 RECOVERY OF EXPENSE AND LOSS**

Clause 33.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**



1 **A34.0 FINAL ACCOUNT AND FINAL PAYMENT**

Clause 34.0

Clause 34.1 is amended by removing "#" next to 34.1

Clause 34.2 is amended by inserting "#" next to 34.2

Clause 34.13 is amended by replacing "seven (7) **calendar days**" with "twenty-one (21) **calendar days**" and deleting the words "subject to the **employer** giving the **contractor** a tax invoice for the amount due"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **A35.0 PAYMENT TO OTHER PARTIES**

Clause 35.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**CANCELLATION**

3 **A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT**

Clause 36.0

Clause 36.1 is amended by the addition of the following clauses:

36.1.3 refuses or neglects to comply strictly with any of the conditions of contract

36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa

36.1.5 in the judgement of the **employer**, has engaged in **corrupt** or **fraudulent practices** in competing for or in executing the contract

Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "**principal agent**" with "**employer**"

**Carried to Collection**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**TMT-DBE-2324-SAFEOS-ECCL94**

**PROVISIONAL BILLS OF QUANTITIES**

Clause 36.0 is amended by the addition of the following clause:

36.3 Remove reference to “No clause”, and replace “principal agent” with “employer”

36.7 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

1 **A37.0 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE**

Clause 37.0

Clause 37.3.5 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"

Clause 37.0 is amended by the addition of the following clause:

37.3.5 Replace “ninety (90)” with “one hundred and twenty (120) and 38.5.4

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **A38.0 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT**

Clause 38.0

Clause 38.5.4 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"

Clause 38.0 is amended by the addition of the following clause:

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

38.7 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

1 **A39.0 CANCELLATION - CESSATION OF THE WORKS**

Clause 39.0

Clause 39.3.5 is amended by the addition of the following at the end of the sentence:

"within one hundred and twenty (120) **working days** of completion of such a report"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

**DISPUTE**

1 **A40.0 DISPUTE SETTLEMENT**

Clause 40.0

Clause 40.2.2 is amended by replacing "one (1) year" with "three (3) years"

Clause 40.6 is amended by removing the reference to:

No clause

Clause 40.7.1 is amended by replacing "(10)" with "(15)" and by the addition of the following:

Whether or not mediation resolves the dispute, the parties shall bear their own costs concerning the mediation and equally share the costs of the **mediator** and related costs

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**SUBSTITUTE PROVISIONS**

2 **A41.0 STATE CLAUSES**

Clause 41.0

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**CONTRACT VARIABLES**

3 **A42.0 THE SCHEDULE (C1.2)**

Clause 42.0

Tenderers are referred to the C1.2 CONDITIONS OF CONTRACT AND CONTRACT VARIABLES for variables pertaining to this contract

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

**SECTION B: JBCC PRELIMINARIES**

**B1.0 DEFINITIONS AND INTERPRETATION**

1 ***B1.1 Definitions and interpretation***

See also clause A1.0 of Section A for additional and/or amended definitions which shall apply equally to this Section

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**B2.0 DOCUMENTS**

2 ***B2.1 Checking of documents***

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3 ***B2.2 Provisional bills of quantities***

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4 ***B2.3 Availability of construction documentation***

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

5 ***B2.4 Interests of agents***

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

6 ***B2.5 Priced documents***

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

7 ***B2.6 Tender submission***

Clause 2.6 is amended by replacing "JBCC Form of Tender" with "Form of Offer and Acceptance DPW-07(EC)"

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

**B3.0 THE SITE**

1 **B3.1 Defined works area**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **B3.2 Geotechnical investigation**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3 **B3.3 Inspection of the site**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4 **B3.4 Existing premises occupied**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

5 **B3.5 Previous work - dimensional accuracy**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

6 **B3.6 Previous work - defects**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

7 **B3.7 Services - known**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

8 **B3.8 Services - unknown**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

9 **B3.9 Protection of trees**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1 **B3.10 Articles of value**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

2 **B3.11 Inspection of adjoining properties**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

**B4.0 MANAGEMENT OF CONTRACT**

3 **B4.1 Management of the works**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: R \_\_\_\_\_

Item

4 **B4.2 Programme for the works**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

5 **B4.3 Progress meetings**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

6 **B4.4 Technical meetings**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

7 **B4.5 Labour and plant records**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

**B5.0 SAMPLES, SHOP DRAWINGS AND  
 MANUFACTURERS' INSTRUCTIONS**

8 **B5.1 Samples of materials**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

Carried to Collection

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1 **B5.2 Workmanship samples**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

2 **B5.3 Shop drawings**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

3 **B5.4 Compliance with manufacturers' instructions**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

**B6.0 TEMPORARY WORKS AND PLANT**

4 **B6.1 Deposits and fees**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

5 **B6.2 Enclosure of the works**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

6 **B6.3 Advertising**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

7 **B6.4 Plant, equipment, sheds and offices**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

8 **B6.5 Main notice board**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

9 **B6.6 Subcontractors' notice board**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time  
 related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**



**B7.0 TEMPORARY SERVICES**

1 **B7.1 Location**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

2 **B7.2 Water**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3 **B7.3 Electricity**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4 **B7.4 Telecommunication facilities**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

5 **B7.5 Ablution facilities**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**B8.0 PRIME COST AMOUNTS**

6 **B8.1 Responsibility for prime cost amounts**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**B9.0 ATTENDANCE ON N/S SUBCONTRACTORS**

7 **B9.1 General attendance**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

8 **B9.2 Special attendance**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

Carried to Collection

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1 **B9.3 Commissioning - fuel, water and electricity**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**B10.0 FINANCIAL ASPECTS**

2 **B10.1 Statutory taxes, duties and levies**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

3 **B10.2 Payment for preliminaries**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

4 **B10.3 Adjustment of preliminaries**  
 Clauses B10.3.1 and B10.3.2 are amended by replacing "within fifteen (15) **working days** of taking possession of the **site**" with "when submitting his priced **bills of quantities / lump sum document**"  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

5 **B10.4 Payment certificate cash flow**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**B11.0 GENERAL**

6 **B11.1 Protection of the works**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

7 **B11.2 Protection / isolation of existing / sectionally occupied works**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1	<b>B11.3 Security of the works</b> Fixed: _____ Value related: _____ Time related: _____	Item
2	<b>B11.4 Notice before covering work</b> Fixed: _____ Value related: _____ Time related: _____	Item
3	<b>B11.5 Disturbance</b> Fixed: _____ Value related: _____ Time related: _____	Item
4	<b>B11.6 Environmental disturbance</b> Fixed: _____ Value related: _____ Time related: _____	Item
5	<b>B11.7 Works cleaning and clearing</b> Fixed: _____ Value related: _____ Time related: _____	Item
6	<b>B11.8 Vermin</b> Fixed: _____ Value related: _____ Time related: _____	Item
7	<b>B11.9 Overhand work</b> Fixed: _____ Value related: _____ Time related: _____	Item
8	<b>B11.10 Instruction manuals and guarantees</b> Fixed: _____ Value related: _____ Time related: _____	Item
9	<b>B11.11 As built information</b> Fixed: _____ Value related: _____ Time related: _____	Item

Carried to Collection

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1 **B11.12 Tenant installations**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

**B12.0 SCHEDULE OF VARIABLES**

2 **B12.1 Schedule of variables**  
 Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_ Time related: \_\_\_\_\_

Item

This **schedule** contains all variables referred to in this document and is divided into pre-tender and post-tender categories. The pre-tender category must be completed in full and included in the tender documents. Both the pre-tender and post-tender categories form part of these **Preliminaries**

Spaces requiring information must be filled in, shown as "not applicable" or deleted and not left blank. Where choices are offered, the non-applicable items are to be deleted. Where insufficient space is provided the information should be annexed hereto and cross-referenced to the applicable clause of the **schedule**. Key cross reference clauses are italicised in [ ] brackets

**12.1 PRE-TENDER INFORMATION**

12.1.1 **Provisional bills of quantities**  
 [2.2] The quantities are provisional

**YES**

12.1.2 **Availability of construction documentation**  
 [2.3] *Construction documentation is complete*

**YES**

12.1.3 **Interests of agents**  
 [2.4] Details:

12.1.4 **Defined works area**  
 [3.1] Details:

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

12.1.5 **Geotechnical investigation**

[3.2] Details:

12.1.6 **Existing premises occupied**

[3.4] Specific requirements:

12.1.7 **Previous work - dimensional accuracy**

[3.5] Details:

12.1.8 **Previous work - defects**

[3.6] Details:

12.1.9 **Services - known**

[3.7] Details:

12.1.10 **Protection of trees**

[3.9] Specific requirements:

12.1.11 **Inspection of adjoining properties**

[3.11] Specific requirements:

12.1.12 **Enclosure of the works**

[6.2] Specific requirements:

12.1.13 **Offices**

[6.4.3] Specific requirements:

The **contractor** shall provide, maintain and remove on completion of the works an office for the exclusive use of the **principal agent**, minimum size 4 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with boarded floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times

Carried to Collection

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**TMT-DBE-2324-SAFEOS-ECCL94**

**PROVISIONAL BILLS OF QUANTITIES**

12.1.14 **Main notice board**

[6.5] Specific requirements:  
 The **contractor** shall provide, erect where directed, maintain and remove on completion of the **works** a notice board size 3 x 3m as type Drawing GEN 063, constructed of suitable boarding with flat smooth surface and with edging bead 19mm thick round outer edges and projecting 12mm from face of boarding and rounded on front edge. The board shall be securely fixed to hoarding, where hoarding is provided, or fixed to and including a suitable supporting structure of timber or tubular posts and braces. The board is to be painted ivory white and the bead and 12mm wide dividing lines dark green. All wording shall be inscribed in dark green as per the coat of arms for SA. All wording shall be inscribed in dark green painted sans serif lettering

12.1.15 **Subcontractors' notice board**

[6.6] *A notice board is required*

Specific requirements: **NO**

12.1.16 **Water**

[7.2] Option A (by **contractor**)

**NO**

Option B (by **employer** - free of charge)

**NO**

Option C (by **employer** - metered)

**YES**

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

12.1.17 **Electricity**

[7.3] Option A (by **contractor**)

**NO**

Option B (by **employer** - free of charge)

**NO**

Option C (by **employer** - metered)

**YES**

12.1.18 **Telecommunications**

[7.4] Telephone

**YES**

Facsimile

**YES**

E-mail

**YES**

12.1.19 **Ablution facilities**

[7.5] Option A (by **contractor**)

**YES**

Option B (by **employer**)

**NO**

12.1.20 **Protection of existing/sectionally occupied works**

[11.2] Protection is required

**NO**

**Carried to Collection**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**TMT-DBE-2324-SAFEOS-ECCL94**

**PROVISIONAL BILLS OF QUANTITIES**

12.1.21 **Special attendance**  
 [9.2] **Subcontractor** (1) details:

**Subcontractor** (2) details:

**Subcontractor** (3) details:

**Subcontractor** (4) details:

12.1.22 **Protection of the works**  
 [11.1] Specific requirements:

12.1.23 **Disturbance**  
 [11.5] Specific requirements:  
 The **contractor** shall keep the site, structures, etc well watered during operations to prevent dust and shall provide and erect and remove on completion of the **works** all necessary temporary dust screens all to the satisfaction of the **principal agent**

12.1.24 **Environmental disturbance**  
 [11.6] Specific requirements:

**12.2 POST-TENDER INFORMATION**

12.2.1 **Payment of preliminaries**  
 [10.2] Option A (prorated)

**NO**

Option B (calculated)

**YES**

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**



12.2.2 **Adjustment of preliminaries**  
 [10.3] Option A (three categories)

**NO**

Option B (detailed breakdown)

**YES**

12.2.3 **Additional agreed preliminaries items**  
 Details:

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

**SECTION C: SPECIFIC PRELIMINARIES**

**Section C** contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item

1 **C1.0 CONTRACT DRAWINGS**

The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the **works** and the manner in which they are to be executed

Should any part of the drawings not be clearly understood by the tenderer he shall, before submitting his tender, obtain clarification in writing from the **principal agent**

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

2 **C2.0 GENERAL PREAMBLES**

The document "Specification of Materials and Methods to be used - PW371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014)." is obtainable on the Department's website (<http://www.publicworks.gov.za/> under "Consultants Guidelines"), and shall be read in conjunction with the **bills of quantities / lump sum document** and be referred to for the full descriptions of work to be done and materials to be used

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1 **C3.0 TRADE NAMES**

Wherever a trade name for any product has been described in the **bills of quantities / lump sum document**, the tenderer's attention is drawn to the fact that any other product of equal quality may be used subject to the written approval of the **principal agent** being obtained prior to the closing date for submission of tenders

If prior written approval for an alternative product is not obtained, the product described shall be deemed to have been tendered for

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
Time related: \_\_\_\_\_

Item

2 **C4.0 HIV/AIDS AWARENESS**

It is required of the **contractor** to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the **bills of quantities / lump sum document**. Provision for pricing of HIV/AIDS awareness is made under items C10.1 to C10.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained

The **contractor** must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the **principal agent**, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress **payment certificate** until the **contractor** provides satisfactory proof of compliance. The **contractor** shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

**C4.1 AWARENESS CHAMPION**

Selection, appointment, briefing and making available of an Awareness Champion including provision of all relevant services, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_

Time related: \_\_\_\_\_

Item

**C4.2 AWARENESS WORKSHOPS**

Selection and appointment of a competent Service Provider approved by the **principal agent**, provision of a Service Provider Workshop Plan and a suitable venue, conducting of awareness workshops by means of traditional and/or modern multi-media techniques, including follow-up courses, making available all tuition material and performing assessment procedures, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_

Time related: \_\_\_\_\_

Item

**C4.3 POSTERS, BOOKLETS, VIDEOS, ETC.**

Provision, displaying, maintaining and replacing when necessary of four plastic laminated posters, booklets and educational videos, etc. for the duration of the

**construction period**, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_

Time related: \_\_\_\_\_

Item

**C4.4 ACCESS TO CONDOMS**

Provision and maintenance of condom dispensers fixed in position, including male and female condoms, replenishing male and female condoms on a daily basis as required for the duration of the **construction period**, all in accordance with the

HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_

Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**TMT-DBE-2324-SAFEOS-ECCL94**

**PROVISIONAL BILLS OF QUANTITIES**

**C4.5 MONITORING**

Monitoring HIV/AIDS awareness of workers, providing the **principal agent** with access to information including making available all reports, thoroughly completed and reflecting the correct information, for the duration of the **construction period** and close out, all in accordance with the HIV/AIDS Specification

Fixed: \_\_\_\_\_ Value related: \_\_\_\_\_  
 Time related: \_\_\_\_\_

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 PRELIMINARIES AND GENERAL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

- 1
- 2
- 3
- 4
- 5
- 6
- 7
- 8
- 9
- 10
- 11
- 12
- 13
- 14
- 15
- 16
- 17
- 18
- 19
- 20

**Carried Forward**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**TMT-DBE-2324-SAFEOS-ECCL94**

**PROVISIONAL BILLS OF QUANTITIES**

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**COLLECTION**

**Brought Forward**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

R

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

**Carried Forward to Summary of Section No. 1**

R

Section No. 1

Bill No. 1

PRELIMINARIES AND GENERAL

**TMT-DBE-2324-SAFEOS-ECCL94**

**PROVISIONAL BILLS OF QUANTITIES**

Item No	Quantity	Rate	Amount
<b><u>BILL No. 2</u></b>			
<b><u>HEALTH AND SAFETY REQUIREMENTS</u></b>			
<u>Note:</u>			
For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications.			
Prior to pricing the principal contractor must familiarize him/herself with the Occupational Health and Safety Act No. 85 Of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety specifications.			
The items in this Bill do not contain quantities hence the Contractor must insert his own quantities based on his individual requirements to comply with the Health and Safety obligations and demands of the Occupational Health and Safety Act No. 85 of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety Specifications.			
<b><u>OCCUPATIONAL HEALTH AND SAFETY</u></b>			
<b><u>General:</u></b>			
1	Preparation of Contractor's site specific Health and Safety Plan.	Item	
2	Submission of the Health and Safety File.	Item	
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations.	Item	
<b>Carried to Collection</b>			R
Section No. 1 Bill No. 2 HEALTH AND SAFETY <b>TMT-DBE-2324-SAFEOS-ECCL94</b> <b>PROVISIONAL BILLS OF QUANTITIES</b>			



1	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period.		Item		
2	Provision of full time Health and Safety Officer for the entire construction period.		Item		
3	Induction training of personnel.	No			
4	Provision of first aid boxes.	No			
<b><u>Provision for Personal Protective Equipment and Protective Clothing:</u></b>					
5	Reflective vests.	No			
6	Hard hats.	No			
7	Protective foot wear.	No			
8	Ear Plugs.	No			
9	Dust Masks.	No			
<b><u>Costs of Medical Certificates and Medical Surveillance:</u></b>					
10	Initial (baseline) medical examinations.	No			
11	Exit Examinations.	No			
<b><u>Noise Monitoring:</u></b>					
12	Establishment of noise zones.	No			
13	Audiograms.	No			
<b>Carried to Collection</b>					
Section No. 1 Bill No. 2 HEALTH AND SAFETY <b>TMT-DBE-2324-SAFEOS-ECCL94</b> <b>PROVISIONAL BILLS OF QUANTITIES</b>				R	

Section No. 1

Bill No. 2

HEALTH AND SAFETY

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

40

41

**Amount**

**Carried Forward to Summary of Section No. 1**

R

Section No. 1

Bill No. 2

HEALTH AND SAFETY

**TMT-DBE-2324-SAFEOS-ECCL94**

**PROVISIONAL BILLS OF QUANTITIES**

**SECTION SUMMARY - SECTION NO.01 - PRELIMINARIES**

Bill No		Page No	Amount
1	PRELIMINARIES AND GENERAL	39	
2	HEALTH AND SAFETY	42	
<b>Carried to Final Summary</b>			R
Section No. 1 <b>TMT-DBE-2324-SAFEOS-ECCL94</b> <b>PROVISIONAL BILLS OF QUANTITIES</b>			

Item No		Quantity	Rate	Amount
	<b><u>SECTION No. 2 - OMITTED SCOPE - NDZONDWENI JUNIOR SECONDARY SCHOOL</u></b>			
	<b><u>BILL No. 1</u></b>			
	<b><u>ALTERATIONS, DEMOLITIONS, ETC (PROVISIONAL)</u></b>			
	<b><u>PLUMBING AND DRAINAGE (PROVISIONAL)</u></b>			
	<b><u>DEMOLITIONS</u></b>			
	<u>Breaking down and removing reinforced concrete, etc</u>			
1	Demolish 100mm thick reinforce concrete V-drain and cart away	m2	280	
2	Demolish 100mm thick reinforced walkway concrete surface bed and cart away.	m2	24	
3	Repair small pothole, crack, etc. approximately 25mm deep in surface of existing concrete floor with a high performance cementations mortar mixed and applied in strict accordance with the Manufacturer's instructions.	m2	50	
4	Enlarge existing circular opening through 255mm thick slab from 200mm to 450mm diameter.	No	4	
	<u>Taking out and removing sanitary fittings, etc</u>			
5	"Atlas Plastics 237 AP" VIP 350 Pit pedestal complete with integral flap four times plugged fixed to floor with 6 x 75mm masonry anchors.	No	4	
	<b><u>SANITARY FITTINGS, TANKS, GEYSERS, ETC.</u></b>			
	<u>Plastic sanitaryware</u>			
6	VIP 450 Pit pedestal complete with integral flap four times plugged to floor with and including 6 x 75mm masonry anchors.	No	4	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 1			
	OMITTED SCOPE - NDZONDWENI JSS			
	<b>TMT-DBE-2324-SAFEOS-ECCL94</b>			
	<b>PROVISIONAL BILLS OF QUANTITIES</b>			

<b><u>Satin Grey Plastics or equal approved</u></b>				
1	"Satin plastic N-SBIN-12-SA SHE Bin size 463 x 140 x 480mm, floor standing loose.	No	9	
<b><u>EXTERNAL WORKS (PROVISIONAL)</u></b>				
<b><u>STORMWATER CHANNELS</u></b>				
<u>Excavation not exceeding 2m deep</u>				
2	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	108	
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
3	Off site to a dumping site to be found by the Contractor.	m3	108	
<u>Filling supplied by the contractor under channels</u>				
4	G7 Base course material compacted to 98% Mod AASHTO density	m3	54	
5	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	54	
<u>Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.</u>				
6	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground in 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	400	
7	Extra for 700mm angle	No	24	
<b>Carried to Collection</b>				R
Section No. 2				
Bill No. 1				
OMITTED SCOPE - NDZONDWENI JSS				
<b>TMT-DBE-2324-SAFEOS-ECCL94</b>				
<b>PROVISIONAL BILLS OF QUANTITIES</b>				

1	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	6		
<b><u>THE FOLLOWING IN ONE BRICK WALL (GARDEN WALL)</u></b>					
<u>Excavation in earth not exceeding 2m deep:</u>					
2	Trenches.	m3	13		
<u>Excavations in earth of more difficult character</u>					
3	Extra over excavations in earth for excavation in soft rock.	m3	1		
4	Extra over excavations in earth for excavation in hard rock.	m3	1		
<u>Extra over all excavations for carting away:</u>					
5	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	8		
<u>Risk of collapse of excavations:</u>					
6	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	50		
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>					
7	Backfilling to trenches, holes, etc.	m3	5		
<u>Earth filling (G7 material) supplied by the contractor in layers not exceeding 150mm thick and compacted to 98% Mod AASHTO density:</u>					
8	Under footings.	m3	3		
<b>Carried to Collection</b>					
Section No. 2					
Bill No. 1					
OMITTED SCOPE - NDZONDWENI JSS					
<b>TMT-DBE-2324-SAFEOS-ECCL94</b>					
<b>PROVISIONAL BILLS OF QUANTITIES</b>					
				R	

<u>Compaction of surfaces</u>					
1	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	25		
<u>25 Mpa/19mm Concrete</u>					
2	Strip footings.	m3	5		
<u>Test blocks:</u>					
3	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	3		
<u>Reinforcement (Provisional)</u>					
4	High tensile steel reinforcement bars to structural concrete work.	t	0.10		
<u>BRICKWORK IN FOUNDATIONS.</u>					
<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>					
5	One brick walls.	m2	15		
<u>BRICKWORK IN SUPERSTRUCTURE</u>					
<u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar (Cement to be 42.5N all-purpose cement):</u>					
6	One brick walls.	m2	15		
<u>Brickwork reinforcement:</u>					
7	230mm Wide reinforcement built in horizontally.	m	50		
8	Ditto but in foundations.	m	50		
<b>Carried to Collection</b>					
Section No. 2					
Bill No. 1					
OMITTED SCOPE - NDZONDWENI JSS					
<b>TMT-DBE-2324-SAFEOS-ECCL94</b>					
<b>PROVISIONAL BILLS OF QUANTITIES</b>					
					R

FACE BRICK

"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):

1	One brickwall faced on both sides.	m2	15
2	230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	50

Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:

**THE FOLLOWING IN DISABLED ACCESS**

**SCREEN WALL**

Excavation in earth not exceeding 2m deep:

3	Trenches.	m3	11
4	Extra over excavations in earth for excavation in soft rock.	m3	1
5	Extra over excavations in earth for excavation in hard rock.	m3	1

Excavations in earth of more difficult character

Extra over all excavations for carting away:

6	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the Contractor.	m3	4
---	---	----	---

Risk of collapse of excavations:

7	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	30
---	---	----	----

**Carried to Collection**

R

Section No. 2  
 Bill No. 1  
 OMITTED SCOPE - NDZONDWENI JSS  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**



	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site compacted to 93% MOD AASHTO density:</u>				
1	Backfilling to trenches, holes, etc.	m3	6		
	<u>Earth filling (G7 material) supplied by the contractor in layers not exceeding 150mm thick and compacted to 98% Mod AASHTO density:</u>				
2	Under footings.	m3	2		
	<u>Compaction of surfaces</u>				
3	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	15		
	<u>25 Mpa/19mm Concrete</u>				
4	Strip footings.	m3	5		
	<u>Test blocks:</u>				
5	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	4		
	<u>Reinforcement (Provisional)</u>				
6	High tensile steel reinforcement bars to structural concrete work.	t	0.21		
	<u>BRICKWORK IN FOUNDATIONS.</u>				
	<u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):</u>				
7	One brick walls.	m2	8		
	<u>BRICKWORK IN SUPERSTRUCTURE</u>				
	<u>Brickwork of NFP bricks (14 MPa nominal compressive strength) in Class II mortar (Cement to be 42.5N all-purpose cement):</u>				
	<b>Carried to Collection</b>				
	Section No. 2				
	Bill No. 1				
	OMITTED SCOPE - NDZONDWENI JSS				
	<b>TMT-DBE-2324-SAFEOS-ECCL94</b>				
	<b>PROVISIONAL BILLS OF QUANTITIES</b>				
					R

1	One brick walls.	m2	45	
	<u>Brickwork reinforcement:</u>			
2	230mm Wide reinforcement built in horizontally.	m	180	
3	Ditto but in foundations.	m	60	
	<u>FACE BRICK</u>			
	<u>"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):</u>			
4	One brickwall faced on both sides.	m2	45	
	<u>Brick-on-edge header course copings, sills, etc. of "Rustgold FBS/Qunu Travertine" or equal approved face bricks pointed with recessed joints on all exposed faces, 220mm wide sill set sloping and slightly projecting:</u>			
5	230mm wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	30	
	<u>ACCESS RAMPS</u>			
	<u>Excavation not exceeding 2m deep</u>			
6	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	9	
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>			
7	Off site to a dumping site to be found by the Contractor.	m3	8	
	<u>Filling supplied by the contractor under floors, aprons, etc</u>			
8	G7 Base course material compacted to 98% Mod AASHTO density	m3	4	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 1			
	OMITTED SCOPE - NDZONDWENI JSS			
	<b>TMT-DBE-2324-SAFEOS-ECCL94</b>			
	<b>PROVISIONAL BILLS OF QUANTITIES</b>			

1	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	4	
	<u>Coarse river sand filling supplied by the contractor:</u>			
2	Under floors etc.	m3	1	
	<u>Compaction of surfaces:</u>			
3	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	27	
	<u>Prescribed density tests on filling:</u>			
4	In-situ dry density test.	No	2	
	<u>Reinforced 25Mpa/19mm Concrete:</u>			
5	Ramps, Landings, etc.	m3	10	
	<u>Finishing top surfaces of concrete smooth with a wood float:</u>			
6	Surface beds, slabs, etc to falls and currents.	m2	27	
	<u>Test blocks:</u>			
7	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	4	
	<u>Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:</u>			
8	12mm Joints not exceeding 300mm high.	m	36	
	<u>Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>			
9	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	36	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 1			
	OMITTED SCOPE - NDZONDWENI JSS			
	<b>TMT-DBE-2324-SAFEOS-ECCL94</b>			
	<b>PROVISIONAL BILLS OF QUANTITIES</b>			

<u>Fabric reinforcement:</u>				
1	REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.	m2	27	
<u>Waterproofing under Surface beds</u>				
2	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid on sand bed (elsewhere measured).	m2	27	
<b><u>THE FOLLOWING IN SECURITY FENCING, ETC</u></b>				
<u>Site clearance</u>				
3	Allow for clearing site for the width of 1 000 mm where fencing is to be erected including removing trees, shrubs etc. not exceeding 200 mm girth, grubbing up roots and roughly levelling.	m2	100	
<u>Straining wires, fencing and razor wire:</u>				
4	Four strands of 4mm Class'A' galvanised straining wires secured to fencing posts with doubled 2 mm galvanised wire inserted through hole in post and turned a minimum of four turns around straining wire and attached to straining frame at one end with not less than four turns at the other end to straining bolts (elsewhere measured).	m	400	
5	3 Strands of galvanised barbed wire tied to standards, posts and eye bolts	m	300	
6	Fencing formed of 50 x 50 x 2.0mm diameter galvanised fencing 1 800mm high and fixed to each straining wire with 8 guage binding wire at 500mm centres including Y12 pegs at 900mm c/c between posts (straining wires elsewhere measured).	m	100	
<u>Posts for 1 800mm high security fence:</u>				
7	60mm Diameter galvanised steel intermediate fencing post 2400mm long fitted with a pressed steel mushroom cap one end and 150 x 150 x 5 mm baseplate at bottom and embedded in and including 350 x 350 x 600 mm mass concrete (15 MPa) base.	No	34	
<b>Carried to Collection</b>				
Section No. 2				R
Bill No. 1				
OMITTED SCOPE - NDZONDWENI JSS				
<b>TMT-DBE-2324-SAFEOS-ECCL94</b>				
<b>PROVISIONAL BILLS OF QUANTITIES</b>				



<u>Excavation not exceeding 2m deep</u>				
1	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	60	
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
2	Off site to a dumping site to be found by the Contractor.	m3	60	
<u>Filling supplied by the contractor under driveways</u>				
3	G7 Base course material compacted to 98% Mod AASHTO density	m3	30	
4	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	30	
<u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>				
5	Under floors,etc.	m2	200	
<u>Prescribed density tests on filling:</u>				
6	In-situ dry density test.	No	8	
<u>150-175mm diameter bollards</u>				
7	2100mm long tanalith treated gum pole planted 800mm deep including excavations, cartaways, concrete base etc.	No	12	
<b><u>BUDGETARY ALLOWANCES</u></b>				
8	Allow the Budgetary Allowance of R 30 000.00 (Thirty Thousand Rand) for the minor repairs to newly built VIP toilets, to be detailed at a later stage.		Item	30,000.00
9	Allow the Budgetary Allowance of R 25 000.00 (Twenty Five Thousand Rand) for the landscaping around the site detailed and specified at a later stage.		Item	25,000.00
<b><u>PROVISION OF TEMPORARY TOILETS DURING THE CONSTRUCTION PERIOD</u></b>				
<b>Carried to Collection</b>				
				R
Section No. 2				
Bill No. 1				
OMITTED SCOPE - NDZONDWENI JSS				
<b>TMT-DBE-2324-SAFEOS-ECCL94</b>				
<b>PROVISIONAL BILLS OF QUANTITIES</b>				

<u>Portable toilets</u>				
1	Supply and erecting of the portable chemical toilet during the duration of the contract.	No	6	
2	Servicing and maintain the ten portable chemical toilets on a weekly basis during duration of the contract. (No = week)	No	24	
3	Removal of the portable chemical toilet on completion of the contract.	No	6	
<u>COMMUNITY LIAISON OFFICER (CLO)</u>				
4	Provide the sum of R 26 000.00 (Twenty Six Thousand Hundred Rand) for the employment of a CLO.(R 6 500.00 per month x contract period allowance)	Item		26,000.00
5	Add for profit on the above if required.	Item		
<b>Carried to Collection</b>				
				R

Section No. 2  
 Bill No. 1  
 OMITTED SCOPE - NDZONDWENI JSS  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

Section No. 2

Bill No. 1

OMITTED SCOPE - NDZONDWENI JSS

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

44  
45  
46  
47  
48  
49  
50  
51  
52  
53  
54  
55

**Carried to Final Summary**

R

Section No. 2

Bill No. 1

OMITTED SCOPE - NDZONDWENI JSS

**TMT-DBE-2324-SAFEOS-ECCL94**

**PROVISIONAL BILLS OF QUANTITIES**



Item No		Quantity	Rate	Amount
	<b><u>SECTION No.3 - OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL</u></b>			
	<b><u>BILL No. 1</u></b>			
	<b><u>PLUMBING AND DRAINAGE (PROVISIONAL)</u></b>			
	<b><u>Satin Grey Plastics or equal approved</u></b>			
1	"Satin plastic N-SBIN-12-SA SHE Bin size 463 x 140 x 480mm, floor standing loose.	No	10	
	<b><u>STORMWATER CHANNELS</u></b>			
	<u>Excavation not exceeding 2m deep</u>			
2	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	74	
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>			
3	Off site to a dumping site to be found by the Contractor.	m3	74	
	<u>Filling supplied by the contractor under channels</u>			
4	G7 Base course material compacted to 98% Mod AASHTO density	m3	37	
5	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	37	
	<b>Carried to Collection</b>			R
	Section No. 3			
	Bill No. 1			
	OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL			
	<b>TMT-DBE-2324-SAFEOS-ECCL94</b>			
	<b>PROVISIONAL BILLS OF QUANTITIES</b>			

Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.

1	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground in 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	350
2	Extra for 700mm angle	No	20
3	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	4

**THE FOLLOWING IN RETAINING WALLS (PROVISIONAL)**

**EXCAVATIONS, FILLING, ETC.**

**Excavations**

**EXCAVATIONS FOR FOUNDATIONS, ETC.**

Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away

4	Surface trenches.	m3	72
	<u>Excavations in earth of more difficult character</u>		
5	Extra over excavations in earth for excavation in soft rock.	m3	7
6	Extra over excavations in earth for excavation in hard rock.	m3	4

**Carried to Collection**

R

Section No. 3  
 Bill No. 1  
 OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

**Carting away of excavated material**

1	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	40
---	---	----	----

**Risk of collapse of excavations**

2	Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.	m2	163
---	---	----	-----

**Keeping excavations free of water**

3	Allow for keeping the excavations free from water.		Item
---	--	--	------

**Filling**

4	Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density.	m3	32
---	---	----	----

**CONCRETE**

**Mass concrete 10MPa (19mm stone) in:**

5	Blinding beneath bases, strip footings, etc cast against excavated surfaces.	m3	4
---	--	----	---

**Reinforced concrete 30MPa (19mm stone) in:**

6	Strip foundations cast against excavated surfaces.	m3	22
---	--	----	----

7	Filling to cavity of hollow brick wall.	m3	7
---	---	----	---

**Test blocks and testing**

8	Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional)	No	5
---	---	----	---

**REINFORCEMENT (PROVISIONAL)**

**Bar reinforcement**

**Carried to Collection**

R

Section No. 3  
 Bill No. 1  
 OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

<u>Mild steel rod reinforcement to structural concrete work</u>					
1	10mm Diameter bars.	t	0.269		
<u>High tensile rod reinforcement to structural concrete work</u>					
2	10mm Diameter bars.	t	0.806		
3	12mm Diameter bars.	t	0.806		
4	16mm Diameter bars.	t	0.806		
<b><u>FOUNDATION BRICKWORK (PROVISIONAL)</u></b>					
<b><u>Walls and linings in stock bricks in 5:1 cement mortar :</u></b>					
5	One brick wall.	m2	8		
6	270mm Thick cavity wall comprising one half brick skin and one brick on edge skin tied together with and including galvanised butterfly wire ties at the minimum rate of 9/m2.	m2	53		
<b><u>Closing cavities</u></b>					
7	Build vertical 50mm wide cavity solid.	m	8		
<b><u>Reinforcement to brickwork</u></b>					
8	Galvanised brick reinforcement 75mm wide built horizontally into brickwork.	m	789		
9	Galvanised brick reinforcement 150mm wide built horizontally into brickwork.	m	24		
<b><u>FACE BRICKWORK</u></b>					
<u>"Rustgold FBS/Quunu Travertine" or other equal and approved FBS quality face bricks including jointing and square recess pointing 6 x 10mm joints</u>					
10	Extra over ordinary brickwork for facing and pointing in stretcher bond.	m2	32		
<b>Carried to Collection</b>					
Section No. 3					
Bill No. 1					
OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL					
<b>TMT-DBE-2324-SAFEOS-ECCL94</b>					
<b>PROVISIONAL BILLS OF QUANTITIES</b>					
				R	



**PLUMBING AND DRAINAGE**

1	50mm Diameter PVC pipe 230mm long built through brick wall.	No	5
2	50mm Diameter PVC pipe 280mm long built through concrete filled cavity brick wall.	No	27

**THE FOLLOWING IN WALKWAYS**

**REFURBISHMENT**

3	Repair small pothole, crack, etc. approximately 25mm deep in surface of existing concrete floor with a high performance cementations mortar mixed and applied in strict accordance with the Manufacturer's instructions.	m2	50
---	--	----	----

**THE FOLLOWING IN SECURITY FENCING, ETC**

Site clearance

4	Allow for clearing site for the width of 1000mm where fencing runs are to be erected including removing trees, shrubs, etc., not exceeding 200mm girth, grubbing up roots and roughly levelling.	m	200
---	--	---	-----

Fencing

5	Six strands of 4mm galvanised straining wires (evenly spaced) secured to straining posts with doubled 2mm galvanised wire inserted through hole in post and turned a minimum of four turns around straining wire and attached to straining frame at one end with not less than four turns at the other end to and including 12mm diameter straining eye bolts.	m	200
6	Fencing formed of 100 x 50 x 2.5mm diameter Class A galvanised "Secumesh" security fence 1.8m high with vertical wires facing outwards secured with "Howgring" clips applied with "Howgring" pliers at 300mm centres to top and bottom straining wires and 500mm centres to four intermediate straining wires (elsewhere).	m	200

**Carried to Collection**

R

Section No. 3  
 Bill No. 1  
 OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL  
**TMT-DBE-2324-SAFEOS-ECCL94**  
**PROVISIONAL BILLS OF QUANTITIES**

1	500mm Diameter flat wrap of galvanised razor barbed tape wire fixed vertically to and including two rows of double stranded barbed wire to top of security fence and secured to straining wire (elsewhere) with and including 2.5mm diameter galvanised binding wire at 300mm centres.	m	200	
	<u>Hot dipped galvanised steel posts, etc.</u>			
2	60mm Diameter x 2.5mm wall thickness intermediate fencing post, 2700mm long fitted with pressed steel mushroom cap, the post fitted with 150 x 150 x 5mm baseplate at bottom and embedded in 350 x 350 x 600mm mass concrete (15 MPa) base including all necessary excavations, backfilling, concrete, etc.	No	50	
3	100mm Diameter x 3mm wall thickness end or corner post 2700mm long fitted with pressed steel mushroom cap and one 60mm diameter x 2mm wall thickness raking stay, the post and stay fitted with 150 x 150 x 5mm baseplate at bottom and embedded in 350 x 350 x 600mm mass concrete (15 MPa) base, including all necessary excavations, backfilling, concrete, etc.	No	6	
4	100mm Diameter x 3mm wall thickness intermediate straining or corner post 2700mm long fitted with pressed steel mushroom cap, but fitted with two 60mm diameter x 2mm wall thickness galvanised steel raking stays, the post and stays fitted with 150 x 150 x 5mm baseplate at bottom and embedded in 350 x 350 x 600mm mass concrete (15 MPa) base, including all necessary excavations, backfilling, concrete, etc.	No	10	
<b>Carried to Collection</b>				R
Section No. 3 Bill No. 1 OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL <b>TMT-DBE-2324-SAFEOS-ECCL94</b> <b>PROVISIONAL BILLS OF QUANTITIES</b>				

<u>Hot dipped galvanised steel gates</u>				
1	Security fence single gate, size 1000mm wide x 1800mm high, formed of 50mm diameter nominal bore x 3.25mm wall thickness mild steel pipe all round with mitred and welded angles and diagonal cross brace, 146 x 280mm hand access opening formed of 40 x 40 x 2.5mm square section framing welded on, the gate covered the gate covered with 100 x 50 x 2.5mm diameter Class A galvanised "Secumesh" security fence secured with "Howgring" clips applied with "Howgring" pliers at 300mm centres to and including six rows of straining wires and fitted with three 24mm diameter x 300mm long eyebolt hinges and stops including all holes, etc., welded or bolted to adjoining galvanised gatepost.	No	1	
<u>Sundries</u>				
2	Extra over excavations in earth (concrete bases) for excavation in soft rock.	m3	1	
3	25mm Diameter x 100mm long galvanised steel dropbolt keep, cast flush in surface bed, including forming necessary mortice and grouting in.	No	1	
4	Mass concrete (15MPa) base, size 200 x 200 x 200mm deep, with 25mm diameter x 100mm galvanised sleeve cast in flush with ground level, to receive towerbolt (elsewhere), including all necessary excavations, etc.	No	1	
5	51mm brass padlock with stainless steel shackle.	No	1	
<b><u>THE FOLLOWING IN ACCESS DRIVEWAY, ETC.</u></b>				
<u>Excavation not exceeding 2m deep</u>				
6	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	60	
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>				
7	Off site to a dumping site to be found by the Contractor.	m3	60	
<b>Carried to Collection</b>				R
Section No. 3				
Bill No. 1				
OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL				
<b>TMT-DBE-2324-SAFEOS-ECCL94</b>				
<b>PROVISIONAL BILLS OF QUANTITIES</b>				



<u>Filling supplied by the contractor under driveways</u>				
1	G7 Base course material compacted to 98% Mod AASHTO density	m3	30	
2	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	30	
<u>Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:</u>				
3	Under floors,etc.	m2	200	
<u>Prescribed density tests on filling:</u>				
4	In-situ dry density test.	No	8	
<u>150-175mm diameter bollards</u>				
5	2100mm long tanalith treated gum pole planted 800mm deep including excavations, cartaways, concrete base etc.	No	12	
<b><u>BUDGETARY ALLOWANCES</u></b>				
6	Allow the Budgetary Allowance of R 30 000.00 (Thirty Thousand Rand) for the minor repairs to newly built VIP toilets, to be detailed at a later stage.		Item	30,000.00
7	Allow the Budgetary Allowance of R 7 500,00 (Seven Thousand Five Rand) for the installation of a 0.75kw water pump including housing, etc.		Item	7,500.00
8	Allow the Budgetary Allowance of R 25 000.00 (Twenty Five Thousand Rand) for the landscaping around the site detailed and specified at a later stage.		Item	25,000.00
<b><u>PROVISION OF TEMPORARY TOILETS DURING THE CONSTRUCTION PERIOD</u></b>				
<u>Portable toilets</u>				
9	Supply and erecting of the portable chemical toilet during the duration of the contract.	No	6	
<b>Carried to Collection</b>				
				R
Section No. 3				
Bill No. 1				
OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL				
<b>TMT-DBE-2324-SAFEOS-ECCL94</b>				
<b>PROVISIONAL BILLS OF QUANTITIES</b>				



Section No. 3

Bill No. 1

OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

57

58

59

60

61

62

63

64

65

66

**Carried to Final Summary**

R

Section No. 3

Bill No. 1

OMITTED SCOPE - SEMONKONG PRIMARY SCHOOL

**TMT-DBE-2324-SAFEOS-ECCL94**

**PROVISIONAL BILLS OF QUANTITIES**

Section No	<u>FINAL SUMMARY</u>	Page No	Amount
1	SECTION NO.01 - PRELIMINARIES	43	
2	SECTION NO.02 - NDZONDWENI JUNIOR SECONDARY SCHOOL	56	
3	SECTION NO.3 - SEMONKONG PRIMARY SCHOOL	67	
	Sub-Total		R
	<b><u>CONTINGENCY PROVISIONS</u></b>		
	The Tenderer is to allow hereunder for 10 (Ten) percent of the Nett Builders Work Sub-Total to be used as a Budgetary Provision for construction contingencies of a general nature and for the finalisation of design detailing. This sum, or any portion thereof, shall be expended at the sole discretion of the Principal Agent. Any residual balance remaining subsequent to such expenditure shall be deducted in its entirety from the Contract Sum.	%	
	Add Value - Added Tax at the rate applicable as at Tender closing date.		R
	Sub - Total		R
	<b>Carried to Form of Tender</b>		R
	<b>TMT-DBE-2324-SAFEOS-ECCL94 PROVISIONAL BILLS OF QUANTITIES</b>		