

Provision for civil work on MV/LV underground cables within Eskom Distribution Gauteng Cluster, for a period of 60 Months on an “as and when” required basis.

Scope of Work

Provision for civil work on MV/LV underground cables within Eskom Distribution Gauteng Cluster.

Civil Scope of Work:

- 1.) P&Gs and Pre-construction related activities. (Specialised barricading, trench covers and traffic control.)
- 2.) River crossing, road crossings and embankment support. (Pipe jacking with sleeves, Directional drilling with sleeves, earth retention and soil erosion mitigation.)
- 3.) MV cable joint bays (Road cutting; excavation, importing and backfilling of soil; rock blasting; shoring; cable route markers.)
- 4.) Reinstatement (Road, paved, concrete, lawn surfaces; fences.)

The amount of work that the contractors will be required to do.

- Contractors must be able to respond to breakdowns or any critical work 24/7.
- Contractors are required to assist with excavation for PPM and CNC in attending to the MV and LV cable breakdowns for the Cluster to manage the risks.
- All excavations must be adequately barricaded and not left open.
- The contractor shall ensure that the necessary plant (including TLB, jackhammer, bulleting machine and etc, are available when required or necessary.



19/02/2025