

ISOMETRIC VIEW

- | NOTES | |
|-------|--|
| 1. | AS-BUILT DRAWINGS LAYOUT PLANS AND SECTIONS (PRODUCED ON THE BASIS OF PROFESSIONAL LAND SURVEYORS AS-BUILT SURVEY, APRIL 2021) (ARROW SURVEYS PTY LTD) AND V/CONSULTING ENGINEERS SITE SURVEY, JANUARY 2021. |
| 2. | DUE TO SURVEYING CONDITIONS, DETAILS OF THE BANK BOTTOM CANNOT BE VERIFIED AT THE TIME OF THE SURVEY. THE CONTRACTOR SHALL RE-VERIFY THE TANK UPON COMPLETION OF BANK AND STRUCTURAL REPAIRS (SEE NOTE 3) TO CONFIRM AS-BUILT DIMENSIONS AND LEVELS. |
| 3. | REPLACEMENT WEIR PLATE TO BE FASTENED TO WALL, SEE DETAIL 4 FOR REINFORCEMENT. FINISH ALL EXPOSED SURFACES TO CONFORM AS-BUILT DIMENSIONS AND LEVELS. |
| 4. | REPLACEMENT WALL RAILINGS TO BE BOLT JOINT TYPE (10mm HIGH) AND TO BE ERECTED ALL AROUND PERIMETER OF TANK |
| 5. | DRAWING TO BE RE-ALIGNED |
| 5.1 | 10090001 - (IN-SITU LAYOUT) |
| 5.2 | 10090001 - 0118 (SERVICES) |
| 5.3 | MCCOMMERCIAL ENDS002602 |
| 6. | FOR BRIDGE STRUCTURAL REPAIRS CRACK SEALING, FLOOR AND WALL SURFACE FINISHING & WATER PROOFING, REFER TO STRUCTURAL ENGINEERING CONTRACTOR REPAIR SPECIFICATION |



FOR TENDER

[illegible]


CLIENT/IMPLEMENTING AGENCY



PROJECT
TSHIAME WWTW REFURBISHMENT
BW CONTRACT: BW298/TSHIWWTW/22

DRAWING DESCRIPTION
PRIMARY SETTLING/IMHOFF TANK LAYOUT
AND SECTIONS - REFURBISHMENT WORK

DRAWING NO. 10909001 - 0513	REVISION T1
------------------------------------	--------------------

SURVEY:	AS	CHECKED:	GM
		ECOA PR No: 20170244	
DRAWN:	HP, GM	SCALE:	AS SHOWN
			A0
APPROVED:		INCEPTION DATE: 2025-02-21	
ECOA PR No: 20170244			
FILE PATH:	SHAREPOINT/BLOEMFONTEIN-10900901 TSHAME WAYW / 02 CONSENT / 04 DRAW		

ISSUED FOR TENDER