	Scope of work	Document Identifier	559-1826396412	Rev	1	
		Effective Date	21 October 2025			
		Review Date	October 2028			

The scope of work entails but not limited to the following:

The scope is the installation and commissioning of smart meters, data concentrator units (DCUs), ready board retrofit, access covers, insulation piercing connector (IPC), pole top split metering kiosks, secure pole mount DC kiosks, passive base units, meter seals, padlocks and all associated accessories including the decommissioning, scrapping and disposal of existing meters for the Eskom Distribution division.

The scope includes the installation and commissioning of:

1. Smart meter installation (BS Footprint, Din-Rail mounted) – replacement of old non-smart meters with smart meters.
2. Pole-top box (use IPC) – installation of pole-top boxes using IPC clamps where applicable.
3. Data Concentrator (DC)– installation of new data concentrators on transformer zone or minisub installation
4. Data Concentrator (DC) Kiosk – installation of data concentrators on transformer zones and minisubs
5. Ready board retrofit – installation of retrofit ready boards where applicable.
6. Access cover – installation of access covers after removal of old ED/ BS Footprint non-smart meter to cover the live terminals where applicable.
7. Customer Data/Information Update and Collection.
8. Smart meters and DC commissioning.

Compiled by



Fanisa Hlungwani

Date.....2026/07/02.....


Supported by



Mmedi Motaung

Date.....2026/07/02.....

Approved by



Edison Makwarela

Date.....2026/07/02.....

Controlled Disclosure

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system. No part of this document may be reproduced in any manner or form by third parties without the written consent of Eskom Holdings SOC Ltd, © copyright Eskom Holdings SOC Ltd, Reg No 2002/015527/30